

**Kingston Fossil Plant
Dry Fly Ash Collection
Design & Install New Fly Ash Handling System**

Estimate Number: 04096 **Option:** 0 **PCN Number:**
Plant: KIF **Revision:** 0 **Estimate Type:** Conceptual
Cost Engineer: B. L. Renfroe **Unit #:** **Estimate Accuracy:** +/- 30%
Requesting Engr: R. E. Purkey **Phase:** 1 **Estimate Issue Date:** 12/10/2003

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$425,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$425,000</u>
<u>Phase II</u>		
Engineering		\$40,000
Long Lead Procurement		\$1,185,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$1,225,000</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$51,521
Labor (T&L)	11,121.00	\$407,918
Labor (Non-Manual)		
Equipment		\$5,000
Subcontracts		\$21,693,750
Partner Fee		\$20,396
Partner Insurance		\$12,238
Escalation		\$805,601
Construction Risk Dollars		\$0
Other		\$21,321
Total Construction Cost		\$23,017,745
Engineering		\$87,000
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$245,255
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$23,350,000</u>
<u>All Phases</u>		
Construction Partner	11,121.00	\$23,017,745
Long Lead Procurement		\$1,185,000
Engineering		\$552,000
Other / Other Organizations		\$0
Total Risk Dollars		\$245,255
<u>Total Project Costs</u>	<u>11,121.00</u>	<u>\$25,000,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**Kingsion Fossil Plant
Dry Fly Ash Collection
Design & Install New Fly Ash Handling System**

Project name	Dry Fly Ash
Estimator	B. L. Renfro
Labor rate table	KIF 60 2003
Plant	KIF
Estimate #	04096
Requesting Engr	R. E. Purkey
Option	0
Revision	0
Phase	1
Estimate Type	Conceptual
Estimate Accuracy	+/- 30%
Est. Issue Date	12/10/2003
Funding Type	Capital
Notes	Electrical Engineered Material Costs based on ABB quote. (1043-03-1633) UC Service Corporation proposal (Q03381) included Fly Ash Handling design & equipment, which is coming from United Conveyor Corporation. 161kV Power Feed is based off of an FY01 TPS estimate that has been escalated. Estimate is in FY04 Dollars.
Report format	Sorted by 'Location/Activity' 'Detail' summary

Location	Activity	Description	Takeoff Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Amount
KIF	Fly Ash Collection								
		480V indoor switchgear	1.00 ls	73,360	150,000	-	-	-	223,360
		1500 KVA, 4.16kV/480V Transformer	2.00 ls	44,016	100,000	15,000	-	-	159,016
		4.16kV Indoor Switchgear	1.00 ls	73,360	150,000	-	-	-	223,360
		4.16kV Outdoor Switchgear	3.00 ls	104,538	210,000	-	-	-	314,538
		10MVA, 161kv/4.16kv liq filled Transformer	2.00 ls	44,016	500,000	75,000	-	-	619,016
		750 KVA, 4.16kV/480V Transformer	1.00 ls	11,004	25,000	3,750	-	-	39,754
		480V Outdoor MCC	1.00 ls	22,925	50,000	-	-	-	72,925
		CJ 5KV 4/0-3C Shielded EPR/CSPE	3,500.00 lf	17,460	29,295	-	-	-	46,755
		UC Service Corporation	1.00 ls	0	0	16,000,000	-	-	16,000,000
		161kV Power Feed	1.00 ls	0	0	5,600,000	-	-	5,600,000
		CJ 600V 2/0-3C XLPE/CSPE	2,250.00 lf	9,903	14,726	-	-	-	24,630
		Mis. Equipment & Unforeseen Items	1.00 ls	7,336	7,500	-	-	5,000	19,836
		Fly Ash Collection		407,918	1,236,521	21,693,750	5,000	-	23,343,189
		KIF		407,918	1,236,521	21,693,750	5,000	5,000	23,343,189

Estimate Totals

Labor	407,918	11,121,000	hrs
Material	1,236,521		
Subcontract	21,893,750		
Equipment	5,000		
	<u>23,343,189</u>	23,343,189	
Engineered Materials - Ph 2	1,185,000	100,000 %	
Adjustment - Engr Materials	(1,185,000)	(100,000) %	
	<u>23,343,189</u>		
Small Tools Expense	5,004	0.450 \$/hr	
Consumables & Expendables	16,317	4.000 %	
	<u>21,321</u>		
Escalation - Craft Labor	20,396	5.000 %	
Escalation - Subcontract	759,281	3.500 %	
Escalation - Perm Materials	24,730	2.000 %	
Escalation - Small Tools	378	0.034 \$/hr	
Escalation - Consumables	816	0.200 %	
	<u>805,601</u>	24,170,111	
Partner Insurance (FY 04)	12,238	3.000 %	
Partner Award Fee (FY04)	20,396	5.000 %	
	<u>32,634</u>	24,202,745	
Elect. Engineering Design	380,000		
Elect. Site Meeting / Travel	45,000		
Mech Engineering - Phase 2	20,000		
Civil Engineering - Phase 2	20,000		
Elect. Field Commissioning	75,000		
Project Controls & Estimating	12,000		
	<u>552,000</u>	24,754,745	2.526 %
Rounding	245,255		
	<u>245,255</u>	25,000,000	
Total	Total	25,000,000	

Powell, Ronald D.

From: Renfroe, Bret
Sent: Monday, December 15, 2003 10:18 AM
To: Powell, Ronald D.
Subject: KIF Dry Fly Ash Collection

Ron,

I rolled up the estimate that included replacing the ash handling with a Dry Fly Ash Collection. The total estimate was for \$25,000,000. My estimated scheduled time to complete, would be 24 months. If you need anything else, let me know.

Bret L. Renfroe

Tennessee Valley Authority
Cost Estimator
1101 Market St. LP 2P - C
Chattanooga, TN 37402-2801
Phone: 423-751-7684
Fax: 423-751-4295

12/18/2003

TVA-00013868

**KINGSTON FOSSIL PLANT
INSTALL A LINER/LEACHATE COLLECTION
SYSTEM ON EXISTING DREDGE CELLS**

Estimate Number 04097 Option: 0 PCN Number:
 Plant: KIF Revision: 0 Estimate Type: Conceptual
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 30%
 Requesting Engr: Harold L. Petty Phase: 1 Estimate Issue Date 12/12/2003

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$28,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$28,000</u>
<u>Phase II</u>		
Engineering		\$143,000
Long Lead Procurement		\$0
Partner (Non-Manual)		
Other / Surveying & Envr Permitting		\$25,000
<u>Total Phase II</u>		<u>\$168,000</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$1,190,688
Labor (T&L)	43,193.89	\$1,026,554
Labor (Non-Manual)	4,320.00	\$216,000
Equipment		\$526,470
Subcontracts		\$1,456,100
Partner Fee		\$62,128
Partner Insurance		\$37,277
Escalation		\$110,290
Construction Risk Dollars		\$0
Other		\$66,979
Total Construction Cost		\$4,692,486
Engineering		\$25,000
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$39,514
Other / Field QA/QC Services		\$47,000
<u>Total Phase III</u>		<u>\$4,804,000</u>
<u>All Phases</u>		
Construction Partner	47,513.89	\$4,692,486
Long Lead Procurement		\$0
Engineering		\$196,000
Other / Other Organizations		\$72,000
Total Risk Dollars		\$39,514
<u>Total Project Costs</u>	<u>47,513.89</u>	<u>\$5,000,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

KINGSTON FOSSIL PLANT
INSTALL A LINER/LEACHATE COLLECTION
SYSTEM ON EXISTING DREDGE CELLS

Project name KIF04097/DREDGE CELLS

Estimator C. L. Toney

Labor rate table KIF 40 2003

Equipment rate table TYA Equipment

Dredge Cell

KIF

04007

Requesting Engr Harold L. Peety

Option 0

Revision 0

Phase 1

Order Of Magnitude

+/- 50%

Estimate Accuracy 12/12/2003

Est. Issue Date O & M

Funding Type

Notes

Installation of a liner/leachate collection system on the existing dredge cells.

This is an order of magnitude cost estimate with conceptual design including sketches and estimated quantities provided by MACTEC.

All costs are estimated in 2004 dollars.

Estimate assumes a 24 month construction duration.

Estimate assumes engineering dollars at +/-4% of construction total.

Estimate includes an allowance for surveying services, environmental permitting and field QA/QC services.

Report format Sorted by 'Location/Activity'
'Detail' summary

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount			
DREDGE CELL	Liner&Underdrain Sys	Haul Bottom Ash Dump & Construct Saw Tooth Anchor Trench Excavation	535,000.00 cy	2,500.000	214.00 cd	828,520	-	-	442,980	-	2.38	1,271,509			
		HDPE Liner, 60-Mil (including Penetration Boots)	1,100.00 sf	0.200	220.00 mh	4,948	-	-	-	2,750	-	7.00	7,698		
		Anchor Trench Compacted Backfill	2,800,000.00 sf	-	-	-	-	-	1,447,600	-	-	0.52	1,447,600		
		6" Non-Perforated Pipe	425.00 lf	0.300	330.00 mh	7,422	602	602	-	8,006	-	14.03	15,428		
		12" Non-Perforated Pipe	125.00 lf	0.200	25.00 mh	532	486	486	-	42	-	8.47	1,059		
		6" Perforated Pipe	13,000.00 lf	0.160	2,080.00 mh	44,246	18,428	18,428	-	3,466	-	5.09	68,141		
		12" Perforated Pipe	285.00 lf	0.170	65.45 mh	1,051	628	628	-	81	-	6.11	1,740		
		Rip Rap Placement	125.00 lf	0.200	25.00 mh	532	486	486	-	42	-	8.47	1,059		
		1032 Crushed Stone	20.00 cy	0.300	6.00 mh	735	473	473	-	125	-	36.62	732		
		1081 Crushed Stone	940.00 cy	0.400	376.00 mh	8,456	16,779	16,779	-	20	-	25.61	26,489		
		Filter Fabric	90,000.00 sf	0.003	240.30 mh	5,404	4,950	4,950	-	1,253	-	0.12	11,155		
		Spread Impacted Sand/Cover / Drainage Layer	102,000.00 cy	700.000	145.71 cd	76,651	1,147,500	1,147,500	-	36,429	-	12.38	1,283,929		
		DREDGE CELL					981,469	1,190,688	1,447,600	1,447,600	496,107	-		4,115,864	
		XCONST FACILITY					981,469	1,190,688	1,447,600	1,447,600	496,107	-		4,115,864	
		Construct Facilities		Mobilization	1.00 ls	192.000	4,734	-	-	-	2,439	-	7,183.95	7,184	
				Admin Time (Employee proc, etc)	1.00 ls	160.000	3,672	-	-	-	-	-	-	3,671.68	3,672
				Maint Road, Buildings & Facilities	1.00 ls	456.000	8,792	-	-	-	-	18,249	-	27,031.69	27,032
Drinking Water	1.00 ls			516.000	10,668	-	-	-	-	-	-	12,902.59	12,903		
Hauling	1.00 ls			516.000	11,897	-	-	-	-	3,870	-	15,856.68	15,857		
Portable Toilet Service	1.00 ls			1.000	192.000	4,734	-	-	8,500	-	-	8,500.00	8,500		
Demobilization	1.00 ls			1.000	192.000	4,734	-	-	-	3,688	-	8,621.95	8,622		
Construct Facilities						45,086	30,363	8,500	8,500	30,363	-		83,949		
XCONST FACILITY						45,086	30,363	8,500	8,500	30,363	-		83,949		
ZNON MANUAL	Field General Expens			Non Manual - Phase 3	1.00 ls	4,320.000	216,000	-	-	-	-	-	216,000.00	216,000	
		Field General Expens			4,320.00 hrs	216,000	216,000	216,000	-	-	-	216,000			
		ZNON MANUAL			4,320.00 hrs	216,000	216,000	216,000	-	-	-	216,000			

Estimate Totals

Labor	1,242,554	47,513,893	hrs
Material	1,180,686		
Subcontract	1,456,100		
Equipment	563,279	24,435,466	hrs
	4,415,812		
Small Tools Expense	19,437	0.450	\$/hr
Consumables & Expendables	41,082	4.000	%
Office Supplies & Expense	66,579	3.000	%
	4,482,791		
Excavation - Craft Labor	49,275	4.800	%
Excavation - Subcontract	36,403	2.500	%
Excavation - Perm Materials	13,098	1.100	%
Excavation - Small Tools	1,489	0.034	\$/hr
Excavation - Consumables	2,053	0.200	%
Excavation - Non-Manual Labor	7,560	3.500	%
Excavation - Office Supplies	432	0.200	%
	110,290	4,593,081	
Partner Insurance (FY04)	37,277	3.000	%
Partner Award Fee (FY04)	62,128	5.000	%
	99,405	4,692,486	
FRG Engineering - Phase 1	28,000		
FRG Engineering - Phase 2	443,000		
FRG Engineering - Phase 3	19,000		
Project Controls & Estimating	5,000		
	195,000	4,888,486	3.158 %
Phase 2 Surveying	20,000		
Phase 2 Environmental Permit	5,000		
	25,000	4,913,486	
Phase 3 Field QA/QC 1% Constr	47,000		
	47,000	4,960,486	
Rounding	38,514	5,000,000	
	38,514		
Total	5,000,000		



December 5, 2003

Mr. Ron Purkey
Tennessee Valley Authority
1101 Market Street, LP-2G
Chattanooga, TN 37402

Phone: (423) 751-4820
Fax: (423) 751-7094

Subject: **Report of Geotechnical Engineering Support Services
Ash Disposal Area
Kingston Fossil Plant
Kingston, Tennessee
MACTEC Project 3043031074/0001**

Dear Mr. Purkey:

MACTEC Engineering and Consulting, Inc., (MACTEC) is pleased to provide continuing geotechnical engineering support for the ash disposal studies at the Tennessee Valley Authority (TVA) Kingston Fossil Plant near Kingston, Tennessee.

Project Information

We have obtained project information through a series of site visits, meetings at the plant site, discussions with you and your staff, discussions with members of the TVA Ash Recovery Team, and discussions with plant personnel. We have also been provided geotechnical investigation reports that include field investigations and laboratory tests performed by Singleton Laboratories, TVA-prepared drawings, and slope stability analyses.

This letter addresses three sub-tasks we have been recently assigned:

1. Investigate the feasibility of installing a liner/leachate collection system on the existing dredge cells and provide a conceptual design including sketches and estimated material quantities. TVA will use the estimated material quantities to develop an order of magnitude cost estimate.

MACTEC Engineering and Consulting
1725 Louisville Drive • Knoxville, TN 37921-5904
865-588-8544 • Fax: 865-588-8026

TVA-00013873

2. Gather information concerning the feasibility of installing a Vibrated Beam Slurry Wall to cut off seepage through the existing dredge cells.
3. Perform a cursory review of slope stability analyses of the dredge cells recently made by members of your staff.

The following paragraphs address these sub-tasks.

Synthetic Liner and Underdrain

At TVA's request, we gathered information related to the use of a synthetic low-permeability liner and underdrain system to assist in determining if this concept might be a potential feasible remediation alternative. Essentially, this concept involves the placing of a low-permeability liner and underdrain system on the prepared surface of the existing Stage C3 cells to create a "bathtub" where future ash placement in the cells would not result in additional piezometric head on the lower dikes and subsequent additional seepage and piping. After evaluating technical literature, construction specifications, and project experience with the placement of such systems, we have determined the construction of this system would consist of the following:

- Grading of the existing surface cell ash to form a "saw-tooth" surface conceptually shown on the attached "Grading and Collector Plan"
- Construction of a 60 mil High Density Polyurethane (HDPE) synthetic liner on the graded surface
- Construction of the collector drain system conceptually shown on the attached figure
- Placement of a protective cover and drainage layer consisting of about 12 inches of free draining sand on the HDPE liner

Conclusion – The construction of the synthetic liner and collector drains would conceptually provide an option for continued use of the dredge cells and reduction of the potential for additional seepage and piping associated with the continued use of the cells. During our limited investigation we did develop concerns related to the feasibility of such a system. These concerns can be summarized as follows.

- Based upon conversations with designers and contractors familiar with synthetic liner systems, we understand that these liners are relatively commonly used for fly and bottom ash landfills. However, we could find no project experience where such a liner had been placed on the surface of an existing ash pond to form a low-permeability cut off for future cell operations.
- Differential settlement caused by compression of the underlying ash sediments as a result of the placement of new ash could result in loss of liner or collector drain integrity. Also, differential settlement could result in distortion of the "saw-tooth" graded surface such that drainage conditions were not favorable.
- Based upon MACTEC's project experience of high volume dredge effluent eroding non-cohesive materials, the placement of new ash materials into the lined cells by uncontrolled dredging might disturb the free draining sand protective cover/drainage layer overlaying the liner. Loss of liner integrity and/or the creation of unfavorable drainage conditions might necessitate the construction of a stilling basin or some other such special feature to slowly release new ash sediments onto the surface of the lined cell.
- Construction of the proposed system would require some relatively fine grading of the existing ash materials. The ability of these materials to be formed and maintained in the necessary shape prior to the construction of the liner is not known.
- Liner systems require seams between adjacent pieces of liner to be joined using one of several different processes. Based upon our investigation, each of these processes requires relatively clean liner material for proper bonding at the seam. Based on the history of "dusting" problems with ash, stringent QA/QC construction procedures and precautions would be required to assure the development of proper seams in the liner.
- Future operations, such as dredging or underdrain or outlet drain construction, would have to be performed in such a way as not to compromise the integrity of the synthetic liner.

The attached quantities were developed based upon the conceptual design shown on the attached figures. Not included in the attached quantities are design services, surveying services, or QA/QC services.

Table 1 Approximate Quantities			
Item	Cell 1	Cell 2	Total
60-mil HDPE Liner	1,000,000 SF	1,800,000 SF	2,800,000 SF (65± Acres)
SP Sand Protective Cover/Drainage Layer	37,000 CY	65,000 CY	102,000 CY
6-Inch Perforated Pipe	---	---	13,000 LF
8-Inch Perforated Pipe	---	---	285 LF
12-Inch Perforated Pipe	---	---	120 LF
6-Inch Non-Perforated Pipe	---	---	425 LF
12-Inch Non-Perforated Pipe	---	---	125 LF
6-Inch Liner Penetration Boots	---	---	8 Each
12-Inch Liner Penetration Boots	---	---	1 Each
Rip Rap	---	---	20 CY
1032 Crushed Stone	---	---	20 CY
1081 Crushed Stone	---	---	940 CY
Filter Fabric	---	---	90,000 SF
Anchor Trench Excavation	---	---	1,100 CY
Anchor Trench Compacted Backfill	---	---	1,100 CY
Ash Grading - Cut	---	---	55,000 CY
Ash Grading - Fill	---	---	58,500 CY
Prepared By <u>MH</u> Date <u>12/4/03</u> Checked By <u>AKL</u> Date <u>12/4/03</u>			

Vibrated Beam Slurry Wall

At TVA's request, we gathered information related to the Vibrated Beam Slurry Wall (VBSW) technique to determine if this concept might be a potential feasible remediation alternative. We discussed this concept with other Mactec employees with actual design and construction experience with this technique; contractors with installation experience; and the President and Vice President of the company that holds the patent rights, Slurry Systems Incorporated (SSI). We also obtained technical literature, construction specifications and project experience. Our limited investigation can be summarized as follows.

- MACTEC has successfully used this concept on several dams but typically to depths of 30 to 35 feet.
- One major commercial construction contractor indicated his experience was limited to a wall depth of about 55 feet maximum.

- We could find no project experience of a wall built through ash sediments although walls have been constructed on the outside of ash containment areas. SSI indicated they had successfully installed many walls in soils that had characteristics and behaviors similar to ash, i.e., wet, soft, fine grain sands and silts.
- SSI provided to us a listing of approximate 70 projects where they have installed VBSW. The majority of the listed projects were walls less than 50 feet in depth. However, there was one project with a wall of 82 feet and another at 100 feet depth.
- SSI indicated a wall with a maximum depth of 95 feet is currently being constructed in the northwest.
- SSI also indicated that most walls have been constructed with active seepage flow similar to the recent seepage at the ash cells at Kingston.
- MACTEC evaluated an existing soils investigation report (Singleton Laboratory Report dated September 29, 1994) supplied by TVA in an attempt to determine the elevation of an in-situ impervious soil to key the bottom of the slurry wall into to establish positive cutoff of flow. The widely spaced borings in this report did not provide sufficient information to confidently establish a required wall depth to ensure a positive cutoff. Based upon extremely limited information, it is believed a wall depth of roughly 90 feet would be required. As noted previously, there are very few existing VBSW that have been installed this deep. It should be noted that no boring information exists along the west side of the cells (along Swan Pond Road) and only one boring along the south side dike, i.e., only one boring in over 3,000 feet length of dike.

Conclusion – A VBSW may be capable of successfully cutting off the existing and future seepage from the dredge cells. However, we have some concerns about this technique before we could make a strong recommendation for its use. These concerns can be summarized as follows.

- We believe that additional borings are necessary to confidently establish a profile of impervious soil beneath the ash to know with some certainty the required depth of slurry wall.
- We cannot find an existing project where a VBSW has been constructed in ash sediments.
- The wall depths anticipated for the Kingston dredge cells would be approaching the upper limits of depths we have been able to determine for existing projects.

We have learned that VBSW cost approximately \$2 to \$4 per square foot to install depending upon the wall depth, i.e., costs increase with depth. Roughly 7,250 linear feet of wall would be required to completely encircle the existing Stage C perimeter dike. Assuming a required wall depth of about 90 feet and a cost of \$5 per square foot due to the significant depth, a completed VBSW would cost roughly \$3,300,000. This cost would not include a boring program to confidently establish a design wall depth.

Slope Stability Analyses

At TVA's request, we reviewed the slope stability analyses performed by TVA on the ash disposal cells. The information provided to us included slope stability input files, as well as corresponding plots showing slope geometries, material types and cross section zonings with assumed densities and shear strength properties, phreatic surfaces, computer generated failure surfaces, and associated factors of safety. The findings of our cursory review can be summarized as follows.

- The provided information included four sets of analyses. The first analysis included an "as is" or existing geometry with an approximate maximum elevation of 810 feet msl. This analysis investigated the short-term condition (end of construction). The minimum factor of safety was 1.6.
- The second analysis included a projected future geometry with a maximum elevation of 841 feet msl. This analysis investigated both the short-term and long-term static conditions. The minimum factors of safety for the short-term and long-term conditions were 0.9 and 1.2, respectively.
- The third analysis included the projected future geometry with a maximum elevation of 841 feet msl. This analysis incorporated the implementation of a hypothesized bentonite slurry cutoff wall which altered the phreatic surface. The factors of safety for the short-term and long-term conditions were 1.0 and 1.4, respectively.
- The fourth analysis included the projected future geometry with a maximum elevation of 841 feet msl. This analysis incorporated a slightly modified fly ash geometry and higher shear strength properties. The factors of safety for the short-term and long-term conditions were 2.9 and 2.3, respectively.

Conclusion - It was observed that the shear strength properties of the various materials (earth dike, residual soil, bottom ash, and fly ash) used in the slope stability analysis were exactly as reported in soils investigation reports (Singleton Laboratory Report(s) dated September 29, 1994 and May 31, 1995). These reports were supplied to us by TVA. Although the shear strength properties used in the analyses were obtained directly from laboratory testing, some of the values tend to be non-

December 5, 2003

conservative based on MACTEC's experience, e.g., angle of internal friction of 35 to 38 degrees used for fly ash. Additionally, there is some basis for considering raising parameters for other zones. Further analyses are recommended using more reasonable shear strength property values. Also, the analyses involving the projected future geometry produced short-term and long-term factors of safety of less than 1.5. Further stability analyses and evaluation of existing and proposed construction is recommended.



Mr. Purkey, we appreciate this opportunity to provide these services to TVA. If you have any questions regarding this information, please contact Carl Tockstein, Matt Haston, or Sam Stone at (865) 588-8544.

Sincerely,

MACTEC ENGINEERING AND CONSULTING, INC.

Matthew B. Haston by sjm
Matthew B. Haston, P.E.
Senior Engineer
with permission

MBH/SDS:sjm

cc: Mr. Lynn Petty
TVA Chattanooga

Samuel D. Stone
Samuel D. Stone, P.E.
Senior Principal Engineer



Electronic AutoCAD File Attachments on CD: DREDGECELLS_SITEPLAN
DREDGECELLS_SECT A & B

KIF HAUL ASH FOR BUFFER DIKE COST R1.xls

STAGE	YEAR	QUANTITY	UNIT	COST/CY	ESCL FACTOR	\$AMOUNT	NPV
	2003		CY	\$ 5.00			
D1	2004	198,800	CY	\$ 5.00	1.030	1,023,820	\$890,278
D2	2005	103,400	CY	\$ 5.00	1.061	548,485	\$421,912
D3	2006	122,200	CY	\$ 5.00	1.093	667,656	\$460,453
E1	2008	92,600	CY	\$ 5.00	1.159	536,744	\$306,711
E2	2010	98,900	CY	\$ 5.00	1.230	608,173	\$296,670
E4	2011	116,800	CY	\$ 5.00	1.267	739,794	\$336,270
						\$4,124,672	\$2,712,293

Note: Estimated escalation is based on 3% per year for combined labor and equipment.

**KINGSTON FOSSIL PLANT
INSTALL 60 MIL HDPE LINER ON SWAN POND
ROAD SIDE OF EXISTING DREDGE CELL**

Estimate Number 04101 Option: 0 PCN Number:
 Plant: KIF Revision: 0 Estimate Type: Conceptual
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 30%
 Requesting Engr: Harold L. Petty Phase: 1 Estimate Issue Date 12/15/2003

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$7,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$7,000</u>
<u>Phase II</u>		
Engineering		\$33,000
Long Lead Procurement		\$0
Partner (Non-Manual)		
Other / Surveying & Envr Permitting		\$10,000
<u>Total Phase II</u>		<u>\$43,000</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$0
Labor (T&L)	2,571.00	\$62,230
Labor (Non-Manual)	260.00	\$13,000
Equipment		\$34,645
Subcontracts		\$483,645
Partner Fee		\$3,762
Partner Insurance		\$2,257
Escalation		\$15,770
Construction Risk Dollars		\$0
Other		\$4,036
Total Construction Cost		\$619,345
Engineering		\$6,421
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$17,234
Other / Field QA/QC Services		\$7,000
<u>Total Phase III</u>		<u>\$650,000</u>
<u>All Phases</u>		
Construction Partner	2,831.00	\$619,345
Long Lead Procurement		\$0
Engineering		\$46,421
Other / Other Organizations		\$17,000
Total Risk Dollars		\$17,234
<u>Total Project Costs</u>	<u>2,831.00</u>	<u>\$700,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
INSTALL 60 MIL HDPE LINER ON SWAN POND
ROAD SIDE OF EXISTING DREDGE CELL**

Project name KIF/04/01/DREDGE CELLS

Estimator C. L. Toney

Labor rate table KIF 40 2003

Equipment rate table TVA Equipment

Project Dredge Cell
 Plant KIF
 Estimate # 04101
 Requesting Engr Harold L. Peety
 Ord'n 0
 Revision 0
 Phase 1
 Estimate Type Conceptual
 Estimate Accuracy +/- 30%
 Est. Issue Date 12/15/2003
 Funding Type O & M

Notes
 Installation of a liner on Swan Pond road side with 1 foot of bottom ash on the existing dredge cells.

This is a conceptual cost estimate based on input provided by FE civil site group.

All costs are estimated in 2004 dollars.

Estimate assumes a 3 month construction duration.

Estimate assumes engineering dollars at +/-7% of construction total.

Estimate includes an allowance for surveying services, environmental permitting and field QA/QC services.

Report format
 Sorted by 'Location/Activity'
 'Detail' summary

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	City/State/Unit	Equip Amount	Other Amount	Total Cost/Unit	Total Amount	
DREDGE CELL	Install Liner	Anchor Trench Excavation	600.00 cy	0.200	120.00 mh	2,669	-	-	1,600	-	7.00	4,199	
		HDPE Liner, 60-Mil (Including Penetration Boots)	875,000.00 sf	-	-	-	482,625	-	-	-	0.72	482,625	
		Anchor Trench Compacted Backfill	600.00 cy	0.300	180.00 mh	4,048	-	-	-	4,367	-	14.03	8,415
		Load, Haul, Dump Bottom Ash And Spread	28,000.00 cy	966.667	30.00 cd	47,340	-	-	-	24,300	-	2.47	71,640
		Install Liner				2,220.00 hrs	54,087	482,625	0	30,167	-		566,879
	DREDGE CELL				2,220.00 hrs	54,087	482,625	0	30,167	-		566,879	
XCONST FACILITY	Construct Facilities	Mobilization	1.00 ls	64,000	64.00 mh	1,576	-	-	810	-	2,387.98	2,388	
		Admin Time (Employee proc, etc)	1.00 ls	64,000	64.00 mh	1,576	-	-	-	-	-	1,577.98	1,578
		Maint Road, Buildings & Facilities	1.00 ls	43,000	43.00 mh	829	-	-	-	1,720	-	2,549.04	2,549
		Drinking Water	1.00 ls	58,000	58.00 mh	1,233	-	-	-	218	-	1,450.29	1,450
		Hauling	1.00 ls	58,000	58.00 mh	1,233	-	-	-	435	-	1,782.34	1,782
		Portable Toilet Service	1.00 ls	58,000	58.00 mh	1,233	-	-	-	1,020	-	1,020.00	1,020
		Demobilization	1.00 ls	64,000	64.00 mh	1,576	-	-	-	1,296	-	2,873.88	2,874
		Construct Facilities				351.00 hrs	8,143	1,020	-	4,479	-		13,642
		XCONST FACILITY				351.00 hrs	8,143	1,020	-	4,479	-		13,642
			Field General Expens				260.000	13,000	-	-	-	-	13,000.00
	Field General Expens				260.00 hrs	13,000	-	-	-	-	13,000	13,000	
	ZNON MANUAL				260.00 hrs	13,000	-	-	-	-	13,000	13,000	

Estimate Totals

Labor	75,230	2,830,989	hrs
Material	0		
Subcontract	483,645		
Equipment	<u>34,925</u>	1,738,000	hrs
	993,920	593,520	
Small Tools Expense	1,157	0.460	\$/hr
Consumables & Expensables	2,489	4,000	%
Office Supplies & Expense	<u>390</u>	3,000	%
	4,036	597,556	
Excavation - Craft Labor	2,987	4,900	%
Excavation - Subcontract	12,091	2,500	%
Excavation - Perm Materials		1,100	%
Excavation - Small Tools	87	0.034	\$/hr
Excavation - Consumables	124	0.200	%
Excavation - Non-Manual Labor	455	3,500	%
Excavation - Office Supplies	<u>29</u>	0.200	%
	15,770	813,326	
Partner Insurance (FY04)	2,257	3,000	%
Partner Award Fee (FY04)	<u>3,762</u>	5,000	%
	6,019	819,345	
PRG Engineering - Phase 1	7,000		
PRG Engineering - Phase 2	33,000		
PRG Engineering - Phase 3	5,000		
Project Controls & Estimating	<u>1,421</u>		
	46,421	665,766	3.158 %
Phase 2 Surveying	5,000		
Phase 2 Environmental Permit	<u>5,000</u>	675,766	
	10,000		
Phase 3 Field QA/QC 1% Constr	<u>7,000</u>	682,766	
	7,000		
Rounding	<u>17,234</u>	700,000	
	17,234		
Total	700,000	700,000	

**KINGSTON FOSSIL PLANT
INSTALL 60 MIL HDPE LINER AROUND
PERIMETER OF EXISTING DREDGE CELL**

Estimate Number 04102 Option: 0 PCN Number:
 Plant: KIF Revision: 0 Estimate Type: Conceptual
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 30%
 Requesting Engr: Harold L. Petty Phase: 1 Estimate Issue Date 12/15/2003

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$16,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$16,000</u>
<u>Phase II</u>		
Engineering		\$77,000
Long Lead Procurement		\$0
Partner (Non-Manual)		
Other / Surveying & Envr Permitting		\$15,000
<u>Total Phase II</u>		<u>\$92,000</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$0
Labor (T&L)	5,827.14	\$141,019
Labor (Non-Manual)	580.00	\$29,000
Equipment		\$78,905
Subcontracts		\$1,164,970
Partner Fee		\$8,501
Partner Insurance		\$5,101
Escalation		\$37,446
Construction Risk Dollars		\$0
Other		\$9,133
Total Construction Cost		\$1,474,075
Engineering		\$13,253
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$9,672
Other / Field QA/QC Services		\$15,000
<u>Total Phase III</u>		<u>\$1,512,000</u>
<u>All Phases</u>		
Construction Partner	6,407.14	\$1,474,075
Long Lead Procurement		\$0
Engineering		\$106,253
Other / Other Organizations		\$30,000
Total Risk Dollars		\$9,672
<u>Total Project Costs</u>	<u>6,407.14</u>	<u>\$1,620,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
INSTALL 60 MIL HDPE LINER AROUND
PERIMETER OF EXISTING DREDGE CELL**

Project name KIF04102/DREDGE CELLS

Estimator C. L. Toney

Labor rate table KIF 40 2003

Equipment rate table TVA Equipment

Dredge Cell

KIF

04/02

Requesting Engr Harold L. Petty

Option 0

Revision 0

Phase 1

Estimate Type Conceptual

Estimate Accuracy +/- 30%

Est. Issue Date 12/15/2003

Funding Type O & M

Notes
Installation of a liner around perimeter with 1 foot of bottom ash on the existing dredge cells.

This is a conceptual cost estimate based on input provided by FE civil site group.

All costs are estimated in 2004 dollars.

Estimate assumes a 6.5 month construction duration.

Estimate assumes engineering dollars at +/-7% of construction total.

Estimate includes an allowance for surveying services, environmental permitting and field QA/QC services.

Report format
Sorted by Location/Activity
Detail summary

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount	
DREDGE CELL	Install Liner	Anchor Trench Excavation	1,350.00 cy	0.200	270.00 mh	6,072	-	-	3,375	-	7.00	9,447	
		HDPE Liner, 60-Mil (Including Penetration Boots)	1,626,000.00 sf	-	-	-	-	1,162,500	-	-	-	0.72	1,162,500
		Anchor Trench Compacted Backfill	1,350.00 cy	0.300	405.00 mh	9,108	-	-	9,825	-	-	14.03	18,854
		Lead, Haul, Dump Bottom Ash And Spread	69,300.00 cy	968.887	71,889 cd	113,128	128,307	-	-	58,069	-	2.47	171,195
		Install Liner				5,263.14 hrs	128,307	0	1,162,500	71,269	-		1,362,166
DREDGE CELL													
XCONST FACILITY	Construct Facilities	Mobilization	1.00 ls	64,000	64.00 mh	1,578	-	-	810	-	2,387.98	2,388	
		Admin Time (Employee proc. etc)	1.00 ls	64,000	64.00 mh	1,578	-	-	-	-	-	1,577.98	1,578
		Maint Road, Buildings & Facilities	1.00 ls	100,000	100.00 mh	1,928	-	-	-	4,000	-	5,928.00	5,928
		Drinking Water	1.00 ls	138,000	138.00 mh	2,891	-	-	-	510	-	3,400.88	3,401
		Hauling	1.00 ls	138,000	138.00 mh	3,159	-	-	-	1,020	-	4,179.28	4,179
		Portable Toilet Service	1.00 ls	138,000	138.00 mh	3,159	-	-	-	2,380	-	2,380.00	2,380
		Demobilization	1.00 ls	64,000	64.00 mh	1,578	-	-	-	1,296	-	2,873.98	2,874
		Construct Facilities				564.00 hrs	12,712	-	-	2,380	-		22,128
		XCONST FACILITY				564.00 hrs	12,712	-	-	7,636	-		22,728
		ZNON MANUAL											
ZNON MANUAL	Field General Expens	Non Manual - Phase 3	1.00 ls	580,000	580.00 mh	29,000	-	-	-	-	29,000.00	29,000	
		Field General Expens				29,000	-	-	-	-	-	29,000	
ZNON MANUAL													

Estimate Totals

Labor	170,019	6,407,136	hrs
Material	0		
Subcontract	1,164,970		
Equipment	<u>78,895</u>	3,875,585	hrs
	1,413,894	1,413,894	
Small Tools Expense	2,622	0.450	\$/hr
Consumables & Expendables	5,641	4.000	%
Office Supplies & Expense	<u>870</u>	3.000	%
	9,133	1,423,027	
Escalation - Craft Labor	6,769	4.800	%
Escalation - Subcontract	29,124	2.500	%
Escalation - Perm Materials		1.100	%
Escalation - Small Tools	198	0.034	\$/hr
Escalation - Consumables	282	0.200	%
Escalation - Non-Manual Labor	1,015	3.500	%
Escalation - Office Supplies	<u>59</u>	0.200	%
	37,446	1,450,473	
Partner Insurance (FY04)	5,101	3.000	%
Partner Award Fee (FY04)	<u>8,501</u>	5.000	%
	13,602	1,474,075	
FRG Engineering - Phase 1	16,000		
FRG Engineering - Phase 2	7,000		
FRG Engineering - Phase 3	10,000		
Project Controls & Estimating	<u>3,233</u>	3.158	%
	106,233	1,580,328	
Phase 2 Surveying	10,000		
Phase 2 Environmental Permit	<u>5,000</u>	1,595,328	
	15,000		
Phase 3 Field CAQC 1% Constr	<u>15,000</u>	1,610,328	
	15,000		
Rounding	<u>9,672</u>	1,620,000	
	9,672		
Total	1,620,000		