

# APPENDIX D

## Hydrogeologic Evaluation of Ash Pond Area

TENNESSEE VALLEY AUTHORITY  
RESOURCE GROUP, ENGINEERING SERVICES  
NORRIS ENGINEERING LABORATORY

HYDROGEOLOGIC EVALUATION OF ASH POND AREA  
KINGSTON FOSSIL PLANT

Report No. WR28-2-36-124

Prepared by  
J. Mark Boggs, P.G. (TN #3671)  
Andrew J. Danzig  
and  
Jami A. Schroeder

Norris, Tennessee  
June 1995

## EXECUTIVE SUMMARY

A hydrogeological investigation was conducted to evaluate the long-term effects of the ash pond area on local groundwater and surface water resources following the expected closure of the facility in the year 2015. The study examined local hydrogeologic conditions, groundwater quality, and groundwater use within a two-mile radius of the site. Hydrogeologic and water quality data were primarily derived from previous groundwater investigations at the plant site.

The ash pond area occupies a peninsula bounded by Watts Bar Reservoir on the north and east sides, and by Pine Ridge on the west side. Total area of the facility is approximately 244 acres. At closure, the surface of the area will be graded to promote runoff. A 1-ft surface cap of low permeability ( $1 \times 10^{-7}$  cm/s) clay will be constructed over the entire surface area to minimize surface infiltration. A 1-ft layer of vegetated top soil will then be placed over the clay cap to prevent erosion.

The area is underlain by shale bedrock of the Conasauga Group and the Rome formation. A mantle of predominantly alluvial soils consisting of clay, silt, and sand with occasional gravel lies above bedrock. Thickness of the alluvium is highly variable, ranging from about 5 to 65 ft. Ash and ash-soil fill materials ranging up to 70 ft in thickness are present above the alluvium. Ash deposits are composed almost entirely of fly ash; bottom ash is estimated to comprise less than ten percent of the ash fill. The water table currently lies within the ash deposits in the ash pond area, and is expected to lie within the ash after facility closure. Groundwater movement at the site generally follows topography with groundwater flowing eastward and southeastward from Pine Ridge toward the reservoir. Groundwater originating on, or flowing beneath, the ash pond area ultimately discharges to the reservoir without traversing private property.

Background groundwater quality as measured in two up-gradient monitoring wells is generally characterized by near-neutral pH, low TDS, and ionic distributions dominated by calcium, magnesium, and carbonate. No exceedances of primary MCLs have been observed in background wells, although secondary MCLs have been exceeded for aluminum, iron, and manganese in some background samples. Groundwater in the immediate vicinity of the ash pond area is affected by ash leachate, and typically exhibits acidic pH, high levels of iron and manganese, and moderate to high levels of sulfate and TDS. Evidence suggests that pyrite oxidation contributes to the high dissolved iron concentrations observed in groundwater. The presence of heavy metals at levels above MCLs is rare. Only arsenic consistently exceeded its MCL in several shallow wells screened in or near ash deposits. Sampling results from depth-staged monitoring wells located around the perimeter of the facility indicate that the effects of ash leachate on groundwater quality are limited to shallow depths.

EPA's HELP2 code [Schroeder et al., 1989] was used to estimate the overall water balance, including leachate production, for the ash fill during a 30-yr period following closure. Results indicated that leachate discharge gradually increases during the first 10 years of the post-closure period reaching a quasi-steady rate of approximately 6.3 million cfy (cubic feet per year)

thereafter. The overall water balance for the ash fill in terms of percent of total incident precipitation was as follows: surface runoff, 18.8 percent; evapotranspiration, 64.1 percent; lateral seepage from top-soil layer, 1.0 percent; net change in water storage, 2.3 percent; and leachate reaching the water table, 13.8 percent. To assess the impact of ash leachate on reservoir water quality, a dilution ratio was estimated by comparing the predicted average leachate flowrate to the mean flow in the reservoir just downstream of the plant outfall. Full mixing of leachate influx and reservoir water was assumed. The mean flow in the Clinch River immediately below the plant outfall is estimated to be approximately 7,000 cfs. The resulting dilution ratio for the quasi-steady leachate discharge predicted during the last 20 years of the water budget simulation of 6.3 million cfy (0.20 cfs) is 1:35,000.

Incremental increases in chemical concentrations in Watts Bar Reservoir due to the influx of ash-leachate effected groundwater were estimated by multiplying the dilution ratio by the mean parameter concentrations. Groundwater quality data for wells located on the perimeter of the disposal area which exhibited exceedances for primary and secondary drinking water standards were selected for the calculation. Parameters exceeding drinking water MCLs included arsenic, nickel, iron, manganese, sulfate, and TDS. Predicted incremental increases in reservoir concentrations were negligible for all constituents except iron which showed a slight increase of 29  $\mu\text{g}/\text{L}$ . However, the iron present in groundwater appears to be in a reduced state, and on entering the oxidizing environment of the reservoir is expected to precipitate out of solution.

A survey of water use in the site vicinity in March 1995 identified six residential wells located within approximately one mile of the center of the ash pond area. Two of these wells lie north of Swan Creek embayment and are hydrologically isolated from the site. The remaining four wells lie up-gradient of the Kingston reservation. There is no evidence that pumping from these wells or any of the more distant wells in the site vicinity has induced off-site ash leachate movement from the ash pond area. No adverse off-site groundwater impacts associated with the ash pond are indicated under present conditions or expected under post-closure conditions.

## TABLE OF CONTENTS

	Page
Executive Summary . . . . .	i
List of Figures . . . . .	iv
List of Tables . . . . .	iv
1. Introduction . . . . .	1
Background . . . . .	1
Purpose and Scope . . . . .	1
Previous Investigations . . . . .	1
2. Site Hydrogeology . . . . .	3
Geology . . . . .	3
Soils and Ash Fill . . . . .	5
Hydraulic Properties . . . . .	5
Groundwater Levels and Movement . . . . .	10
Precipitation and Recharge . . . . .	10
3. Groundwater Quality . . . . .	10
Methods and Approach . . . . .	10
Background Water Quality . . . . .	14
Ash Pond Area Groundwater Quality . . . . .	14
Ash Leachate Composition . . . . .	38
Summary . . . . .	39
4. Local Groundwater Use . . . . .	39
5. Evaluation of Potential Water Quality Impacts . . . . .	42
Post-Closure Ash Fill Water Budget Analysis . . . . .	42
Potential Impacts to Reservoir Water Quality . . . . .	44
Potential Impacts to Groundwater Users . . . . .	47
6. References . . . . .	49
Appendix I. Lithologic Logs . . . . .	50
Appendix II. Installation Records for Monitoring Wells 9A Through 20 . . . . .	102
Appendix III. Groundwater Quality Data . . . . .	123

## TABLE OF CONTENTS

(continued)

### LIST OF FIGURES

	Page
1-1. Site Location Map Showing Monitoring Well and Corehole Locations . . . . .	2
2-1. Site Geologic Map . . . . .	4
2-2. Top-of-Rock Elevation Contour Map . . . . .	6
2-3. Hydrogeologic Sections Through Ash Pond Area . . . . .	7
2-4. Soil Thickness Contour Map . . . . .	8
2-5. Water Table Contour Map . . . . .	11
2-6. Groundwater Hydrographs . . . . .	12
3-1. Ionic Distributions for Ash Pond Area . . . . .	19
3-2. Ionic Distributions for Metal Cleaning Pond and Coal Yard Areas . . . . .	20
3-3. Key to Box and Whiskers Plots . . . . .	21
3-4. Arsenic Groundwater Data Through April 1995 . . . . .	22
3-5. Barium Groundwater Data Through April 1995 . . . . .	23
3-6. Boron Groundwater Data Through April 1995 . . . . .	24
3-7. Calcium Groundwater Data Through April 1995 . . . . .	25
3-8. Iron Groundwater Data Through April 1995 . . . . .	26
3-9. Lead Groundwater Data Through April 1995 . . . . .	27
3-10. Manganese Groundwater Data Through April 1995 . . . . .	28
3-11. pH Groundwater Data Through April 1995 . . . . .	29
3-12. Strontium Groundwater Data Through April 1995 . . . . .	30
3-13. Sulfate Groundwater Data Through April 1995 . . . . .	31
3-14. Total Dissolved Solids Groundwater Data Through April 1995 . . . . .	32
3-15. Total Organic Carbon Groundwater Data Through April 1995 . . . . .	33
4-1. Wells and Springs Within Two Miles of Ash Pond Area . . . . .	40
5-1. Subregion Areas and Profiles Used in HELP2 Simulations . . . . .	43
5-2. Predicted Leachate Discharge From Ash Pond Area During 30-Year Post-Closure Period . . . . .	45
5-3. Locations of Residential Wells in Relation of Groundwater Flow Patterns in Ash Pond Area . . . . .	48

### LIST OF TABLES

2-1. Summary of Hydraulic Conductivity Data . . . . .	9
3-1. Maximum Contaminant Levels for Drinking Water - Inorganics . . . . .	15

## TABLE OF CONTENTS

(continued)

	Page
3-2. Comparison of Groundwater Data With Primary Water Quality Standards - Number of Samples Exceeding an MCL/Total Number of Samples, For Each Parameter, For Each Well . . . . .	16
3-3. Comparison of Groundwater Data With Secondary Water Quality Standards - Number of Samples Exceeding an MCL/Total Number of Samples, For Each Parameter, For Each Well . . . . .	17
3-4. Unfiltered (Total Concentration) vs. Filtered (Dissolved Concentration) Samples Collected on December 7-10, 1992 . . . . .	18
3-5. Fly Ash Leachate Characteristics Based on EPRI Estimates and TVA Data . . . . .	34
3-6. Indications of Ash Leachate in Wells in the Active Ash Pond Area at KIF . . . . .	35
3-7. Summary of Analyses Indicating Ash Leachate Effects at Kingston Fossil Plant Through December 1994 . . . . .	36
4-1. List of Wells, Springs, and Water Supplies in Site Vicinity . . . . .	41
5-1. Material Properties Used in the HELP2 Simulations . . . . .	44
5-2. Predicted Increases in Arsenic, Nickel, Iron, Manganese, Sulfate, and TDS Due to Ash Leachate Influx . . . . .	46

# HYDROGEOLOGIC EVALUATION OF ASH POND AREA KINGSTON FOSSIL PLANT

## 1. INTRODUCTION

### Background

The ash pond area at Kingston Fossil Plant is located in Roane County, Tennessee, on Watts Bar Lake (Emory River Mile 2) as shown on Figure 1-1. The ash pond area consists of the active ash pond, three dredge cells, and a stilling pool. Total area of the facility is approximately 244 acres. Final closure of the disposal area is planned for the year 2015. At closure the surface of the area will be graded to promote runoff. A 1-ft surface cap of low permeability ( $1 \times 10^{-7}$  cm/s) clay will be constructed over the entire surface area to minimize surface infiltration. Then a 1-ft layer of vegetated top soil will be placed over the clay cap to prevent erosion.

### Purpose and Scope

A hydrogeological investigation was conducted to evaluate the long-term effects of the ash pond area on local groundwater and surface water resources following facility closure. The study was initiated with an examination of local hydrogeologic conditions, groundwater quality, and groundwater use in the site vicinity. Hydrogeologic and water quality data were primarily derived from previous groundwater investigations at the plant site. Local groundwater use was established by a survey of residents within a two-mile radius of the disposal site. A water budget simulation of the closed facility was performed to quantify ash leachate production rates during a 30-year post-closure period. The ultimate impact of the closed facility was evaluated using the predicted leachate discharge in conjunction with a knowledge of leachate chemical characteristics and groundwater flow patterns in the site vicinity.

### Previous Investigations

The hydrogeologic data and groundwater quality data used in the present investigation are based largely on three previous investigations at the Kingston plant site. The first was an EPA-sponsored study by Milligan and Ruane [1980] to examine the effects of coal ash leachate on groundwater quality. This study was initiated in 1976 with core sampling and monitoring well construction at eight sites, J1 through J8 (Figure 1-1). (Note that the "J" well prefix was dropped in later investigations and does not appear on figure well labels in the present report.) Soil samples were collected using a 2-inch diameter split-spoon sampler through a 12-inch outer diameter hollow-stem auger. Fourteen, four-inch diameter PVC wells, screened over the lower 1.5 ft, were installed through the auger following core sampling. Wells were installed either singly or in staged multiple-well clusters. Lithologic logs for these wells are presented in Appendix I. In addition, laboratory permeameter measurements of the horizontal and vertical components of hydraulic conductivity were performed on selected core samples.






Figure 1-1. Site Location Map Showing Monitoring Well and Corehole Locations

The second investigation consisted of a site-wide assessment of groundwater conditions at the Kingston reservation [Velasco and Bohac, 1991]. Single-well or multiple-well clusters were installed at eight additional sites (sites 9 through 16) in 1988 as part of the investigation. Wells were constructed with 2-inch PVC casing and were screened over the lower 10 ft. Lithologic logs for these wells are given in Appendix I and well construction diagrams are presented in Appendix II. These wells and those installed in 1976 were sampled six times between 1988 and 1990 to examine spatial and temporal trends in groundwater quality at the plant site. Constant-rate injection tests were performed at eight wells to determine bulk hydraulic conductivities of the overburden and shallow bedrock materials. These data were used in development of a groundwater flow model of the site. In June 1992, the original casings of the three wells at site 5 were removed and replaced with near fully-screened PVC casing thereby rendering these wells unsuitable for sampling. Four additional wells (17-20) were installed across the dike at site 5 in July 1992.

A third investigation was conducted by Singleton Laboratories [1994] in the dredge cell area which provided additional useful subsurface information. Two-inch split- spoon and three-inch Shelby tube samples were collected at ten sites for laboratory geotechnical testing. Top-of-rock and groundwater level elevations were established at each site. Appendix I contains lithologic logs for the ten coreholes.

## 2. SITE HYDROGEOLOGY

### Geology

The Kingston plant site is located in the Valley and Ridge physiographic province of the Appalachian Highlands region. This region is characterized by a sequence of long, narrow ridges and valleys trending northeast-southwest. In general, ridges are formed by relatively resistant sandstone, limestone, and dolomite units while the valleys are underlain by soluble limestones and easily weathered shales. The controlling structural feature of the site is a series of northeast-striking thrust faults which have forced older Cambrian and Ordovician rocks over younger units. Bedrock dips southeast at angles ranging from a few degrees to about 90 degrees [Velasco and Bohac, 1991].

The site geologic map shown on Figure 2-1 indicates that the entire ash pond area is underlain by the Conasauga Group (middle to upper Cambrian age) with exception of the northern tip of the area where the Rome formation (lower Cambrian age) is present. Specific geologic units within the Conasauga Group represented at the site include the Maynardville, Nolichucky, Maryville, Rogersville, Rutledge, and Pumpkin Valley formations. These formations are locally of low water-producing capacity, and predominantly consist of shale with interbedded siltstones, limestones, and conglomerates [Velasco and Bohac, 1991]. Total thickness of the Conasauga Group beneath the site is unknown but is estimated to be approximately 1500 ft [Harris and Foxx, 1980]. Pine Ridge, which borders the ash pond area to the northwest, is underlain by interbedded shale, sandstone, and siltstone of the Rome formation.




Figure 2-1. Site Geologic Map

The elevation of the top-of-rock directly beneath the ash pond area is relatively uniform, varying from approximately 700 to 715 ft-MSL (Figure 2-2). Outside this area the bedrock surface rises steeply to the west and southwest. The lower bedrock terrace corresponding to the disposal area apparently represents an erosion surface associated with the ancestral Emory River. The upper few feet of bedrock generally consists of a weathered fissile shale with occasional limestone fragments.

### **Soils and Ash Fill**

A mantle of predominantly alluvial soils generally lies above bedrock in the ash pond area as indicated in the two hydrogeologic profiles presented on Figure 2-3 and the soil isopachous map of Figure 2-4. Soil thickness is highly variable, ranging from about 5 ft along a portion of the northern perimeter of the site to a maximum of 65 ft on the western boundary. The alluvial deposits are unconsolidated and lenticular, and consist of clay, silt, and sand with occasional gravel. A thin layer of residuum is occasionally present directly above bedrock. The residuum is composed of clay and silt with weathered shale fragments.

The ash and ash-soil fill materials present above the alluvium/bedrock range up to 70 ft in thickness. Ash deposits consist almost entirely of fly ash; bottom ash is estimated to comprise less than ten percent of the ash fill. Ash pond dikes are constructed of mixtures of fly ash, bottom ash, clay, and silt. As indicated on Figure 2-3 the water table generally lies within the ash deposits.

### **Hydraulic Properties**

Field and laboratory measurements of hydraulic conductivity for soil, ash, and shallow bedrock were performed during previous plant site investigations. A summary of these data are given in Table 2-1. In general, the field conductivity measurements are about an order of magnitude larger than the laboratory estimates for the same material. Such differences between field and laboratory measures are commonly observed and are attributed to differences in measurement scale.

The upper weathered bedrock zone exhibited the highest field-measured horizontal hydraulic conductivity ( $K_h$ ) with values averaging about  $2 \times 10^{-5}$  cm/s. Field estimates of  $K_h$  for the "silty clay" alluvium averaged approximately  $7 \times 10^{-6}$  cm/s. A conductivity of approximately  $2 \times 10^{-5}$  cm/s was indicated for the permeameter-tested fly ash sample.




Figure 2-2. Top-of-Rock Elevation Contour Map




Figure 2-3. Hydrogeologic Sections Through Ash Pond Area




Figure 2-4. Soil Thickness Contour Map

TABLE 2-1

Summary of Hydraulic Conductivity Data

Well No.	Laboratory Permeameter Tests				Field Tests			
	Sample Elevation (ft-MSL)	Kh (cm/s)	Kv (cm/s)	Material Type	Screen Elevation Interval (ft-MSL)		Kh (cm/s)	Material Type
					Top	Bottom		
2	715.6	7.4E-08	6.3E-08	silty clay	723.4	721.9	9.1E-06	silty clay
4	721.4	8.8E-06	3.1E-06	sand	--	--	--	--
	728.9	6.6E-08	2.8E-07	silty clay	--	--	--	--
4B	--	--	--	--	716.3	714.8	6.1E-06	silty clay
5	731.4	2.8E-07	4.0E-07	silty clay	725.4	723.9	9.1E-06	silty clay
6	702.4	1.3E-06	1.4E-06	weathered shale	--	--	--	--
	725.7	2.5E-06	4.4E-07	silty clay	--	--	--	--
9B	--	--	--	--	697.2	687.2	6.1E-06	shale
13A	--	--	--	--	712.6	702.6	3.0E-06	silty clay
13B	--	--	--	--	697.4	685.4	2.1E-05	shale w/ ls. and ss
16A	--	--	--	--	777.9	767.9	3.0E-05	shale
--	(surface sample)	2.1E-05	2.1E-05	fly ash	--	--	--	--

References: soil permeameter test results reported by Milligan and Ruane [1980]; fly ash data from Young et al. [1993], Appendix A; all field test data from Velasco and Bohac [1991].



## Groundwater Levels and Movement

Groundwater movement at the plant site is generally eastward and southeastward from Pine Ridge toward the reservoir as indicated by the water table contour map shown on Figure 2-5. Because the ash pond area occupies a peninsula bounded on two sides by the reservoir, groundwater originating on or upgradient of the disposal area ultimately discharges to the reservoir. Although potentiometric head data for the interior of the disposal area are limited, it is probable that the continuous recharge by ash sluice water in the active ash pond produces local on-site mounding of the water table. Similarly, temporary local mounding of the water table may occur during periodic sluicing/dredging of ash to the three dredge cells.

It is difficult to discern any natural seasonal trends in groundwater levels in the monitoring well hydrographs shown on Figure 2-6. This may be partially due to the infrequency of the measurements, i.e., only four or less observations were made per year. However, given the close proximity of most monitoring wells to the active ash pond, dredge cells, and/or the reservoir, it is likely that these artificial hydrologic features largely control local groundwater levels.

## Precipitation and Recharge

Based on historical meteorological data for Oak Ridge (approximately 20 miles northwest of the site), the annual precipitation at the site is estimated to range from 39 to 70 inches and average approximately 52 inches. Average net groundwater recharge at the site, according to the Kingston groundwater investigation of Velasco and Bohac [1991], is 2.4 inches per year.

# 3. GROUNDWATER QUALITY

## Methods and Approach

From three to 23 samples have been collected from wells at Kingston since 1989. All wells were purged with either a centrifugal, bladder, or peristaltic pump and sampled with either a bladder or peristaltic pump. Wells 2, 4A, 4B, 5, 5B, 6A, and 8 were pumped dry and sampled after they recovered, either later the same day or the next day. Dedicated sampling equipment (QED systems) was installed in wells 10A, 13B, and 16A on January 27, 1993.

While data from all wells sampled at Kingston are presented, this analysis focuses on groundwater quality in the active ash pond area. This area includes wells 2, 4A, 4B, 5, 5A, 5B, 6A, 13A, 13B, 16A, 16B, 17, and 19. The periods of record for each well sampled at Kingston are indicated in the summary tables in Appendix III. These tables also present sample number, mean, median, and range of values for each parameter measured. Results reported as less than the analytical determination limit were recorded at the concentration of that limit. Thus, the




Figure 2-5. Water Table Contour Map









Figure 2-6. Groundwater Hydrographs









Figure 2-6. Groundwater Hydrographs (Continued)

median values listed may be higher than the true values. The number of observations which exceeded Maximum Contaminant Levels (MCLs) for drinking water is also shown.

Groundwater data for wells in the ash pond area were compared to drinking water criteria as one means of evaluating the potential impacts to groundwater quality from the plant's ash disposal activities. (The MCLs are listed in Table 3-1.) Tables 3-2 and 3-3 summarize the number of samples which were above the primary (health-related) and secondary (aesthetic) MCLs for drinking water. The MCLs are shown in parentheses below each parameter. The number above the slash shows the number of samples for which the concentration was observed to be above the particular MCL. The number below the slash shows the total number of analyses available from the well for the parameter in question.

Due to concerns about the effects of turbidity on the results, a number of samples were filtered through a pore size of 0.45  $\mu\text{m}$ . Table 3-4 contains the total and dissolved concentrations from the 12 samples that were both filtered and unfiltered. Figures 3-1 and 3-2 show the ionic distributions, on the basis of equivalents, of the major mineral constituents based on the median values reported in the summary tables (Appendix III). (An equivalent is 1 molecular weight of an element divided by its valence.) For comparison, data obtained from eight stations on the Emory River are included in Figure 3-1 and data from the coal yard drainage basin (CYDB) are included in Figure 3-2.

Figure 3-3 is a key to the quartile plots for twelve indicator parameters (Figures 3-4 through 3-15). Tables 3-5 and 3-6 relate to ash leachate indicators. Table 3-7 summarizes all the analyses considered to gauge impacts to groundwater at Kingston Fossil Plant.

### **Background Water Quality**

The wells at sites 15 and 16 are upgradient of the plant and are considered to provide background water quality. There were virtually no exceedances of primary MCLs observed in these wells and almost all of the secondary MCL exceedances occurred for aluminum, iron, and manganese. These constituents, while not uncommon in groundwater, are also associated with particulate matter in samples. Comparison with other wells, e.g., Figures 3-8 and 3-10 for iron and manganese, shows that these wells contain some of the lowest levels observed at the Kingston site. It is clear from Figure 3-11 that the pH of the groundwater in these wells is near neutral. The ionic distributions of these waters are marked by low ionic levels (which is related to total dissolved solids (TDS)) predominated by calcium, magnesium, and carbonate.

### **Ash Pond Area Groundwater Quality**

Tables 3-2 and 3-3 identify 108 out of 3074 observations that exceeded primary MCLs and 1586 out of a total of 3616 observations that exceeded secondary MCLs. While four-fifths of the primary exceedances are for arsenic, it appears that 5 of the 6 wells that had high arsenic levels were screened in or near ash, i.e. only well 19 was not screened in ash. Of the wells closest to the closure plan area, 13A, 17, and 19 had frequent exceedances of arsenic and 4A

**TABLE 3-1**

**Maximum Contaminant Levels for Drinking Water - Inorganics**

Parameter	Current Concentration
<b>Primary</b>	
Antimony..	6 mg/L
Arsenic	50 mg/L
Asbestos	7 X 10 <sup>6</sup> fibers/L (fibers > 10m)
Barium	2000 mg/L
Beryllium	4 mg/L
Cadmium	5 mg/L
Chromium	100 mg/L
Copper	1.3 mg/L <sup>a</sup>
Cyanide	200 mg/L
Fluoride	4.0 mg/L
Lead	50 mg/L <sup>b</sup>
Mercury	2 mg/L
Nickel	100 mg/L
Nitrate (as N)	10 mg/L
Nitrite (as N)	1 mg/L
Selenium	50 mg/L
Sulfate	500 mg/L - Proposed
Thallium	2 mg/L
<b>Secondary</b>	
Aluminum	50 to 200 mg/L <sup>c</sup>
Chloride	250 mg/L
Copper	1000 mg/L
Fluoride	2.0 mg/L
Iron	300 mg/L
Manganese	50 mg/L
pH	6.5-8.5
Silver	100 mg/L
Sulfate	250 mg/L
TDS	500 mg/L
Zinc	5000 mg/L
<sup>a</sup> EPA established action levels (ALs) rather than MCLs; effective December 7, 1992 <sup>b</sup> MCL used by states; EPA AL = 15 mg/L <sup>c</sup> Limit is to be determined by states	
Sources: Federal Register, Vol. 57, No. 138, July 17, 1992 Federal Register, Vol. 56, No. 20, January 30, 1991 Federal Register, Vol. 55, No. 143, July 25, 1990 Federal Register, Vol. 59, No. 243, December 20, 1994	

TABLE 3.2  
Kingston Fossil Plant. Data Through December 1994.  
Comparison of Groundwater Data with Primary Water Quality Standards - Number of Samples Exceeding  
an MCL/Total Number of Samples, for Each Parameter, for Each Well.

MCL WELL ID	Sb (6) (µg/L)	As (50) (µg/L)	Ba (2.0) (mg/L)	Be (4) (µg/L)	Cd (5) (µg/L)	Cr (100) (µg/L)	Cu (1.3) (mg/L)	Pb (50) (µg/L)	Ni (100) (µg/L)	Se (50) (µg/L)	NO3-N (10) (mg/L)	TOTAL
2	0/ 4	20/ 20	0/ 18	1/4	0/ 20	0/ 18	0/ 20	0/ 18	0/4	0/13	0/13	21/152
4A	0/ 5	0/ 19	0/ 17	0/5	2/19	0/ 17	0/ 19	0/ 17	4/6	0/10	0/10	6/144
4B	0/ 5	0/ 21	0/ 19	0/5	0/ 20	0/ 18	0/ 21	0/ 19	0/6	0/12	0/12	0/158
6A	0/ 5	0/ 17	0/ 15	0/5	0/ 16	0/ 14	0/ 17	0/ 15	0/6	0/11	0/10	0/131
8	0/ 6	0/ 20	0/ 18	0/6	0/ 19	0/ 17	0/ 20	0/ 18	0/6	0/13	0/12	0/155
9A	0/ 4	17/ 18	0/ 16	1/4	0/ 17	0/ 15	0/ 18	0/ 16	0/4	0/13	0/12	18/137
9B	0/ 4	0/ 17	0/ 15	0/4	0/ 16	0/ 14	0/ 17	0/ 15	0/4	0/12	0/11	0/129
10	0/ 5	21/ 21	0/ 19	0/5	0/ 20	0/ 18	0/ 21	0/ 19	0/5	0/12	0/12	21/157
10A	0/ 5	0/ 21	0/ 19	1/5	0/ 20	0/ 18	0/ 21	3/19	0/5	0/12	0/11	4/156
10B	0/ 3	0/ 14	0/ 12	0/3	0/ 13	0/ 11	0/ 14	0/ 12	0/3	0/10	0/10	0/105
11B	0/ 3	0/ 15	0/ 13	0/3	0/ 14	0/ 12	0/ 15	0/ 13	0/3	0/11	0/11	0/113
12A	0/ 3	0/ 15	0/ 14	1/3	0/ 14	0/ 13	0/ 15	0/ 14	0/3	0/10	0/10	1/114
12B	0/ 3	0/ 16	0/ 14	1/3	0/ 15	0/ 14	0/ 16	0/ 15	0/4	0/10	0/10	1/120
13A	0/ 5	21/ 21	0/ 19	0/5	0/ 20	0/ 18	0/ 21	1/19	0/5	0/13	0/12	22/158
13B	0/ 3	0/ 17	0/ 15	0/3	0/ 16	0/ 15	0/ 17	0/ 16	0/4	0/10	0/10	0/126
14A	0/ 5	2/21	0/ 19	0/5	0/ 20	0/ 18	0/ 21	0/ 20	0/5	0/13	0/12	2/159
14B	0/ 5	0/ 20	0/ 18	0/5	1/19	0/ 18	0/ 20	0/ 19	0/7	0/12	0/11	1/154
15A	0/ 5	0/ 18	0/ 16	0/5	1/17	0/ 15	0/ 18	0/ 16	0/5	0/14	0/12	1/141
15B	0/ 5	0/ 17	0/ 15	0/5	0/ 16	0/ 15	0/ 17	0/ 16	0/6	0/13	0/11	0/136
16A	0/ 5	0/ 23	0/ 20	0/5	0/ 22	0/ 20	0/ 23	0/ 21	0/6	0/16	0/14	0/175
16B	0/ 5	0/ 20	0/ 18	0/5	0/ 19	0/ 18	0/ 20	0/ 19	0/6	0/10	0/10	0/150
17	0/ 3	3/3	0/ 3	0/3	0/ 2	0/ 2	0/ 3	0/ 3	0/3	0/1	0/0	3/26
19	0/ 4	2/4	0/ 4	0/4	0/ 3	0/ 3	0/ 4	0/ 4	0/4	0/1	0/0	2/35
CYDB	0/5	0/5	0/5	1/5	0/4	0/4	0/5	0/5	4/5	0/0	0/0	5/43
TOTAL	0/105	86/403	0/361	6/105	4/381	0/345	0/403	4/368	8/115	0/252	0/236	108/3074

TABLE 3.3  
 Kingston Fossil Plant. Data Through December 1994.  
 Comparison of Groundwater Data with Secondary Water Quality Standards - Number of Samples  
 Exceeding an MCL/Total Number of Samples, for Each Parameter, for Each Well.

MCL WELL ID	pH (6.5-8.5) (SU)	Cl (250) (mg/L)	SO4 (250) (mg/L)	TDS (500) (mg/L)	Al (200) (µg/L)	Cu (1000) (µg/L)	Fe (300) (µg/L)	Mn (50) (µg/L)	Zn (5000) (µg/L)	TOTAL
2	2/18	0/20	0/20	2/20	19/20	0/20	20/20	20/20	0/20	63/178
4A	19/19	0/19	19/19	19/19	19/19	0/19	19/19	19/19	0/19	114/171
4B	5/21	0/21	20/21	21/21	16/21	0/21	21/21	21/21	0/21	104/189
6A	17/17	0/17	17/17	17/17	15/17	0/17	17/17	17/17	0/17	100/153
8	0/19	0/20	19/19	20/20	12/20	0/20	19/20	20/20	0/20	90/178
9A	13/18	0/17	18/18	18/18	18/18	0/18	18/18	18/18	0/18	103/161
9B	5/18	0/17	3/17	0/17	3/17	0/17	3/17	11/17	0/17	25/154
10	0/20	0/21	9/21	8/21	14/21	0/21	21/21	21/21	0/21	73/188
10A	22/22	0/21	14/21	14/21	21/21	0/21	21/21	21/21	0/21	113/190
10B	14/14	0/14	14/14	13/14	9/14	0/14	14/14	14/14	0/14	78/126
11B	1/15	0/15	15/15	15/15	9/15	0/15	13/15	15/15	0/15	69/135
12A	2/15	0/15	1/15	10/15	8/15	0/15	14/15	14/15	0/15	49/135
12B	0/15	0/16	16/16	16/16	4/16	0/16	16/16	16/16	0/16	68/143
13A	2/20	0/21	3/21	2/21	20/21	0/21	21/21	21/21	0/21	69/188
13B	0/17	0/17	0/17	0/17	4/17	0/17	1/17	1/17	0/17	6/153
14A	21/21	0/21	20/21	20/21	12/21	0/21	21/21	21/21	0/21	115/189
14B	2/19	0/20	19/20	19/20	11/20	0/20	19/20	20/20	0/20	90/179
15A	0/19	0/18	1/18	2/18	10/18	0/18	8/18	15/18	0/18	36/163
15B	0/17	0/17	1/17	3/17	7/17	0/17	17/17	17/17	0/17	45/153
16A	0/21	0/23	1/23	0/23	16/23	0/23	23/23	23/23	0/23	63/205
16B	0/19	0/20	0/20	0/19	14/20	0/20	11/20	20/20	0/20	45/178
17	3/3	0/3	3/3	3/3	3/3	0/3	3/3	3/3	0/3	18/27
19	3/3	0/4	4/4	4/4	4/4	0/4	4/4	4/4	0/4	23/35
CYDB	5/5	0/5	4/5	3/5	5/5	0/5	5/5	5/5	0/5	27/45
TOTAL	136/395	0/402	221/402	229/402	274/403	0/403	349/403	377/403	0/403	1586/3616



TABLE 3-4

Kingston Groundwater Data  
Unfiltered (Total Concentration) vs. Filtered (Dissolved Concentration)  
Samples Collected on December 7-10, 1992

Parameter	Units	CYDB		Well I.D.									
		Tot.	Diss.	4A		4B		6A		9A		10	
				Tot.	Diss.	Tot.	Diss.	Tot.	Diss.	Tot.	Diss.	Tot.	Diss.
Aluminum	µg/L	9900	8900	15000	9800	4200	<50	10000	<50	3900	80	1000	<50
Iron	µg/L	40000	40000	290,000	250,000	16000	60	1,300,000	950,000	47000	35000	11000	6400
Manganese	µg/L	5800	5600	54000	48000	5000	130	76000	66000	35000	32000	310	250
Copper	µg/L	20	20	<10	<10	<10	<10	<10	<10	<50	<10	<10	<10
Calcium	mg/L	180	180	330	300	220	190	380	320	300	250	66	60
Magnesium	mg/L	39	39	76	71	19	17	69	64	57	51	8.2	7.9
Zinc	µg/L	250	250	670	570	60	<10	240	100	50	30	<10	<10
Barium	µg/L	20	10	30	<10	40	<10	210	40	70	30	60	20
Boron	µg/L	<500	<500	670	500	<500	<500	3500	2800	1600	1500	<500	<500
Molybdenum	µg/L	<20	<20	<20	<20	<20	<20	<20	<20	<20	<20	70	70
Strontium	µg/L	740	730	1500	1400	390	280	3500	2900	3100	2900	700	670
Beryllium	µg/L	<1	<1	<1	<1	<1	<1	<1	<1	6	<1	<1	<1
Arsenic	µg/L	<1	<1	2	2	5	1	4	4	120	87	180	150
Cadmium	µg/L	1.5	1.5	2.9	2	0.4	0.1	1.9	0.1	0.4	0.1	<0.1	<0.1
Chromium	µg/L	<1	<1	<1	<1	2	<1	13	<1	2	<1	<1	<1
Lead	µg/L	<1	<1	12	5	6	<1	37	<1	2	<1	2	<1
Antimony	µg/L	<1	<1	<1	<1	<1	<1	<1	<1	<1	5	<1	<1
Lithium	µg/L	60	60	30	30	<10	<10	50	40	30	30	110	100
Nickel	µg/L	140	140	120	52	9	2	12	5	53	35	4	3
Vanadium	µg/L	10	<10	<10	<10	<10	<10	<10	<10	10	<10	<10	<10
Total Susp Sol	µg/L	5		170		420		470		170		90	
Total Diss Sol	µg/L	1200		2600		710		4200		1700		280	

Parameter	Units	10A		10B		14A		14B		17		19	
		Tot.	Diss.	Tot.	Diss.	Tot.	Diss.	Tot.	Diss.	Tot.	Diss.	Tot.	Diss.
Aluminum	µg/L	6900	520	340	<50	60	<50	2200	<50	38000	<50	2400	60
Iron	µg/L	26000	18000	18000	15000	130,000	100,000	3000	720	100,000	69000	390,000	330,000
Manganese	µg/L	7700	5800	8400	6900	7600	5000	790	600	3700	3200	12000	9200
Copper	µg/L	<10	<10	<10	<10	<10	<10	<10	<10	70	<10	<10	<10
Calcium	mg/L	67	55	150	120	710	590	260	220	430	380	550	460
Magnesium	mg/L	10	9.5	23	20	120	120	33	27	28	26	46	44
Zinc	µg/L	100	60	<10	<10	<10	<10	<10	<10	130	40	150	120
Barium	µg/L	40	20	60	30	20	<10	90	30	310	20	40	20
Boron	µg/L	1300	1100	<500	<500	560	<500	<500	<500	1000	930	3100	2300
Molybdenum	µg/L	<20	<20	<20	<20	<20	<20	<20	<20	<20	<20	<20	<20
Strontium	µg/L	1100	940	670	550	2300	1900	420	370	2200	2000	3400	2700
Beryllium	µg/L	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1	<1
Arsenic	µg/L	4	3	5	5	42	42	<1	<1	580	500	50	44
Cadmium	µg/L	<0.1	<0.1	0.1	0.1	0.3	<0.1	0.2	0.1	1.4	0.3	<0.1	<0.1
Chromium	µg/L	<1	<1	<1	<1	<1	<1	1	<1	56	<1	<1	<1
Lead	µg/L	6	<1	1	<1	<1	<1	<1	<1	46	<1	<1	<1
Antimony	µg/L	<1	<1	<1	<1	<1	<1	<1	<1	5	5	1	1
Lithium	µg/L	50	40	10	<10	40	40	20	20	230	160	310	300
Nickel	µg/L	56	42	4	1	3	3	2	<1	49	9	<1	<1
Vanadium	µg/L	<10	<10	<10	<10	<10	<10	<10	<10	130	<10	<10	<10
Total Susp Sol	mg/L	78		47		44		39		1800		110	
Total Diss Sol	mg/L	390		660		3100		890		1900		3500	





Figure 3-1. Ionic Distributions for Ash Pond Area

20

Cations



Anions





Figure 3-2. Ionic Distributions for Metal Cleaning Pond and Coal Yard Areas




Figure 3-3. Key to Box and Whiskers Plots




Figure 3-4. Arsenic Groundwater Data Through April 1995




Figure 3-5. Barium Groundwater Data Through April 1995




Figure 3-6. Boron Groundwater Data Through April 1995




Figure 3-7. Calcium Groundwater Data Through April 1995






Figure 3-8. Iron Groundwater Data Through April 1995




Figure 3-9. Lead Groundwater Data Through April 1995




Figure 3-10. Manganese Groundwater Data Through April 1995




Figure 3-11. pH Groundwater Data Through April 1995




Figure 3-12. Strontium Groundwater Data Through April 1995




Figure 3-13. Sulfate Groundwater Data Through April 1995




Figure 3-14. Total Dissolved Solids Groundwater Data Through April 1995




Figure 3-15. Total Organic Carbon Groundwater Data Through April 1995



TABLE 3-5  
Fly Ash Leachate Characteristics Based on EPRI Estimates and TVA Data.

FOWL Leachate Estimates <sup>a</sup>						TVA Well Point data <sup>b</sup>		
Constituent	Units	Leachate Concentration				Minimum	Maximum	Mean
		4	5	6	7			
pH	S.U.	4	5	6	7	6.0	9.4	7.6
Al	µg/L	4037	523	149	146	50	3500	309
Ba	µg/L	254	255	253	253	30	630	190
Ca	mg/L	395	396	394	394	15	390	92
Cr	µg/L	40	2	2	2	1	4	1
Mo	µg/L	1879	748	679	672	20	6200	688
Si	mg/L	26	26	26	26	1	18	6
Sr	µg/L	1624	1631	1616	1616	220	2700	945
So <sub>4</sub>	mg/L	960	953	946	946	8	990	163
As	µg/L	109	99	99	99	3	3520	945
B	µg/L	2856	3340	3907	4569	500	23000	5270
Cd	µg/L	34	8	2	2	0.1	6	1
Cu	µg/L	244	24	4	4	10	770	43
Fe	µg/L	511	104	21	5	10	25000	4684
Mg	mg/L	8.9	4.9	2.7	1.5	0.6	41	14
Na	mg/L	8.5	9.7	11	12	90	20	5.8
Ni	µg/L	197	50	13	9	1	65	10
Se	µg/L	0	0	41	65	1	27	4
Zn	µg/L	747	85	10	10	10	10000	794
TDS	mg/L	772	762	757	758	110	1500	464

<sup>a</sup> Source: Hostetler et al., 1988

<sup>b</sup> Based on approximately 40 samples from 17 well points at 4 different TVA fossil plants

TABLE 3.6

Indications of Ash Leachate in Wells in the Active Ash Pond Area at KIF.  
Comparison of Predicted Threshold Concentrations (FOWL) with Observed Median Values.

Well Number	Arsenic µg/L	Barium µg/L	Boron µg/L	Calcium mg/L	Iron mg/L	Strontium µg/L	Sulfate mg/L	TDS mg/L	pH S.U.
2	210/180 <sup>a</sup>	530/460	2800/2400	96/99	48.5/36	1500/1400	20.5	455	6.6
4A	2/1	90/20	890/720	320/300	320/280	1300/1400	1600	2800	3.2
4B	2/1	30/10	500/500	230/220	3.6/0.2	360/280	430	800	6.7
5	4/7.5	330/190	4000/1900	290/290	1100/500	2300/1520	2400	4350	5.6
5A	2/2	80/50	500/500	35/40	4.8/7.5	270/50	160	250	5.4
5B	1/1	70/40	500/560	43/107.5	2/125	290/475	165	260	5.6
6A	4/2.5	310/370	3500/3650	340/350	1200/1250	2000/2000	2800	4900	5.8
13A	85/82	220/170	500/500	47/44	48/43	630/550	88	290	6.6
13B	1/1	210/190	500/500	8.4/8.8	0.12/0.2	170/160	2	200	8.3
17	100/293	140/15	580/755	340/360	53/58	1600/1750	830	1300	6.1
19	55.5/44	40/20	2400/2000	560/460	325/300	3000/2600	1900	3000	5.9
16A	1/1	50/60	500/500	49/51	1.10/0.70	350/340	70	250	7.3
16B	1/1	50/40	500/500	50.5/49	.33/0.1	360/320	72.5	260	7.3
FOWL <sup>b</sup>	100	250	3000	400	0.2	1600	950	750	4 TO 7

<sup>a</sup> Total/Dissolved Median Values

<sup>b</sup> Hostetler et al., 1988

Shaded values consistent with FOWL predictions

TABLE 3-7

Summary of Analyses Indicating Ash Leachate Effects at Kingston Fossil Plant Through December 1994

Well	Regulated Parameters								Nonregulated Parameters	Ionic Distribution Effects	Nearest Possible Source
	1° (% > MCL)					2° (% > MCL)					
	As	Be	Cd	Pb	Ni	pH	SO4	TDS			
2	100	25				11		10	B, Sr	No	CTP
4A			10		67	100	100	100	Sr	Yes	Dredge Cells
4B						24	95	100		Yes	Dredge Cells
5						100	100	100	B, Sr	Yes	Ash Pond
5A						100	12			Maybe	Ash Pond
5B						100	25	13		Maybe	Ash Pond
6A						100	100	100	B, Sr	Yes	Stilling Pond
8							100	100		Yes	Coal Yard
9A	94	25				72	100	100	Sr	Yes	CTP
9B						28	18		Na	No	CTP
10	100						43	38		Maybe	ALD
10A		20		16		100	67	67	Sr	Maybe	ALD
10B						100	100	93		Yes	ALD
11B						7	100	100		Yes	ALD
12A		33				13	7	67		Maybe	Coal Yard
12B		33					100	100	Sr	Yes	Coal Yard
13A	100			5		10	14	10		No	Ash Pond
13B									Na	No	Ash Pond
14A	10					100	95	95	Sr	Yes	CYDB
14B		5				11	95	95		Yes	CYDB
15A		6					6	11		No	Coal Yard
15B							6	18		No	Coal Yard
16A							4			No	Dredge Cells
16B										No	Dredge Cells
17	100					100	100	100	Sr	Yes	Ash Pond
19	50					100	100	100	B, Sr	Yes	Ash Pond
CYDB		20			80	100	80	60			CYDB

Abbreviations: ALD = Anoxic Limestone Drain CTP = Chemical Treatment Plant CYDB = Coal Yard Drainage Basin

exceeded the MCL for nickel two-thirds of the time. Previous modeling studies [Velasco and Bohac, 1991] suggest that arsenic is readily adsorbed by soil and is not very mobile in groundwater. This is supported by the data from the deeper wells at sites 9, 10, and 13, where high arsenic levels were observed in the shallow wells. The only other MCL exceedances for health-related parameters were for lead at two wells and beryllium at six wells. However, most were single occurrences...

Of the secondary parameters, MCLs were frequently exceeded for pH, sulfate, TDS, aluminum, iron, and manganese. High levels of the three metals mentioned are often attributed to sediment in the samples. About half the wells produced samples with some level of turbidity. Total suspended solids (TSS) is a quantitative measure of the amount of sediments and particulate matter in a sample. Unfiltered samples provide total concentrations of all constituents and are therefore viewed as being the most conservative. However, concerns have been raised that levels of some regulated metals such as arsenic and lead will be abnormally high if they are associated with the sediment and not mobile in the aqueous phase. To remove these biases, it is often suggested to filter all samples through a glass fiber filter of standard pore size, usually 0.45  $\mu\text{m}$ , to yield dissolved concentrations. However, false low levels may arise if mobile elements adsorb onto soil particles during filtration. In order to help resolve some of these questions, both filtered and unfiltered samples were collected at the same time at several locations. Table 3-4 contains the total and dissolved concentrations from the 12 samples that were both filtered and unfiltered.

From Table 3-4, it is clear that for the sample from wells 14A and 14B there was very little difference observed between the total and dissolved concentrations. These results would be expected because that sample also had a very low amount of TSS (5 mg/L). In the other samples, where TSS levels ranged from 39 to 1800 mg/L, the greatest differences between total and dissolved concentrations were for constituents associated with sediment, i.e., aluminum, iron, and manganese. In only one instance, beryllium in well 9A, the dissolved value was below an MCL that was exceeded in the unfiltered samples. The higher level of antimony observed in the dissolved 9A sample was assumed to be anomalous.

In four of the five wells on the ash pond dike (wells 4A, 6A, 17, 19), the levels of most metals, such as aluminum, barium, boron, iron, manganese, strontium, and zinc in the filtered samples were usually within 20 percent of the levels in the unfiltered samples. That is, if the total concentration of a constituent was elevated, its dissolved fraction was usually elevated also, albeit at a lower level. Levels of other indicator parameters such as arsenic and lithium were very similar in both filtered and unfiltered samples. These results suggest that while sediment in samples can cause interferences in the levels of some parameters, including some heavy metals, sample filtration is not warranted for the purpose of monitoring ash leachate effects in groundwater. The levels of iron and manganese in wells 4A, 6A, and 19 are particularly noteworthy as they are much higher than would be expected to occur from just fly ash leaching.

## Ash Leachate Composition

While pore water samples were not collected at Kingston, *in situ* samples have been collected at five other TVA fossil plants using a well point leachate collection method developed by Milligan and Bohac [1991]. The range and mean of values observed from these samples is shown in Table 3-5. Also shown in Table 3-5 are the values provided by FOWL, the Electric Power Research Institute's computer code used to estimate ash leachate composition as a function of pH [Hostetler et al., 1988]. Data collected from the TVA ash pond wells reveal that the characteristics of ash leachate may vary at a site, as well as from site to site. Differences are probably due to age of ash and types of coal burned.

The pH of most of the TVA pore water samples was alkaline. However, the pH of the groundwater in the active ash pond area is acidic. Therefore, the Kingston data were compared with the FOWL leachate estimates at the pH 4 to 7 range (Table 3-6). The quartile plots (box and whisker graphs) in Figures 3-4 to 3-15 facilitate ready comparison of all wells at the site for most of the parameters of interest. The median values of eight indicator parameters are shown in Table 3-6. The numbers in the shaded boxes exceed or are near the threshold concentrations predicted by FOWL. Wells 2, 5, 6A, 17, and 19 showed the most evidence of ash leachate. Wells 2 and 17 are screened in ash; wells 5, 6A, and 19 are screened in the ash pond dike which could contain significant amounts of bottom ash.

Aside from iron, which was found in all wells, TDS, strontium, sulfate, and boron were the indicator parameters that most frequently exceeded the threshold values. The iron levels were found to be high in wells 4A, 5, 6A, 17, and 19, suggesting the occurrence of pyrite oxidation in the ash pond or in the dikes. The oxidation state of the iron is not known. If this iron-rich water were to enter a surface water, such as the river, its potential impacts would depend on the oxidation state. If it is in the ferric (+3) form, the iron would likely hydrolyze to form insoluble ferric hydroxide and produce 3 moles of acidity for every mole of iron. However, if the iron is in the ferrous (+2) form, the iron will consume acidity as it is oxidized to the ferric form before it is hydrolyzed [Milligan and Ruane, 1980]. The oxidation reduction potential (ORP) values observed in most of the wells along the ash pond dike suggest that the waters are in a slightly oxidizing state. Specific analyses for ferrous and ferric iron would have to be conducted to determine the actual oxidation state of the iron.

In terms of ionic distributions in ash leachate, the predominant anion is sulfate and the predominant cation is calcium. In addition, ash leachate has high TDS. The length of the bars is related to the amount of TDS in the water. Figures 3-1 and 3-2 may be compared to Figure 3-15 in order to associate which bar lengths are most closely related to a TDS level of interest. For example, the MCL of 500 mg/L appears to be associated with a bar length of approximately 8 milli-equivalents (meq), and the level predicted by FOWL (750 mg/L) with a bar length of about 12 meq. The ionic distributions of wells 4A, 4B, 5, 6A, 17, and 19, as well as wells 9A, 10B, 11B, 12B, 8, 14A, and 14B have bar lengths greater than 12 meq. In addition, the predominant anion in all these wells is sulfate. On the other hand, ionic distributions most similar to background were observed in wells 2 and 13A. Several wells, including 5A and 5B have low ionic levels, but the anions are nearly all sulfate. A high predominance of sulfate with low ionic levels may be indicative of pyrite oxidation rather than

ash leachate. The only wells that stand out on the basis of the cation distribution are wells 9B and 13B which were predominated by sodium.

### Summary

Table 3-7 presents a well-by-well summary of all the analyses considered herein to gauge potential impacts to groundwater at Kingston Fossil Plant. The percentage of samples that exceeded MCLs for primary (1°) drinking water standards (based on Table 3-2) and the percentage of samples that exceeded MCLs for secondary (2°) parameters pH, SO<sub>4</sub>, and TDS (based on Table 3-3) are shown. Also listed in Table 3-7 are non-regulated ash leachate indicator parameters that were found at elevated levels, ionic distribution effects, and the nearest possible source. Ash leachate contamination was indicated by acidic pH, high levels of sulfate, TDS, boron, and strontium, and ionic distribution effects. The wells in the active ash pond area exhibiting most of these indicators were 2, 4A, 4B, 5, 6A, 17, and 19. Possible decreasing trends were apparent for iron and pH in well 4A, iron and sulfate in well 6A, and arsenic in well 13A. Unusual levels of sodium were observed in wells 9B and 13B, but this is not considered to be an indicator of ash leachate. Turbid samples persist in several wells. However, analysis of data from filtered and unfiltered samples suggested that sample filtration is not warranted for the purpose of monitoring ash leachate effects in groundwater at Kingston.

## 4. LOCAL GROUNDWATER USE

A survey of local groundwater use within an approximate two-mile radius of the center of the ash pond area was conducted in March 1995. The survey included interviews with local residents and utility district managers. Water well records maintained by the State of Tennessee were also examined for wells within the survey region.

A total of 22 residential wells were identified during the survey (Figure 4-1). A listing of these wells and their coordinate locations is given in Table 4-1. Note that wells are numbered 1 through 23 with no well 15. Spring 1 is an untreated water source for 10 to 12 residences along Swan Pond Road and for several residents of the Kingston Heights subdivision. The spring emanates from aquifers of the Knox Group. This spring appears to be the only spring in the survey region used for water supply. There are six wells (numbers 7, 8, 9, 20, 21, and 22) located within approximately one mile of the center of the disposal site and another 15 wells situated between one and two miles of the site. The depths of these residential wells are unknown; however, it is likely that most are completed in the Conasauga formation at relatively shallow depths (i.e., less than 300 ft).

Other residents within the survey region are served by one of the four local water utilities listed in Table 4-1. These utilities provide treated water from intakes on Watts Bar Lake or the Emory River.



Figure 4-1. Wells and Springs Within Two Miles of Ash Pond Area

TABLE 4-1

List of Wells, Springs, and Water Supplies in Site Vicinity

Location Identifier	Location Description	Longitude (dg-mn-sc) est	Latitude (dg-mn-sc) est	Inside 1 mile radius	Inside 2 mile radius	Outside 2 mile radius
Well 1	Swan Pond Rd south of Hwy 70	35-53-35 N	84-32-05.5 W		X	
Well 2	Swan Pond Rd south of Hwy 70	35-53-34 N	84-32-09 W		X	
Well 3	Swan Pond Rd south of Hwy 70	35-53-33-N	84-32-10.5 W		X	
Well 4	North of Hwy 70, South of I-40	35-53-41.5 N	84-32-14 W		X	
Well 5	Swan Pond Rd north of Hwy 70	35-53-44.5 N	84-32-09.5 W		X	
Well 6	Swan Pond Rd north of Hwy 70	35-53-45-N	84-32-06 W		X	
Well 7	Swan Pond Circle north of Swan Pond Rd	35-55-18 N	84-31-04.5 W	X		
Well 8	Swan Pond Rd north of Hwy 70	35-54-06 N	84-31-31 W	X		
Well 9	Swan Pond Rd north of Hwy 70	35-54-07 N	84-31-37 W	X		
Well 10	Swan Pond Rd north of Hwy 70	35-54-00.5 N	84-31-41 W		X	
Well 11	Swan Pond Rd north of Hwy 70	35-53-58.5 N	84-31-46 W		X	
Well 12	Swan Pond Rd north of Hwy 70	35-54-00.5 N	84-31-50.5 W		X	
Well 13	Swan Pond Rd north of Hwy 70	35-53-52 N	84-31-47 W		X	
Well 14	Swan Pond Rd north of Hwy 70	35-53-55 N	84-31-50 W		X	
Well 16	Swan Pond Rd north of Hwy 70	35-53-53 N	84-31-53 W		X	
Well 17	Swan Pond Rd north of Hwy 70	35-53-55 N	84-31-56 W		X	
Well 18	Swan Pond Rd north of Hwy 70	35-53-52 N	84-31-58.5 W		X	
Well 19	Swan Pond Rd north of Hwy 70	35-53-56 N	84-32-00 W		X	
Well 20	Swan Pond Rd west of Swan Pond circle	35-55-06.5 N	84-31-09 W	X		
Well 21(N)	Swan Pond Rd north of Hwy 70	35-54-11 N	84-31-31.5 W	X		
Well 22(N)	Swan Pond Rd north of Hwy 70	35-54-05 N	84-31-05 W	X		
Well 23(N)	Hassler Mill Rd west of Swan Pond Rd	35-54-43 N	84-31-54 W		X	
Spring 1	Near intersection of Swan Pond Rd and Frost Hollow Rd (used for portion of municipal supply by City of Kingston)	35-55-07 N	84-31-54 W		X	
City of Kingston	Intake off Hwy 58 south of Kingston on Watts Bar Lake	n/a	n/a			X
Swan Pond U.D.	Purchase water from City of Harriman	n/a	n/a			X
Midtown Utilities	Purchase water from City of Rockwood	n/a	n/a			X
City of Harriman	Intake on Emory River near Mile 13	n/a	n/a			X
City of Rockwood	Intake on Watts Bar Lake near Post Oak Creek	n/a	n/a			X



## 5. EVALUATION OF POTENTIAL WATER QUALITY IMPACTS

The potential impacts of the closed ash pond area on adjacent groundwater and surface water resources are examined in this section. The focus of the evaluation is on the effect of the facility on reservoir water quality since all shallow groundwater originating on, or flowing beneath, the site ultimately discharges to the reservoir without traversing private property. Estimates of ash leachate flowrates generated during a 30-year post-closure period are compared with historical flows in Watts Bar Reservoir to quantify potential water quality impacts. In evaluating potential impacts to groundwater users, consideration is given to the location of existing residential wells in relation to groundwater flow patterns in the site vicinity.

### Post-Closure Ash Fill Water Budget Analysis

EPA's HELP2 code [Schroeder et al., 1989] was used to estimate the overall water balance, including leachate production, for the ash fill during a 30-yr period following closure. For purposes of the simulation, the ash fill was divided into three regions as shown schematically on Figure 5-1. Region 1 corresponds to what is now the active ash pond area. This region is 114.6 acres in area and will have a final average grade of elevation of about 770 ft and surface slope of 5 percent. Region 2 comprises the 3:1 side-slope area of the dredge cells and will be approximately 36 acres in size. The area on top of the dredge cells at closure is represented by Region 3. This region will encompass 58.8 acres and will be sloped at a 5 percent grade. The entire surface of ash fill will be covered with one foot of  $10^{-7}$  cm/s clay followed by one foot of vegetated topsoil.

Table 5-1 lists the hydraulic properties required by HELP2 for each material type shown in Figure 5-1. The hydraulic properties of the Kingston fly ash were obtained from laboratory-measured data for three samples presented in Appendix A of Young et al. [1993]. The field capacity, wilting point, and porosity for the clay cap were those given by Schroeder et al. [1989] for a soil liner. The values for the top soil were those given by Schroeder et al. [1989] for a soil loam. The top soil was represented in the model as a lateral/vertical percolation layer, the clay cap a barrier layer, and the ash a vertical percolation layer. The initial moisture contents for the top soil and clay cap were arbitrarily set at field capacity. Field-measured moisture contents for ash samples collected at TVA's Bull Run [Young, 1992] and John Sevier [Velasco and Boggs, 1992] plants were used to estimate the initial ash moisture content for the simulation.

In addition to the properties in Table 5-1, HELP2 requires a Soil Conservation Service (SCS) curve number, an evaporation depth, and a leaf area index for the vegetative cover. Using information given by Schroeder et al. [1989], the SCS curve number for the top soil was estimated as 75. An evaporation depth of 18 inches was selected for the analysis. These values are consistent with those used in water budget analyses for other ash fills [e.g., Young and Velasco, 1991; Velasco and Boggs, 1992]. A leaf area index of 3.3, corresponding to a "good" grass cover, was assumed.





Figure 5-1. Subregion Areas and Profiles Used in HELP2 Simulations  
43

TABLE 5-1					
Material Properties Used in the HELP2 Simulations					
Soil Type	Porosity	Field Capacity	Wilting Point	Initial Moisture Content (%)	Hydraulic Conductivity (cm/s)
Top Soil*	.46	.23	.12	.23	$3.7 \times 10^{-4}$
Clay Cap	.43	.37	.28	.37	$1.0 \times 10^{-7}$
Fly Ash	.47	.40	.12	.25	$2.1 \times 10^{-5}$

\*Evaporation coefficient  $\alpha$  is 5.1 mm/day<sup>0.5</sup>

Meteorological data was compiled from a National Oceanographic and Atmospheric Administration (NOAA) station located in Oak Ridge, Tennessee. This station was selected because of its close proximity to the Kingston plant and because high quality data was available for a continuous 20-year period. The data include daily rainfalls and mean daily temperatures from 1968 to 1987. In order to provide 30 years of rainfall/temperature data for the water budget simulation, data for years 1968-77 were added to the end of the 1968-87 record. Daily solar radiation values were generated using a HELP2 subroutine that incorporates several factors including latitude and daily rainfall.

The yearly combined leachate flowrates from the three subregions of the ash disposal area are shown on Figure 5-2. Leachate discharge gradually increases during the first 10 years of the post-closure period reaching a quasi-steady rate of approximately 6.3 million cfy (cubic feet per year) thereafter. The average leachate discharge for the 30-yr simulation was approximately 5.7 million cfy. The overall water balance for the ash fill in terms of percent of total incident precipitation was as follows: surface runoff, 18.8 percent; evapotranspiration, 64.1 percent; lateral seepage from top-soil layer, 1.0 percent; net change in water storage, 2.3 percent; and leachate reaching the water table, 13.8 percent.

#### Potential Impacts to Reservoir Water Quality

Groundwater flow patterns indicate that all leachate produced in the ash pond area will ultimately discharge into Watts Bar Reservoir. To assess the impact of ash leachate on reservoir water quality, a dilution ratio was estimated by comparing the predicted average leachate flowrate to the mean flow in the reservoir just downstream of the plant outfall. Full mixing of leachate influx and reservoir water was assumed. Considering that stream flow and leachate production from the ash fill are both functions of meteorological conditions, comparison of their mean flows appears to be a reasonable basis for calculating a dilution ratio. The mean flow in the Clinch River immediately below the plant outfall (approximate river mile 2.5) is estimated to be approximately 7,000 cfs. This estimate was based on the combined drainage-area adjusted mean flows for the Emory River (at Oakdale for the period 1927-93 as reported by Flohr et al.,




Figure 5-2. Predicted Leachate Discharge From Ash Pond Area During 30-Year Post-Closure Period

1993) and the Clinch River (at Melton Hill Dam for the period 1964-94). The resulting dilution ratio for the quasi-steady leachate discharge predicted during the last 20 years of the water budget simulation of 6.3 million cfy (0.20 cfs) is 1:35,000.

Incremental increases in chemical concentrations in Watts Bar Reservoir due to the influx of ash-leachate effected groundwater were estimated by multiplying the dilution ratio by the mean parameter concentrations. Groundwater quality data for wells located on the perimeter of the disposal area which exhibited exceedances for primary and secondary drinking water standards were selected for the calculation. Parameters exceeding drinking water MCLs included arsenic, nickel, iron, manganese, sulfate, and TDS. The analysis conservatively assumed all ash leachate was contaminated to the highest observed levels. In addition, the method did not account for groundwater dilution of ash leachate, which would reduce constituent concentrations before reaching the reservoir. The results presented in Table 5-2 indicate the predicted incremental increases ( $\Delta C$ ) in reservoir are negligible for all constituents iron which showed a slight increase of 29  $\mu\text{g/L}$ .

Well	Parameter	Units	N <sup>a</sup>	MCL	Mean	$\Delta C^b$
13A	Total Arsenic	$\mu\text{g/L}$	21	50	92	0.003
4A	Total Nickel	$\mu\text{g/L}$	4	100	125	0.004
6A	Total Iron	$\mu\text{g/L}$	17	300	1.01E06	29
6A	Total Manganese	$\mu\text{g/L}$	17	50	61,282	1.8
6A	Sulfate	mg/L	17	250	2,513	0.072
6A	TDS	mg/L	17	500	4,453	0.13

<sup>a</sup>N = number of MCL exceedances  
<sup>b</sup> $\Delta C$  = mean concentration x dilution ratio

The small predicted increase in iron entering the reservoir via groundwater should not represent a problem. Dissolved iron accounts for essentially all of the total iron measurement for well 6A. The iron is expected to be present in a reduced (Fe-II) state given the mean oxidation-reduction potential (77 mV) and mean pH (5.5) [Freeze and Cherry, 1979, page 124] observed at this well. Upon entering the oxidizing environment of the reservoir, iron present in groundwater would be expected to precipitate out of solution.

## Potential Impacts to Groundwater Users

There are six residential wells (numbers 7, 8, 9, 20, 21, and 22) located within approximately one mile of the center of the ash pond area (Figure 4-1). Wells 7 and 20 lie north of Swan Creek embayment and are hydrologically isolated from the disposal site. The remaining four wells (numbers 8, 9, 21, 22), located southwest of the site along Swan Pond Road, lie off-gradient of the ash pond area (Figure 5-3). There is no evidence that pumping from these wells and the other 15 residential wells located south of Pine Ridge has induced ash leachate movement from the site. As indicated on Figure 5-3, these wells are generally situated up-gradient of the Kingston plant reservation. No adverse off-site groundwater impacts associated with the ash pond are indicated under present conditions or expected under post-closure conditions.




Figure 5-3. Locations of Residential Wells in Relation of Groundwater Flow Patterns in Ash Pond Area


## 6. REFERENCES

- Flohr, D. F., F. D. Edwards, J. G. Lewis, and R. A. Orr, 1993, "Water Resources Data, Tennessee, Water Year 1993," U.S. Geological Survey Water-Data Report TN-93-1.
- Freeze, R. A., and J. A. Cherry, 1979, Groundwater, Prentice-Hall, Inc.
- Harris, W. F., and M. S. Foxx, 1982, "Potential Ground-Water Quality Impacts at TVA Steam Plants," TVA Report WR28-2-520-119.
- Hostetler, C. J., R. L. Erikson, and D. Rai, 1988, The Fossil Fuel Combustion Waste Leaching (FOWL™) Code: Version I User's Manual, Electric Power Research Institute, Palo Alto, California, EA-5742-CCM.
- Milligan, J. D., and C. E. Bohac, 1991, "Evaluation of Sampling Techniques for Coal-Ash Leachate and "Red Water" Seeps at TVA's Widows Creek Steam Plant," TVA/WR/WQ--91/6, Tennessee Valley Authority, Water Resources, Chattanooga, Tennessee.
- Milligan, J. D., and R. J. Ruane, 1980, "Effects of Coal-Ash Leachate on Ground Water Quality," EPA-600/7-80-066.
- Singleton Laboratories, Inc., 1994, "Kingston Fossil Plant Dredge Cells/Closure Soil Investigation," SL Report 015-672-142A.
- Schroeder, P. R., A. C. Gibson, and M. D. Smolen, 1989, "Hydrologic Evaluation of Landfill Performance Model (Version 2)," Draft Report, U.S. Army Corps of Engineers Waterways Experiment Station, Vicksburg, Mississippi, Interagency Agreement No. AD-96-F-2-A140.
- Velasco, M. L., and C. E. Bohac, 1991, "Kingston Groundwater Assessment," TVA Report WR28-1-36-115.
- Velasco, M. L., and J. M. Boggs, 1992, "Evaluation of Water Resource Impacts From Proposed Fly Ash Dry Stack at John Sevier Fossil Plant," TVA Report WR28-2-41-126.
- Young, S. C., 1992, "Vertical Moisture Profiles in the Bull Run Dry Stack and Implications to Leachate Generation," TVA Report WR28-1-49-109.
- Young, S. C., R. Schmidt-Petersen, M. Ankeny, and D. B. Stephens, 1993, "Physical and Hydraulic Properties of Fly Ash and Other By-Products From Coal Combustion," Electric Power Research Institute Report TR-101999, Project 2485-05.
- Young, S. C., and M. L. Velasco, 1991, "Water Budget Predictions for an Active Fly Ash Dry Stack Using the HELP2 Model," TVA Report WR28-1-49-106.



**APPENDIX I**  
**LITHOLOGIC LOGS**

VERTICAL PROFILE OF THE SUBSTRATUM AT PLANT J's MONITORING WELL LOCATIONS



[from Milligan and Ruane, 1980]







# Law Engineering

## Boring Record

BORING NUMBER J-9B

DATE DRILLED 10-3-88

JOB NUMBER K-88195

PAGE 1 OF 3

DEPTH (FT.)  
0.0

DESCRIPTION

ELEV.  
\*

PENETRATION-BLOWS PER FOOT

5 10 20 30 40 50 60 80 100 "N"

DRY GRAY ASH

35.0

ALLUVIAL CLAY, SAND AND GRAVEL  
WITH WEATHERED SHALE FRAGMENTS

40.0

REMARKS: BORING DRILLED USING AIR ROTARY EQUIPMENT

\* ELEVATION TO BE PROVIDED BY TVA



# Law Engineering

## Boring Record

BORING NUMBER J-9B  
 DATE DRILLED 10-3-88  
 JOB NUMBER K-88195  
 PAGE 2 OF 3

DEPTH (FT.)  
 40.0

DESCRIPTION

ELEV.

PENETRATION-BLOWS PER FOOT  
 5 10 20 30 40 50 60 80 100 "N"

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																		
			5	10	20	30	40	50	60	80	100	"N"									
40.0	ALLUVIAL CLAY, SAND AND GRAVEL WITH WEATHERED SHALE FRAGMENTS																				
67.5	BLUE GRAY SHALE WITH CALCITE JOINTS																				
80.0																					

REMARKS:





# Law Engineering

## Boring Record

BORING NUMBER J-10  
 DATE DRILLED 9-27-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 1

DEPTH (FT.)	DESCRIPTION	ELEV. *	PENETRATION-BLOWS PER FOOT																			
			5	10	20	30	40	50	60	80	100	"N"										
0.0	WASH BORING TO A PREDETERMINED DEPTH																					
		12.0																				
15.0	BORING TERMINATED																					

REMARKS: \* ELEVATION TO BE PROVIDED BY TVA











# Law Engineering

## Boring Record

BORING NUMBER J-11B  
 DATE DRILLED 9-19-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 1

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																	
			5	10	20	30	40	50	60	80	100	"N"								
1.0	RED SILTY CLAY-POSSIBLE FILL																			
	TANNISH-BROWN SHALEY SILTY CLAY - RESIDUUM																			
5.0	DARK BROWN AND GRAYISH GREEN SHALE																			
31.5	BORING TERMINATED																			

REMARKS: BORING ADVANCED USING AIR ROTARY EQUIPMENT





# Law Engineering


## Soil Test Boring Record

BORING NUMBER J-12A

DATE DRILLED 9-22-88

JOB NUMBER K-88195

PAGE 1 OF 1



REMARKS: \* ELEVATION TO BE PROVIDED BY TVA



# Law Engineering

## Boring Record

BORING NUMBER J-12B  
 DATE DRILLED 9-26-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 2

DEPTH (FT.)	DESCRIPTION	ELEV. *	PENETRATION-BLOWS PER FOOT																		
			5	10	20	30	40	50	60	80	100	"N"									
3.0	RED-BROWN SILTY CLAY WITH CHERT FRAGMENTS																				
	DARK GRAY ASH AND ASH AND ASH CLAY MIXTURE																				
20.0	GREENISH GRAY SHALE SLURRY WITH LIMESTONE FRAGMENTS																				
28.0	DUE TO A CAVE-IN AT 28.0 FEET THE BORING WAS OFFSET AND RE-DRILLED																				
	GRAY SHALE																				
40.0																					

REMARKS: BORING ADVANCED USING AIR ROTARY EQUIPMENT  
 \* ELEVATION TO BE PROVIDED BY TVA



# Law Engineering

## Boring Record

BORING NUMBER J-12B

DATE DRILLED 9-26-88

JOB NUMBER K-88195

PAGE 2 OF 2

DEPTH (FT.)  
40.0

DESCRIPTION

ELEV.

PENETRATION-BLOWS PER FOOT

5 10 20 30 40 50 60 80 100 "N"

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																	
			5	10	20	30	40	50	60	80	100	"N"								
40.0	GRAY SHALE																			
54.2	BORING TERMINATED																			

REMARKS:






# Law Engineering

## Soil Test Boring Record

BORING NUMBER J-13 A  
 DATE DRILLED 9-28-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 2



REMARKS: \* ELEVATION TO BE PROVIDED BY TVA





# Law Engineering

## Spring Record

BORING NUMBER J-13B  
 DATE DRILLED 9/29 - 30/88  
 JOB NUMBER K-88195  
 PAGE 1 OF 3

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																	
			*	5	10	20	30	40	50	60	80	100 "N"								
0.0																				
0.5	TOPSOIL																			
	BROWN SILTY CLAY AND WEATHERED SHALE																			
4.0	GRAY ASH																			
40.0																				

REMARKS: BORING ADVANCED USING AIR ROTARY EQUIPMENT  
 \* ELEVATION TO BE PROVIDED BY TVA



# Law Engineering

## Boring Record

BORING NUMBER J-13B

DATE DRILLED 9/29-30/88

JOB NUMBER K-88195

PAGE 2 OF 3

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																		
			5	10	20	30	40	50	60	80	100	"N"									
40.0	GRAY ASH																				
45.0	ASH AND SAND (VERY WET)																				
65.0	GRAY SHALE WITH ZONES OF LIMESTONE AND SANDSTONE																				
80.0																					

REMARKS:









# Law Engineering

## Boring Record

BORING NUMBER J-14B

DATE DRILLED 9-22-88

JOB NUMBER K-88195

PAGE 1 OF 1

DEPTH (FT.)	DESCRIPTION	ELEV. *	PENETRATION-BLOWS PER FOOT																	
			5	10	20	30	40	50	60	80	100 "N"									
0.0	RED BROWN SILTY CLAY -FILL (FILL USED FOR CONSTRUCTING THE RAILROAD)																			
18.0	GRAY BROWN SILTY CLAY WITH A TRACE OF ASH																			
24.5	REFUSAL																			
40.0	BROWN AND GRAY TO GRAY SHALE WITH CALCITE SEAMS																			

BORING TERMINATED

REMARKS: BORING ADVANCED USING AIR ROTARY EQUIPMENT

\* ELEVATION TO BE PROVIDED BY TVA





# Law Engineering


## Soil Test Boring Record

BORING NUMBER J-15

DATE DRILLED 9-23-88

JOB NUMBER K-88195

PAGE 1 OF 1



REMARKS: \* ELEVATION TO BE PROVIDED BY TVA





# Law Engineering

## Boring Record

BORING NUMBER J-15B  
 DATE DRILLED 9-21-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 2

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																	
			*	5	10	20	30	40	50	60	80	100 "N"								
0.0	WEATHERED SHALE																			
3.0	BROWN AND GRAY-BROWN SILTY CLAY WITH TRACE SHALE FRAGMENTS																			
14.0	GRAY SHALE																			
40.0																				

REMARKS: BORING ADVANCED USING AIR ROTARY EQUIPMENT

\* ELEVATION TO BE PROVIDED BY TVA





# Law Engineering

## Boring Record

BORING NUMBER J-16A  
 DATE DRILLED 10-5-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 2

DEPTH (FT.)	DESCRIPTION	ELEV. *	PENETRATION-BLOWS PER FOOT																		
			5	10	20	30	40	50	60	80	100	"N"									
0.0																					
0.2	TOPSOIL																				
	RED-BROWN AND BROWN SILTY CLAY - FILL																				
13.0	GRAY BROWN SILTY CLAY - FILL (SOME OF THE SOILS APPEAR TO BE ASSOCIATED WITH AN OLD ROAD SURFACE)	14.0																			
18.0	RED BROWN SANDY CLAY (SLURRY) - POSSIBLE RESIDUUM																				
40.0																					

REMARKS: \* ELEVATION TO BE PROVIDED BY TVA





# Law Engineering

## Boring Record

BORING NUMBER J-16B  
 DATE DRILLED 9-23-88  
 JOB NUMBER K-88195  
 PAGE 1 OF 2

DEPTH (FT.)	DESCRIPTION	ELEV. *	PENETRATION-BLOWS PER FOOT																		
			5	10	20	30	40	50	60	80	100	"N"									
0.0	RED-BROWN SILTY CLAY WITH SMALL ROCK FRAGMENTS - FILL																				
10.0	RED TO RED-BROWN TO BROWN SILTY CLAY - FILL																				
20.5	BROWN SILTY CLAY - POSSIBLE TOPSOIL																				
22.0	GRAY AND BROWN SLURRY WITH ROCK FRAGMENTS																				
40.0																					

REMARKS: BORING ADVANCED USING AIR ROTARY EQUIPMENT

\* ELEVATION TO BE PROVIDED BY TVA



# Law Engineering

## Boring Record

BORING NUMBER J-16B  
 DATE DRILLED 9-23-88  
 JOB NUMBER K-88195  
 PAGE 2 OF 2

DEPTH (FT.)	DESCRIPTION	ELEV.	PENETRATION-BLOWS PER FOOT																		
			5	10	20	30	40	50	60	80	100	"N"									
40.0																					
41.0	CASING "BLEW-OUT" AROUND 41 FEET. THE BORING WAS OFFSET AND REDRILLED  RED-BROWN, BROWN AND GRAY SILTY CLAY WITH SHALE FRAGMENTS																				
56.0	BROWN AND GRAY SHALE																				
73.0	BORING TERMINATED																				

REMARKS:



# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-1      STATION:

RANGE:

SURFACE EL: 752.0

DATE DRILLED: 7/28/94

PREPARED BY: mhd

CHECKED BY: *JA*

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	750							
5			CL	12.4	31	12	5	TN & GY SI CL, D
	745							
10			CL	19.2	26	8	9	LT BRN SI CL w/TR GY TS, MST
	740							
15			CL	17.0	26	8	6	BRN SI CL, D
	735							
20			CL	27.1	26	8	9	BRN & GY SI CL, V MST
	730							
25			CL	24.1	26	8	9	BRN & GY SI CL, V MST
	725							
30			SM	19.5	NP	NP	10	GY SI SC TR GY, MST (FA)
	720							
35								

1''-5'

\*  
LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-1 STATION:

RANGE:

SURFACE EL: 752.0

DATE DRILLED: 7/28/94

PREPARED BY: mhd

CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
			SM	27.6	NP	NP	10	BY SI SD, V MST (FA)
	715							
40								REFUSAL
	710							GROUND WATER LEVEL - 8'9"
45								
	705							
50								
	700							
55								
	695							
60								
	690							
65								
	685							
70								
1'-5'								

\*  
LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 2

PROJECT: KINGSTON FP  
 BORING: SS-2 STATION:  
 DATE DRILLED: 7/27/94

FEATURE: DREDGE CELLS  
 RANGE:  
 PREPARED BY: mhd

SURFACE EL: 764.0  
 CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
5	760	14	MH- CH	21.9	59	28	2	BRN SI CL w/GV, TR TS, D
10	755	10	MH- CH	22.8	59	28	2	R-BRN SI CL, TR GV, D
15	750	8	MH- CH	28.0	59	28	2	R-BRN SI CL, TR GV, MST
20	745	13	SM	25.6	NP	NP	10	GY SI SD w/TR GV (FA), V MST
25	740	-	SM	19.0	NP	NP	10	GY SI SD w/GV (FA), N
30	735	-	SM	28.1	NP	NP	3	BRN SD WI CL (FA), W
35	730							

1"=5'

\*  
LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-2 STATION:

RANGE:

SURFACE EL: 764.0

DATE DRILLED: 7/27/94

PREPARED BY: mhd

CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
		-	CL	33.6	26	8	9	BRN SI CL w/GY SI (FA). V MST
40	725							
		3	CL	20.1	26	8	9	ORNG & GY SI CL, V MST
45	720							
		28	ML	14.0	NP	NP	8	GY SD mix w/PKTS GY CL, MST
50	715							
		50+	ML	15.8	NP	NP	8	GY SD mix w/PKTS GY CL, MST
55	710							REFUSAL GROUND WATER LEVEL - 5'8"
60	705							
65	700							
70	695							
1'-5'								

\* AB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-3 STATION:

RANGE:

SURFACE EL: 773.0

DATE DRILLED: 7/28/94

PREPARED BY: mhd

CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	770							
5		25	ML	23.3	NP	NP	12	GY CL SI (FA), MST
	765							
10		5	SM	23.0	NP	NP	10	GY SD CL, TR GV (FA), V MST
	760							
15		4	SM	28.6	NP	NP	10	GY SD CL, TR GV (FA), V MST
	755							
20		1	SM	28.6	NP	NP	10	GY SD SI CL, TR GV (FA), W
	750							
25		2	SM	27.1	NP	NP	10	GY SD SI CL, TR GV (FA), W
	745							
30		1	SM	27.0	NP	NP	10	GY SD SI CL, TR GV (FA), W
	740							
35								

1' = 5'

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 2

PROJECT: KINGSTON FP  
BORING: SS-3 STATION:  
DATE DRILLED: 7/28/94

FEATURE: DREDGE CELLS  
RANGE:  
PREPARED BY: mhd

SURFACE EL: 773.0  
CHECKED BY: JAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
		2	ML	28.8	NP	NP	12	GY SD SI CL, TR GV (FA), W
40	735							
		2	SM	22.0	NP	NP	10	GY SD SI CL, TR GV (FA), W
45	730							
		-	ML	33.9	NP	NP	12	GY CL SI, TR GV (FA), W
50	725							
		-	ML	15.7	NP	NP	8	GY CL SI w/GV (FA), V MST
55	720							
		50+	ML	5.8	NP	NP	12	GY CL SI, TR GV
60	715							REFUSAL GROUND WATER LEVEL - 9'8"
65	710							
70	705							

1"=5'

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 2

PROJECT: KINGSTON FP  
BORING: SS-4 STATION:  
DATE DRILLED: 7/26/94

FEATURE: DREDGE CELLS  
RANGE:  
PREPARED BY: mhd

SURFACE EL: 752.0  
CHECKED BY: TA

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	750							
5		10	CL	14.2	26	8	6	LT BRN SI CL W/TS, D
	745							
10		3	CL- ML	23.8	26	4	1	BRN & GY SI CL W/TS, MST
	740							
15		8	CL	22.3	31	12	5	TN & GY SI CL (FA), V MST
	735							
20		4	SM	20.9	NP	NP	3	TN SI SD, MST
	730							
25		-	SM	34.8	NP	NP	3	TN SI SD, MST
	725							
30		7	SM	21.4	NP	NP	3	TN SI SD, MST
	720							
35								
1'-5'								

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 2

PROJECT: KINGSTON FP  
 BORING: SS-4 STATION:  
 DATE DRILLED: 7/26/94

FEATURE: DREDGE CELLS  
 RANGE:  
 PREPARED BY: mhd

SURFACE EL: 752.0  
 CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	715	36	SM	20.4	NP	NP	3	TN SI SD, MST
40								REFUSAL
	710							GROUND WATER LEVEL = 9'0"
45								
	705							
50								
	700							
55								
	695							
60								
	690							
65								
	685							
70								
1'-5'								

\* LAB CLASSIF.



# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-5 STATION:

RANGE:

SURFACE EL: 764.0

DATE DRILLED: 7/27/94

PREPARED BY: mhd

CHECKED BY: TAC

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
5	760	18	MH- CH	19.6	59	28	2	R-BRN SI CL w/TR CTH, D
10	755	14	MH- CH	24.2	59	28	2	BRN SI CL w/GV, D
15	750	54	CL- ML	23.5	26	4	1	BRN SI CL w/PKTS GY CL SI, TR CHT, MST
20	745	20	SM	24.3	NP	NP	10	GY SI SD, TR GV (FA), MST
25	740	3	CL	20.9	26	8	6	LT BRN SD SI CL, TR GV, V MST
30	735	14	CL	23.6	31	12	5	TN & GY SI CL, V MST
35	730							
1'-5'			*					LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 2

PROJECT: KINGSTON FP  
 BORING: SS-5 STATION:  
 DATE DRILLED: 7/27/94

FEATURE: DREDGE CELLS  
 RANGE:  
 PREPARED BY: mhd

SURFACE EL: 764.0  
 CHECKED BY: JAL

DEPTH ft.	EL	SPT (N)	* LOG	N	LL	PI	GR	FIELD DESCRIPTION
		16	ML	21.5	NP	NP	7	BRN SI CL w/GY FA, V MST
40	725							
		2	SM	24.2	NP	NP	3	ORNG CL SD, V MST
45	720							
		2	CL	21.9	26	8	9	TN CL SI w/PKTS GY FA, V MST
50	715							
		30	SC/ SM	10.8	NP	NP	4	LT BRN SI SD w/GV, V MST
55	710							
		50+	ML	13.9	NP	NP	12	BRN & GY CL SI, FA, MST
								REFUSAL
60	705							GROUND WATER LEVEL = 20'
65	700							
70	695							

1'-5'

\*  
LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-6      STATION:

RANGE:

SURFACE EL: 773.0

DATE DRILLED: 8/1/94

PREPARED BY: mhd

CHECKED BY: TAC

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	770							
5		24	ML	25.2	NP	NP	12	GY SI (FA), MST
	765							
10		5	SM	19.7	NP	NP	10	GY SI (FA), MST
	760							
15		2	SM	28.8	NP	NP	11	GY SI SD (FA), MST
	755							
20		-	ML	25.8	NP	NP	12	GY SI (FA), MST
	750							
25		3	ML	23.3	NP	NP	8	BRN SI CL w/GY FA, TR GY, V MST
	745							
30		1	ML	32.7	NP	NP	12	GY SI (FA), W
	740							
35								

1' = 5'

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 2

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-6      STATION:

RANGE:

SURFACE EL: 773.0

DATE DRILLED: 8/1/94

PREPARED BY: mhd

CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
		9	CL	19.6	26	8	9	BRN CL SI mix w/FA
	735							
40		12	SM	19.4	NP	NP	3	BRN SI SD, V MST
	730							
45		1	SM	29.3	NP	NP	3	BRN SI SD, V MST
	725							
50		3	SM	21.8	NP	NP	3	BRN SD CL, V MST
	720							
55		6	ML	22.3	NP	NP	8	GY SI SD w/FA, MST
	715							
60		50+	ML	9.9	NP	NP	12	GY SI, FA, MST
	710							
65								REFUSAL GROUND WATER LEVEL = 16' 7"
	705							
70								
1'-5'								

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 3

PROJECT: KINGSTON FP  
 BORING: SS-8 STATION:  
 DATE DRILLED: 8/2/94

FEATURE: DREDGE CELLS  
 RANGE:  
 PREPARED BY: mhd

SURFACE EL: 782.0  
 CHECKED BY: TAC

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	780							
5		50+	SM	17.6	NP	NP	10	GY SI (FA), TR GV, D
	775							
10		50+	SM	18.4	NP	NP	10	GY SI (FA), TR GV, D
	770							
15		50+	SM	21.9	NP	NP	10	GY SI (FA), TR GV, D
	765							
20		8	SM	43.9	NP	NP	11	GY SI SD (FA), MST
	760							
25		15	SM	17.9	NP	NP	10	GY SI SD w/GV (FA), MST
	755							
30		-	ML	31.7	NP	NP	12	GY SI (FA), N
	750							
35								
1'-5'								

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 3

PROJECT: KINGSTON FP  
 BORING: SS-8 STATION:  
 DATE DRILLED: 8/2/94

FEATURE: DREDGE CELLS  
 RANGE:  
 PREPARED BY: mhd

SURFACE EL: 782.0  
 CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
40	745	-	ML	24.4	NP	NP	12	GY SI (FA), MST
45	740	3	ML	23.8	NP	NP	12	GY SI (FA), MST
50	735	9	ML	31.2	NP	NP	12	GY SI (FA), MST
55	730	4	ML	22.3	NP	NP	8	GY CL SI w/LUMPS TN SI CL, MST
60	725	13	ML	18.2	NP	NP	7	MOTT BRN/TN/GY SI CL, MST
65	720	13	ML	18.6	NP	NP	7	MOTT BRN/TN/GY SI CL, MST
70	715	4	SC/ SM	27.7	NP	NP	4	TN SI SD, W
1'-5'		* LAB CLASSIF.						

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 3 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-8      STATION:

RANGE:

SURFACE EL: 782.0

DATE DRILLED: 8/2/94

PREPARED BY: mhd

CHECKED BY: TAC

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	710	5	SM	24.9	NP	NP	10	GY SD SI (FA), W
75								
	705	7	SC/ SM	22.7	NP	NP	4	TN SI SD, V MST
80								REFUSAL
	700							GROUND WATER LEVEL = 11' 3"
85								
	695							
90								
	690							
95								
	685							
100								
	680							
105								
1'-5'								

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-9      STATION:

RANGE:

SURFACE EL: 795.0

DATE DRILLED: 8/2/94

PREPARED BY: mhd

CHECKED BY: TA✓

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	795							
5	790	20	ML	17.8	NP	NP	12	GY SI (FA), MST
10	785	50+	ML	19.5	NP	NP	12	GY SI (FA), MST
15	780	44	ML	20.1	NP	NP	12	GY SI (FA), MST
20	775	46	ML	18.3	NP	NP	12	GY SI (FA), MST
25	770	6	ML	30.2	NP	NP	12	GY SI (FA), MST
30	765	5	ML	35.2	NP	NP	12	GY SI (FA), W
35	760							

1' = 5'

\*  
LAB CLASSIF.



# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-9 STATION:

RANGE:

SURFACE EL: 795.0

DATE DRILLED: 8/2/94

PREPARED BY: mhd

CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	760	2	ML	17.3	NP	NP	12	GY SI (FA), W
40	755	1	ML	31.0	NP	NP	12	GY SI (FA), W
45	750	-	ML	23.0	NP	NP	12	GY SI (FA), D
50	745	-	ML	31.7	NP	NP	12	GY SI (FA), TR GY, W
55	740	5	ML	30.0	NP	NP	12	GY SI (FA), TR GY, W
60	735	6	ML	32.6	NP	NP	12	GY SI (FA), TR GY, W
65	730	-	ML	26.9	NP	NP	8	BRN SI CL w/GY SI (FA), MST
70	725							

1''-5'      \*  
LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 3 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-9      STATION:

RANGE:

SURFACE EL: 795.0

DATE DRILLED: 8/2/94

PREPARED BY: mhd

CHECKED BY: *TAL*

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	725							
		13	CL	19.2	26	8	9	BRN, TN & GY SI CL, TR CL, MST
75	720	19	CL	19.5	26	8	6	ORNG-BRN SI CL, MST
80	715	4	SM	20.5	NP	NP	10	GY SD SI, W
85	710	19	SC/ SM	23.1	NP	NP	4	TN SI SD
90	705	8	SC/ SM	23.1	NP	NP	4	GY SI SD
95	700							REFUSAL GROUND WATER LEVEL - 29'
100	695							
105	690							
1'-5"			* LAB CLASSIF.					

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 1 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-10 STATION:

RANGE:

SURFACE EL: 797.5

DATE DRILLED: 8/8/94

PREPARED BY: mhd

CHECKED BY: TAL

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
	795							
5		50+	ML	17.3	NP	NP	12	GY SI (FA), MST
	790							
10		26	ML	24.7	NP	NP	12	GY SI (FA), MST
	785							
15		25	ML	15.0	NP	NP	12	GY SD SI, TR GY, MST
	780							
20		5	ML	22.1	NP	NP	12	GY SI (FA), MST
	775							
25		4	ML	27.4	NP	NP	12	GY SI (FA), MST
	770							
30		14	ML	29.1	NP	NP	12	GY SI (FA), MST
	765							
35								
1'-5'								

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 2 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-10 STATION:

RANGE:

SURFACE EL: 797.5

DATE DRILLED: 8/8/94

PREPARED BY: mhd

CHECKED BY: 7A

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
		18	SM	31.2	NP	NP	11	GY SD SI (FA) w/GV. W
40	760							
		9	ML	31.4	NP	NP	12	GY SI (FA), V MST
45	755							
		-	ML	27.0	NP	NP	12	GY SD SI w/GV (FA), V MST
50	750							
		-	ML	27.2	NP	NP	12	GY SD SI w/GV (FA), V MST
55	745							
		6	SM	30.7	NP	NP	11	GY PGD SI SD (FA), V MST
60	740							
		9	SM	16.4	NP	NP	11	GY PGD SI SD (FA), V MST
65	735							
		25	SM	19.4	NP	NP	11	CRS PGD SI SD w/GV (FA)
70	730							

1" = 5'

\* LAB CLASSIF.

# SINGLETON LABORATORIES

SOIL PROFILE: SPLIT-SPOON

SHEET 3 OF 3

PROJECT: KINGSTON FP

FEATURE: DREDGE CELLS

BORING: SS-10 STATION:

RANGE:

SURFACE EL: 797.5

DATE DRILLED: 8/8/94

PREPARED BY: mhd

CHECKED BY: TAC

DEPTH ft.	EL	SPT (N)	* LOG	W	LL	PI	GR	FIELD DESCRIPTION
		39	ML	19.0	NP	NP	8	BRN SI CL w/PKTS GY SI (FA), V MST
	725							
75		17	CL	19.2	26	8	9	BRN & GY SI CL, V MST
	720							
80		18	CL	16.9	26	8	6	ORNG-BRN SD SI CL, MST
	715							
85		16	ML	18.9	NP	NP	8	GY SI SD, MST
	710							
90		50+	ML	3.7	NP	NP	8	GY SI SD w/GV
	705							
95								REFUSAL GROUND WATER LEVEL -
	700							
100								
	695							
105								

1''=5'

\*  
LAB CLASSIF.

**APPENDIX II**


**INSTALLATION RECORDS FOR MONITORING WELLS 9A THROUGH 20**

**[from Velasco and Bohac, 1991]**

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-8 A</u>	INSTALLATION DATE <u>10-3 TO 10-4-88</u>
LOCATION <u>PLANT COORDINATES W 9+44 N 19+07</u>	
GROUND SURFACE ELEVATION <u>769.4' MSL</u>	TOP OF INNER CASING <u>772.5' MSL</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>POWER AUGER</u>	DRILLING CONTRACTOR <u>LAW ENGINEERING</u>
BOREHOLE DIAMETER <u>11 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)




ENQ LAB 10/2/80

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-9B</u>	INSTALLATION DATE <u>9-28 TO 9-29-88</u>
LOCATION <u>PLANT COORDINATES W 9+42, N 19+22</u>	
GROUND SURFACE ELEVATION <u>789.6' MLS</u>	TOP OF INNER CASING <u>772.4' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIR ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>5 7/8 (ROLLER CONE)</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)




ENG LAB 10/2/88



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-10</u>	INSTALLATION DATE <u>9-27-88</u>
LOCATION <u>PLANT COORDINATES W 4+79, N 18+36</u>	
GROUND SURFACE ELEVATION <u>753.8' MLS</u>	TOP OF INNER CASING <u>756.8' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>POWER AUGER</u>	DRILLING CONTRACTOR <u>LAW ENGINEERING</u>
BOREHOLE DIAMETER <u>11 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J - 10A</u>	INSTALLATION DATE <u>9-18 TO 9-27-88</u>
LOCATION <u>PLANT COORDINATES W 4+88, N 16+51</u>	
GROUND SURFACE ELEVATION <u>753.5' MLS</u>	TOP OF INNER CASING <u>756.3' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIR ROTARY &amp; POWER AUGER</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING &amp; LAW ENGINEERING</u>
BOREHOLE DIAMETER <u>11 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-10 B</u>	INSTALLATION DATE <u>9-23-88</u>
LOCATION <u>PLANT COORDINATES W 4+73, N 16+51</u>	
GROUND SURFACE ELEVATION <u>753.6' MLS</u>	TOP OF INNER CASING <u>756.4' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>POWER AUGER</u>	DRILLING CONTRACTOR <u>LAW ENGINEERING</u>
BOREHOLE DIAMETER <u>11 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)




ENG LAB 10/2/90

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-11 B</u>	INSTALLATION DATE <u>9-19-88</u>
LOCATION <u>PLANT COORDINATES W 7+84, N 7+87</u>	
GROUND SURFACE ELEVATION <u>765.6' MLS</u>	TOP OF INNER CASING <u>769.1' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>0.10 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIR/WATER ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)




ENGLAB 10/2/80

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>	
WELL NUMBER <u>J-12 A</u>	INSTALLATION DATE <u>9-22-88</u>	
LOCATION <u>PLANT COORDINATES W 17+40, N 15+57</u>		
GROUND SURFACE ELEVATION <u>784.3' MLS</u>	TOP OF INNER CASING <u>757.3' MLS</u>	
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>	
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>	
DRILLING TECHNIQUE <u>POWER AUGER</u>	DRILLING CONTRACTOR <u>LAW ENGINEERING</u>	
BOREHOLE DIAMETER <u>10 1/4 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>	
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>	
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>	

COMMENTS \_\_\_\_\_


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-12B</u>	INSTALLATION DATE <u>9-27-88</u>
LOCATION <u>PLANT COORDINATES W 17+53, N 15+85</u>	
GROUND SURFACE ELEVATION <u>764.1' MLS</u>	TOP OF INNER CASING <u>767.1' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AUGER AND AIR ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>AUGER 8" ROTARY 5 7/8" DIA.</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)




ENG LAB 10/2/80

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-13 A</u>	INSTALLATION DATE <u>9-28 TO 9-30-88</u>
LOCATION <u>PLANT COORDINATES W 7+13, N 31+23</u>	
GROUND SURFACE ELEVATION <u>788.5' M.L.S.</u>	TOP OF INNER CASING <u>789.2' M.L.S.</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>POWER AUGER</u>	DRILLING CONTRACTOR <u>LAW ENGINEERING</u>
BOREHOLE DIAMETER <u>APPROXIMATELY 11 INCHES</u>	FIELD REPRESENTATIVE <u>H. W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON STEAM PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-13 B</u>	INSTALLATION DATE <u>9-28 TO 9-30-88</u>
LOCATION <u>PLANT COORDINATES</u>	<u>W 7+34, N 31+04</u>
GROUND SURFACE ELEVATION <u>767.4' MLS</u>	TOP OF INNER CASING <u>770.5' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AUGER AND AIR ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8" AUGER, 5 7/8" (ROLLER CONE)</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)






## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-14 A</u>	INSTALLATION DATE <u>9-22-88</u>
LOCATION <u>PLANT COORDINATES W 30+46, N 37+49</u>	
GROUND SURFACE ELEVATION <u>758.3' MLS</u>	TOP OF INNER CASING <u>761.3' MLS</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIR/WATER ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8 INCHES</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-14 B</u>	INSTALLATION DATE <u>9-22-88</u>
LOCATION <u>PLANT COORDINATES</u>	<u>W 30+56, S 37+60</u>
GROUND SURFACE ELEVATION <u>758.3' MSL</u>	TOP OF INNER CASING <u>761.3' MSL</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIR/WATER ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8 INCHES</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-15 A</u>	INSTALLATION DATE <u>9-21-88</u>
LOCATION <u>PLANT COORDINATES W 24+39. N 6+35</u>	
GROUND SURFACE ELEVATION <u>793.1' MSL</u>	TOP OF INNER CASING <u>796.1' MSL</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIR/WATER ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8 INCHES</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-15 B</u>	INSTALLATION DATE <u>8-21-88</u>
LOCATION <u>PLANT COORDINATES</u>	<u>W 24+38, N 8+50</u>
GROUND SURFACE ELEVATION <u>792.9' MSL</u>	TOP OF INNER CASING <u>795.9' MSL</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AIRWATER ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8 INCHES</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	

(NOT TO SCALE)




ENQ LAB 10/5/80

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-16 A</u>	INSTALLATION DATE <u>10-5-88</u>
LOCATION <u>PLANT COORDINATES W 27+87, N 40+08</u>	
GROUND SURFACE ELEVATION <u>756.6'</u>	TOP OF INNER CASING <u>768.6'</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCH</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>POWER AUGER</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>11 INCHES</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT <u>KINGSTON FOSSIL PLANT</u>	JOB NUMBER <u>K-88195</u>
WELL NUMBER <u>J-16 B</u>	INSTALLATION DATE <u>9-23-88</u>
LOCATION <u>PLANT COORDINATES W 27+80.N 40+34</u>	
GROUND SURFACE ELEVATION <u>765.4' MSL</u>	TOP OF INNER CASING <u>768.1' MSL</u>
GRANULAR BACKFILL MATERIAL <u>QUARTZ SAND, COARSE</u>	SLOT SIZE <u>.010 INCHES</u>
CASING MATERIAL <u>PVC</u>	CASING DIAMETER <u>2 INCHES</u>
DRILLING TECHNIQUE <u>AUGER AND AIR ROTARY</u>	DRILLING CONTRACTOR <u>HIGHLAND DRILLING</u>
BOREHOLE DIAMETER <u>8" AUGER, 5 7/8" AIR ROTARY</u>	FIELD REPRESENTATIVE <u>H.W. ROBINSON</u>
LOCKABLE COVER ? <u>YES</u>	KEY CODE/COMBINATION <u>2043</u>
RISER MATERIAL <u>PVC</u>	SCREEN MATERIAL <u>PVC</u>
COMMENTS _____	


(NOT TO SCALE)



## TYPE II MONITORING WELL INSTALLATION RECORD

<b>PROJECT</b>	Kingston Fossil Plant		
<b>WELL NUMBER</b>	17	<b>INSTALLATION DATE</b>	July 8, 1992
<b>LOCATION</b>	Plant coordinates	W 1+81, N 58+80	
<b>GROUND SURFACE ELEVATION</b>	762.42' MSL	<b>TOP OF INNER CASING</b>	765.42' MSL
<b>GRANULAR BACKFILL MATERIAL</b>	Sand	<b>SLOT SIZE</b>	0.010"
<b>CASING MATERIAL</b>	4" SCH 40 PVC	<b>CASING DIAMETER</b>	4" SCH 40 PVC
<b>DRILLING TECHNIQUE</b>	HSA	<b>DRILLING CONTRACTOR</b>	John Voekel, Law Engr.
<b>BOREHOLE DIAMETER</b>	4.25" HSA (ID)	<b>FIELD REPRESENTATIVE</b>	Mel Wagner
<b>LOCKABLE COVER ?</b>	Yes	<b>FILTER CLOTH AROUND SCREEN?</b>	No
<b>COMMENTS</b>	The 4.25" HSA was used first with the continuous sampling barrel. Next, the 6.25" (ID) auger was used to provide room for the sand pack around the screen.		

(NOT TO SCALE)




ENG LAB 6/10/92

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT	Kingston Fossil Plant		
WELL NUMBER	18	INSTALLATION DATE	July 10, 1992
LOCATION	Plant coordinates	W 1+70, N 58+98	
GROUND SURFACE ELEVATION	764.32' MSL	TOP OF INNER CASING	767.32' MSL
GRANULAR BACKFILL MATERIAL	Sand	SLOT SIZE	0.010 "
CASING MATERIAL	4" SCH 40 PVC	CASING DIAMETER	4" SCH 40 PVC
DRILLING TECHNIQUE	HSA	DRILLING CONTRACTOR	John Voekel, Law Engr.
BOREHOLE DIAMETER	4.25" HSA (ID)	FIELD REPRESENTATIVE	Mel Wagner
LOCKABLE COVER ?	Yes	FILTER CLOTH AROUND SCREEN?	No
COMMENTS	The 4.25" HSA was used first with the continuous sampling barrel. Next, the 6.25" (ID) auger was used to provide room for the sand pack around the screen.		

(NOT TO SCALE)



END LAB 6/19/92




## TYPE II MONITORING WELL INSTALLATION RECORD

**PROJECT** Kingston Fossil Plant  
**WELL NUMBER** 19 **INSTALLATION DATE** July 13, 1992  
**LOCATION** Plant coordinates W 1+55, N 59+21  
**GROUND SURFACE ELEVATION** 763.90' MSL **TOP OF INNER CASING** 766.90' MSL  
**GRANULAR BACKFILL MATERIAL** Sand **SLOT SIZE** 0.010"  
**CASING MATERIAL** 4" SCH 40 PVC **CASING DIAMETER** 4" SCH 40 PVC  
**DRILLING TECHNIQUE** HSA **DRILLING CONTRACTOR** John Voekel, Law Engr.  
**BOREHOLE DIAMETER** 4.25" HSA (ID) **FIELD REPRESENTATIVE** Mel Wagner  
**LOCKABLE COVER ?** Yes **FILTER CLOTH AROUND SCREEN?** No

**COMMENTS** The 4.25" HSA was used first with the continuous sampling barrel. Next, the 6.25" (ID) auger was used to provide room for the sand pack around the screen.

(NOT TO SCALE)




END LAB 8/19/92

## TYPE II MONITORING WELL INSTALLATION RECORD

PROJECT	Kingston Fossil Plant		
WELL NUMBER	20	INSTALLATION DATE	July 10, 1992
LOCATION	Plant coordinates W 1+24, N 59+67		
GROUND SURFACE ELEVATION	750.06' MSL	TOP OF INNER CASING	753.06' MSL
GRANULAR BACKFILL MATERIAL	Sand	SLOT SIZE	0.010 "
CASING MATERIAL	4" SCH 40 PVC	CASING DIAMETER	4" SCH 40 PVC
DRILLING TECHNIQUE	HSA	DRILLING CONTRACTOR	John Voekel, Law Engr.
BOREHOLE DIAMETER	4.25" HSA (ID)	FIELD REPRESENTATIVE	Mel Wagner
LOCKABLE COVER ?	Yes	FILTER CLOTH AROUND SCREEN?	No

**COMMENTS**    The 4.25" HSA was used first with the continuous sampling barrel. The 6.25" HSA was not used because the well was drilled in a clay-filled berm.

(NOT TO SCALE)



ENG. LAB 6/19/92

**APPENDIX III**  
**GROUNDWATER QUALITY DATA**

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 94/12/06.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
2	ORP (MV)	18	-49.3	-78.5	-120	135	
2	CONDUCTIVITY (UMHOS/CM)	18	840.7	847	756	914	
2	DISSOLVED OXYGEN (MG/L)	18	0.3	0.3	0.1	1	
2	TEMPERATURE (DEG C)	18	16.2	16.3	13.6	17.7	
2	COD (MG/L)	1	22	22	22	22	
2	PH (STANDARD UNITS)	18	6.6	6.6	6.3	6.8	2
2	ALKALINITY (MG/L)	17	430.8	470	42	535	
2	PHEN-PH ALKALINITY (MG/L)	3	0	0	0	0	
2	ACIDITY (MG/L)	9	199.6	223	0	282	
2	CO2 ACIDITY (MG/L)	6	199.1	225.5	52	246	
2	CO2 (MG/L)	7	196.9	196	154	248	
2	CA/MG HARDNESS (MG/L)	20	415.9	411.5	377	489	
2	NITRATE+NITRITE NITROGEN (MG/L)	13	0.1	0	0	0.6	0
2	TOTAL ORGANIC CARBON (MG/L)	20	6.8	7.5	0.9	11	
2	TOTAL INORGANIC CARBON (MG/L)	20	148.2	149.5	68	310	
2	SULFIDE (MG/L)	9	0.1	0.1	0	0.2	
2	CALCIUM (MG/L)	20	97.6	96	87	110	
2	DISSOLVED CALCIUM (MG/L)	3	102	99	97	110	
2	MAGNESIUM (MG/L)	20	41.8	42	31	52	
2	DISSOLVED MAGNESIUM (MG/L)	3	44	43	41	48	
2	SODIUM (MG/L)	20	5.9	6.2	2.6	7.9	
2	POTASSIUM (MG/L)	20	3.5	2.8	2.2	8.5	
2	CHLORIDE (MG/L)	20	3.5	4	1	6	0
2	SULFATE (MG/L)	20	39.2	20.5	2	210	0
2	FLUORIDE (MG/L)	13	0.2	0.1	0.1	0.5	0
2	ALUMINUM (UG/L)	20	7785	5550	170	19000	19
2	DISSOLVED ALUMINUM (UG/L)	3	56.7	50	50	70	0
2	ANTIMONY (UG/L)	4	1.3	1	1	2	0
2	ARSENIC (UG/L)	20	225.9	210	73	440	20
2	DISSOLVED ARSENIC (UG/L)	3	176.7	180	150	200	3
2	BARIUM (UG/L)	18	551.1	530	200	770	0
2	DISSOLVED BARIUM (UG/L)	3	433.3	460	360	480	0
2	BERYLLIUM (UG/L)	4	2.3	1	1	6	1
2	BORON (UG/L)	20	4095	2800	1700	25000	
2	DISSOLVED BORON (UG/L)	3	2433.3	2400	2100	2800	
2	CADMIUM (UG/L)	20	0.4	0.3	0.1	1	0
2	DISSOLVED CADMIUM (UG/L)	3	0.7	0.6	0.1	1.4	0
2	CHROMIUM (UG/L)	18	7.2	6	2	17	0
2	DISSOLVED CHROMIUM (UG/L)	3	1	1	1	1	0
2	COPPER (UG/L)	20	18.5	10	10	70	0
2	DISSOLVED COPPER (UG/L)	3	20	20	10	30	0
2	IRON - TOTAL (UG/L)	20	48200	48500	4000	73000	20
2	DISSOLVED IRON (UG/L)	3	35666.7	36000	34000	37000	3
2	LEAD (UG/L)	18	11.6	9.5	1	25	0
2	DISSOLVED LEAD (UG/L)	3	1	1	1	1	0

Continued

2	LITHIUM (UG/L)	13	30	30	10	70	
2	DISSOLVED LITHIUM (UG/L)	3	20	20	20	20	
2	MANGANESE (UG/L)	20	5075	5200	2100	6500	20
2	DISSOLVED MANGANESE (UG/L)	3	4966.7	5100	4500	5300	3
2	MOLYBDENUM (UG/L)	6	63.3	35	20	180	
2	DISSOLVED MOLYBDENUM (UG/L)	1	20	20	20	20	
2	MERCURY (UG/L)	1	0.2	0.2	0.2	0.2	0
2	NICKEL (UG/L)	4	10.3	8	7	18	0
2	SELENIUM (UG/L)	13	1.2	1	1	3	0
2	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
2	SILICON (UG/L)	16	21981.3	21000	8700	36000	
2	DISSOLVED SILICON (UG/L)	3	15666.7	16000	15000	16000	
2	STRONTIUM (UG/L)	18	1644.4	1500	1200	2700	
2	DISSOLVED STRONTIUM (UG/L)	3	1366.7	1400	1200	1500	
2	VANADIUM (UG/L)	18	17.2	10	10	30	
2	DISSOLVED VANADIUM (UG/L)	3	10	10	10	10	
2	ZINC (UG/L)	20	98.5	95	10	330	0
2	DISSOLVED ZINC (UG/L)	3	20	20	10	30	0
2	TOTAL DISSOLVED SOLIDS (MG/L)	20	428	455	240	540	2
2	TOTAL SUSPENDED SOLIDS (MG/L)	15	393.9	400	12	1000	
2	WATER SURF. FR MP (M)	21	3	3	2.5	5.1	
2	WATER SURF. ELVN (M, MSL)	12	230.3	230.9	224.7	231.3	
2	WATER SURF. ELVN (FT, MSL)	12	755.5	757.5	737.3	758.8	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 94/12/06.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
4A	ORP (MV)	18	349.8	373.5	170	632	
4A	CONDUCTIVITY (UMHOS/CM)	19	2478.6	2825	1.5	3500	
4A	DISSOLVED OXYGEN (MG/L)	19	0.7	0.6	0	1.7	
4A	TEMPERATURE (DEG C)	19	16.6	16.3	13.6	21.2	
4A	PH (STANDARD UNITS)	19	3.5	3.2	2.6	5.6	19
4A	ALKALINITY (MG/L)	18	14.3	0	0	179	
4A	PHEN-PH ALKALINITY (MG/L)	6	0	0	0	0	
4A	ACIDITY (MG/L)	7	497.9	680	0	830	
4A	CO2 ACIDITY (MG/L)	7	679.3	832	0	943	
4A	CO2 (MG/L)	6	608.7	616	440	730	
4A	CA/MG HARDNESS (MG/L)	19	1089	1124.2	822	1285.6	
4A	NITRATE+NITRITE NITROGEN (MG/L)	10	0.2	0	0	0.9	0
4A	TOTAL ORGANIC CARBON (MG/L)	18	1.6	1.4	0.7	2.6	
4A	TOTAL INORGANIC CARBON (MG/L)	18	31.4	30	6	90	
4A	SULFIDE (MG/L)	6	0	0	0	0	
4A	CALCIUM (MG/L)	19	301.6	320	240	360	
4A	DISSOLVED CALCIUM (MG/L)	5	302	300	270	340	
4A	MAGNESIUM (MG/L)	19	81.6	84	51	101	
4A	DISSOLVED MAGNESIUM (MG/L)	5	77	72	52	96	
4A	SODIUM (MG/L)	19	9.1	9.2	4.5	12	
4A	POTASSIUM (MG/L)	19	5.4	5.7	1.7	8	
4A	CHLORIDE (MG/L)	19	3.4	3	1	8	0
4A	SULFATE (MG/L)	19	1626.3	1600	880	2400	19
4A	FLUORIDE (MG/L)	18	1.1	0.8	0.1	3.2	0
4A	ALUMINUM (UG/L)	19	8752.6	8800	3900	17000	19
4A	DISSOLVED ALUMINUM (UG/L)	5	8700	8500	8000	9800	5
4A	ANTIMONY (UG/L)	5	1.4	1	1	3	0
4A	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
4A	ARSENIC (UG/L)	19	3.1	2	1	13	0
4A	DISSOLVED ARSENIC (UG/L)	5	3.6	1	1	13	0
4A	BARIUM (UG/L)	17	107.1	90	10	470	0
4A	DISSOLVED BARIUM (UG/L)	5	106	20	10	300	0
4A	BERYLLIUM (UG/L)	5	1.6	2	1	2	0
4A	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
4A	BORON (UG/L)	19	1372.6	890	500	7300	
4A	DISSOLVED BORON (UG/L)	5	852	720	500	1400	
4A	CADMIUM (UG/L)	19	3.5	3.2	1.9	5.4	2
4A	DISSOLVED CADMIUM (UG/L)	5	3.8	3	2	6.1	2
4A	CHROMIUM (UG/L)	17	5.3	2	1	24	0
4A	DISSOLVED CHROMIUM (UG/L)	5	1.4	1	1	2	0
4A	COPPER (UG/L)	19	37.9	10	10	170	0
4A	DISSOLVED COPPER (UG/L)	5	76	80	10	190	0
4A	IRON - TOTAL (UG/L)	19	318211	320000	36000	490000	19
4A	DISSOLVED IRON (UG/L)	5	334000	280000	250000	470000	5

Continued

4A	LEAD (UG/L)	17	14	11	1	38	0
4A	DISSOLVED LEAD (UG/L)	5	7.2	5	2	12	0
4A	LITHIUM (UG/L)	12	24.8	30	10	30	
4A	DISSOLVED LITHIUM (UG/L)	5	22.8	24	10	40	
4A	MANGANESE (UG/L)	19	53473.7	56000	19000	87000	19
4A	DISSOLVED MANGANESE (UG/L)	5	53200	50000	42000	67000	5
4A	MOLYBDENUM (UG/L)	8	20	20	20	20	
4A	DISSOLVED MOLYBDENUM (UG/L)	5	20	20	20	20	
4A	NICKEL (UG/L)	6	124.7	115	98	180	4
4A	DISSOLVED NICKEL (UG/L)	1	52	52	52	52	0
4A	SELENIUM (UG/L)	10	1	1	1	1	0
4A	SILICON (UG/L)	14	17407.1	18500	8800	22000	
4A	DISSOLVED SILICON (UG/L)	4	20500	21000	18000	22000	
4A	STRONTIUM (UG/L)	17	1282.4	1300	900	1600	
4A	DISSOLVED STRONTIUM (UG/L)	5	1300	1400	1000	1500	
4A	VANADIUM (UG/L)	17	24.1	10	10	90	
4A	DISSOLVED VANADIUM (UG/L)	5	14	10	10	30	
4A	ZINC (UG/L)	19	727.4	690	440	1200	0
4A	DISSOLVED ZINC (UG/L)	5	780	660	520	1200	0
4A	TOTAL DISSOLVED SOLIDS (MG/L)	19	2678.9	2800	1700	3600	19
4A	TOTAL SUSPENDED SOLIDS (MG/L)	13	63.8	27	10	240	
4A	WATER SURF. FR MP (M)	21	4.4	4.6	2.3	6.3	
4A	WATER SURF. ELVN (M, MSL)	10	225.7	225.8	223.4	227.9	
4A	WATER SURF. ELVN (FT, MSL)	10	740.5	740.8	733.1	747.8	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 94/12/06.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
4B	ORP (MV)	21	260.3	278	20	470	
4B	CONDUCTIVITY (UMHOS/CM)	21	1072.3	1074	770	1550	
4B	DISSOLVED OXYGEN (MG/L)	21	4.4	4	0.4	8.8	
4B	TEMPERATURE (DEG C)	20	16.5	16.5	13.2	22	
4B	PH (STANDARD UNITS)	21	6.6	6.7	5.2	7	5
4B	ALKALINITY (MG/L)	20	229.3	228.5	125	360	
4B	PHEN-PH ALKALINITY (MG/L)	6	0	0	0	0	
4B	ACIDITY (MG/L)	8	33.6	25	0	87	
4B	CO2 ACIDITY (MG/L)	9	83.7	71	37	185	
4B	CO2 (MG/L)	8	36.7	32.5	16.7	76.6	
4B	CA/MG HARDNESS (MG/L)	21	645.8	656.6	445	923	
4B	NITRATE+NITRITE NITROGEN (MG/L)	12	0.2	0	0	1.3	0
4B	TOTAL ORGANIC CARBON (MG/L)	20	3.4	3	1.8	6.4	
4B	TOTAL INORGANIC CARBON (MG/L)	21	89.5	89	41	150	
4B	SULFIDE (MG/L)	8	0	0	0	0	
4B	CALCIUM (MG/L)	21	222.9	230	150	320	
4B	DISSOLVED CALCIUM (MG/L)	7	235.7	220	170	310	
4B	MAGNESIUM (MG/L)	21	21.7	20	17	32	
4B	DISSOLVED MAGNESIUM (MG/L)	7	21.9	18	16	31	
4B	SODIUM (MG/L)	21	2.9	2.8	1.7	6.8	
4B	POTASSIUM (MG/L)	21	4	3.7	2.3	8.2	
4B	CHLORIDE (MG/L)	21	2.9	2	1	7	0
4B	SULFATE (MG/L)	21	441.6	430	54	800	20
4B	FLUORIDE (MG/L)	20	0.2	0.2	0.1	0.7	0
4B	ALUMINUM (UG/L)	21	1016.2	400	50	4200	16
4B	DISSOLVED ALUMINUM (UG/L)	7	51.4	50	50	60	0
4B	ANTIMONY (UG/L)	5	1.6	1	1	4	0
4B	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
4B	ARSENIC (UG/L)	21	3.6	2	1	11	0
4B	DISSOLVED ARSENIC (UG/L)	7	1.2	1	1	2	0
4B	BARIUM (UG/L)	19	39.5	30	10	80	0
4B	DISSOLVED BARIUM (UG/L)	7	20	10	10	40	0
4B	BERYLLIUM (UG/L)	5	1	1	1	1	0
4B	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
4B	BORON (UG/L)	21	533.3	500	500	1200	
4B	DISSOLVED BORON (UG/L)	7	500	500	500	500	
4B	CADMIUM (UG/L)	20	0.3	0.3	0.1	0.8	0
4B	DISSOLVED CADMIUM (UG/L)	7	0.4	0.2	0.1	1.5	0
4B	CHROMIUM (UG/L)	18	6.4	2	1	58	0
4B	DISSOLVED CHROMIUM (UG/L)	7	1	1	1	1	0
4B	COPPER (UG/L)	21	16.7	10	10	60	0
4B	DISSOLVED COPPER (UG/L)	7	17.1	10	10	60	0
4B	IRON - TOTAL (UG/L)	21	5077.6	3600	380	16000	21
4B	DISSOLVED IRON (UG/L)	7	172.9	180	10	340	2



Continued

4B	LEAD (UG/L)	19	6.2	3	1	38	0
4B	DISSOLVED LEAD <sup>2+</sup> (UG/L)	7	1	1	1	1	0
4B	LITHIUM (UG/L)	14	10	10	10	10	
4B	DISSOLVED LITHIUM (UG/L)	7	10	10	10	10	
4B	MANGANESE (UG/L)	21	3171.9	2600	760	11000	21
4B	DISSOLVED MANGANESE (UG/L)	7	382.1	420	5	800	6
4B	MOLYBDENUM (UG/L)	8	20	20	20	20	
4B	DISSOLVED MOLYBDENUM (UG/L)	5	20	20	20	20	
4B	NICKEL (UG/L)	6	14.3	15.5	3	23	0
4B	DISSOLVED NICKEL (UG/L)	1	2	2	2	2	0
4B	SELENIUM (UG/L)	12	1	1	1	1	0
4B	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
4B	SILICON (UG/L)	16	7825	7050	3500	13000	
4B	DISSOLVED SILICON (UG/L)	6	8116.7	7750	6400	11000	
4B	STRONTIUM (UG/L)	19	357.9	360	240	500	
4B	DISSOLVED STRONTIUM (UG/L)	7	314.3	280	190	490	
4B	VANADIUM (UG/L)	19	10	10	10	10	
4B	DISSOLVED VANADIUM (UG/L)	7	10	10	10	10	
4B	ZINC (UG/L)	21	46.7	40	10	110	0
4B	DISSOLVED ZINC (UG/L)	7	15.7	10	10	30	0
4B	TOTAL DISSOLVED SOLIDS (MG/L)	21	811	800	590	1200	21
4B	TOTAL SUSPENDED SOLIDS (MG/L)	15	47.2	15	6	420	
4B	WATER SURF. FR MP (M)	23	4.1	3.2	1.6	10.1	
4B	WATER SURF. ELVN (M, MSL)	11	225.2	224.9	223.4	227.3	
4B	WATER SURF. ELVN (FT, MSL)	11	738.9	737.8	732.9	745.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 92/09/01

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
5	ORP (MV)	15	91.1	60	20	320	
5	CONDUCTIVITY (UMHOS/CM)	15	2949.1	3300	386	4530	
5	DISSOLVED OXYGEN (MG/L)	15	0.4	0.4	0	0.9	
5	TEMPERATURE (DEG C)	15	17.5	17	14.6	23	
5	PH (STANDARD UNITS)	15	5.6	5.6	5.3	6.1	15
5	ALKALINITY (MG/L)	13	84.4	80	34	195	
5	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
5	ACIDITY (MG/L)	5	1194.4	1500	0	1692	
5	CO2 ACIDITY (MG/L)	4	1085.3	1090	365	1796	
5	CO2 (MG/L)	4	1314	1346.5	1074	1489	
5	CA/MG HARDNESS (MG/L)	15	1079.7	1111	572.9	1352	
5	NITRATE+NITRITE NITROGEN (MG/L)	10	0.6	0.1	0	3.6	0
5	TOTAL ORGANIC CARBON (MG/L)	14	3.6	3.5	1.1	5.9	
5	TOTAL INORGANIC CARBON (MG/L)	14	37.7	33	4	130	
5	SULFIDE (MG/L)	6	0	0	0	0	
5	CALCIUM (MG/L)	15	285.3	290	180	360	
5	DISSOLVED CALCIUM (MG/L)	4	285	290	210	350	
5	MAGNESIUM (MG/L)	15	89.2	95	30	120	
5	DISSOLVED MAGNESIUM (MG/L)	4	71.8	65.5	46	110	
5	SODIUM (MG/L)	14	9	9.2	6.5	12	
5	POTASSIUM (MG/L)	14	6.2	5.7	3.5	12	
5	CHLORIDE (MG/L)	14	3.4	4	1	6	0
5	SULFATE (MG/L)	15	2189.3	2400	610	3200	15
5	FLUORIDE (MG/L)	10	0.2	0.1	0.1	0.8	0
5	ALUMINUM (UG/L)	15	4657.3	1900	210	22000	15
5	DISSOLVED ALUMINUM (UG/L)	4	50	50	50	50	0
5	ARSENIC (UG/L)	14	6.9	4	2	17	0
5	DISSOLVED ARSENIC (UG/L)	4	7.3	7.5	3	11	0
5	BARIUM (UG/L)	12	305.8	330	50	480	0
5	DISSOLVED BARIUM (UG/L)	4	222.5	190	30	480	0
5	BORON (UG/L)	14	6064.3	4000	500	40000	
5	DISSOLVED BORON (UG/L)	4	2125	1900	500	4200	
5	CADMIUM (UG/L)	14	0.4	0.3	0.1	1.3	0
5	DISSOLVED CADMIUM (UG/L)	4	0.3	0.2	0.1	0.6	0
5	CHROMIUM (UG/L)	12	3.4	2.5	1	11	0
5	DISSOLVED CHROMIUM (UG/L)	4	1	1	1	1	0
5	COPPER (UG/L)	15	36	30	10	80	0
5	DISSOLVED COPPER (UG/L)	4	17.5	10	10	40	0
5	IRON - TOTAL (UG/L)	15	896267	1100000	61000	1E+06	15
5	DISSOLVED IRON (UG/L)	4	588000	497500	57000	1E+06	4
5	LEAD (UG/L)	12	7.1	5	1	19	0
5	DISSOLVED LEAD (UG/L)	4	1	1	1	1	0
5	LITHIUM (UG/L)	8	15.5	10	10	40	
5	DISSOLVED LITHIUM (UG/L)	4	19	13	10	40	
5	MANGANESE (UG/L)	15	54000	51000	40000	91000	15

Continued

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
5	DISSOLVED MANGANESE (UG/L)	4	67000	66500	44000	91000	4
5	MOLYBDENUM (UG/L)	4	35	20	20	80	
5	DISSOLVED MOLYBDENUM (UG/L)	4	67.5	20	20	210	
5	NICKEL (UG/L)	1	33	33	33	33	0
5	SELENIUM (UG/L)	10	1	1	1	1	0
5	SILICON (UG/L)	14	7821.4	4250	2100	36000	
5	DISSOLVED SILICON (UG/L)	4	10100	10100	4200	16000	
5	STRONTIUM (UG/L)	12	2094.2	2300	690	2900	
5	DISSOLVED STRONTIUM (UG/L)	4	1825	1520	660	3600	
5	VANADIUM (UG/L)	12	103.3	35	10	290	
5	DISSOLVED VANADIUM (UG/L)	4	60	10	10	210	
5	ZINC (UG/L)	15	149.3	140	30	310	0
5	DISSOLVED ZINC (UG/L)	4	62.5	40	20	150	0
5	TOTAL DISSOLVED SOLIDS (MG/L)	14	4121.4	4350	1600	5300	14
5	TOTAL SUSPENDED SOLIDS (MG/L)	8	370.3	145	82	1500	
5	WATER SURF. FR MP (M)	17	4.2	4.6	1.4	6.3	
5	WATER SURF. ELVN (M, MSL)	10	225.4	225.4	223.9	226.3	
5	WATER SURF. ELVN (FT, MSL)	10	739.6	739.4	734.7	742.3	

Table 1. Kingston Groundwater Quality Summary. Data from 89/03/28 to 92/08/20

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
5A	ORP (MV)	9	235.7	266	54	369	
5A	CONDUCTIVITY (UMHOS/CM)	9	774.9	361	300	2310	
5A	DISSOLVED OXYGEN (MG/L)	9	1.9	1.1	0.4	7	
5A	TEMPERATURE (DEG C)	9	17.6	17.9	15.9	19.4	
5A	PH (STANDARD UNITS)	9	5	5.4	3.4	5.7	9
5A	ALKALINITY (MG/L)	6	15.7	13	7	27	
5A	PHEN-PH ALKALINITY (MG/L)	1	0	0	0	0	
5A	ACIDITY (MG/L)	6	73.2	77	0	112	
5A	CO2 ACIDITY (MG/L)	1	85	85	85	85	
5A	CO2 (MG/L)	5	77.5	70	61	99	
5A	CA/MG HARDNESS (MG/L)	9	275.8	137	83	979.6	
5A	NITRATE+NITRITE NITROGEN (MG/L)	6	0	0	0	0.1	0
5A	TOTAL ORGANIC CARBON (MG/L)	7	1.2	0.9	0.3	3.8	
5A	TOTAL INORGANIC CARBON (MG/L)	7	24.8	12	3.3	98	
5A	SULFIDE (MG/L)	5	0	0	0	0	
5A	CALCIUM (MG/L)	9	81.2	35	22	300	
5A	DISSOLVED CALCIUM (MG/L)	1	40	40	40	40	
5A	MAGNESIUM (MG/L)	9	17.7	12	6.9	56	
5A	DISSOLVED MAGNESIUM (MG/L)	1	13	13	13	13	
5A	SODIUM (MG/L)	7	6.8	6.8	6.4	7.2	
5A	POTASSIUM (MG/L)	7	1.8	1.8	1.8	1.9	
5A	CHLORIDE (MG/L)	7	1.7	2	1	2	0
5A	SULFATE (MG/L)	8	343.3	160	96	1700	1
5A	FLUORIDE (MG/L)	6	0.1	0.1	0.1	0.1	0
5A	ALUMINUM (UG/L)	9	29998.9	180	50	250000	2
5A	DISSOLVED ALUMINUM (UG/L)	1	50	50	50	50	0
5A	ARSENIC (UG/L)	7	2.9	2	1	8	0
5A	DISSOLVED ARSENIC (UG/L)	1	2	2	2	2	0
5A	BARIUM (UG/L)	6	78.3	80	60	90	0
5A	DISSOLVED BARIUM (UG/L)	1	50	50	50	50	0
5A	BORON (UG/L)	7	500	500	500	500	
5A	DISSOLVED BORON (UG/L)	1	500	500	500	500	
5A	CADMIUM (UG/L)	7	0.6	0.5	0.3	1.2	0
5A	DISSOLVED CADMIUM (UG/L)	1	0.5	0.5	0.5	0.5	0
5A	CHROMIUM (UG/L)	6	2	2	1	3	0
5A	DISSOLVED CHROMIUM (UG/L)	1	1	1	1	1	0
5A	COPPER (UG/L)	9	41.1	10	10	190	0
5A	DISSOLVED COPPER (UG/L)	1	10	10	10	10	0
5A	IRON - TOTAL (UG/L)	9	140156	4800	2300	820000	9
5A	DISSOLVED IRON (UG/L)	1	7500	7500	7500	7500	1
5A	LEAD (UG/L)	6	5.3	5	1	10	0
5A	DISSOLVED LEAD (UG/L)	1	1	1	1	1	0
5A	LITHIUM (UG/L)	5	10	10	10	10	
5A	DISSOLVED LITHIUM (UG/L)	1	10	10	10	10	
5A	MANGANESE (UG/L)	9	9566.7	3100	1800	37000	9
5A	DISSOLVED MANGANESE (UG/L)	1	3200	3200	3200	3200	1

Continued

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
5A	MOLYBDENUM (UG/L)	1	20	20	20	20	
5A	DISSOLVED MOLYBDENUM (UG/L)	1	20	20	20	20	
5A	SELENIUM (UG/L)	6	1	1	1	1	0
5A	SILICON (UG/L)	7	4742.9	5500	2400	6000	
5A	DISSOLVED SILICON (UG/L)	1	5200	5200	5200	5200	
5A	STRONTIUM (UG/L)	6	268.3	270	220	300	
5A	DISSOLVED STRONTIUM (UG/L)	1	50	50	50	50	
5A	VANADIUM (UG/L)	6	16.7	10	10	40	
5A	DISSOLVED VANADIUM (UG/L)	1	10	10	10	10	
5A	ZINC (UG/L)	9	355.6	90	10	1300	0
5A	DISSOLVED ZINC (UG/L)	1	74	74	74	74	0
5A	TOTAL DISSOLVED SOLIDS (MG/L)	7	250	250	200	360	0
5A	TOTAL SUSPENDED SOLIDS (MG/L)	5	12.4	12	8	16	
5A	WATER SURF. FR MP (M)	11	5.9	4.3	3	8.7	
5A	WATER SURF. ELVN (M, MSL)	6	221.6	221.1	219.6	225.3	
5A	WATER SURF. ELVN (FT, MSL)	6	727	725.5	720.6	739	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 92/09/01

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
5B	ORP (MV)	15	199	200	90	323	
5B	CONDUCTIVITY (UMHOS/CM)	15	698	365	290	2180	
5B	DISSOLVED OXYGEN (MG/L)	15	0.5	0.3	0	3.3	
5B	TEMPERATURE (DEG C)	15	16.7	16.4	14.8	19.2	
5B	PH (STANDARD UNITS)	15	5.6	5.6	5.3	5.9	15
5B	ALKALINITY (MG/L)	13	30.2	30	24	42	
5B	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
5B	ACIDITY (MG/L)	6	65.8	76.5	0	85	
5B	CO2 ACIDITY (MG/L)	4	393.3	368.5	75	761	
5B	CO2 (MG/L)	5	69.6	69	65.1	74.8	
5B	CA/MG HARDNESS (MG/L)	16	278.9	166.5	153	921.7	
5B	NITRATE+NITRITE NITROGEN (MG/L)	11	1	0	0	10.3	1
5B	TOTAL ORGANIC CARBON (MG/L)	15	1	0.5	0.2	3.1	
5B	TOTAL INORGANIC CARBON (MG/L)	15	32.3	29	10	62	
5B	SULFIDE (MG/L)	7	0	0	0	0	
5B	CALCIUM (MG/L)	16	79.2	43	40	290	
5B	DISSOLVED CALCIUM (MG/L)	4	137	107.5	43	290	
5B	MAGNESIUM (MG/L)	16	19.8	14	13	48	
5B	DISSOLVED MAGNESIUM (MG/L)	4	27	23	14	48	
5B	SODIUM (MG/L)	15	6.3	6.4	5	7.5	
5B	POTASSIUM (MG/L)	15	2.3	1.7	1.5	7	
5B	CHLORIDE (MG/L)	15	2.3	2	1	4	0
5B	SULFATE (MG/L)	16	410	165	110	1900	4
5B	FLUORIDE (MG/L)	11	0.1	0.1	0.1	0.3	0
5B	ALUMINUM (UG/L)	16	9607.5	510	50	74000	12
5B	DISSOLVED ALUMINUM (UG/L)	4	90	80	50	150	0
5B	ARSENIC (UG/L)	15	4.9	1	1	47	0
5B	DISSOLVED ARSENIC (UG/L)	4	1.3	1	1	2	0
5B	BARIUM (UG/L)	13	90	70	50	300	0
5B	DISSOLVED BARIUM (UG/L)	4	50	40	30	90	0
5B	BORON (UG/L)	15	606.7	500	500	1500	
5B	DISSOLVED BORON (UG/L)	4	655	560	500	1000	
5B	CADMIUM (UG/L)	15	0.3	0.2	0.1	1	0
5B	DISSOLVED CADMIUM (UG/L)	4	0.3	0.1	0.1	0.7	0
5B	CHROMIUM (UG/L)	13	8.8	1	1	52	0
5B	DISSOLVED CHROMIUM (UG/L)	4	1	1	1	1	0
5B	COPPER (UG/L)	16	75.6	10	10	1000	0
5B	DISSOLVED COPPER (UG/L)	4	12.5	10	10	20	0
5B	IRON - TOTAL (UG/L)	16	89753.8	1850	660	600000	16
5B	DISSOLVED IRON (UG/L)	4	125128	125170	170	250000	3
5B	LEAD (UG/L)	13	6.2	2	1	35	0
5B	DISSOLVED LEAD (UG/L)	4	1	1	1	1	0
5B	LITHIUM (UG/L)	9	11.6	10	10	20	
5B	DISSOLVED LITHIUM (UG/L)	4	10	10	10	10	

Continued

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
5B	MANGANESE (UG/L)	16	5487.5	1550	310	29000	16
5B	DISSOLVED MANGANESE (UG/L)	4	10050	9100	2000	20000	4
5B	MOLYBDENUM (UG/L)	4	20	20	20	20	
5B	DISSOLVED MOLYBDENUM (UG/L)	4	20	20	20	20	
5B	NICKEL (UG/L)	1	12	12	12	12	0
5B	SELENIUM (UG/L)	11	1	1	1	1	0
5B	SILICON (UG/L)	15	11466.7	8000	4100	43000	
5B	DISSOLVED SILICON (UG/L)	4	7750	8450	5400	8700	
5B	STRONTIUM (UG/L)	13	426.2	290	230	1400	
5B	DISSOLVED STRONTIUM (UG/L)	4	600	475	50	1400	
5B	VANADIUM (UG/L)	13	22.3	10	10	80	
5B	DISSOLVED VANADIUM (UG/L)	4	10	10	10	10	
5B	ZINC (UG/L)	16	74.4	30	10	260	0
5B	DISSOLVED ZINC (UG/L)	4	42.5	40	10	80	0
5B	TOTAL DISSOLVED SOLIDS (MG/L)	15	535.3	260	180	2400	2
5B	TOTAL SUSPENDED SOLIDS (MG/L)	9	448.6	16	4	2100	
5B	WATER SURF. FR MP (M)	18	3.7	3.8	2.2	6.1	
5B	WATER SURF. ELVN (M, MSL)	11	225.5	225.9	223.1	227	
5B	WATER SURF. ELVN (FT, MSL)	11	739.7	741	731.9	744.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
6A	ORP (MV)	17	77.2	20	-27	429	
6A	CONDUCTIVITY (UMHOS/CM)	17	3274.8	3680	428	4330	
6A	DISSOLVED OXYGEN (MG/L)	17	0.5	0.4	0	1.7	
6A	TEMPERATURE (DEG C)	17	17.7	17.2	14.9	24.4	
6A	COD (MG/L)	1	56	56	56	56	
6A	PH (STANDARD UNITS)	17	5.5	5.8	3.1	6	17
6A	ALKALINITY (MG/L)	15	181.9	191	58	250	
6A	PHEN-PH ALKALINITY (MG/L)	5	0	0	0	0	
6A	ACIDITY (MG/L)	6	1514.3	1935	0	2600	
6A	CO2 ACIDITY (MG/L)	7	1532.6	1586	584	2184	
6A	CO2 (MG/L)	4	1912.8	1911.5	1540	2288	
6A	CA/MG HARDNESS (MG/L)	17	1152.2	1161.8	855	1335	
6A	NITRATE+NITRITE NITROGEN (MG/L)	10	0.1	0.1	0	0.2	0
6A	TOTAL ORGANIC CARBON (MG/L)	17	9	9.1	2.9	19	
6A	TOTAL INORGANIC CARBON (MG/L)	17	80.9	65	4	260	
6A	SULFIDE (MG/L)	6	0	0	0	0	
6A	CALCIUM (MG/L)	17	332.4	340	260	390	
6A	DISSOLVED CALCIUM (MG/L)	2	350	350	320	380	
6A	MAGNESIUM (MG/L)	17	78.3	83	31	110	
6A	DISSOLVED MAGNESIUM (MG/L)	2	74.5	74.5	64	85	
6A	SODIUM (MG/L)	17	8.4	8.2	7.6	9.7	
6A	POTASSIUM (MG/L)	17	17.2	17	13	26	
6A	CHLORIDE (MG/L)	17	3.6	4	1	6	0
6A	SULFATE (MG/L)	17	2513.5	2800	630	3700	17
6A	FLUORIDE (MG/L)	10	0.2	0.1	0.1	0.8	0
6A	ALUMINUM (UG/L)	17	2017.6	890	50	10000	15
6A	DISSOLVED ALUMINUM (UG/L)	8	356.3	50	50	2500	1
6A	ANTIMONY (UG/L)	5	1.6	1	1	4	0
6A	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
6A	ARSENIC (UG/L)	17	4.6	4	1	13	0
6A	DISSOLVED ARSENIC (UG/L)	8	2.3	2.5	1	4	0
6A	BARIUM (UG/L)	15	284.7	310	30	630	0
6A	DISSOLVED BARIUM (UG/L)	8	351.3	370	40	470	0
6A	BERYLLIUM (UG/L)	5	1	1	1	1	0
6A	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
6A	BORON (UG/L)	17	5176.5	3500	500	42000	
6A	DISSOLVED BORON (UG/L)	8	3737.5	3650	2200	5000	
6A	CADMIUM (UG/L)	16	0.5	0.5	0.1	1.9	0
6A	DISSOLVED CADMIUM (UG/L)	8	1	0.5	0.1	3	0
6A	CHROMIUM (UG/L)	14	4	3.5	1	13	0
6A	DISSOLVED CHROMIUM (UG/L)	8	4.3	3	1	14	0
6A	COPPER (UG/L)	17	34.7	30	10	70	0
6A	DISSOLVED COPPER (UG/L)	2	10	10	10	10	0
6A	IRON - TOTAL (UG/L)	17	1007177	1200000	92000	2E+06	17
6A	DISSOLVED IRON (UG/L)	8	1055000	1050000	120000	2E+06	8



Continued

6A	LEAD (UG/L)	15	5.7	2	1	37	0
6A	DISSOLVED LEAD (UG/L)	8	2.5	1	1	12	0
6A	LITHIUM (UG/L)	10	43.1	50	21	60	
6A	DISSOLVED LITHIUM (UG/L)	2	45	45	40	50	
6A	MANGANESE (UG/L)	17	61282.4	71000	7800	86000	17
6A	DISSOLVED MANGANESE (UG/L)	8	65375	64500	59000	73000	8
6A	MOLYBDENUM (UG/L)	6	43.3	20	20	160	
6A	DISSOLVED MOLYBDENUM (UG/L)	2	60	60	20	100	
6A	NICKEL (UG/L)	6	4.5	3	1	12	0
6A	DISSOLVED NICKEL (UG/L)	1	5	5	5	5	0
6A	SELENIUM (UG/L)	11	1	1	1	1	0
6A	DISSOLVED SELENIUM (UG/L)	6	1.2	1	1	2	0
6A	SILICON (UG/L)	12	13808.3	12000	5100	42000	
6A	DISSOLVED SILICON (UG/L)	7	9014.3	9600	5300	11000	
6A	STRONTIUM (UG/L)	15	2200	2000	1100	3700	
6A	DISSOLVED STRONTIUM (UG/L)	8	2025	2000	1400	2900	
6A	VANADIUM (UG/L)	15	58	10	10	310	
6A	DISSOLVED VANADIUM (UG/L)	8	77.5	45	10	200	
6A	ZINC (UG/L)	17	141.2	140	10	260	0
6A	DISSOLVED ZINC (UG/L)	8	153.5	150	18	280	0
6A	TOTAL DISSOLVED SOLIDS (MG/L)	17	4452.9	4900	1500	5500	17
6A	TOTAL SUSPENDED SOLIDS (MG/L)	11	188.7	170	63	470	
6A	WATER SURF. FR MP (M)	19	3.3	3.1	2.3	5.8	
6A	WATER SURF. ELVN (M, MSL)	10	225.6	225.9	222.3	227	
6A	WATER SURF. ELVN (FT, MSL)	10	740.1	741	729.2	744.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 89/03/29.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
6B	ORP (MV)	2	210	210	140	280	
6B	CONDUCTIVITY (UMHOS/CM)	2	2030	2030	2020	2040	
6B	DISSOLVED OXYGEN (MG/L)	2	0.2	0.2	0	0.4	
6B	TEMPERATURE (DEG C)	2	15.5	15.5	14	17	
6B	PH (STANDARD UNITS)	2	5.2	5.2	5.1	5.3	2
6B	ALKALINITY (MG/L)	1	17	17	17	17	
6B	CA/MG HARDNESS (MG/L)	2	1366	1366	1343	1389	
6B	NITRATE+NITRITE NITROGEN (MG/L)	2	0.1	0.1	0	0.1	0
6B	TOTAL ORGANIC CARBON (MG/L)	2	3.1	3.1	3	3.2	
6B	TOTAL INORGANIC CARBON (MG/L)	2	4.6	4.6	4.5	4.8	
6B	CALCIUM (MG/L)	2	495	495	480	510	
6B	MAGNESIUM (MG/L)	2	31.5	31.5	28	35	
6B	SODIUM (MG/L)	2	8.3	8.3	7.5	9.1	
6B	POTASSIUM (MG/L)	2	33.5	33.5	33	34	
6B	CHLORIDE (MG/L)	2	3.5	3.5	3	4	0
6B	SULFATE (MG/L)	2	915	915	730	1100	2
6B	FLUORIDE (MG/L)	2	0.2	0.2	0.1	0.3	0
6B	ALUMINUM (UG/L)	2	21000	21000	12000	30000	2
6B	ARSENIC (UG/L)	2	70	70	40	100	1
6B	BARIUM (UG/L)	2	215	215	180	250	0
6B	BORON (UG/L)	2	1700	1700	1600	1800	
6B	CADMIUM (UG/L)	2	0.2	0.2	0.1	0.3	0
6B	CHROMIUM (UG/L)	2	15	15	8	22	0
6B	COPPER (UG/L)	2	15	15	10	20	0
6B	IRON - TOTAL (UG/L)	2	150000	150000	110000	190000	2
6B	LEAD (UG/L)	2	25	25	20	30	0
6B	MANGANESE (UG/L)	2	6500	6500	5900	7100	2
6B	SELENIUM (UG/L)	2	1.5	1.5	1	2	0
6B	SILICON (UG/L)	2	50500	50500	45000	56000	
6B	STRONTIUM (UG/L)	2	3000	3000	3000	3000	
6B	VANADIUM (UG/L)	2	60	60	20	100	
6B	ZINC (UG/L)	2	100	100	60	140	0
6B	TOTAL DISSOLVED SOLIDS (MG/L)	2	2100	2100	1900	2300	2
6B	WATER SURF. FR MP (M)	4	0.8	0.8	0.6	0.9	
6B	WATER SURF. ELVN (M, MSL)	2	228.2	228.2	228.2	228.3	
6B	WATER SURF. ELVN (FT, MSL)	2	748.9	748.9	748.8	748.9	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 94/12/06.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
8	ORP (MV)	19	117.9	50	-56	372	
8	CONDUCTIVITY (UMHOS/CM)	19	1300.1	1293	1020	1680	
8	DISSOLVED OXYGEN (MG/L)	19	0.8	0.6	0.3	1.8	
8	TEMPERATURE (DEG C)	19	17.7	17.4	15.6	20	
8	PH (STANDARD UNITS)	19	7	7	6.8	7.1	0
8	ALKALINITY (MG/L)	18	257	260	211	296	
8	PHEN-PH ALKALINITY (MG/L)	4	0	0	0	0	
8	ACIDITY (MG/L)	8	39.6	43	0	60	
8	CO2 ACIDITY (MG/L)	7	46.1	47	35	55	
8	CO2 (MG/L)	8	38.2	37.8	22	53	
8	CA/MG HARDNESS (MG/L)	20	803.6	784.8	581	1067.1	
8	NITRATE+NITRITE NITROGEN (MG/L)	12	0	0	0	0	0
8	TOTAL ORGANIC CARBON (MG/L)	19	0.9	0.8	0.4	1.8	
8	TOTAL INORGANIC CARBON (MG/L)	20	94.7	81	42	290	
8	SULFIDE (MG/L)	8	0	0	0	0	
8	CALCIUM (MG/L)	20	253.5	250	180	340	
8	DISSOLVED CALCIUM (MG/L)	3	316.7	310	300	340	
8	MAGNESIUM (MG/L)	20	41.5	39.5	26	56	
8	DISSOLVED MAGNESIUM (MG/L)	3	54	54	53	55	
8	SODIUM (MG/L)	20	13.5	13.5	12	16	
8	POTASSIUM (MG/L)	20	4.5	4.5	3.8	5.4	
8	CHLORIDE (MG/L)	20	5.8	6	4	9	0
8	SULFATE (MG/L)	19	581.1	480	300	1700	19
8	FLUORIDE (MG/L)	12	0.1	0.1	0.1	0.5	0
8	ALUMINUM (UG/L)	20	1323	350	50	15000	12
8	DISSOLVED ALUMINUM (UG/L)	3	50	50	50	50	0
8	ANTIMONY (UG/L)	6	1.2	1	1	2	0
8	ARSENIC (UG/L)	20	3	1	1	12	0
8	DISSOLVED ARSENIC (UG/L)	3	5.7	2	2	13	0
8	BARIUM (UG/L)	18	35.6	10	10	250	0
8	DISSOLVED BARIUM (UG/L)	3	26.7	30	10	40	0
8	BERYLLIUM (UG/L)	6	1	1	1	1	0
8	BORON (UG/L)	20	500	500	500	500	
8	DISSOLVED BORON (UG/L)	3	500	500	500	500	
8	CADMIUM (UG/L)	19	0.2	0.1	0.1	0.6	0
8	DISSOLVED CADMIUM (UG/L)	3	0.9	0.6	0.5	1.5	0
8	CHROMIUM (UG/L)	17	2.7	2	1	13	0
8	DISSOLVED CHROMIUM (UG/L)	3	1	1	1	1	0
8	COPPER (UG/L)	20	11.5	10	10	20	0
8	DISSOLVED COPPER (UG/L)	3	13.3	10	10	20	0
8	IRON - TOTAL (UG/L)	20	2413	1300	290	21000	19
8	DISSOLVED IRON (UG/L)	3	373.3	220	10	890	1
8	LEAD (UG/L)	18	6.4	2	1	41	0
8	DISSOLVED LEAD (UG/L)	3	1	1	1	1	0

Continued

8	LITHIUM (UG/L)	13	34.3	40	20	40	
8	DISSOLVED LITHIUM (UG/L)	3	33.3	30	30	40	
8	MANGANESE (UG/L)	20	1321	1150	220	2500	20
8	DISSOLVED MANGANESE (UG/L)	3	1800	2000	1300	2100	3
8	MOLYBDENUM (UG/L)	7	20	20	20	20	
8	DISSOLVED MOLYBDENUM (UG/L)	1	20	20	20	20	
8	NICKEL (UG/L)	6	2	1.5	1	5	0
8	SELENIUM (UG/L)	13	1.2	1	1	2	0
8	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
8	SILICON (UG/L)	14	13142.9	12000	6200	34000	
8	DISSOLVED SILICON (UG/L)	3	12000	12000	11000	13000	
8	STRONTIUM (UG/L)	18	823.3	815	650	1000	
8	DISSOLVED STRONTIUM (UG/L)	3	860	860	840	880	
8	VANADIUM (UG/L)	18	11.7	10	10	30	
8	DISSOLVED VANADIUM (UG/L)	3	10	10	10	10	
8	ZINC (UG/L)	20	24	10	10	60	0
8	DISSOLVED ZINC (UG/L)	3	10	10	10	10	0
8	TOTAL DISSOLVED SOLIDS (MG/L)	20	1041.5	1100	580	1400	20
8	TOTAL SUSPENDED SOLIDS (MG/L)	14	43	11	2	360	
8	WATER SURF. FR MP (M)	21	3.3	2.5	2.1	7	
8	WATER SURF. ELVN (M, MSL)	12	230.5	231.7	225.6	232.9	
8	WATER SURF. ELVN (FT, MSL)	12	756.1	760	740.1	764	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/05 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
9A	ORP (MV)	18	-6.8	-40	-93	207	
9A	CONDUCTIVITY (UMHOS/CM)	18	1346.6	1180.5	840	2273	
9A	DISSOLVED OXYGEN (MG/L)	18	0.3	0.3	0.1	0.5	
9A	TEMPERATURE (DEG C)	18	18.1	18.1	16.4	19.9	
9A	5-DAY BOD (MG/L)	7	3.5	3.8	2.3	4.1	
9A	PH (STANDARD UNITS)	18	6.3	6.2	5.8	6.7	13
9A	ALKALINITY (MG/L)	18	73.4	74	40	103	
9A	PHEN-PH ALKALINITY (MG/L)	3	0	0	0	0	
9A	ACIDITY (MG/L)	10	135.7	139	83	188	
9A	CO2 ACIDITY (MG/L)	7	277.6	190	151	840	
9A	CO2 (MG/L)	8	123.4	122.3	96	165	
9A	CA/MG HARDNESS (MG/L)	18	734.1	627	373	1531.4	
9A	NITRATE+NITRITE NITROGEN (MG/L)	12	0.1	0.1	0	0.5	0
9A	AMMONIA NITROGEN (MG/L)	7	0.2	0.2	0	0.3	
9A	TOTAL KJELDAHL NITROGEN (MG/L)	8	0.4	0.3	0.2	0.9	
9A	TOTAL ORTHO PHOSPHORUS (MG/L)	4	0.1	0.1	0	0.1	
9A	TOTAL ORGANIC CARBON (MG/L)	17	0.8	0.6	0.3	2.4	
9A	TOTAL INORGANIC CARBON (MG/L)	18	42.9	41.5	7	140	
9A	SULFIDE (MG/L)	8	0	0	0	0.1	
9A	CALCIUM (MG/L)	18	221.1	190	110	460	
9A	DISSOLVED CALCIUM (MG/L)	3	226.7	220	210	250	
9A	MAGNESIUM (MG/L)	18	44.2	37	24	93	
9A	DISSOLVED MAGNESIUM (MG/L)	3	42.3	44	32	51	
9A	SODIUM (MG/L)	18	14	14	9.1	18	
9A	POTASSIUM (MG/L)	18	11.2	9.3	6.8	35	
9A	CHLORIDE (MG/L)	17	11.6	9	3	26	0
9A	SULFATE (MG/L)	18	798.9	615	400	2000	18
9A	FLUORIDE (MG/L)	12	0.2	0.2	0.1	0.4	0
9A	ALUMINUM (UG/L)	18	4375	2250	950	25000	18
9A	DISSOLVED ALUMINUM (UG/L)	3	60	50	50	80	0
9A	ANTIMONY (UG/L)	4	1	1	1	1	0
9A	DISSOLVED ANTIMONY (UG/L)	1	5	5	5	5	0
9A	ARSENIC (UG/L)	18	104.8	92.5	34	190	17
9A	DISSOLVED ARSENIC (UG/L)	3	61.3	87	1	96	2
9A	BARIUM (UG/L)	16	111.3	105	10	310	0
9A	DISSOLVED BARIUM (UG/L)	3	130	170	30	190	0
9A	BERYLLIUM (UG/L)	4	2.3	1	1	6	1
9A	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
9A	BORON (UG/L)	18	2161.1	1500	1000	13000	
9A	DISSOLVED BORON (UG/L)	3	1433.3	1400	1400	1500	
9A	CADMIUM (UG/L)	17	0.3	0.2	0.1	1	0
9A	DISSOLVED CADMIUM (UG/L)	3	0.8	0.8	0.1	1.4	0
9A	CHROMIUM (UG/L)	15	4.5	3	1	18	0
9A	DISSOLVED CHROMIUM (UG/L)	3	1	1	1	1	0

Continued

9A	COPPER (UG/L)	18	32.2	10	10	260	0
9A	DISSOLVED COPPER (UG/L)	3	93.3	10	10	260	0
9A	IRON - TOTAL (UG/L)	18	40833.3	37500	20000	79000	18
9A	DISSOLVED IRON (UG/L)	3	38000	38000	35000	41000	3
9A	LEAD (UG/L)	16	2.8	1	1	17	0
9A	DISSOLVED LEAD (UG/L)	3	1	1	1	1	0
9A	LITHIUM (UG/L)	11	35.4	30	19	60	
9A	DISSOLVED LITHIUM (UG/L)	3	36.7	30	30	50	
9A	MANGANESE (UG/L)	18	26044.4	20500	9800	69000	18
9A	DISSOLVED MANGANESE (UG/L)	3	27666.7	26000	25000	32000	3
9A	MOLYBDENUM (UG/L)	5	20	20	20	20	
9A	DISSOLVED MOLYBDENUM (UG/L)	1	20	20	20	20	
9A	NICKEL (UG/L)	4	52	48.5	43	68	0
9A	DISSOLVED NICKEL (UG/L)	1	35	35	35	35	0
9A	SELENIUM (UG/L)	13	1.2	1	1	3	0
9A	DISSOLVED SELENIUM (UG/L)	1	1	1	1	1	0
9A	SILICON (UG/L)	14	16042.9	15000	6800	38000	
9A	DISSOLVED SILICON (UG/L)	2	11500	11500	11000	12000	
9A	STRONTIUM (UG/L)	16	2593.8	2150	1700	4200	
9A	DISSOLVED STRONTIUM (UG/L)	3	2500	2500	2100	2900	
9A	VANADIUM (UG/L)	16	25	10	10	110	
9A	DISSOLVED VANADIUM (UG/L)	3	43.3	10	10	110	
9A	ZINC (UG/L)	18	52.2	50	10	120	0
9A	DISSOLVED ZINC (UG/L)	3	50	30	20	100	0
9A	TOTAL DISSOLVED SOLIDS (MG/L)	18	1157.8	965	670	2100	18
9A	TOTAL SUSPENDED SOLIDS (MG/L)	15	162.9	100	24	790	
9A	FECAL COLIFORM (#/100ML)	3	7	10	1	10	
9A	WATER SURF. FR MP (M)	20	5.2	5.1	4.5	6.9	
9A	WATER SURF. ELVN (M, MSL)	13	229	230.1	222.2	230.8	
9A	WATER SURF. ELVN (FT, MSL)	13	751.3	754.9	729.1	757	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/05 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
9B	ORP (MV)	18	-33.3	-85.5	-190	454	
9B	CONDUCTIVITY (UMHOS/CM)	18	453.4	455	380	534	
9B	DISSOLVED OXYGEN (MG/L)	18	0.4	0.3	0.2	0.8	
9B	TEMPERATURE (DEG C)	18	17.9	18	16.2	19.5	
9B	5-DAY BOD (MG/L)	7	1	1	1	1.1	
9B	PH (STANDARD UNITS)	18	8.2	8	7.8	9.1	5
9B	ALKALINITY (MG/L)	17	171.8	170	155	192	
9B	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
9B	ACIDITY (MG/L)	9	1.6	0.2	0	7	
9B	CO2 ACIDITY (MG/L)	5	3.4	3	1	8	
9B	CO2 (MG/L)	4	2.9	2.6	0	6.2	
9B	CA/MG HARDNESS (MG/L)	17	105.1	110.8	61	145.7	
9B	NITRATE+NITRITE NITROGEN (MG/L)	11	0	0	0	0.1	0
9B	AMMONIA NITROGEN (MG/L)	6	0.1	0.1	0	0.1	
9B	TOTAL KJELDAHL NITROGEN (MG/L)	7	0.1	0.1	0.1	0.2	
9B	TOTAL ORTHO PHOSPHORUS (MG/L)	4	0.1	0	0	0.2	
9B	TOTAL ORGANIC CARBON (MG/L)	16	0.6	0.4	0.2	2.7	
9B	TOTAL INORGANIC CARBON (MG/L)	17	68.8	57	11	160	
9B	SULFIDE (MG/L)	7	0	0	0	0	
9B	CALCIUM (MG/L)	17	31.1	33	16	44	
9B	DISSOLVED CALCIUM (MG/L)	1	35	35	35	35	
9B	MAGNESIUM (MG/L)	17	6.7	7.2	4	8.7	
9B	DISSOLVED MAGNESIUM (MG/L)	1	6.5	6.5	6.5	6.5	
9B	SODIUM (MG/L)	17	59.8	62	5.7	78	
9B	POTASSIUM (MG/L)	17	6.4	5.4	3.4	13	
9B	CHLORIDE (MG/L)	17	3.5	3	1	12	0
9B	SULFATE (MG/L)	17	147.3	74	18	650	3
9B	FLUORIDE (MG/L)	11	0.2	0.2	0.1	0.4	0
9B	ALUMINUM (UG/L)	17	235.3	50	50	1500	3
9B	DISSOLVED ALUMINUM (UG/L)	1	50	50	50	50	0
9B	ANTIMONY (UG/L)	4	1	1	1	1	0
9B	ARSENIC (UG/L)	17	1.9	1	1	5	0
9B	DISSOLVED ARSENIC (UG/L)	1	2	2	2	2	0
9B	BARIUM (UG/L)	15	293.3	280	220	380	0
9B	DISSOLVED BARIUM (UG/L)	1	310	310	310	310	0
9B	BERYLLIUM (UG/L)	4	1	1	1	1	0
9B	BORON (UG/L)	17	558.8	500	500	1500	
9B	DISSOLVED BORON (UG/L)	1	500	500	500	500	
9B	CADMIUM (UG/L)	16	0.2	0.1	0.1	0.5	0
9B	DISSOLVED CADMIUM (UG/L)	1	1.4	1.4	1.4	1.4	0
9B	CHROMIUM (UG/L)	14	1.8	1	1	6	0
9B	DISSOLVED CHROMIUM (UG/L)	1	1	1	1	1	0
9B	COPPER (UG/L)	17	18.2	10	10	110	0
9B	DISSOLVED COPPER (UG/L)	1	10	10	10	10	0

Continued

9B	IRON - TOTAL (UG/L)	17	319.4	190	70	2000	3
9B	DISSOLVED IRON (UG/L)	1	100	100	100	100	0
9B	LEAD (UG/L)	15	1.1	1	1	3	0
9B	DISSOLVED LEAD (UG/L)	1	1	1	1	1	0
9B	LITHIUM (UG/L)	10	38.5	40	25	50	
9B	DISSOLVED LITHIUM (UG/L)	1	40	40	40	40	
9B	MANGANESE (UG/L)	17	75.3	90	5	130	11
9B	DISSOLVED MANGANESE (UG/L)	1	69	69	69	69	1
9B	MOLYBDENUM (UG/L)	5	22	20	20	30	
9B	NICKEL (UG/L)	4	2	1.5	1	4	0
9B	SELENIUM (UG/L)	12	1	1	1	1	0
9B	DISSOLVED SELENIUM (UG/L)	1	1	1	1	1	0
9B	SILICON (UG/L)	13	7292.3	8000	3800	8800	
9B	DISSOLVED SILICON (UG/L)	1	8500	8500	8500	8500	
9B	STRONTIUM (UG/L)	15	506.7	520	320	670	
9B	DISSOLVED STRONTIUM (UG/L)	1	480	480	480	480	
9B	VANADIUM (UG/L)	15	11.3	10	10	30	
9B	DISSOLVED VANADIUM (UG/L)	1	10	10	10	10	
9B	ZINC (UG/L)	17	21.2	10	10	150	0
9B	DISSOLVED ZINC (UG/L)	1	10	10	10	10	0
9B	TOTAL DISSOLVED SOLIDS (MG/L)	17	273.5	290	80	360	0
9B	TOTAL SUSPENDED SOLIDS (MG/L)	14	2.1	1	1	6	
9B	FECAL COLIFORM (#/100ML)	3	7	10	1	10	
9B	WATER SURF. FR MP (M)	19	5.1	5.1	4.5	5.9	
9B	WATER SURF. ELVN (M, MSL)	13	228.3	230	217.2	230.6	
9B	WATER SURF. ELVN (FT, MSL)	13	749.2	754.6	712.6	756.6	



Table 1. Kingston Groundwater Quality Summary. Data from 92/12/08 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
CYDB	ORP (MV)	5	450.6	385	346	636	
CYDB	CONDUCTIVITY (UMHOS/CM)	5	1011.6	1088	289	1402	
CYDB	DISSOLVED OXYGEN (MG/L)	5	7	7.2	4	9.3	
CYDB	TEMPERATURE (DEG C)	5	16	12.3	4.2	29.1	
CYDB	PH (STANDARD UNITS)	5	3.8	3.4	2.8	4.8	5
CYDB	ALKALINITY (MG/L)	5	0.6	0	0	2	
CYDB	PHEN-PH ALKALINITY (MG/L)	3	0	0	0	0	
CYDB	CO2 ACIDITY (MG/L)	5	152.2	149	22	300	
CYDB	CA/MG HARDNESS (MG/L)	5	380.8	377.6	119.6	610	
CYDB	TOTAL ORGANIC CARBON (MG/L)	4	1.3	1.2	0.9	1.8	
CYDB	TOTAL INORGANIC CARBON (MG/L)	5	3.2	2	1	6	
CYDB	CALCIUM (MG/L)	5	111.4	110	37	180	
CYDB	DISSOLVED CALCIUM (MG/L)	2	108.5	108.5	37	180	
CYDB	MAGNESIUM (MG/L)	5	24.9	25	6.6	39	
CYDB	DISSOLVED MAGNESIUM (MG/L)	2	22.8	22.8	6.6	39	
CYDB	SODIUM (MG/L)	5	19.6	13	3	45	
CYDB	POTASSIUM (MG/L)	5	3.2	3.1	1.5	5.7	
CYDB	CHLORIDE (MG/L)	5	4	2	2	9	0
CYDB	SULFATE (MG/L)	5	474	470	130	800	4
CYDB	ALUMINUM (UG/L)	5	11860	9900	2000	25000	5
CYDB	DISSOLVED ALUMINUM (UG/L)	2	5450	5450	2000	8900	2
CYDB	ANTIMONY (UG/L)	5	1.2	1	1	2	0
CYDB	DISSOLVED ANTIMONY (UG/L)	2	1	1	1	1	0
CYDB	ARSENIC (UG/L)	5	1.2	1	1	2	0
CYDB	DISSOLVED ARSENIC (UG/L)	2	1	1	1	1	0
CYDB	BARIUM (UG/L)	5	16	20	10	20	0
CYDB	DISSOLVED BARIUM (UG/L)	2	10	10	10	10	0
CYDB	BERYLLIUM (UG/L)	5	2.2	1	1	5	1
CYDB	DISSOLVED BERYLLIUM (UG/L)	2	1	1	1	1	0
CYDB	BORON (UG/L)	5	500	500	500	500	
CYDB	DISSOLVED BORON (UG/L)	2	500	500	500	500	
CYDB	CADMIUM (UG/L)	4	1.6	1.4	0.3	3.1	0
CYDB	DISSOLVED CADMIUM (UG/L)	2	0.9	0.9	0.3	1.5	0
CYDB	CHROMIUM (UG/L)	4	3.5	1	1	11	0
CYDB	DISSOLVED CHROMIUM (UG/L)	2	1	1	1	1	0
CYDB	COPPER (UG/L)	5	60	70	10	120	0
CYDB	DISSOLVED COPPER (UG/L)	2	15	15	10	20	0
CYDB	IRON - TOTAL (UG/L)	5	16500	13000	1000	40000	5
CYDB	DISSOLVED IRON (UG/L)	2	20440	20440	880	40000	2
CYDB	LEAD (UG/L)	5	1.4	1	1	3	0
CYDB	DISSOLVED LEAD (UG/L)	2	1	1	1	1	0
CYDB	LITHIUM (UG/L)	4	45	50	10	70	
CYDB	DISSOLVED LITHIUM (UG/L)	2	35	35	10	60	
CYDB	MANGANESE (UG/L)	5	3318	3200	590	5800	5
CYDB	DISSOLVED MANGANESE (UG/L)	2	3095	3095	590	5600	2
CYDB	MOLYBDENUM (UG/L)	4	20	20	20	20	

Continued

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
CYDB	DISSOLVED MOLYBDENUM (UG/L)	2	20	20	20	20	
CYDB	NICKEL (UG/L)	5	126.2	130	21	210	4
CYDB	DISSOLVED NICKEL (UG/L)	2	79.5	79.5	19	140	1
CYDB	STRONTIUM (UG/L)	5	434	400	130	740	
CYDB	DISSOLVED STRONTIUM (UG/L)	2	435	435	140	730	
CYDB	VANADIUM (UG/L)	5	10	10	10	10	
CYDB	DISSOLVED VANADIUM (UG/L)	2	10	10	10	10	
CYDB	ZINC (UG/L)	5	224	250	10	470	0
CYDB	DISSOLVED ZINC (UG/L)	2	155	155	60	250	0
CYDB	TOTAL DISSOLVED SOLIDS (MG/L)	5	638	600	190	1200	3
CYDB	TOTAL SUSPENDED SOLIDS (MG/L)	5	6	5	2	16	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/04.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
10	ORP (MV)	20	-45.7	-61.5	-102	128	
10	CONDUCTIVITY (UMHOS/CM)	20	716.3	593	220	1190	
10	DISSOLVED OXYGEN (MG/L)	20	0.2	0.2	0.1	0.5	
10	TEMPERATURE (DEG C)	20	20.1	20.1	16.5	24	
10	PH (STANDARD UNITS)	20	6.7	6.7	6.5	7	0
10	ALKALINITY (MG/L)	20	90.7	85.5	55	135	
10	PHEN-PH ALKALINITY (MG/L)	4	0	0	0	0	
10	ACIDITY (MG/L)	9	77.6	67	0	132	
10	CO2 ACIDITY (MG/L)	8	35.5	32.5	23	56	
10	CO2 (MG/L)	7	73.8	59	37.8	116	
10	CA/MG HARDNESS (MG/L)	21	343.9	245	169.9	706	
10	NITRATE+NITRITE NITROGEN (MG/L)	12	0.1	0	0	0.5	0
10	TOTAL ORGANIC CARBON (MG/L)	20	0.6	0.5	0.2	2	
10	TOTAL INORGANIC CARBON (MG/L)	21	34.1	32	4	68	
10	SULFIDE (MG/L)	8	0	0	0	0	
10	CALCIUM (MG/L)	21	112.6	80	55	230	
10	DISSOLVED CALCIUM (MG/L)	7	72.1	71	55	100	
10	MAGNESIUM (MG/L)	21	15.2	11	7.9	32	
10	DISSOLVED MAGNESIUM (MG/L)	7	9	9	7.9	9.9	
10	SODIUM (MG/L)	21	9.6	10	6.2	13	
10	POTASSIUM (MG/L)	21	7.6	7.3	6.4	9.4	
10	CHLORIDE (MG/L)	21	4.1	4	2	7	0
10	SULFATE (MG/L)	21	306.2	230	90	730	9
10	FLUORIDE (MG/L)	12	0.5	0.5	0.1	1	0
10	ALUMINUM (UG/L)	21	1492.9	1800	50	3400	14
10	DISSOLVED ALUMINUM (UG/L)	7	50	50	50	50	0
10	ANTIMONY (UG/L)	5	1.2	1	1	2	0
10	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
10	ARSENIC (UG/L)	21	211.1	210	170	280	21
10	DISSOLVED ARSENIC (UG/L)	7	177.1	170	150	200	7
10	BARIUM (UG/L)	19	71.6	70	20	150	0
10	DISSOLVED BARIUM (UG/L)	7	35.7	30	20	60	0
10	BERYLLIUM (UG/L)	5	1	1	1	1	0
10	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
10	BORON (UG/L)	21	720.5	500	500	4800	
10	DISSOLVED BORON (UG/L)	7	500	500	500	500	
10	CADMIUM (UG/L)	20	0.2	0.1	0.1	1	0
10	DISSOLVED CADMIUM (UG/L)	7	0.4	0.3	0.1	1.4	0
10	CHROMIUM (UG/L)	18	2.6	1	1	7	0
10	DISSOLVED CHROMIUM (UG/L)	7	1	1	1	1	0
10	COPPER (UG/L)	21	16.2	10	10	130	0
10	DISSOLVED COPPER (UG/L)	7	10	10	10	10	0
10	IRON - TOTAL (UG/L)	21	41819	21000	6500	460000	21
10	DISSOLVED IRON (UG/L)	7	11442.9	10000	6400	23000	7
10	LEAD (UG/L)	19	2.3	1	0.8	8	0

Continued

10	DISSOLVED LEAD (UG/L)	7	1	1	1	1	0
10	LITHIUM (UG/L)	14	124.9	125	80	200	
10	DISSOLVED LITHIUM (UG/L)	7	122.1	130	95	140	
10	MANGANESE (UG/L)	21	731.4	660	250	1600	21
10	DISSOLVED MANGANESE (UG/L)	7	382.9	350	250	560	7
10	MOLYBDENUM (UG/L)	8	93.8	95	30	140	
10	DISSOLVED MOLYBDENUM (UG/L)	5	58	60	20	120	
10	NICKEL (UG/L)	5	1.6	1	1	4	0
10	DISSOLVED NICKEL (UG/L)	1	3	3	3	3	0
10	SELENIUM (UG/L)	12	1	1	1	1	0
10	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
10	SILICON (UG/L)	16	9550	10100	4000	12000	
10	DISSOLVED SILICON (UG/L)	6	7733.3	7750	7200	8300	
10	STRONTIUM (UG/L)	19	1070.5	810	560	2100	
10	DISSOLVED STRONTIUM (UG/L)	7	772.9	760	620	1000	
10	VANADIUM (UG/L)	19	10	10	10	10	
10	DISSOLVED VANADIUM (UG/L)	7	10	10	10	10	
10	ZINC (UG/L)	21	21	10	10	80	0
10	DISSOLVED ZINC (UG/L)	7	61.4	10	10	350	0
10	TOTAL DISSOLVED SOLIDS (MG/L)	21	503.8	360	260	1000	8
10	TOTAL SUSPENDED SOLIDS (MG/L)	15	59.3	43	4	130	
10	WATER SURF. FR MP (M)	23	0.9	0.3	0	1.8	
10	WATER SURF. ELVN (M, MSL)	12	228.7	229	225.4	229.4	
10	WATER SURF. ELVN (FT, MSL)	12	750.4	751.2	739.6	752.5	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
10A	ORP (MV)	22	256.1	245	31	455	
10A	CONDUCTIVITY (UMHOS/CM)	22	753.5	797	419	1020	
10A	DISSOLVED OXYGEN (MG/L)	22	0.6	0.3	0.1	3.3	
10A	TEMPERATURE (DEG C)	22	20.6	20.8	17.9	22.9	
10A	PH (STANDARD UNITS)	22	4.9	4.8	4.2	6.4	22
10A	ALKALINITY (MG/L)	21	16.1	6	0	106	
10A	PHEN-PH ALKALINITY (MG/L)	5	0	0	0	0	
10A	ACIDITY (MG/L)	12	187.7	223.5	0	294	
10A	CO2 ACIDITY (MG/L)	9	121.6	117	34	180	
10A	CO2 (MG/L)	8	171.3	196.1	0	259	
10A	CA/MG HARDNESS (MG/L)	21	337.5	365	151.6	564	
10A	NITRATE+NITRITE NITROGEN (MG/L)	11	0.1	0.1	0	0.6	0
10A	TOTAL ORGANIC CARBON (MG/L)	20	0.9	0.6	0.3	2.7	
10A	TOTAL INORGANIC CARBON (MG/L)	20	27.7	27	3	110	
10A	SULFIDE (MG/L)	8	0	0	0	0	
10A	CALCIUM (MG/L)	21	101.4	110	48	160	
10A	DISSOLVED CALCIUM (MG/L)	7	82.6	82	55	110	
10A	MAGNESIUM (MG/L)	21	20.5	22	7.1	40	
10A	DISSOLVED MAGNESIUM (MG/L)	7	13.9	15	9.5	16	
10A	SODIUM (MG/L)	21	8	8	5.4	11	
10A	POTASSIUM (MG/L)	21	7.2	7.2	4.9	12	
10A	CHLORIDE (MG/L)	21	4.1	4	2	6	0
10A	SULFATE (MG/L)	21	360	370	40	640	14
10A	FLUORIDE (MG/L)	12	0.2	0.1	0.1	0.7	0
10A	ALUMINUM (UG/L)	21	21833.3	7900	2800	130000	21
10A	DISSOLVED ALUMINUM (UG/L)	7	740	590	50	1600	5
10A	ANTIMONY (UG/L)	5	1	1	1	1	0
10A	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
10A	ARSENIC (UG/L)	21	6	4	2	20	0
10A	DISSOLVED ARSENIC (UG/L)	7	5.9	3	1	25	0
10A	BARIUM (UG/L)	19	152.1	90	10	750	0
10A	DISSOLVED BARIUM (UG/L)	7	47.1	40	20	80	0
10A	BERYLLIUM (UG/L)	5	3.4	3	1	8	1
10A	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
10A	BORON (UG/L)	21	2445.7	1900	500	17000	
10A	DISSOLVED BORON (UG/L)	7	1514.3	1400	1100	2000	
10A	CADMIUM (UG/L)	20	0.3	0.2	0.1	1.4	0
10A	DISSOLVED CADMIUM (UG/L)	7	0.5	0.4	0.1	1.6	0
10A	CHROMIUM (UG/L)	18	14.2	4.5	1	80	0
10A	DISSOLVED CHROMIUM (UG/L)	7	1	1	1	1	0
10A	COPPER (UG/L)	21	47.1	20	10	210	0
10A	DISSOLVED COPPER (UG/L)	7	17.1	10	10	60	0
10A	IRON - TOTAL (UG/L)	21	102714	63000	18000	810000	21
10A	DISSOLVED IRON (UG/L)	7	27285.7	27000	18000	40000	7
10A	LEAD (UG/L)	19	18.1	7	2	86	3
10A	DISSOLVED LEAD (UG/L)	7	1	1	1	1	0

Continued

10A	LITHIUM (UG/L)	14	66.5	57.5	20	160	
10A	DISSOLVED LITHIUM (UG/L)	7	54.3	54	40	70	
10A	MANGANESE (UG/L)	21	8690.5	9300	2800	15000	21
10A	DISSOLVED MANGANESE (UG/L)	7	7900	7800	5600	13000	7
10A	MOLYBDENUM (UG/L)	8	20	20	20	20	
10A	DISSOLVED MOLYBDENUM (UG/L)	5	20	20	20	20	
10A	NICKEL (UG/L)	5	33.8	26	20	56	0
10A	DISSOLVED NICKEL (UG/L)	1	42	42	42	42	0
10A	SELENIUM (UG/L)	12	1	1	1	1	0
10A	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
10A	SILICON (UG/L)	16	25975	20000	7600	53000	
10A	DISSOLVED SILICON (UG/L)	6	12500	12500	11000	15000	
10A	STRONTIUM (UG/L)	19	1594.2	1700	810	2400	
10A	DISSOLVED STRONTIUM (UG/L)	7	1377.1	1400	940	1700	
10A	VANADIUM (UG/L)	19	29.5	10	10	150	
10A	DISSOLVED VANADIUM (UG/L)	7	10	10	10	10	
10A	ZINC (UG/L)	21	169.5	170	50	350	0
10A	DISSOLVED ZINC (UG/L)	7	82	80	54	110	0
10A	TOTAL DISSOLVED SOLIDS (MG/L)	21	604.8	640	230	1000	14
10A	TOTAL SUSPENDED SOLIDS (MG/L)	15	441.2	180	26	2100	
10A	WATER SURF. FR MP (M)	23	2.1	2	1.2	4.3	
10A	WATER SURF. ELVN (M, MSL)	12	227.6	227.8	225.3	228.5	
10A	WATER SURF. ELVN (FT, MSL)	12	746.6	747.5	739.2	749.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
10B	ORP (MV)	14	9.9	0	-90	150	
10B	CONDUCTIVITY (UMHOS/CM)	14	1124.4	1158	861	1300	
10B	DISSOLVED OXYGEN (MG/L)	14	0.3	0.3	0.1	0.5	
10B	TEMPERATURE (DEG C)	14	19.8	20	17.9	21	
10B	PH (STANDARD UNITS)	14	6.1	6.1	5.9	6.3	14
10B	ALKALINITY (MG/L)	13	121.3	117	110	146	
10B	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
10B	ACIDITY (MG/L)	6	168.5	181	0	275	
10B	CO2 ACIDITY (MG/L)	3	175	176	150	199	
10B	CO2 (MG/L)	5	178	164.6	152.2	242	
10B	CA/MG HARDNESS (MG/L)	14	566	593.5	394.3	677	
10B	NITRATE+NITRITE NITROGEN (MG/L)	10	0.1	0	0	0.4	0
10B	TOTAL ORGANIC CARBON (MG/L)	13	1.4	1.1	0.3	4.1	
10B	TOTAL INORGANIC CARBON (MG/L)	14	72.1	64.5	24	180	
10B	SULFIDE (MG/L)	6	0	0	0	0	
10B	CALCIUM (MG/L)	14	175	180	120	210	
10B	DISSOLVED CALCIUM (MG/L)	1	120	120	120	120	
10B	MAGNESIUM (MG/L)	14	31.4	32	22	40	
10B	DISSOLVED MAGNESIUM (MG/L)	1	20	20	20	20	
10B	SODIUM (MG/L)	14	36.1	35.5	31	42	
10B	POTASSIUM (MG/L)	14	3.3	2.8	2.4	7.3	
10B	CHLORIDE (MG/L)	14	13.6	14	10	17	0
10B	SULFATE (MG/L)	14	519.3	550	300	660	14
10B	FLUORIDE (MG/L)	10	0.1	0.1	0.1	0.5	0
10B	ALUMINUM (UG/L)	14	3888.6	335	50	25000	9
10B	DISSOLVED ALUMINUM (UG/L)	7	271.4	50	50	1600	1
10B	ANTIMONY (UG/L)	3	1	1	1	1	0
10B	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
10B	ARSENIC (UG/L)	14	2.4	2	1	5	0
10B	DISSOLVED ARSENIC (UG/L)	7	2.3	2	1	5	0
10B	BARIUM (UG/L)	12	99.2	55	30	320	0
10B	DISSOLVED BARIUM (UG/L)	7	28.6	30	10	40	0
10B	BERYLLIUM (UG/L)	3	1	1	1	1	0
10B	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
10B	BORON (UG/L)	14	910.7	520	500	5900	
10B	DISSOLVED BORON (UG/L)	7	500	500	500	500	
10B	CADMIUM (UG/L)	13	0.5	0.1	0.1	4	0
10B	DISSOLVED CADMIUM (UG/L)	7	0.7	0.2	0.1	3.5	0
10B	CHROMIUM (UG/L)	11	5.9	1	1	30	0
10B	DISSOLVED CHROMIUM (UG/L)	7	1.2	1	1	2	0
10B	COPPER (UG/L)	14	26.4	10	10	160	0
10B	DISSOLVED COPPER (UG/L)	1	10	10	10	10	0
10B	IRON - TOTAL (UG/L)	14	26571.4	24000	15000	49000	14
10B	DISSOLVED IRON (UG/L)	7	18287.1	22000	10	24000	6

Continued

10B	LEAD (UG/L)	12	3.8	1	1	20	0
10B	DISSOLVED LEAD (UG/L)	6	1.2	1	1	2	0
10B	LITHIUM (UG/L)	7	10	10	10	10	
10B	DISSOLVED LITHIUM (UG/L)	1	10	10	10	10	
10B	MANGANESE (UG/L)	14	9592.9	9950	7100	11000	14
10B	DISSOLVED MANGANESE (UG/L)	7	8900	9100	6900	10000	7
10B	MOLYBDENUM (UG/L)	3	20	20	20	20	
10B	DISSOLVED MOLYBDENUM (UG/L)	1	20	20	20	20	
10B	NICKEL (UG/L)	3	3.3	4	2	4	0
10B	DISSOLVED NICKEL (UG/L)	1	1	1	1	1	0
10B	SELENIUM (UG/L)	10	1	1	1	1	0
10B	DISSOLVED SELENIUM (UG/L)	6	1.3	1	1	2	0
10B	SILICON (UG/L)	11	13754.5	9700	4400	49000	
10B	DISSOLVED SILICON (UG/L)	6	6550	6900	4300	7800	
10B	STRONTIUM (UG/L)	12	769.2	745	520	1100	
10B	DISSOLVED STRONTIUM (UG/L)	7	684.3	700	550	750	
10B	VANADIUM (UG/L)	12	15.8	10	10	50	
10B	DISSOLVED VANADIUM (UG/L)	7	10	10	10	10	
10B	ZINC (UG/L)	14	31.4	20	10	100	0
10B	DISSOLVED ZINC (UG/L)	7	78.6	80	10	190	0
10B	TOTAL DISSOLVED SOLIDS (MG/L)	14	833.6	875	370	1100	13
10B	TOTAL SUSPENDED SOLIDS (MG/L)	8	21.6	18.5	6	47	
10B	WATER SURF. FR MP (M)	16	1.6	1.6	0.6	2.4	
10B	WATER SURF. ELVN (M, MSL)	10	228.5	228.6	226.2	229.2	
10B	WATER SURF. ELVN (FT, MSL)	10	749.6	750	742.2	751.9	



Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/06.

WELL	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
11B	ORP (MV)	15	164.3	160	20	289	
11B	CONDUCTIVITY (UMHOS/CM)	14	1800.2	1907.5	190	2180	
11B	DISSOLVED OXYGEN (MG/L)	15	0.9	0.4	0.2	3.7	
11B	TEMPERATURE (DEG C)	15	17	16.9	15.8	19	
11B	PH (STANDARD UNITS)	15	6.7	6.6	6.2	7	1
11B	ALKALINITY (MG/L)	14	302.4	306	237	356	
11B	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
11B	ACIDITY (MG/L)	6	91.8	88.5	0	193	
11B	CO2 ACIDITY (MG/L)	4	92	104	40	120	
11B	CO2 (MG/L)	5	97.1	86.2	63.4	170	
11B	CA/MG HARDNESS (MG/L)	15	1407.8	1374	1076	1719	
11B	NITRATE+NITRITE NITROGEN (MG/L)	11	0.1	0	0	0.6	0
11B	TOTAL ORGANIC CARBON (MG/L)	14	1	0.9	0.7	1.5	
11B	TOTAL INORGANIC CARBON (MG/L)	15	115.7	100	53	220	
11B	SULFIDE (MG/L)	6	0	0	0	0	
11B	CALCIUM (MG/L)	15	452	440	350	540	
11B	MAGNESIUM (MG/L)	15	67.8	67	49	90	
11B	SODIUM (MG/L)	15	9.9	9.7	8.7	12	
11B	POTASSIUM (MG/L)	15	2.7	2.6	2.2	3.3	
11B	CHLORIDE (MG/L)	15	6.3	7	4	8	0
11B	SULFATE (MG/L)	15	988.7	1000	650	1400	15
11B	FLUORIDE (MG/L)	11	0.1	0.1	0.1	0.2	0
11B	ALUMINUM (UG/L)	15	1612.7	650	50	9200	10
11B	ANTIMONY (UG/L)	3	1	1	1	1	0
11B	ARSENIC (UG/L)	15	1.5	1	1	6	0
11B	BARIUM (UG/L)	13	43.1	40	10	130	0
11B	BERYLLIUM (UG/L)	3	1	1	1	1	0
11B	BORON (UG/L)	15	501.3	500	500	520	
11B	CADMIUM (UG/L)	14	0.1	0.1	0.1	0.3	0
11B	CHROMIUM (UG/L)	12	2.8	1	1	12	0
11B	COPPER (UG/L)	15	20.7	10	10	80	0
11B	IRON - TOTAL (UG/L)	15	1934.7	980	210	12000	13
11B	LEAD (UG/L)	13	1.9	1	1	6	0
11B	LITHIUM (UG/L)	7	28.6	30	10	40	
11B	MANGANESE (UG/L)	15	662	660	160	1200	15
11B	MOLYBDENUM (UG/L)	4	25	20	20	40	
11B	NICKEL (UG/L)	3	2.7	1	1	6	0
11B	SELENIUM (UG/L)	11	1	1	1	1	0
11B	SILICON (UG/L)	12	11666.7	9900	5600	23000	
11B	STRONTIUM (UG/L)	13	510.8	520	390	680	
11B	TITANIUM (UG/L)	1	170	170	170	170	
11B	VANADIUM (UG/L)	13	11.5	10	10	20	
11B	ZINC (UG/L)	15	17.3	10	10	50	0
11B	TOTAL DISSOLVED SOLIDS (MG/L)	15	1773.3	1800	1300	2000	15
11B	TOTAL SUSPENDED SOLIDS (MG/L)	8	108.3	78	2	320	
11B	WATER SURF. FR MP (M)	17	2.8	2.5	2	4.2	
11B	WATER SURF. ELVN (M, MSL)	11	231.2	231.6	227.7	232.4	
11B	WATER SURF. ELVN (FT, MSL)	11	758.4	759.8	747.2	762.5	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/06.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
12A	ORP (MV)	15	26.4	5	-41	180	
12A	CONDUCTIVITY (UMHOS/CM)	15	775.9	780	621	920	
12A	DISSOLVED OXYGEN (MG/L)	15	0.3	0.2	0.1	0.7	
12A	TEMPERATURE (DEG C)	15	16.8	16.6	14.2	20.8	
12A	PH (STANDARD UNITS)	15	6.6	6.6	6.2	6.8	2
12A	ALKALINITY (MG/L)	14	213	212.5	175	253	
12A	PHEN-PH ALKALINITY (MG/L)	3	0	0	0	0	
12A	ACIDITY (MG/L)	6	68	77.5	0	107	
12A	CO2 ACIDITY (MG/L)	5	79.6	71	63	108	
12A	CO2 (MG/L)	5	71.7	68.6	57	94	
12A	CA/MG HARDNESS (MG/L)	14	405.2	404.5	221	523	
12A	NITRATE+NITRITE NITROGEN (MG/L)	10	0.1	0	0	0.1	0
12A	TOTAL ORGANIC CARBON (MG/L)	14	1.8	1.7	1.3	3.3	
12A	TOTAL INORGANIC CARBON (MG/L)	15	92.5	74	48	190	
12A	SULFIDE (MG/L)	5	0	0	0	0	
12A	CALCIUM (MG/L)	15	106.1	110	0.1	150	
12A	MAGNESIUM (MG/L)	15	27.5	28	0	38	
12A	SODIUM (MG/L)	15	6.9	6.7	5.7	8	
12A	POTASSIUM (MG/L)	15	2.9	2.9	2.4	3.3	
12A	CHLORIDE (MG/L)	15	3.3	3	2	4	0
12A	SULFATE (MG/L)	15	215.3	230	140	400	1
12A	FLUORIDE (MG/L)	10	0.3	0.2	0.1	0.4	0
12A	ALUMINUM (UG/L)	15	1116.7	210	50	5500	8
12A	ANTIMONY (UG/L)	3	1	1	1	1	0
12A	ARSENIC (UG/L)	15	1.6	1	1	4	0
12A	BARIUM (UG/L)	14	40.7	30	10	110	0
12A	BERYLLIUM (UG/L)	3	2.7	1	1	6	1
12A	BORON (UG/L)	15	500	500	500	500	
12A	CADMIUM (UG/L)	14	0.2	0.1	0.1	1	0
12A	CHROMIUM (UG/L)	13	2	1	1	6	0
12A	COPPER (UG/L)	15	20.7	10	10	110	0
12A	IRON - TOTAL (UG/L)	15	4132	2200	10	15000	14
12A	LEAD (UG/L)	14	2.7	1.5	1	9	0
12A	LITHIUM (UG/L)	8	10	10	10	10	
12A	MANGANESE (UG/L)	15	4547	4100	5	10000	14
12A	MOLYBDENUM (UG/L)	4	20	20	20	20	
12A	NICKEL (UG/L)	3	1	1	1	1	0
12A	SELENIUM (UG/L)	10	1	1	1	1	0
12A	SILICON (UG/L)	12	4285	4300	20	11000	
12A	STRONTIUM (UG/L)	14	237.1	230	50	390	
12A	VANADIUM (UG/L)	14	19.3	10	10	50	
12A	ZINC (UG/L)	15	16	10	10	70	0
12A	TOTAL DISSOLVED SOLIDS (MG/L)	15	548	540	300	940	10
12A	TOTAL SUSPENDED SOLIDS (MG/L)	9	8.3	7	2	23	
12A	WATER SURF. FR MP (M)	18	1.8	1.7	1.3	2.6	
12A	WATER SURF. ELVN (M, MSL)	16	232.1	232.1	231.7	232.3	
12A	WATER SURF. ELVN (FT, MSL)	12	761.4	761.5	760.1	762.2	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/06.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
12B	ORP (MV)	15	-5	-40	-100	161	
12B	CONDUCTIVITY (UMHOS/CM)	15	1317.8	1345	1200	1390	
12B	DISSOLVED OXYGEN (MG/L)	15	0.3	0.3	0.1	0.5	
12B	TEMPERATURE (DEG C)	15	16.3	16.5	14.3	18.7	
12B	PH (STANDARD UNITS)	15	7	7	6.8	7.1	0
12B	ALKALINITY (MG/L)	15	298.8	320	46	330	
12B	PHEN-PH ALKALINITY (MG/L)	3	0	0	0	0	
12B	ACIDITY (MG/L)	7	51.6	57	0	75	
12B	CO2 ACIDITY (MG/L)	5	50	53	32	61	
12B	CO2 (MG/L)	6	52.9	54	34.3	66	
12B	CA/MG HARDNESS (MG/L)	16	714.7	745	203	837	
12B	NITRATE+NITRITE NITROGEN (MG/L)	10	0.1	0	0	0.7	0
12B	TOTAL ORGANIC CARBON (MG/L)	15	0.7	0.5	0.2	2.2	
12B	TOTAL INORGANIC CARBON (MG/L)	16	108.2	94.5	58	200	
12B	SULFIDE (MG/L)	6	0	0	0	0	
12B	CALCIUM (MG/L)	16	210	220	60	240	
12B	MAGNESIUM (MG/L)	16	46.3	47	13	70	
12B	SODIUM (MG/L)	16	35.5	36	31	38	
12B	POTASSIUM (MG/L)	16	8.9	8.7	8.2	11	
12B	CHLORIDE (MG/L)	16	3.3	3.5	1	4	0
12B	SULFATE (MG/L)	16	491.3	490	380	580	16
12B	FLUORIDE (MG/L)	10	0.1	0.1	0.1	0.1	0
12B	ALUMINUM (UG/L)	16	825.6	50	50	7100	4
12B	ANTIMONY (UG/L)	3	1	1	1	1	0
12B	ARSENIC (UG/L)	16	1.3	1	1	3	0
12B	BARIUM (UG/L)	14	16.4	10	10	50	0
12B	BERYLLIUM (UG/L)	3	2.7	1	1	6	1
12B	BORON (UG/L)	16	500	500	500	500	
12B	CADMIUM (UG/L)	15	0.2	0.1	0.1	1	0
12B	CHROMIUM (UG/L)	14	1.6	1	1	5	0
12B	COPPER (UG/L)	16	18.1	10	10	100	0
12B	IRON - TOTAL (UG/L)	16	2100	1700	1400	7300	16
12B	LEAD (UG/L)	15	1.2	1	1	2	0
12B	LITHIUM (UG/L)	9	60.7	60	50	70	
12B	MANGANESE (UG/L)	16	462.5	445	360	820	16
12B	MOLYBDENUM (UG/L)	5	20	20	20	20	
12B	NICKEL (UG/L)	4	1.3	1	1	2	0
12B	SELENIUM (UG/L)	10	1	1	1	1	0
12B	SILICON (UG/L)	13	11184.6	12000	6000	19000	
12B	STRONTIUM (UG/L)	14	5011.4	5350	360	6100	
12B	VANADIUM (UG/L)	14	10.7	10	10	20	
12B	ZINC (UG/L)	16	20	10	10	70	0
12B	TOTAL DISSOLVED SOLIDS (MG/L)	16	1036.9	1000	590	1400	16
12B	TOTAL SUSPENDED SOLIDS (MG/L)	10	3.7	4	1	6	
12B	WATER SURF. FR MP (M)	18	2	1.9	1.6	3.6	
12B	WATER SURF. ELVN (M, MSL)	17	231.8	231.9	230.2	232.2	
12B	WATER SURF. ELVN (FT, MSL)	12	760.3	760.8	755.1	761.8	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/11 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
13A	ORP (MV)	20	-71.1	-109.5	-138	151	
13A	CONDUCTIVITY (UMHOS/CM)	20	621.3	551	427	1470	
13A	DISSOLVED OXYGEN (MG/L)	20	0.2	0.2	0	0.7	
13A	TEMPERATURE (DEG C)	20	17.9	17.8	14.8	22.3	
13A	PH (STANDARD UNITS)	20	6.6	6.6	6.4	6.7	2
13A	ALKALINITY (MG/L)	19	208.9	211	179	258	
13A	PHEN-PH ALKALINITY (MG/L)	5	0	0	0	0	
13A	ACIDITY (MG/L)	9	170.1	133	0	500	
13A	CO2 ACIDITY (MG/L)	8	165.1	167.5	122	216	
13A	CO2 (MG/L)	8	168.5	129.5	97	440	
13A	CA/MG HARDNESS (MG/L)	21	194.5	151	113.3	498	
13A	NITRATE+NITRITE NITROGEN (MG/L)	12	0.1	0	0	1.2	0
13A	AMMONIA NITROGEN (MG/L)	2	0.7	0.7	0.7	0.8	
13A	TOTAL KJELDAHL NITROGEN (MG/L)	2	1.1	1.1	1.1	1.2	
13A	TOTAL ORGANIC CARBON (MG/L)	20	2.8	2.6	1	6.1	
13A	TOTAL INORGANIC CARBON (MG/L)	21	95.7	77	31	480	
13A	SULFIDE (MG/L)	9	0	0	0	0.1	
13A	CALCIUM (MG/L)	21	58.3	47	35	150	
13A	DISSOLVED CALCIUM (MG/L)	7	40.4	44	28	49	
13A	MAGNESIUM (MG/L)	21	11.9	8.8	6.3	30	
13A	DISSOLVED MAGNESIUM (MG/L)	7	6.6	6.6	4.5	8.9	
13A	SODIUM (MG/L)	21	28.2	25	21	67	
13A	POTASSIUM (MG/L)	21	7.3	5.4	3.6	25	
13A	CHLORIDE (MG/L)	21	1.8	2	1	3	0
13A	SULFATE (MG/L)	21	180	88	20	950	3
13A	FLUORIDE (MG/L)	12	0.2	0.2	0.1	0.3	0
13A	ALUMINUM (UG/L)	21	9343.8	1300	80	110000	20
13A	DISSOLVED ALUMINUM (UG/L)	11	82.7	50	50	410	1
13A	ANTIMONY (UG/L)	5	1	1	1	1	0
13A	ARSENIC (UG/L)	21	91.8	85	51	180	21
13A	DISSOLVED ARSENIC (UG/L)	11	89.3	82	28	150	10
13A	BARIUM (UG/L)	19	277.4	220	110	1200	0
13A	DISSOLVED BARIUM (UG/L)	11	171.8	170	100	270	0
13A	BERYLLIUM (UG/L)	5	1	1	1	1	0
13A	BORON (UG/L)	21	639.5	500	500	1700	
13A	DISSOLVED BORON (UG/L)	11	603.6	500	500	1500	
13A	CADMIUM (UG/L)	20	0.4	0.2	0.1	1.7	0
13A	DISSOLVED CADMIUM (UG/L)	11	0.7	0.4	0.1	3.1	0
13A	CHROMIUM (UG/L)	18	12.7	2	1	86	0
13A	DISSOLVED CHROMIUM (UG/L)	11	1.1	1	1	2	0
13A	COPPER (UG/L)	21	17.6	10	10	90	0
13A	DISSOLVED COPPER (UG/L)	7	10	10	10	10	0
13A	IRON - TOTAL (UG/L)	21	64952.4	48000	30000	220000	21
13A	DISSOLVED IRON (UG/L)	11	58090.9	43000	26000	210000	11

## Continued

13A	LEAD (UG/L)	19	7	2	1	60	1
13A	DISSOLVED LEAD (UG/L)	11	1	1	1	1	0
13A	LITHIUM (UG/L)	15	50.5	40	10	200	
13A	DISSOLVED LITHIUM (UG/L)	7	35.7	30	23	60	
13A	MANGANESE (UG/L)	21	1496.2	1200	840	4000	21
13A	DISSOLVED MANGANESE (UG/L)	11	1271.8	1000	840	3600	11
13A	MOLYBDENUM (UG/L)	8	20	20	20	20	
13A	DISSOLVED MOLYBDENUM (UG/L)	4	20	20	20	20	
13A	NICKEL (UG/L)	5	1.6	1	1	4	0
13A	SELENIUM (UG/L)	13	1.2	1	1	3	0
13A	DISSOLVED SELENIUM (UG/L)	7	1.1	1	1	2	0
13A	SILICON (UG/L)	16	17681.3	14500	2300	56000	
13A	DISSOLVED SILICON (UG/L)	11	11345.5	12000	8100	14000	
13A	STRONTIUM (UG/L)	19	709.5	630	400	1300	
13A	DISSOLVED STRONTIUM (UG/L)	11	628.2	550	400	1200	
13A	TITANIUM (UG/L)	1	84	84	84	84	
13A	VANADIUM (UG/L)	19	32.1	10	10	240	
13A	DISSOLVED VANADIUM (UG/L)	11	12.7	10	10	40	
13A	ZINC (UG/L)	21	50.5	20	10	250	0
13A	DISSOLVED ZINC (UG/L)	11	44.5	20	10	170	0
13A	TOTAL DISSOLVED SOLIDS (MG/L)	21	344.3	290	160	990	2
13A	TOTAL SUSPENDED SOLIDS (MG/L)	16	197.7	130	22	1200	
13A	WATER SURF. FR MP (M)	22	3.2	3.1	2	4.9	
13A	WATER SURF. ELVN (M, MSL)	11	230.8	231.1	229.1	232.5	
13A	WATER SURF. ELVN (FT, MSL)	11	757.1	758.1	751.8	762.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/05 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
13B	ORP (MV)	17	-34.1	-80	-170	573	
13B	CONDUCTIVITY (UMHOS/CM)	17	311.3	319	277	322	
13B	DISSOLVED OXYGEN (MG/L)	17	0.3	0.3	0.1	1.5	
13B	TEMPERATURE (DEG C)	17	16.5	16.6	15.1	18.6	
13B	PH (STANDARD UNITS)	17	8.3	8.3	8	8.4	0
13B	ALKALINITY (MG/L)	16	171.4	167.5	159	249	
13B	PHEN-PH ALKALINITY (MG/L)	4	0	0	0	0	
13B	ACIDITY (MG/L)	7	21.9	4	0	120	
13B	CO2 ACIDITY (MG/L)	6	0.8	0	0	4	
13B	CO2 (MG/L)	5	27	3.5	0	106	
13B	CA/MG HARDNESS (MG/L)	17	27.3	26	22	40	
13B	NITRATE+NITRITE NITROGEN (MG/L)	10	0	0	0	0.1	0
13B	TOTAL ORGANIC CARBON (MG/L)	16	0.6	0.5	0.2	2.5	
13B	TOTAL INORGANIC CARBON (MG/L)	17	71.1	52	39	160	
13B	SULFIDE (MG/L)	6	0	0	0	0	
13B	CALCIUM (MG/L)	17	8.4	8.4	7.1	9.6	
13B	DISSOLVED CALCIUM (MG/L)	4	8.7	8.8	7.3	10	
13B	MAGNESIUM (MG/L)	17	1.5	1.2	0.9	4.3	
13B	DISSOLVED MAGNESIUM (MG/L)	4	1.2	1.1	1	1.5	
13B	SODIUM (MG/L)	17	62.7	66	6.3	77	
13B	POTASSIUM (MG/L)	17	2.1	2.1	1.7	2.6	
13B	CHLORIDE (MG/L)	17	1.2	1	1	2	0
13B	SULFATE (MG/L)	17	6.7	2	1	77	0
13B	FLUORIDE (MG/L)	10	0.3	0.2	0.1	0.5	0
13B	ALUMINUM (UG/L)	17	242.9	50	50	1500	4
13B	DISSOLVED ALUMINUM (UG/L)	5	50	50	50	50	0
13B	ANTIMONY (UG/L)	3	1	1	1	1	0
13B	ARSENIC (UG/L)	17	1.5	1	1	9	0
13B	DISSOLVED ARSENIC (UG/L)	5	1.2	1	1	2	0
13B	BARIUM (UG/L)	15	214.7	210	180	260	0
13B	DISSOLVED BARIUM (UG/L)	5	190	190	150	240	0
13B	BERYLLIUM (UG/L)	3	1	1	1	1	0
13B	BORON (UG/L)	17	529.4	500	500	1000	
13B	DISSOLVED BORON (UG/L)	5	500	500	500	500	
13B	CADMIUM (UG/L)	16	0.3	0.1	0.1	1	0
13B	DISSOLVED CADMIUM (UG/L)	5	0.3	0.2	0.1	0.5	0
13B	CHROMIUM (UG/L)	15	5	1	1	56	0
13B	DISSOLVED CHROMIUM (UG/L)	5	1	1	1	1	0
13B	COPPER (UG/L)	17	12.4	10	10	40	0
13B	DISSOLVED COPPER (UG/L)	4	10	10	10	10	0
13B	IRON - TOTAL (UG/L)	17	217.6	120	10	1900	1
13B	DISSOLVED IRON (UG/L)	5	26	20	10	60	0
13B	LEAD (UG/L)	16	1.3	1	1	3	0
13B	DISSOLVED LEAD (UG/L)	5	1.2	1	1	2	0
13B	LITHIUM (UG/L)	10	27.2	30	20	30	

Continued

13B	DISSOLVED LITHIUM (UG/L)	4	27.5	25	20	40	
13B	MANGANESE (UG/L)	17	22.8	19	5	55	1
13B	DISSOLVED MANGANESE (UG/L)	5	25.6	27	20	30	0
13B	MOLYBDENUM (UG/L)	6	20	20	20	20	
13B	DISSOLVED MOLYBDENUM (UG/L)	4	17.5	20	10	20	
13B	NICKEL (UG/L)	4	1.3	1	1	2	0
13B	SELENIUM (UG/L)	10	1.1	1	1	2	0
13B	DISSOLVED SELENIUM (UG/L)	1	1	1	1	1	0
13B	SILICON (UG/L)	14	6421.4	6350	3500	8600	
13B	DISSOLVED SILICON (UG/L)	5	6660	6400	5900	7400	
13B	STRONTIUM (UG/L)	15	174	170	150	220	
13B	DISSOLVED STRONTIUM (UG/L)	5	140	160	50	180	
13B	VANADIUM (UG/L)	15	10.7	10	10	20	
13B	DISSOLVED VANADIUM (UG/L)	5	10	10	10	10	
13B	ZINC (UG/L)	17	18.8	10	10	100	0
13B	DISSOLVED ZINC (UG/L)	5	12	10	10	20	0
13B	TOTAL DISSOLVED SOLIDS (MG/L)	17	188.8	200	90	230	0
13B	TOTAL SUSPENDED SOLIDS (MG/L)	12	1.9	1	1	7	
13B	WATER SURF. FR MP (M)	19	3.9	3.7	2.8	6.7	
13B	WATER SURF. ELVN (M, MSL)	10	230.6	230.9	227.6	231.2	
13B	WATER SURF. ELVN (FT, MSL)	10	756.5	757.6	746.6	758.6	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/05 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
14A	ORP (MV)	21	43.4	3	-50	270	
14A	CONDUCTIVITY (UMHOS/CM)	21	3208	3240	2913	3380	
14A	DISSOLVED OXYGEN (MG/L)	21	0.7	0.3	0.1	6.2	
14A	TEMPERATURE (DEG C)	21	18.1	17.7	15.7	23.3	
14A	PH (STANDARD UNITS)	21	6.1	6.1	5.9	6.4	21
14A	ALKALINITY (MG/L)	20	420.1	426	353	466	
14A	PHEN-PH ALKALINITY (MG/L)	6	0	0	0	0	
14A	ACIDITY (MG/L)	8	633.8	713	0	994	
14A	CO2 ACIDITY (MG/L)	9	501.2	530	380	602	
14A	CO2 (MG/L)	7	637.4	651.2	466	875	
14A	CA/MG HARDNESS (MG/L)	21	2023.9	2191	210	2446	
14A	NITRATE+NITRITE NITROGEN (MG/L)	12	0.2	0	0	0.9	0
14A	TOTAL ORGANIC CARBON (MG/L)	20	4.6	4.5	0.5	9.1	
14A	TOTAL INORGANIC CARBON (MG/L)	21	146.1	160	42	270	
14A	SULFIDE (MG/L)	7	0	0	0	0	
14A	CALCIUM (MG/L)	21	578.9	630	66	710	
14A	DISSOLVED CALCIUM (MG/L)	7	508.6	590	110	630	
14A	MAGNESIUM (MG/L)	21	140.5	150	11	200	
14A	DISSOLVED MAGNESIUM (MG/L)	7	133.3	140	53	170	
14A	SODIUM (MG/L)	21	23.2	24	9.3	32	
14A	POTASSIUM (MG/L)	21	51	54	2.9	74	
14A	CHLORIDE (MG/L)	21	11.2	12	3	15	0
14A	SULFATE (MG/L)	21	1651.7	1800	65	2300	20
14A	FLUORIDE (MG/L)	12	0.1	0.1	0.1	0.2	0
14A	ALUMINUM (UG/L)	21	2201.4	510	50	10000	12
14A	DISSOLVED ALUMINUM (UG/L)	7	50	50	50	50	0
14A	ANTIMONY (UG/L)	5	1.2	1	1	2	0
14A	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
14A	ARSENIC (UG/L)	21	39	41	1	71	2
14A	DISSOLVED ARSENIC (UG/L)	7	38.9	38	30	46	0
14A	BARIUM (UG/L)	19	76.3	70	10	200	0
14A	DISSOLVED BARIUM (UG/L)	7	58.6	20	10	160	0
14A	BERYLLIUM (UG/L)	5	1	1	1	1	0
14A	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
14A	BORON (UG/L)	21	596.2	560	500	870	
14A	DISSOLVED BORON (UG/L)	7	535.7	500	500	650	
14A	CADMIUM (UG/L)	20	0.2	0.1	0.1	1.1	0
14A	DISSOLVED CADMIUM (UG/L)	7	0.4	0.3	0.1	1.4	0
14A	CHROMIUM (UG/L)	18	4	2.5	1	17	0
14A	DISSOLVED CHROMIUM (UG/L)	7	2.6	1	1	12	0
14A	COPPER (UG/L)	21	19	10	10	70	0
14A	DISSOLVED COPPER (UG/L)	7	12.9	10	10	20	0
14A	IRON - TOTAL (UG/L)	21	124184	120000	870	220000	21
14A	DISSOLVED IRON (UG/L)	7	102857	100000	93000	110000	7



## Continued

14A	LEAD (UG/L)	20	2.7	1.5	0.9	9	0
14A	DISSOLVED LEAD (UG/L)	7	1.1	1	1	2	0
14A	LITHIUM (UG/L)	13	35.2	30	28	50	
14A	DISSOLVED LITHIUM (UG/L)	7	34.7	40	25	40	
14A	MANGANESE (UG/L)	21	9590.3	8300	97	25000	21
14A	DISSOLVED MANGANESE (UG/L)	7	7814.3	6700	5000	13000	7
14A	MOLYBDENUM (UG/L)	8	20	20	20	20	
14A	DISSOLVED MOLYBDENUM (UG/L)	5	42	20	20	130	
14A	NICKEL (UG/L)	5	1.4	1	1	3	0
14A	DISSOLVED NICKEL (UG/L)	1	3	3	3	3	0
14A	SELENIUM (UG/L)	13	1.8	1	1	3	0
14A	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
14A	SILICON (UG/L)	16	23500	26000	10000	38000	
14A	DISSOLVED SILICON (UG/L)	6	25166.7	23000	18000	38000	
14A	STRONTIUM (UG/L)	19	2116.8	2200	220	2700	
14A	DISSOLVED STRONTIUM (UG/L)	7	2271.4	2300	1800	2900	
14A	VANADIUM (UG/L)	19	27.4	10	10	70	
14A	DISSOLVED VANADIUM (UG/L)	7	20	10	10	50	
14A	ZINC (UG/L)	21	46.7	30	10	170	0
14A	DISSOLVED ZINC (UG/L)	7	30	10	10	80	0
14A	TOTAL DISSOLVED SOLIDS (MG/L)	21	2963.8	3100	240	6600	20
14A	TOTAL SUSPENDED SOLIDS (MG/L)	14	142.1	52	4	690	
14A	WATER SURF. FR MP (M)	23	4.6	4.4	3	9.4	
14A	WATER SURF. ELVN (M, MSL)	12	227.6	227.6	227.2	227.9	
14A	WATER SURF. ELVN (FT, MSL)	12	746.7	746.7	745.3	747.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/05 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
14B	ORP (MV)	19	102.9	47	-20	603	
14B	CONDUCTIVITY (UMHOS/CM)	19	1131.1	1075	783	1572	
14B	DISSOLVED OXYGEN (MG/L)	19	0.5	0.4	0.2	1.6	
14B	TEMPERATURE (DEG C)	19	17.3	17	14.9	21.8	
14B	PH (STANDARD UNITS)	19	6.8	6.9	6.2	7.2	2
14B	ALKALINITY (MG/L)	19	284.1	276	226	376	
14B	PHEN-PH ALKALINITY (MG/L)	5	0	0	0	0	
14B	ACIDITY (MG/L)	7	48.7	32	0	135	
14B	CO2 ACIDITY (MG/L)	9	90.2	80	40	182	
14B	CO2 (MG/L)	6	50	29	18	119	
14B	CA/MG HARDNESS (MG/L)	20	707.8	654.5	307	1142.6	
14B	NITRATE+NITRITE NITROGEN (MG/L)	11	0.6	0	0	6.5	0
14B	TOTAL ORGANIC CARBON (MG/L)	19	0.9	1	0.2	1.9	
14B	TOTAL INORGANIC CARBON (MG/L)	20	102.5	94	50	230	
14B	SULFIDE (MG/L)	6	0	0	0	0	
14B	CALCIUM (MG/L)	20	232.5	215	90	390	
14B	DISSOLVED CALCIUM (MG/L)	5	226	220	200	270	
14B	MAGNESIUM (MG/L)	20	30.9	30.5	20	44	
14B	DISSOLVED MAGNESIUM (MG/L)	5	30.6	31	26	36	
14B	SODIUM (MG/L)	20	7.1	6.6	2.6	14.6	
14B	POTASSIUM (MG/L)	20	3.7	3.2	2.4	11	
14B	CHLORIDE (MG/L)	20	5.6	5.5	3	8	0
14B	SULFATE (MG/L)	20	382.9	375	68	610	19
14B	FLUORIDE (MG/L)	11	0.1	0.1	0.1	0.5	0
14B	ALUMINUM (UG/L)	20	643.5	360	50	2200	11
14B	DISSOLVED ALUMINUM (UG/L)	5	50	50	50	50	0
14B	ANTIMONY (UG/L)	5	1.2	1	1	2	0
14B	DISSOLVED ANTIMONY (UG/L)	1	1	1	1	1	0
14B	ARSENIC (UG/L)	20	1.6	1	1	8	0
14B	DISSOLVED ARSENIC (UG/L)	5	1.8	1	1	4	0
14B	BARIUM (UG/L)	18	46.7	40	10	100	0
14B	DISSOLVED BARIUM (UG/L)	5	40	30	20	70	0
14B	BERYLLIUM (UG/L)	5	1	1	1	1	0
14B	DISSOLVED BERYLLIUM (UG/L)	1	1	1	1	1	0
14B	BORON (UG/L)	20	500	500	500	500	
14B	DISSOLVED BORON (UG/L)	5	500	500	500	500	
14B	CADMIUM (UG/L)	19	0.5	0.1	0.1	5.2	1
14B	DISSOLVED CADMIUM (UG/L)	5	0.2	0.2	0.1	0.3	0
14B	CHROMIUM (UG/L)	18	1.8	1	1	7	0
14B	DISSOLVED CHROMIUM (UG/L)	5	1	1	1	1	0
14B	COPPER (UG/L)	20	18	10	10	120	0
14B	DISSOLVED COPPER (UG/L)	5	10	10	10	10	0
14B	IRON - TOTAL (UG/L)	20	1417	1300	150	3000	19
14B	DISSOLVED IRON (UG/L)	5	814	770	720	1000	5

Continued

14B	LEAD (UG/L)	19	1.8	1	1	8	0
14B	DISSOLVED LEAD (UG/L)	5	1	1	1	1	0
14B	LITHIUM (UG/L)	12	23	20	10	60	
14B	DISSOLVED LITHIUM (UG/L)	5	21	20	10	40	
14B	MANGANESE (UG/L)	20	602.5	545	140	1200	20
14B	DISSOLVED MANGANESE (UG/L)	5	576	550	490	720	5
14B	MOLYBDENUM (UG/L)	8	20	20	20	20	
14B	DISSOLVED MOLYBDENUM (UG/L)	5	20	20	20	20	
14B	NICKEL (UG/L)	7	1.7	2	1	3	0
14B	DISSOLVED NICKEL (UG/L)	1	1	1	1	1	0
14B	SELENIUM (UG/L)	12	1.4	1	1	6	0
14B	SILICON (UG/L)	15	10126.7	10000	4300	14000	
14B	DISSOLVED SILICON (UG/L)	4	10400	10500	9600	11000	
14B	STRONTIUM (UG/L)	17	457.1	420	350	680	
14B	DISSOLVED STRONTIUM (UG/L)	5	374	370	240	490	
14B	VANADIUM (UG/L)	17	10	10	10	10	
14B	DISSOLVED VANADIUM (UG/L)	5	10	10	10	10	
14B	ZINC (UG/L)	20	16	10	10	90	0
14B	DISSOLVED ZINC (UG/L)	5	10	10	10	10	0
14B	TOTAL DISSOLVED SOLIDS (MG/L)	20	839	790	370	1300	19
14B	TOTAL SUSPENDED SOLIDS (MG/L)	13	22.1	14	3	81	
14B	WATER SURF. FR MP (M)	23	5.3	5	4.8	8.5	
14B	WATER SURF. ELVN (M, MSL)	11	226.7	227	223.9	227.3	
14B	WATER SURF. ELVN (FT, MSL)	11	743.7	744.8	734.7	745.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/03 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
15A	ORP (MV)	18	131	111.5	-70	308	
15A	CONDUCTIVITY (UMHOS/CM)	19	403.3	408	340	427	
15A	DISSOLVED OXYGEN (MG/L)	19	0.7	0.7	0.2	2	
15A	TEMPERATURE (DEG C)	19	29.2	17.3	15	243	
15A	PH (STANDARD UNITS)	19	7.4	7.4	7.1	7.7	0
15A	ALKALINITY (MG/L)	19	195.6	193	180	221	
15A	PHEN-PH ALKALINITY (MG/L)	5	0	0	0	0	
15A	ACIDITY (MG/L)	10	14.1	13.5	0	27	
15A	CO2 ACIDITY (MG/L)	6	16.8	16.5	12	21	
15A	CO2 (MG/L)	9	13.7	12	6.2	24	
15A	CA/MG HARDNESS (MG/L)	18	371.8	213.6	182.7	2439	
15A	NITRATE+NITRITE NITROGEN (MG/L)	12	0.1	0	0	1	0
15A	TOTAL ORGANIC CARBON (MG/L)	17	0.9	0.5	0.2	4.1	
15A	TOTAL INORGANIC CARBON (MG/L)	18	77.8	69.5	46	130	
15A	SULFIDE (MG/L)	8	0	0	0	0	
15A	CALCIUM (MG/L)	18	113.3	68	58	680	
15A	DISSOLVED CALCIUM (MG/L)	2	74	74	66	82	
15A	MAGNESIUM (MG/L)	18	21.6	11	9	180	
15A	DISSOLVED MAGNESIUM (MG/L)	2	9.2	9.2	9.2	9.3	
15A	SODIUM (MG/L)	18	11.1	10	7.9	27	
15A	POTASSIUM (MG/L)	18	5.8	2.2	1.8	62	
15A	CHLORIDE (MG/L)	18	3.6	3	1	14	0
15A	SULFATE (MG/L)	18	127.3	22	12	1900	1
15A	FLUORIDE (MG/L)	12	0.1	0.1	0.1	0.2	0
15A	ALUMINUM (UG/L)	18	1428.9	705	50	11000	10
15A	DISSOLVED ALUMINUM (UG/L)	2	50	50	50	50	0
15A	ANTIMONY (UG/L)	5	1	1	1	1	0
15A	ARSENIC (UG/L)	18	3.8	1	1	34	0
15A	DISSOLVED ARSENIC (UG/L)	2	1	1	1	1	0
15A	BARIUM (UG/L)	16	148.8	140	40	330	0
15A	DISSOLVED BARIUM (UG/L)	2	175	175	170	180	0
15A	BERYLLIUM (UG/L)	5	1	1	1	1	0
15A	BORON (UG/L)	18	525	500	500	950	
15A	DISSOLVED BORON (UG/L)	2	500	500	500	500	
15A	CADMIUM (UG/L)	17	0.9	0.1	0.1	9.5	1
15A	DISSOLVED CADMIUM (UG/L)	2	0.7	0.7	0.1	1.4	0
15A	CHROMIUM (UG/L)	15	2.6	1	1	14	0
15A	DISSOLVED CHROMIUM (UG/L)	2	1	1	1	1	0
15A	COPPER (UG/L)	18	14.4	10	10	40	0
15A	DISSOLVED COPPER (UG/L)	2	10	10	10	10	0
15A	IRON - TOTAL (UG/L)	18	12620	245	20	210000	8
15A	DISSOLVED IRON (UG/L)	2	90	90	10	170	0
15A	LEAD (UG/L)	16	2.9	1.2	1	14	0

Continued

15A	DISSOLVED LEAD (UG/L)	2	1	1	1	1	0
15A	LITHIUM (UG/L)	10	14	10	10	20	
15A	DISSOLVED LITHIUM (UG/L)	2	10	10	10	10	
15A	MANGANESE (UG/L)	18	1611	110	9	25000	15
15A	DISSOLVED MANGANESE (UG/L)	2	40	40	28	52	1
15A	MOLYBDENUM (UG/L)	5	22	20	20	30	
15A	NICKEL (UG/L)	5	1.2	1	1	2	0
15A	SELENIUM (UG/L)	14	1.1	1	1	2	0
15A	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
15A	SILICON (UG/L)	13	10392.3	8500	4600	33000	
15A	DISSOLVED SILICON (UG/L)	2	8650	8650	8100	9200	
15A	STRONTIUM (UG/L)	16	353.8	215	90	2000	
15A	DISSOLVED STRONTIUM (UG/L)	2	340	340	230	450	
15A	TITANIUM (UG/L)	1	5	5	5	5	
15A	VANADIUM (UG/L)	16	12.5	10	10	40	
15A	DISSOLVED VANADIUM (UG/L)	2	10	10	10	10	
15A	ZINC (UG/L)	18	17.8	10	10	50	0
15A	DISSOLVED ZINC (UG/L)	2	15	15	10	20	0
15A	TOTAL DISSOLVED SOLIDS (MG/L)	18	436.7	250	200	3500	2
15A	TOTAL SUSPENDED SOLIDS (MG/L)	12	68.6	25	1	390	
15A	WATER SURF. FR MP (M)	21	2.7	2.7	2.3	3.6	
15A	WATER SURF. ELVN (M, MSL)	13	239.5	239.9	237.2	240.4	
15A	WATER SURF. ELVN (FT, MSL)	13	785.7	787.2	778.1	788.7	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/03 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
15B	ORP (MV)	16	8.7	-27.5	-70	184	
15B	CONDUCTIVITY (UMHOS/CM)	17	577.1	584	530	620	
15B	DISSOLVED OXYGEN (MG/L)	17	0.3	0.3	0.1	0.6	
15B	TEMPERATURE (DEG C)	17	16.7	16.4	15	19.9	
15B	PH (STANDARD UNITS)	17	7.1	7.1	6.8	7.3	0
15B	ALKALINITY (MG/L)	17	257.6	252	241	340	
15B	PHEN-PH ALKALINITY (MG/L)	5	0	0	0	0	
15B	ACIDITY (MG/L)	7	25.4	23	0	45	
15B	CO2 ACIDITY (MG/L)	6	26.8	27.5	10	40	
15B	CO2 (MG/L)	6	26.2	21.6	14.1	40	
15B	CA/MG HARDNESS (MG/L)	17	317.4	303	186.5	586	
15B	NITRATE+NITRITE NITROGEN (MG/L)	11	0	0	0	0	0
15B	TOTAL ORGANIC CARBON (MG/L)	16	0.5	0.5	0.2	0.8	
15B	TOTAL INORGANIC CARBON (MG/L)	17	85.3	77	48	140	
15B	SULFIDE (MG/L)	6	0	0	0	0	
15B	CALCIUM (MG/L)	17	95.2	90	61	190	
15B	MAGNESIUM (MG/L)	17	19.4	19	8.3	27	
15B	SODIUM (MG/L)	17	11.5	12	5.9	14	
15B	POTASSIUM (MG/L)	17	3.5	3.5	3.3	3.8	
15B	CHLORIDE (MG/L)	17	6.2	6	3	8	0
15B	SULFATE (MG/L)	17	74.4	58	50	310	1
15B	FLUORIDE (MG/L)	11	0.1	0.1	0.1	0.1	0
15B	ALUMINUM (UG/L)	17	381.8	70	50	1400	7
15B	ANTIMONY (UG/L)	5	1	1	1	1	0
15B	ARSENIC (UG/L)	17	1.1	1	1	2	0
15B	BARIUM (UG/L)	15	50	50	10	130	0
15B	BERYLLIUM (UG/L)	5	1	1	1	1	0
15B	BORON (UG/L)	17	500	500	500	500	
15B	CADMIUM (UG/L)	16	0.2	0.1	0.1	0.6	0
15B	CHROMIUM (UG/L)	15	1.5	1	1	5	0
15B	COPPER (UG/L)	17	22.4	10	10	150	0
15B	IRON - TOTAL (UG/L)	17	1021.8	660	320	4800	17
15B	LEAD (UG/L)	16	2.2	1	1	10	0
15B	LITHIUM (UG/L)	9	22.2	20	10	30	
15B	MANGANESE (UG/L)	17	162.7	140	86	330	17
15B	MOLYBDENUM (UG/L)	5	20	20	20	20	
15B	NICKEL (UG/L)	6	1	1	1	1	0
15B	SELENIUM (UG/L)	13	1	1	1	1	0
15B	SILICON (UG/L)	12	10341.7	11000	5500	12000	
15B	STRONTIUM (UG/L)	15	630	670	200	790	
15B	VANADIUM (UG/L)	15	10	10	10	10	
15B	ZINC (UG/L)	17	50.6	10	10	320	0
15B	TOTAL DISSOLVED SOLIDS (MG/L)	17	401.2	360	270	700	3
15B	TOTAL SUSPENDED SOLIDS (MG/L)	10	21.1	3	1	150	
15B	WATER SURF. FR MP (M)	19	1.9	1.9	1.4	2.4	
15B	WATER SURF. ELVN (M, MSL)	11	240.1	240.7	233.8	241.2	
15B	WATER SURF. ELVN (FT, MSL)	11	787.7	789.6	767.2	791.3	

Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
16A	ORP (MV)	21	-11.6	-35	-110	165	
16A	CONDUCTIVITY (UMHOS/CM)	21	392.8	396	368	415	
16A	DISSOLVED OXYGEN (MG/L)	21	0.4	0.3	0.1	0.9	
16A	TEMPERATURE (DEG C)	21	16.8	17	14.9	20.8	
16A	PH (STANDARD UNITS)	21	7.3	7.3	7	7.4	0
16A	ALKALINITY (MG/L)	21	135.8	135	117	148	
16A	PHEN-PH ALKALINITY (MG/L)	6	0	0	0	0	
16A	ACIDITY (MG/L)	9	29.9	10	0	180	
16A	CO2 ACIDITY (MG/L)	9	18.1	12	7	70	
16A	CO2 (MG/L)	8	29.6	9.7	6.2	158	
16A	CA/MG HARDNESS (MG/L)	23	172.5	170	149	278.1	
16A	NITRATE+NITRITE NITROGEN (MG/L)	14	0	0	0	0.3	0
16A	TOTAL ORGANIC CARBON (MG/L)	22	0.6	0.5	0	1.2	
16A	TOTAL INORGANIC CARBON (MG/L)	23	56.3	55	28	100	
16A	SULFIDE (MG/L)	10	0	0	0	0	
16A	CALCIUM (MG/L)	23	50.4	49	45	85	
16A	DISSOLVED CALCIUM (MG/L)	6	51.8	51	47	59	
16A	MAGNESIUM (MG/L)	23	11.3	11	9	16	
16A	DISSOLVED MAGNESIUM (MG/L)	6	10.4	9.9	9.3	13	
16A	SODIUM (MG/L)	23	18.1	18	15	23.2	
16A	POTASSIUM (MG/L)	23	2.3	2.3	2.1	2.6	
16A	CHLORIDE (MG/L)	23	1.4	1	1	4	0
16A	SULFATE (MG/L)	23	78.5	70	48	300	1
16A	FLUORIDE (MG/L)	14	0.4	0.4	0.1	0.6	0
16A	ALUMINUM (UG/L)	23	1174.8	550	50	4700	16
16A	DISSOLVED ALUMINUM (UG/L)	6	50	50	50	50	0
16A	ANTIMONY (UG/L)	5	1	1	1	1	0
16A	ARSENIC (UG/L)	23	1.3	1	1	3	0
16A	DISSOLVED ARSENIC (UG/L)	6	1	1	1	1	0
16A	BARIUM (UG/L)	20	50	50	30	80	0
16A	DISSOLVED BARIUM (UG/L)	6	60	60	30	100	0
16A	BERYLLIUM (UG/L)	5	1	1	1	1	0
16A	BORON (UG/L)	23	500	500	500	500	
16A	DISSOLVED BORON (UG/L)	6	500	500	500	500	
16A	CADMIUM (UG/L)	22	0.2	0.1	0.1	1	0
16A	DISSOLVED CADMIUM (UG/L)	6	0.5	0.4	0.1	1.2	0
16A	CHROMIUM (UG/L)	20	2.5	1	1	15	0
16A	DISSOLVED CHROMIUM (UG/L)	6	1	1	1	1	0
16A	COPPER (UG/L)	23	12.6	10	10	30	0
16A	DISSOLVED COPPER (UG/L)	6	10	10	10	10	0
16A	IRON - TOTAL (UG/L)	23	1889.6	1100	410	5900	23
16A	DISSOLVED IRON (UG/L)	6	603.3	695	210	900	4
16A	LEAD (UG/L)	21	2.5	1	1	8	0
16A	DISSOLVED LEAD (UG/L)	6	1	1	1	1	0

Continued

16A	LITHIUM (UG/L)	15	25.8	30	10	40	
16A	DISSOLVED LITHIUM (UG/L)	6	24.2	30	10	30	
16A	MANGANESE (UG/L)	23	1271.7	1300	150	1700	23
16A	DISSOLVED MANGANESE (UG/L)	6	1233.3	1250	1100	1300	6
16A	MOLYBDENUM (UG/L)	8	20	20	20	20	
16A	DISSOLVED MOLYBDENUM (UG/L)	4	20	20	20	20	
16A	NICKEL (UG/L)	6	4.2	2.5	1	13	0
16A	SELENIUM (UG/L)	16	1	1	1	1	0
16A	DISSOLVED SELENIUM (UG/L)	2	1	1	1	1	0
16A	SILICON (UG/L)	18	8722.2	8350	4200	12000	
16A	DISSOLVED SILICON (UG/L)	6	8333.3	8300	7700	9200	
16A	STRONTIUM (UG/L)	20	365.5	350	300	650	
16A	DISSOLVED STRONTIUM (UG/L)	6	330	340	190	450	
16A	VANADIUM (UG/L)	20	11	10	10	20	
16A	DISSOLVED VANADIUM (UG/L)	6	10	10	10	10	
16A	ZINC (UG/L)	23	22.2	10	10	150	0
16A	DISSOLVED ZINC (UG/L)	6	10	10	10	10	0
16A	TOTAL DISSOLVED SOLIDS (MG/L)	23	248.7	250	210	280	0
16A	TOTAL SUSPENDED SOLIDS (MG/L)	16	58.8	10	1	330	
16A	WATER SURF. FR MP (M)	25	2.7	2.9	1.1	4.6	
16A	WATER SURF. ELVN (M, MSL)	14	230.7	231	227.8	232.6	
16A	WATER SURF. ELVN (FT, MSL)	14	756.9	758	747.4	763	



Table 1. Kingston Groundwater Quality Summary. Data from 89/01/04 to 94/12/08.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
16B	ORP (MV)	19	138.6	90	-10	443	
16B	CONDUCTIVITY (UMHOS/CM)	19	403	410	375	420	
16B	DISSOLVED OXYGEN (MG/L)	19	0.3	0.3	0.1	0.6	
16B	TEMPERATURE (DEG C)	19	16.6	16.7	14.8	19.8	
16B	PH (STANDARD UNITS)	19	7.3	7.3	6.9	7.4	0
16B	ALKALINITY (MG/L)	19	136.6	137	117	145	
16B	PHEN-PH ALKALINITY (MG/L)	6	0	0	0	0	
16B	ACIDITY (MG/L)	7	30.4	9	0	160	
16B	CO2 ACIDITY (MG/L)	9	13.3	10	7	26	
16B	CO2 (MG/L)	6	31.3	8.8	6.2	141	
16B	CA/MG HARDNESS (MG/L)	20	174.4	171.5	154	207	
16B	NITRATE+NITRITE NITROGEN (MG/L)	10	0	0	0	0.3	0
16B	TOTAL ORGANIC CARBON (MG/L)	19	0.5	0.4	0.2	1.3	
16B	TOTAL INORGANIC CARBON (MG/L)	20	54.1	39.5	14	150	
16B	SULFIDE (MG/L)	5	0	0	0	0	
16B	CALCIUM (MG/L)	20	51.7	50.5	48	60	
16B	DISSOLVED CALCIUM (MG/L)	5	52.8	49	46	65	
16B	MAGNESIUM (MG/L)	20	11	11	8.2	14	
16B	DISSOLVED MAGNESIUM (MG/L)	5	10	9.3	8.2	13	
16B	SODIUM (MG/L)	19	18.6	18	0.1	35	
16B	POTASSIUM (MG/L)	19	2.4	2.3	1.7	3.6	
16B	CHLORIDE (MG/L)	20	1.5	1	1	4	0
16B	SULFATE (MG/L)	20	73.9	72.5	56	110	0
16B	FLUORIDE (MG/L)	10	0.4	0.5	0.1	0.8	0
16B	ALUMINUM (UG/L)	20	2297.5	270	50	12000	14
16B	DISSOLVED ALUMINUM (UG/L)	5	50	50	50	50	0
16B	ANTIMONY (UG/L)	5	1	1	1	1	0
16B	ARSENIC (UG/L)	20	1.2	1	1	3	0
16B	DISSOLVED ARSENIC (UG/L)	5	1	1	1	1	0
16B	BARIUM (UG/L)	18	64.4	50	30	200	0
16B	DISSOLVED BARIUM (UG/L)	5	50	40	20	80	0
16B	BERYLLIUM (UG/L)	5	1	1	1	1	0
16B	BORON (UG/L)	20	500	500	500	500	
16B	DISSOLVED BORON (UG/L)	5	500	500	500	500	
16B	CADMIUM (UG/L)	19	0.2	0.1	0.1	1	0
16B	DISSOLVED CADMIUM (UG/L)	5	0.3	0.3	0.1	0.6	0
16B	CHROMIUM (UG/L)	18	2.4	1	1	11	0
16B	DISSOLVED CHROMIUM (UG/L)	5	1	1	1	1	0
16B	COPPER (UG/L)	20	16	10	10	60	0
16B	DISSOLVED COPPER (UG/L)	5	10	10	10	10	0
16B	IRON - TOTAL (UG/L)	20	2516	325	10	12000	11
16B	DISSOLVED IRON (UG/L)	5	14	10	10	30	0
16B	LEAD (UG/L)	19	3	1	1	12	0
16B	DISSOLVED LEAD (UG/L)	5	1	1	1	1	0

Continued

16B	LITHIUM (UG/L)	13	22.5	20	10	70	
16B	DISSOLVED LITHIUM (UG/L)	5	16.4	20	10	20	
16B	MANGANESE (UG/L)	20	858	815	620	2000	20
16B	DISSOLVED MANGANESE (UG/L)	5	708	690	620	820	5
16B	MOLYBDENUM (UG/L)	10	20	20	20	20	
16B	DISSOLVED MOLYBDENUM (UG/L)	5	20	20	20	20	
16B	NICKEL (UG/L)	6	1	1	1	1	0
16B	SELENIUM (UG/L)	10	1	1	1	1	0
16B	SILICON (UG/L)	14	11271.4	9650	6500	28000	
16B	DISSOLVED SILICON (UG/L)	5	8040	7700	7500	8800	
16B	STRONTIUM (UG/L)	18	368.3	360	320	440	
16B	DISSOLVED STRONTIUM (UG/L)	5	324	320	280	360	
16B	VANADIUM (UG/L)	18	11.1	10	10	30	
16B	DISSOLVED VANADIUM (UG/L)	5	10	10	10	10	
16B	ZINC (UG/L)	20	13	10	10	40	0
16B	DISSOLVED ZINC (UG/L)	5	12	10	10	20	0
16B	TOTAL DISSOLVED SOLIDS (MG/L)	19	257.9	260	220	290	0
16B	TOTAL SUSPENDED SOLIDS (MG/L)	14	24	10.5	1	96	
16B	WATER SURF. FR MP (M)	21	2.2	1.9	1.2	7	
16B	WATER SURF. ELVN (M, MSL)	10	231	231.7	223.2	232.4	
16B	WATER SURF. ELVN (FT, MSL)	10	757.9	760.2	732.3	762.6	

Table 1. Kingston Groundwater Quality Summary. Data from 92/12/07 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
17	ORP (MV)	3	122	177	-13	202	
17	CONDUCTIVITY (UMHOS/CM)	3	2029.7	1500	1429	3160	
17	DISSOLVED OXYGEN (MG/L)	3	0.4	0.3	0.1	0.8	
17	TEMPERATURE (DEG C)	3	17.9	17.8	16.5	19.3	
17	PH (STANDARD UNITS)	3	6	6.1	5.6	6.3	3
17	ALKALINITY (MG/L)	3	84	88	71	93	
17	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
17	CO2 ACIDITY (MG/L)	2	168	168	166	170	
17	CO2 (MG/L)	1	204	204	204	204	
17	CA/MG HARDNESS (MG/L)	3	1011.6	935.4	910.4	1189	
17	TOTAL ORGANIC CARBON (MG/L)	2	0.9	0.9	0.4	1.5	
17	TOTAL INORGANIC CARBON (MG/L)	3	40.3	42	36	43	
17	CALCIUM (MG/L)	3	366.7	340	330	430	
17	DISSOLVED CALCIUM (MG/L)	2	360	360	340	380	
17	MAGNESIUM (MG/L)	3	23.3	21	21	28	
17	DISSOLVED MAGNESIUM (MG/L)	2	23	23	20	26	
17	SODIUM (MG/L)	3	8.3	8.1	7.5	9.2	
17	POTASSIUM (MG/L)	3	21.7	17	14	34	
17	CHLORIDE (MG/L)	3	4	4	4	4	0
17	SULFATE (MG/L)	3	923.3	830	740	1200	3
17	ALUMINUM (UG/L)	3	17633.3	13000	1900	38000	3
17	DISSOLVED ALUMINUM (UG/L)	2	50	50	50	50	0
17	ANTIMONY (UG/L)	3	2.3	1	1	5	0
17	DISSOLVED ANTIMONY (UG/L)	2	3.5	3.5	2	5	0
17	ARSENIC (UG/L)	3	255	100	85	580	3
17	DISSOLVED ARSENIC (UG/L)	2	292.5	292.5	85	500	2
17	BARIUM (UG/L)	3	160	140	30	310	0
17	DISSOLVED BARIUM (UG/L)	2	15	15	10	20	0
17	BERYLLIUM (UG/L)	3	1	1	1	1	0
17	DISSOLVED BERYLLIUM (UG/L)	2	1	1	1	1	0
17	BORON (UG/L)	3	693.3	580	500	1000	
17	DISSOLVED BORON (UG/L)	2	755	755	580	930	
17	CADMIUM (UG/L)	2	0.9	0.9	0.4	1.4	0
17	DISSOLVED CADMIUM (UG/L)	2	0.2	0.2	0.1	0.3	0
17	CHROMIUM (UG/L)	2	40.5	40.5	25	56	0
17	DISSOLVED CHROMIUM (UG/L)	2	1	1	1	1	0
17	COPPER (UG/L)	3	33.3	20	10	70	0
17	DISSOLVED COPPER (UG/L)	2	10	10	10	10	0
17	IRON - TOTAL (UG/L)	3	65000	53000	42000	100000	3
17	DISSOLVED IRON (UG/L)	2	58000	58000	47000	69000	2
17	LEAD (UG/L)	3	24.7	27	1	46	0
17	DISSOLVED LEAD (UG/L)	2	1	1	1	1	0
17	LITHIUM (UG/L)	2	170	170	110	230	
17	DISSOLVED LITHIUM (UG/L)	2	130	130	100	160	
17	MANGANESE (UG/L)	3	2600	2100	2000	3700	3
17	DISSOLVED MANGANESE (UG/L)	2	2600	2600	2000	3200	2

Continued

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
17	MOLYBDENUM (UG/L)	2	20	20	20	20	
17	DISSOLVED MOLYBDENUM (UG/L)	2	20	20	20	20	
17	NICKEL (UG/L)	3	28.7	28	9	49	0
17	DISSOLVED NICKEL (UG/L)	2	5	5	1	9	0
17	SELENIUM (UG/L)	1	1	1	1	1	0
17	STRONTIUM (UG/L)	3	1733.3	1600	1400	2200	
17	DISSOLVED STRONTIUM (UG/L)	2	1750	1750	1500	2000	
17	VANADIUM (UG/L)	3	60	40	10	130	
17	DISSOLVED VANADIUM (UG/L)	2	10	10	10	10	
17	ZINC (UG/L)	3	77.7	73	30	130	0
17	DISSOLVED ZINC (UG/L)	2	40	40	40	40	0
17	TOTAL DISSOLVED SOLIDS (MG/L)	3	1400	1300	1000	1900	3
17	TOTAL SUSPENDED SOLIDS (MG/L)	3	980	940	200	1800	
17	WATER SURF. FR MP (M)	4	2.5	2.6	2.3	2.6	

Table 1. Kingston Groundwater Quality Summary. Data from 92/12/07 to 94/12/07.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX	NUMBER OF EXCEEDANCES
19	ORP (MV)	3	124	169	-16	219	
19	CONDUCTIVITY (UMHOS/CM)	3	2301.3	2391	2040	2473	
19	DISSOLVED OXYGEN (MG/L)	3	0.5	0.3	0.1	1.2	
19	TEMPERATURE (DEG C)	3	17.9	17.8	17.7	18.1	
19	PH (STANDARD UNITS)	3	6	5.9	5.9	6.2	3
19	ALKALINITY (MG/L)	3	95.3	102	70	114	
19	PHEN-PH ALKALINITY (MG/L)	2	0	0	0	0	
19	CO2 ACIDITY (MG/L)	2	440	440	414	466	
19	CO2 (MG/L)	1	666	666	666	666	
19	CA/MG HARDNESS (MG/L)	4	1601.3	1593.8	1525.6	1691.9	
19	TOTAL ORGANIC CARBON (MG/L)	3	0.5	0.6	0.4	0.6	
19	TOTAL INORGANIC CARBON (MG/L)	4	54.3	53.5	44	66	
19	CALCIUM (MG/L)	4	570	560	550	610	
19	DISSOLVED CALCIUM (MG/L)	3	470	460	400	550	
19	MAGNESIUM (MG/L)	4	43.3	43.5	37	49	
19	DISSOLVED MAGNESIUM (MG/L)	3	39.3	42	32	44	
19	SODIUM (MG/L)	4	9.9	9.9	8.8	11	
19	POTASSIUM (MG/L)	4	36.5	37	30	42	
19	CHLORIDE (MG/L)	4	4	4	4	4	0
19	SULFATE (MG/L)	4	1850	1900	1400	2200	4
19	ALUMINUM (UG/L)	4	1467.5	1300	870	2400	4
19	DISSOLVED ALUMINUM (UG/L)	3	56.7	60	50	60	0
19	ANTIMONY (UG/L)	4	1.3	1	1	2	0
19	DISSOLVED ANTIMONY (UG/L)	3	1.7	2	1	2	0
19	ARSENIC (UG/L)	4	59.3	55.5	47	79	2
19	DISSOLVED ARSENIC (UG/L)	3	48.3	44	43	58	1
19	BARIUM (UG/L)	4	37.5	40	30	40	0
19	DISSOLVED BARIUM (UG/L)	3	23.3	20	20	30	0
19	BERYLLIUM (UG/L)	4	1	1	1	1	0
19	DISSOLVED BERYLLIUM (UG/L)	3	1	1	1	1	0
19	BORON (UG/L)	4	2275	2400	1200	3100	
19	DISSOLVED BORON (UG/L)	3	1833.3	2000	1200	2300	
19	CADMIUM (UG/L)	3	0.1	0.1	0.1	0.1	0
19	DISSOLVED CADMIUM (UG/L)	3	0.1	0.1	0.1	0.1	0
19	CHROMIUM (UG/L)	3	1	1	1	1	0
19	DISSOLVED CHROMIUM (UG/L)	3	1	1	1	1	0
19	COPPER (UG/L)	4	10	10	10	10	0
19	DISSOLVED COPPER (UG/L)	3	10	10	10	10	0
19	IRON - TOTAL (UG/L)	4	312500	325000	180000	420000	4
19	DISSOLVED IRON (UG/L)	3	286667	300000	230000	330000	3
19	LEAD (UG/L)	4	1.3	1	1	2	0
19	DISSOLVED LEAD (UG/L)	3	1	1	1	1	0
19	LITHIUM (UG/L)	3	273.3	310	200	310	
19	DISSOLVED LITHIUM (UG/L)	3	266.7	300	200	300	
19	MANGANESE (UG/L)	4	9625	9700	7100	12000	4
19	DISSOLVED MANGANESE (UG/L)	3	8033.3	8100	6800	9200	3

Continued

19	MOLYBDENUM (UG/L)	3	20	20	20	20	
19	DISSOLVED MOLYBDENUM (UG/L)	3	20	20	20	20	
19	NICKEL (UG/L)	4	1.3	1	1	2	0
19	DISSOLVED NICKEL (UG/L)	3	1	1	1	1	0
19	SELENIUM (UG/L)	1	1	1	1	1	0
19	STRONTIUM (UG/L)	4	3050	3000	2800	3400	
19	DISSOLVED STRONTIUM (UG/L)	3	2533.3	2600	2300	2700	
19	VANADIUM (UG/L)	4	10	10	10	10	
19	DISSOLVED VANADIUM (UG/L)	3	10	10	10	10	
19	ZINC (UG/L)	4	112.5	115	70	150	0
19	DISSOLVED ZINC (UG/L)	3	96.7	100	70	120	0
19	TOTAL DISSOLVED SOLIDS (MG/L)	4	2750	3000	1500	3500	4
19	TOTAL SUSPENDED SOLIDS (MG/L)	4	98	101	60	130	
19	WATER SURF. FR MP (M)	4	3.3	3.4	3.1	3.4	

Emory River Water Quality. Summary of 8 Stations near Kingston Fossil Plant.  
Data from 60/05/12 to 85/01/01.

WELL I.D.	PARAMETER	N	MEAN	MEDIAN	MIN	MAX
Emory R.	DISSOLVED OXYGEN (MG/L)	231	8.6	8.5	0.2	13.7
Emory R.	COD (MG/L)	45	5.6	5	1	25
Emory R.	PH (STANDARD UNITS)	259	7.2	7.3	5.5	8.5
Emory R.	ALKALINITY (MG/L)	340	28	17	1	189
Emory R.	PHEN-PH ALKALINITY (MG/L)	339	0.2	0	0	87
Emory R.	ACIDITY (MG/L)	206	2	2	0	10
Emory R.	CA/MG HARDNESS (MG/L)	125	51	32	6	170
Emory R.	CALCIUM as CaCO3 (MG/L)	207	21	17	6	63
Emory R.	CALCIUM (MG/L)	77	12	8	1	33
Emory R.	MAGNESIUM as CaCO3 (MG/L)	113	16	14	2.9	52
Emory R.	MAGNESIUM (MG/L)	171	3.4	2.2	0.5	24
Emory R.	SODIUM (MG/L)	270	2.9	2.15	0	63
Emory R.	POTASSIUM (MG/L)	271	1.3	1.1	0	50
Emory R.	CHLORIDE (MG/L)	312	4.2	4	0.93	21
Emory R.	SULFATE (MG/L)	270	16.7	14	3	80
Emory R.	ALUMINUM (UG/L)	123	995	380	20	50000
Emory R.	ANTIMONY (UG/L)	61	2.5	1	1	30
Emory R.	ARSENIC (UG/L)	75	3.2	1	1	110
Emory R.	BARIUM (UG/L)	129	43	30	5	400
Emory R.	BERYLLIUM (UG/L)	15	10	10	10	10
Emory R.	BORON (UG/L)	13	103	100	10	250
Emory R.	CADMIUM (UG/L)	132	1.2	1	0	30
Emory R.	CHROMIUM (UG/L)	125	4	1	1	113
Emory R.	COBALT (UG/L)	109	8.9	10	1	40
Emory R.	COPPER (UG/L)	220	272	212	10	1850
Emory R.	IRON - TOTAL (UG/L)	286	628	430	7	4600
Emory R.	LEAD (UG/L)	132	8.9	10	5	31
Emory R.	LITHIUM (UG/L)	15	11.3	10	10	30
Emory R.	MANGANESE (UG/L)	272	124	100	2	1350
Emory R.	NICKEL (UG/L)	200	24.5	10	0	290
Emory R.	SELENIUM (UG/L)	69	1.2	1	1	8
Emory R.	SILVER (UG/L)	124	2.3	1	1	10
Emory R.	STRONTIUM (UG/L)	1	40	40	40	40
Emory R.	ZINC (UG/L)	212	35.2	20.5	1	200
Emory R.	WATER TEMP. (Deg. C)	289	18	19.3	1	29.6
Emory R.	TURBIDITY (JTU)	322	13	7	0	330
Emory R.	BOD.5 Day (MG/L)	92	1.4	1.1	1	4.3
Emory R.	TOTAL DISSOLVED SOLIDS (MG/L)	36	77.5	50	20	210
Emory R.	TOTAL SUSPENDED SOLIDS (MG/L)	240	19.4	10	0	195

emory.xls

**KINGSTON FOSSIL PLANT**

**REPLACE KENNEDY WEIR**





STATE OF TENNESSEE  
DEPARTMENT OF ENVIRONMENT AND CONSERVATION  
KNOXVILLE ENVIRONMENTAL FIELD OFFICE

2700 MIDDLEBROOK PIKE, SUITE 220  
KNOXVILLE, TENNESSEE 37921-5602  
PHONE (865) 594-6035 STATEWIDE 1-888-891-8332 FAX (865) 594-6105

February 22, 2005

Mr. Gordon G. Park, Manager of Permitted Programs  
Tennessee Valley Authority  
1101 Market Street  
Chattanooga, Tennessee 37402-2801


RE: Proposed modification to approved construction and operation plans-TVA Kingston  
Fossil Plant Landfill IDL 73-0094


Dear Mr. Park:

The revised plan for the Tennessee Valley Authority's Kingston Fossil Plant Landfill submitted on February 18, 2005, has been reviewed in accordance with Rule Chapter 1200-1-7, Solid Waste Processing and Disposal. This modification consists of a new outfall structure to enhance water movement from the ash pond to the stilling basin. We find that the revised plan meets the regulatory requirements, and we agree that this revision should be considered a minor modification. We are therefore approving the plan as submitted. In all aspects of construction and operation affected by the modification, this plan will replace and supercede the original plan.

An approved copy of the modified plan is enclosed for your use. If you have any questions concerning this matter, do not hesitate to contact me.

Yours truly,

  
Paula Plont  
Environmental Protection Specialist  
Division of Solid Waste Management

  
Larry Cook  
Environmental Field Office Manager  
Division of Solid Waste Management

PJP \TVAKingoutfall.doc

cc: DSWM, Nashville

EXISTING DREDGE CELL

FOR EXISTING CONDITIONS, SEE 10W425-26 THRU -33.

PHASE 1 SEE 10W425-26 THRU -33 & 10W425-34 THRU 37 & 10W425-38 THRU -41

FOR PHASE 1 DEVELOPMENT SEE STAGE 1 & STAGE 2 PLAN SHEETS 10W425-34 THRU -41

PHASE 2 FOR INITIAL DEVELOPMENT SEE 10W425-28 THRU 31, FOR STAGE 1 DEVELOPMENT, SEE 10W425-28 THRU -33.


FOR EXISTING WEIR REPLACEMENT SEE 10W425-77 THRU 10W425-80 & 10W425-70

STILLING BASIN

FOR MODIFICATIONS TO EXISTING WEIRS, SEE 10W425-33.

PHASE 3 DEVELOPMENT SHOWN ON STAGE 1- STAGE 6 DRAWINGS

INTERIM POND (SEE NOTE 3)



NOTES:

1. FOR DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-20.
2. DRAWINGS 10W425-24 AND -25 DEPICT PHASED CONSTRUCTION INFORMATION. INITIAL CONSTRUCTION DRAWINGS BEGIN WITH 10W425-26.
3. FOR INTERIM POND DEVELOPMENT, SEE NOTE 3 ON 10W425-28.

RD	HLP	DRD	REP	SRG	LIP	DLL	KEFSI	J
INITIAL ISSUE PER DCA KIP-05-1074-001-R0								
DATE	ISSUE	REVISED	CHG	APPV	APPR	ISS	PROJECT	AS CONST
SCALE: 1" = 200'								EXCEPT AS NOTED
YARD								
PHASE 1 DREDGE CELL								
LATERAL EXPANSION								
DEVELOPMENT PLAN SHEET 1								
DESIGNED BY	DRAWN BY	CHECKED BY	SUPERVISED BY	REVIEWED BY	APPROVED BY	ISSUED BY		
H.L. PETTY	B.R. DOODSON	S.E. PURKEY	S.E. CAINBY	L.J. PETERSON	D.L. LUNDY			
KINGSTON FOSSIL PLANT								
TENNESSEE VALLEY AUTHORITY								
FOSSIL AND HYDRO ENGINEERING								
AUTOCAD R 14	DATE	36 C	10W425-24	RD				


PLOT FACTOR: 200

W\_TVA

C.A.D. DRAWING DO NOT ALTER MANUALLY

TASK COMPLETED BY: REV. NO.

TVA-00020009



WEIR DISCHARGE * IN CUBIC FEET PER SECOND										
HEAD IN FEET	0.0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09
0.0	.0	.04	.11	.21	.35	.52	.72	.95	1.20	1.34
0.1	1.54	1.75	1.97	2.20	2.44	2.70	2.96	3.24	3.52	3.81
0.2	4.11	4.41	4.72	5.04	5.36	5.69	6.04	6.38	6.73	7.10
0.3	7.47	7.85	8.23	8.62	9.00	9.41	9.82	10.20	10.60	11.10
0.4	11.50	11.90	12.40	12.80	13.30	13.70	14.20	14.70	15.10	15.60
0.5	16.10	16.60	17.10	17.60	18.10	18.60	19.10	19.60	20.10	20.70
0.6	21.20	21.70	22.30	22.80	23.40	23.90	24.50	25.00	25.60	26.20
0.7	26.70	27.30	27.90	28.50	29.10	29.70	30.30	30.90	31.50	32.10
0.8	32.70	33.40	34.00	34.60	35.20	35.90	36.50	37.20	37.80	38.50
0.9	39.10	39.80	40.40	41.10	41.80	42.50	43.10	43.80	44.50	45.20
1.0	45.90									

\* 4'-6" DIAMETER

BILL OF MATERIAL				
ITEM	DESCRIPTION	NO. SPLWYS.	PER SPLWY.	TOTAL REQ'D.
WEIR				
ANGLE BOLT	6 x 6 x 3/4 x 0'-6" 1" #10-10" HEAVY DUTY (FULL THREADS) WITH NUT			3
PL CAULKING	1/4x12 x 14'-2" TYPE 304 STAINLESS BY FIELD			1
SKIMMER				
660 BOLT	120"x12 GAGE CORRUGATED METAL PIPE (NOTE 4) 1/2" #60-1 1/2 GALVANIZED			5 FT. 12
PL ANGLE	1/8" METAL COVER (BY FIELD SEE DETAILS) 2 1/2 x 2 1/2 x 3/8			1 23 FT.
ANGLE	3 x 3 x 3/8			64 FT.
ANGLE	4 x 4 x 3/8			8 FT.

L C70  
WIRED  
1'-0"

BENT BAR LIST					
BAR MARK	NO RECD	BENDING DIMENSIONS			
		a	b	c	e
4L6-3	10	4-4	EX		
4T20-6	1	5-0	5-0		
4U14-9	1	5-0	5-0	EX	
4L2-6	4	1-3	EX		

BILL OF MATERIAL				
ITEM	DESCRIPTION	NO. OF SPLWYS.	PER SPLWY.	TOTAL REQ'D.
402	CLASS X CONCRETE			5 CU. YD.
418	REINFORCING STEEL			170 LB.
	18" D REINFORCED CONCRETE PIPE-CLASS II			
	36" D REINFORCED CONCRETE PIPE-CLASS III			
603	48" D REINFORCED CONCRETE PIPE-CLASS IV			

TYPE A SPILLWAYS

- NOTES:
- A SECTION OF 120" DIA. CORRUGATED METAL PIPE, FULLY COATED, SHALL BE USED FOR THE SKIMMER DEVICE. FABRICATION OF THE PIPE SHALL BE COMPLETE PRIOR TO COATING.
  - ONE SECTION OF 48" PIPE SHALL BE INSTALLED DURING INITIAL CONSTRUCTION.
  - AS ADDITIONAL SECTIONS OF 48" PIPE ARE ADDED, GROUT THE JOINT TO FORM A STABLE AND WATER TIGHT CONNECTION.
  - ALL CONNECTIONS TO BE WELDED.
  - FOR SPILLWAY DETAILS SEE STD. DWG. SD-C11.1.
  - CAULKING SHALL EXTEND COMPLETELY AROUND THE WEIR AND FORM A WATER TIGHT SEAL.
  - WHEN THE WEIR IS INSTALLED THE TOP SHALL BE LEVELLED WITH THE USE OF LEVELING BOLTS.
  - ALL WELDS BY TVA FIELD SHALL BE MADE AND INSPECTED IN ACCORDANCE WITH TVA CONSTRUCTION SPECIFICATION G29C.
  - ALL WELDS BY TVA TO HAVE VISUAL INSPECTION.
  - ALL SURFACES OF FABRICATED STEEL ITEMS SHALL BE PAINTED IN ACCORDANCE WITH CONSTRUCTION SPECIFICATION G14, PART XIX.
  - DEWATER AREA WHERE WEIRS ARE TO BE INSTALLED BY CONSTRUCTING ASH DIKES OR INSTALLING SHEET PILE, AND REMOVING WATER FROM THE INSTALLATION AREA. DESIGN OF ASH DIKES AND/OR SHEET PILE BY TVA FES.
  - PROVIDE ADEQUATE FIRM BASE FOR INSTALLATION OF CONCRETE SPILLWAY BY INSTALLING ROCK BASE OR TENSAR GEOGRID. SELECTION OF TENSAR GEOGRID BY TVA FES.
- NOTES:
- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE T-1 SPECIFICATIONS, UNLESS OTHERWISE NOTED.
  - ALL CONCRETE SHALL BE CLASS "X" IN ACCORDANCE WITH SECTION 400.
  - ALL REINFORCEMENT SHALL CONFORM TO ASTM SPECIFICATION A615 GRADE 60, DEFORMED.
  - DIMENSIONS SHOWN ARE TO THE CENTERLINE OF REINFORCING BARS, UNLESS OTHERWISE NOTED.
  - CONCRETE CLEAR COVER DIMENSIONS ARE AS FOLLOWS:  
3 INCHES FOR FACES CAST AGAINST EARTH OR ROCK;  
2 INCHES FOR ALL OTHER FACES.



7/4


1/8

x3

BENT BAR LIST					
BAR MARK	NO RECD	BENDING DIMENSIONS			
		a	b	c	e
4L6-3	16	4-4	EX		
4T20-6	1	5-0	5-0		
4U14-9	3	5-0	5-0	EX	



TYPE B SPILLWAYS

ACCESS TO SPILLWAY FIELD AS REQUIRED




OR  
1/4

RISE AS REQD. WITH FT. LENGTHS OF 48" CONC. PIPE, CLASS IV



SECTION H70  
SECTION J70  
(OPPOSITE HAND)



SECTION K70  
SECTION L70  
(OPPOSITE HAND)

REV. NO.	DATE	BY	CHKD.	APP'D.	REVISION
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					

SCALE: NONE EXCEPT AS NOTED

YARD



ASH DISPOSAL AREA  
LATERAL EXPANSION  
WEIR & SKIMMER DETAILS

DESIGNED BY:	DRAWN BY:	CHECKED BY:	SUPERVISED BY:	REVIEWED BY:	APPROVED BY:	ISSUED BY:
M.L. PETTY	D.R. DOOSON	R.E. PURKEY	S.R. CATHEY	L.J. PETERSON	D.L. LUNDY	

KINGSTON FOSSIL PLANT  
TENNESSEE VALLEY AUTHORITY  
FOSSIL AND HYDRO ENGINEERING

AUTOCAD R14 DATE 36 c 10W425-70 R 0


TVA-00020010




- NOTES:
- FOR DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-20.
  - DRAWINGS 10W425-24 AND -25 DEPICT PHASED CONSTRUCTION INFORMATION. INITIAL CONSTRUCTION DRAWINGS BEGIN WITH 10W425-26.
  - FOR INTERIM POND DEVELOPMENT, SEE NOTE 3 ON 10W425-28.

REV	DATE	BY	CHKD	APPD	DESCRIPTION
1					INITIAL ISSUE PER DCA KIP-06-1074-001-R0
SCALE: 1" = 200' EXCEPT AS NOTED					
YARD					
PHASE 1 DREDGE CELL LATERAL EXPANSION DEVELOPMENT PLAN SHEET 1					
DESIGNED BY	DRAWN BY	CHECKED BY	SPONSORED BY	REVIEWED BY	APPROVED BY
J.L. PETTY	D.A. BOGSON	R.E. PURKEY	S.A. CATNEY	L.L. PETERSON	D.L. LINDY
KINGSTON FOSSIL PLANT TENNESSEE VALLEY AUTHORITY FOSSIL AND HYDRO ENGINEERING					
AUTOCAD R 14	DATE	36 C	10W425-24	R 0	


TVA-00020011



SECTION A70



DETAIL B70 WEIR DETAILS



DETAIL C70 3 REQUIRED 3'-1'-0"

**WEIR DISCHARGE \* IN CUBIC FEET PER SECOND**

HEAD IN FEET	0.0	0.01	0.02	0.03	0.04	0.05	0.06	0.07	0.08	0.09
0.0	.0	.04	.11	.21	.35	.52	.72	.95	1.20	1.34
0.1	1.54	1.75	1.97	2.20	2.44	2.70	2.96	3.24	3.52	3.81
0.2	4.11	4.41	4.72	5.04	5.36	5.69	6.04	6.38	6.73	7.10
0.3	7.47	7.85	8.23	8.62	9.00	9.41	9.82	10.20	10.60	11.10
0.4	11.50	11.90	12.40	12.80	13.30	13.70	14.20	14.70	15.10	15.60
0.5	16.10	16.60	17.10	17.60	18.10	18.60	19.10	19.60	20.10	20.70
0.6	21.20	21.70	22.30	22.80	23.40	23.90	24.50	25.00	25.60	26.20
0.7	26.70	27.30	27.90	28.50	29.10	29.70	30.30	30.90	31.50	32.10
0.8	32.70	33.40	34.00	34.60	35.20	35.90	36.50	37.20	37.80	38.50
0.9	39.10	39.80	40.40	41.10	41.80	42.50	43.10	43.80	44.50	45.20
1.0	45.90									

\* 4'-6" DIAMETER

**BILL OF MATERIAL**

ITEM	DESCRIPTION	NO. SPLWS.	PER SPLW.	TOTAL REQD.
ANGLE BOLT	WEIR 6 x 6 x 3/4 x 0'-6" 1"x4"-10" HEAVY DUTY (FULL THREADS) WITH NUT			3
PL CAULKING	1/4"x12" x 14'-2" TYPE 304 STAINLESS BY FIELD			1
SKIMMER				
860 BOLT	120"x12 GAGE CORRUGATED METAL PIPE (NOTE 4) 1/2" PHD-1 1/2 GALVANIZED			5 FT. 12
PL ANGLE	1/8" METAL COVER (BY FIELD SEE DETAILS) 2 1/2 x 2 1/2 x 3/8			1 23 FT.
ANGLE	3 x 3 x 3/8			64 FT.
ANGLE	4 x 4 x 3/8			8 FT.


**BENT BAR LIST**

BAR MARK	NO REQD	BENDING DIMENSIONS			
		a	b	c	e
4L6-3	10	4-4	EX		
4T20-6	1	5-0	5-0		
4U14-9	1	5-0	5-0	EX	
4L2-6	4	1-3	EX		


**BILL OF MATERIAL**

ITEM	DESCRIPTION	NO. OF SPLWS.	PER SPLW.	TOTAL REQD.
402	CLASS X CONCRETE			5 CU. YD.
418	REINFORCING STEEL 18" D REINFORCED CONCRETE PIPE-CLASS II 36" D REINFORCED CONCRETE PIPE-CLASS III			170 LB.
603	48" D REINFORCED CONCRETE PIPE-CLASS IV			


- NOTES:
- A SECTION OF 120" DIA. CORRUGATED METAL PIPE, FULLY COATED, SHALL BE USED FOR THE SKIMMER DEVICE. FABRICATION OF THE PIPE SHALL BE COMPLETE PRIOR TO COATING.
  - ONE SECTION OF 48" PIPE SHALL BE INSTALLED DURING INITIAL CONSTRUCTION.
  - AS ADDITIONAL SECTIONS OF 48" PIPE ARE ADDED, GROUT THE JOINT TO FORM A STABLE AND WATER TIGHT CONNECTION.
  - ALL CONNECTIONS TO BE WELDED.
  - FOR SPILLWAY DETAILS SEE STD. DWG. SD-C11.1.
  - CAULKING SHALL EXTEND COMPLETELY AROUND THE WEIR AND FORM A WATER TIGHT SEAL.
  - WHEN THE WEIR IS INSTALLED THE TOP SHALL BE LEVELED WITH THE USE OF LEVELING BOLTS.
  - ALL WELDS BY TVA FIELD SHALL BE MADE AND INSPECTED IN ACCORDANCE WITH TVA CONSTRUCTION SPECIFICATION G29C.
  - ALL WELDS BY TVA TO HAVE VISUAL INSPECTION.
  - ALL SURFACES OF FABRICATED STEEL ITEMS SHALL BE PAINTED IN ACCORDANCE WITH CONSTRUCTION SPECIFICATION G14, PART XIX.
  - DEWATER AREA WHERE WEIRS ARE TO BE INSTALLED BY CONSTRUCTING ASH DIKES OR INSTALLING SHEET PILE, AND REMOVING WATER FROM THE INSTALLATION AREA. DESIGN OF ASH DIKES AND/OR SHEET PILE BY TVA FES.
  - PROVIDE ADEQUATE FIRM BASE FOR INSTALLATION OF CONCRETE SPILLWAY BY INSTALLING ROCK BASE OR TENSAR GEOGRID. SELECTION OF TENSAR GEOGRID BY TVA FES.
- NOTES:
- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE T-1 SPECIFICATIONS, UNLESS OTHERWISE NOTED.
  - ALL CONCRETE SHALL BE CLASS "X" IN ACCORDANCE WITH SECTION 400.
  - ALL REINFORCEMENT SHALL CONFORM TO ASTM SPECIFICATION A615 GRADE 60, DEFORMED.
  - DIMENSIONS SHOWN ARE TO THE CENTERLINE OF REINFORCING BARS, UNLESS OTHERWISE NOTED.
  - CONCRETE CLEAR COVER DIMENSIONS ARE AS FOLLOWS:  
3 INCHES FOR FACES CAST AGAINST EARTH OR ROCK;  
2 INCHES FOR ALL OTHER FACES.




SECTIONAL PLAN



SECTIONAL ELEVATION  
DETAIL D70 SKIMMER DETAILS



DETAIL F70 3'-1'-0"




DETAIL E70 TYPICAL SECTION FOR ACCESS TO SPILLWAY 3/16" = 1'-0"


**BENT BAR LIST**

BAR MARK	NO REQD	BENDING DIMENSIONS			
		a	b	c	e
4L6-3	16	4-4	EX		
4T20-6	1	5-0	5-0		
4U14-9	3	5-0	5-0	EX	


TYPE B SPILLWAYS




SECTION N70 (TYPE A & B)




DETAIL G70 PLAN-SPILLWAY TYPE B



SECTION M70



SECTION H70 SECTION J70 (OPPOSITE HAND)



SECTION K70 SECTION L70 (OPPOSITE HAND)

REV	DATE	BY	CHKD	APPD	REVISION
1					
2					
3					
4					
5					
6					
7					
8					
9					
10					
11					
12					

SCALE: NONE EXCEPT AS NOTED

**YARD**

**ASH DISPOSAL AREA LATERAL EXPANSION WEIR & SKIMMER DETAILS**

DESIGNED BY: H.L. PETTY  
 DRAWN BY: D.R. DOBSON  
 CHECKED BY: R.E. PURKEY  
 SUPERVISED BY: S.R. CATNEY  
 REVIEWED BY: L.J. PETERSON  
 APPROVED BY: D.L. LINDY

KINGSTON FOSSIL PLANT  
 TENNESSEE VALLEY AUTHORITY  
 FOSSIL AND HYDRO ENGINEERING


AUTOCAD R14 DATE 3/93 C 10W425-70 R 0

TVA-00020012

36 C 10W425-77 2 3 4 5 6 7 8 9 10 11 12



- WEIR REPLACEMENT GENERAL NOTES:**
- FOR DRAWING INDEX & LEGEND SEE 10W425-20
  - FOR GENERAL NOTES SEE 10W425-26.
  - AFTER INSTALLATION OF NEW WEIRS, DISCONNECT STORM DRAIN FROM WEIR AT LOCATION NEAR DIVIDE DIKE. TREMIE GROUT STORM DRAINS CONNECTED TO EXISTING WEIRS. GROUT SHALL CONSIST OF VOLCLAY GROUT OR VOLCLAY GRANULAR GROUT, AS MANUFACTURED BY CETCO. MIX AND PLACE GROUT AS RECOMMENDED BY THE MANUFACTURER. VOLCLAY GRANULAR GROUT MAY BE MIXED WITH FLYASH IN LIEU OF SILICA SAND. MIXTURE SHALL BE PUMPABLE, YET STIFF ENOUGH TO INSTALL UNDERWATER. INSTALL TREMIE PIPE & VERIFY FULL PENETRATION TO OUTLET END OF STORM DRAIN. SEAL WELD 1/4" THICK A36 STEEL PLATE TO END OF STORM DRAIN TO PREVENT FLOWING WATER. PUMP GROUT MIXTURE INTO PIPE AND GRADUALLY WITHDRAW TREMIE PIPE DURING FILLING. MAINTAIN TREMIE PIPE WITHIN GROUT TO PREVENT THE FORMATION OF AIR POCKETS OR HONEYCOMB AREAS.
  - OTHER METHODS MAY BE USED BY THE CONTRACTOR TO GROUT WEIR DISCHARGE PIPING, IF APPROVED BY ENGINEERING.
  - NEW DIKE SHOWN IN FINAL CONFIGURATION. SEE DRAWING 10W425-78 FOR DIKE CONSTRUCTION
  - REMOVE TWO SECTIONS (APPROXIMATELY 20 FT) OF THE EXISTING WALKWAY AT THE DIVIDER DIKE SIDE TO PREVENT PERSONNEL FROM ACCESSING THE EXISTING WEIR. THE REMAINING SECTION OF THE WALKWAY SHALL REMAIN IN PLACE. EXISTING WOODEN POLES SHALL BE LEFT IN PLACE AND NOT REMOVED.



**KEY PLAN**

REV	DATE	BY	CHKD	APPD	ISSD	PROJECT	AS NOTED

SCALE: 1" = 50' EXCEPT AS NOTED

**DREDGE CELL WEIR REPLACEMENT OVERALL PLAN**

DESIGNED BY:	DRAWN BY:	CHECKED BY:	APPROVED BY:	REVIEWED BY:	APPROVED BY:	ISSUED BY:
HL. PETTY	D.R. BOSSON	R.E. PURNEY	S.R. CARNEY	L.J. PETERSON	D.L. LUNDY	

**KINGSTON FOSSIL PLANT**  
**TENNESSEE VALLEY AUTHORITY**  
 FOSSIL AND HYDRO ENGINEERING

AUTOCAD R14	DATE	36 C	10W425-77	R O
-------------	------	------	-----------	-----



PLOT FACTOR: 50  
 W TVA  
 C.A.D. DRAWING  
 DO NOT ALTER MANUALLY

TVA-00020013

8/10W425-78 36 C 96 2 3 4 5 6 7 8 9 10 11 12

A  
B  
C  
D  
E  
F  
G  
H

A  
B  
C  
D  
E  
F



- NOTES:
1. FOR WEIR REPLACEMENT GENERAL NOTES, SEE 10W425-77
  2. NEW DIKE SHALL BE CONSTRUCTED AS SHOWN TO ALLOW FOR DEWATERING OF THE CONSTRUCTION AREA. CONSTRUCT THE NEW DIKE IN CONFORMANCE WITH DETAILS SHOWN ON 10W425-6 AND 10W425-72, EXCEPT THAT UNDERDRAINS ARE NOT REQUIRED. ASH SHALL BE BOTTOM ASH OR A MIXTURE OF FLYASH AND BOTTOM ASH OBTAINED FROM THE DREDGE CELL. PLACE BOTTOM ASH AND COMPACT TO ESTABLISH AN INITIAL WORKING BASE SUITABLE TO SUSTAIN EQUIPMENT LOADS. THEN PLACE ASH IN THIN LIFTS AND COMPACT.
  3. TESTING FOR COMPACTED DIKES AS PRESCRIBED IN THE QA/QC PLAN IS NOT REQUIRED FOR THIS DIKE, BECAUSE IT IS NOT A LOAD-BEARING DIKE FOR ASH DISPOSAL. AFTER A FIRM BASE IS ESTABLISHED, PERFORM COMPACTION TESTING AT FOUR TESTS PER LIFT.

REV.	DATE	BY	CHKD.	APPV.	ISSD.	PROJECT	AS NOTED

SCALE: 1" = 20' EXCEPT AS NOTED


YARD

**DREDGE CELL  
WEIR REPLACEMENT  
INITIAL DIKE LAYOUT**

DESIGNED BY:	DRAWN BY:	CHECKED BY:	SUPPLIED BY:	REVIEWED BY:	APPROVED BY:	ISSUED BY:
H.L. PETTY	D.R. DOBSON	R.E. PURKEY	S.R. CADEY	L.A. PETERSON	D.L. LINDY	


**KINGSTON FOSSIL PLANT  
TENNESSEE VALLEY AUTHORITY  
FOSSIL AND HYDRO ENGINEERING**

AUTOCAD R14    DATE 36 C 10W425-78    R 0



- NOTES:
- FOR WEIR REPLACEMENT GENERAL NOTES, SEE 10W425-77.
  - REMOVE EXISTING LIME SLUDGE DISCHARGE LINE WHERE IT IS ROUTED FROM THE BANK TO THE EXISTING WEIR. PIPE MAY BE REUSED AT CONSTRUCTOR'S OPTION, OR A NEW PIPE USED TO REROUTE THE LIME SLUDGE DISCHARGE LINE TO THE NEW WEIRS. NEW PIPE SHALL BE STEEL PIPE TO MATCH DIAMETER AND WALL THICKNESS OF EXISTING. BUTT WELD OR USE FLANGE CONNECTION TO SPLICE THE PIPE TOGETHER WHERE IT IS REROUTED TO THE NEW WEIR. INSTALL LIME SLUDGE DISCHARGE LINE TO THE NEW WEIRS AS SHOWN.
  - WHERE DISCHARGE PIPE IS TO BE SUBMERGED, PIPING SHALL BE HDPE, SDR 11, WELD A STEEL FLANGE ADAPTOR TO THE FABRICATED AS A SPARGER. SEE DETAILS ON 10W425-80.
  - AFTER COMPLETION OF WEIR INSTALLATION, EXCAVATE THE CENTER SECTION FROM THE DIKE AS SHOWN, TO ALLOW THE ASH POND TO DISCHARGE TO THE STILLING BASIN.
  - REMOVE SECTIONS OF DISCHARGE FROM EXISTING WEIRS, AND TREMIE GROUT AS DISCUSSED IN NOTE 3 ON 10W425-77.
  - PIPE AND FITTING USED TO CONSTRUCT HDPE LIME SLUDGE DISCHARGE PIPING SHALL BE HIGH-DENSITY POLYETHYLENE (HDPE) PE 3408 PIPE, CELL CLASSIFICATION 345444C IN ACCORDANCE WITH ASTM D 3350. ALL PIPING AND FITTINGS SHALL BE NEW MATERIAL AND BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
  - ALL HDPE PIPING AND FITTINGS SHALL BE JOINED BY BUTT FUSION WELDING, IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
  - PROVIDE MINIMUM 0.5% SLOPE ON LIME SLURRY PIPE.
  - INSTALL WEIR AT EL 760 AS SHOWN. WEIR WILL BE LOWERED TO EL 758 PRIOR TO GYPSUM/ASH DISPOSAL FACILITY CONSTRUCTION.
  - PROTECT EXCAVATIONS BY SHORING, BRACING, SHEET PILING, OR OTHER METHODS AS REQUIRED TO PREVENT CAVE-IN OF LOOSE SOIL INTO EXCAVATION IN ACCORDANCE WITH OSHA 29 CFR 1926, SUBPART P - EXCAVATION.
  - PRIOR TO REMOVING INSULATION FROM EXISTING LIME SLURRY DISCHARGE PIPE, DETERMINE WHETHER INSULATION CONTAINS ASBESTOS. CONTACT KIF ENVIRONMENTAL PROGRAM ADMINISTRATOR PA(E) (LINDA CAMPBELL) PRIOR TO REMOVING INSULATION. REMOVE INSULATION IN ACCORDANCE WITH OSHA REQUIREMENTS, IF IT CONTAINS ASBESTOS. DISPOSE OF ASBESTOS-CONTAINING MATERIALS IN ACCORDANCE WITH STATE OF TENNESSEE SOLID WASTE REQUIREMENTS.
  - SPACE SUPPORTS FOR 4" # LIME SLURRY PIPING ON 10' CENTER TO CENTER. SEE PIPE SUPPORT DETAIL H80 ON 10W425-80.

KIF-05-1074  
 PIC-05-1097  
 AA-01




REV.	DATE	BY	CHKD.	APP'D.	DESC.	PROJECT	AS NOTED
SCALE: 1" = 20' EXCEPT AS NOTED							
YARD							
DREDGE CELL							
WEIR REPLACEMENT							
FINAL DIKE & WEIR LAYOUT							
DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY	NOTED BY	APPROVED BY	ISSUED BY	
H.L. PETTY	D.R. DODSON	R.E. PURKEY	S.R. CATNEY	L.S. PETERSON	D.L. LUNDY		
KINGSTON FOSSIL PLANT							
TENNESSEE VALLEY AUTHORITY							
FOSSIL AND HYDRO ENGINEERING							
AUTOCAD R14	DATE	36 C	10W425-79	R D			




A  
B  
C  
D  
E  
F  
G  
H


A  
B  
C  
D  
E  
F




SECTION A80-A80  
SCALE: HORIZONTAL: 1"=20'  
VERTICAL: 1"=10'




SECTION B80-B80  
SCALE: HORIZONTAL: 1"=20'  
VERTICAL: 1"=10'




DETAIL C80  
N.T.S.




DETAIL E80  
N.T.S.




DETAIL D80  
(ANTI SEEP COLLAR)  
N.T.S.




DETAIL F80  
N.T.S.




DETAIL G80  
N.T.S.



DETAIL H80  
PIPE SUPPORT  
N.T.S.




DETAIL I80  
PIPE BOLLARD  
N.T.S.



DETAIL J80  
TEMPORARY SILT FENCE  
N.T.S.

- NOTES:
1. FOR ADDITIONAL NOTES SEE 10W425-79.
  2. CHAIN SHALL BE HIGH STRENGTH GRADE 80 ALLOY STEEL CHAIN TRADE SIZE 9/32", .28" Ø, 3500 LB W/L, McMASTER-CARR, PART #345731.
  3. FOR WEIR REPLACEMENT NOTES, SEE 10W425-77.
  4. WATER STOP SHALL BE AKWASTOP GASKET WATERSTOP AS MANUFACTURED BY CETCO. INSTALL IN ACCORDANCE WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.
  5. L SECTION SHALL BE GALVANIZED FINISH, TOUCH UP AREAS WHERE GALVANIZED FINISH IS REMOVED DURING CONSTRUCTION WITH ZINC RICH PAINT.

- NOTES:
1. FILTER FABRIC FENCE TO BE PLACED PRIOR TO THE START OF ROUGH GRADING.
  2. STEEL POSTS SHALL BE METAL "T" POSTS - 6'-0" LONG.
  3. POSTS SHALL BE PLACED AT 4' INTERVALS MAX.
  4. WIRE FABRIC AND FILTER FABRIC SHALL BE SECURELY BOUND TO POSTS WITH EITHER STAPLES OR WIRE TIES.
  5. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING CONDITION OF FILTER FABRIC FENCE IN A CONDITION THAT IS SATISFACTORY TO TVA UNTIL FINAL ACCEPTANCE OF WORK. REMOVE SEDIMENT WHEN SEDIMENT HEIGHT IS ONE-THIRD THE HEIGHT OF THE FENCE.
  6. FILTER FABRIC SHALL BE A CLASS A FABRIC IN ACCORDANCE WITH TVA SPECIFICATION T-1, SECTION 571.



DETAIL K80  
N.T.S.

- NOTES:
1. PLACE COMPACTED MINERAL AGGREGATE BEDDING SOIL BACKFILL IN LOOSE LIFTS NOT EXCEEDING 8" IN THICKNESS & COMPACT TO 95% STANDARD PROCTOR DENSITY IN ACCORDANCE WITH ASTM D 898. MOISTURE & DENSITY TESTING SHALL BE IN ACCORDANCE WITH ASTM D 2922. AT A FREQUENCY OF NOT LESS THAN 6 TESTS PER LIFT. SCARIFY EXISTING SOIL TO A DEPTH OF 3" PRIOR TO PLACEMENT OF THE FIRST LIFT. COMPACTION TESTING FOR COMPACTED FILL AROUND STORM DRAIN PIPING AND DITCH ONLY REQUIRES 2 TESTS PER LIFT.
  2. STORM DRAIN PIPING FOR WEIR INSTALLATION IS PLACED ON THE STILLING POND SIDE OF THE DIVIDER DIKE, BEDDING MAY BE DUMPED INTO THE TRENCHES. DO NOT PLACE DUMPED MATERIAL BENEATH ANY ROADWAYS.

REV. NO.	DATE	BY	CHKD BY	APP'D BY	PROJECT	AS SHOWN	DATE
1							
SCALE: NONE EXCEPT AS NOTED							
YARD							
DREDGE CELL							
WEIR REPLACEMENT							
CROSS SECTION & DETAILS							
DESIGNED BY	DRAWN BY	CHECKED BY	SUPERVISED BY	REVIEWED BY	APPROVED BY	ISSUED BY	DATE
H.L. PETTY	D.R. DOBSON	R.E. PURKEY	S.R. CATNEY	L.S. PETERSON	D.L. LUNDY		
KINGSTON FOSSIL PLANT							
TENNESSEE VALLEY AUTHORITY							
FOSSIL AND HYDRO ENGINEERING							
AUTOCAD R14	DATE	36	C	10W425-80	R 0		



**ADVANCE AUTHORIZATION FORM**

AA-01	Parent DCN: KIF - 05 - 1093	FTS:
	Parent PIC: KIF - 05 - 1093	Responsible Design Engineer/ORG/Phone: Mike Hughes /(423)751-2783

**Requested Change or Problem:**

1. Relocate weirs closer to existing divider dike so that there are not pipe joints in the 36 in dia RCP between the divider dike and the concrete spillway. The other alternative is to place additional concrete on the pipe to provide adequate ballast.

**Suggested Solution (not required):**

See attached sketches (Attachment 1 and 2) to this AA.

**Approved Change**

Resp. Engineer:	Signature	Date	Supv.	Signature	Date
-----------------	-----------	------	-------	-----------	------


**NOTES**

1. FIELD SHALL ADJUST WETL LOCATION SUCH THAT THERE ARE NO PIPE JOINTS BETWEEN THE CONCRETE SPILLWAY & THE DIVIDER DIKE. MAINTAIN MINIMUM SPACING BETWEEN EXISTING DIVIDER DIKE AND SKIMMER IN ACCORDANCE WITH DETAIL E70.


2. IF THE WETL RELOCATION RESULTS IN A PIPE JOINT BEING LOCATED BETWEEN THE CONCRETE SPILLWAY & DIVIDER DIKE, SEE DETAIL L80 (THIS AA).

**ATTACHMENT 1**

DCN KIF-05-1074 RΦ  
 PIC KIF-05-1093 RΦ  
 AA-01



ATTACHMENT 2  
DCN KIF-05-1074 RØ  
PIC KIF-05-1093 RØ  
AA-01



DETAIL 1 80  
(NEW)  
(10W425-80)

**ADVANCE AUTHORIZATION FORM**

AA-02	Parent DCN: KIF - 05 - 1074	FTS:
	Parent PIC: KIF - 05 - 1093	Responsible Design Engineer/ORG/Phone: Mike Hughes /(423)751-2783


**Requested Change or Problem:**

1. Provide riprap surfacing to the outer face of the new dike (constructed for the new weir installation) for slope protection, as shown on the attached sketch.

**Suggested Solution (not required):**

1. See attached sketches to this AA.

**Approved Change**

Resp. Engineer:		7/27/05	Supv.		
	Signature	Date		Signature	Date

**FORM G – ADVANCE AUTHORIZED TRACKING SHEET**

Parent DCN Number KIF - 05 - 1074

PIC Number KIF - 05 - 1093 (Enter one number per sheet)

AA-01 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-02 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-03 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-04 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-05 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-06 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-07 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-08 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-09 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-10 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-11 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-12 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-13 Issue Date	_____	Initiator	_____	Signature	_____	Date
AA-14 Issue Date	_____	Initiator	_____	Signature	_____	Date

**NOTE:** If additional AAs are needed, additional tracking sheets may be added with the AA level numbers above increased accordingly. Any unused AA lines should be lined through with a diagonal line and marked "N/A."

Last AA issued before requesting final approval \_\_\_\_\_

Final approval requested \_\_\_\_\_ Date \_\_\_\_\_ Initiator \_\_\_\_\_ Signature \_\_\_\_\_ Date \_\_\_\_\_

**FORM G - ADVANCE AUTHORIZED TRACKING SHEET**

AA- 02 PIC# KIF - 05 - 1093 Page \_\_\_\_\_ of \_\_\_\_\_

**Block 6 - Requested Change**

Provide riprap surfacing to the outer face of the new dike (constructed for the new weir installation) for slope protection, as shown on the attached sketch.


**Block 11 - Approved Change**

See attached sketches to this AA.

Supv/Prin Egnr: \_\_\_\_\_ Signature \_\_\_\_\_ Date \_\_\_\_\_ RE: \_\_\_\_\_ Signature \_\_\_\_\_ Date \_\_\_\_\_



PIC KIF -0. 93 4



DRAWING # 10W425-80  
 DCN: KIF-05-1074  
 PIC: KIF-05-1093  
 AA# 02

TVA-00020024

**TENNESSEE VALLEY AUTHORITY  
KINGSTON FOSSIL PLANT**

**PROPOSED DREDGE CELL REPAIR  
SUPPORTING INFORMATION**

Requested Minor Modification to:

**IDL 73-0094**

**April 26, 2005**



**Prepared By**

**Tennessee Valley Authority  
Fossil Engineering Services**

Summary Handout  
TDEC/TVA Meeting – April 27, 2005  
Kingston Dredge Cell Repair  
Minor Modification Request

# Aerial View of the Site



Blow-out Area

Cell II

Existing Dredge Cells

Cell III


Cell I

Proposed Lateral  
Expansion Area

# Model Stratigraphy and Existing Geometry

Outer dike material  
(fly ash/bottom ash  
mixture)

Base material  
(fly ash/bottom ash  
mixture)



Alluvium

Shale

Clay at toe

- Vertical and horizontal extent of subsurface stratigraphy were estimated based on visual field identification, SPT data, knowledge of the likely construction sequence, and in-situ hydraulic conductivity obtained during the January 2005 site investigation.
- Model geometry and subsurface stratigraphy were agreed on by the Project Team during the meeting that took place on 31<sup>st</sup> January 2005.

## Proposed Repair

The proposed improvements for the lower portion of the dredge cell side slope consists of the following major items:

- A trench drain constructed to a minimum depth of 6 feet deep from the existing bench at EL 795 feet
- A trench drain constructed to a minimum depth of 5 feet deep from the existing bench at EL 781 feet
- A trench drain constructed to a minimum depth of 5 feet deep from the existing bench at EL 775 feet
- A buttress type toe drain pipe with rip rap lining to the existing drainage channel adjacent to Swan Pond Road.




Figure 1 – Generalized Section Along Swan Pond Road

# Conclusions

## GeoSyntec

Based on analytical results for Case 3, the proposed improvements are expected to lower the phreatic surface away from the face of the lower portion of the side slope significantly reducing the future potential for piping and providing an acceptable factor of safety.

The independent seepage analyses prepared by GeoSyntec are in general agreement with the analyses prepared by Parsons.

## Parsons E&C

Analysis confirms that the proposed trench drains, riprap buttress and ditch system as configured more than adequately handles the anticipated seepage.





Tennessee Valley Authority, 1101 Market Street, Chattanooga, Tennessee 37402-2801

April 27, 2005

Mr. Larry Cook, Manager  
Environmental Assistance Center  
Division of Solid Waste Management  
2700 Middlebrook 2700  
Knoxville, Tennessee 37921-5602

TENNESSEE VALLEY AUTHORITY (TVA) – KINGSTON FOSSIL PLANT – MINOR  
MODIFICATION REQUEST FOR DREDGE CELL REPAIR - IDL 73-0094

Dear Mr. Cook:

TVA requests a minor modification of its Class II Permit IDL 73-0094 to allow the repair of the "blowout" that occurred in November 2003 at the subject facility. Enclosed are detailed engineering drawings of the proposed repair along with supporting information outlining the various analysis that were performed to arrive at this method of repair. Please note that TVA proposes to begin this repair on June 1, 2005. Expedient review and approval of this request would be greatly appreciated.

Please contact Mr. Larry C. Bowers at (423)751-4947, if you have questions concerning this correspondence.

Sincerely,

A handwritten signature in cursive script that reads "Gordon St. Park".

Gordon Park, Manager  
Manager of Permitted Programs  
Environmental Affairs  
5D Lookout Place

Enclosures

cc: Mr. Glenn Pugh,  
Division of Solid Waste Management  
5<sup>th</sup> Floor, L & C Tower  
401 Church Street  
Nashville, Tennessee 37243

Title: Proposed Dredge Cell Restoration Supporting Information		DCN # KIF-05-1090	
		Plant/Unit: KINGSTON FOSSIL PLANT	
Vendor	Contract No.	Key Nouns: Minor Modification, Permit, Dredge Cell	
Applicable Design Documents	REV	EDMS NUMBER	DESCRIPTION
	R0	<b>B65 050426 254</b>	April, 2005 IDL 73-0094
References	R1		

TENNESSEE VALLEY AUTHORITY  
FOSSIL POWER GROUP  
FOSSIL ENGINEERING SERVICES  
SITE AND ENVIRONMENTAL ENGINEERING

4/26/05

	Revision 0	R1
Date	April, 2005	
Prepared	KIF Seep Team	
Checked	Larry C. Bowers	
Supervised	Harold L. Petty	

**TENNESSEE VALLEY AUTHORITY  
KINGSTON FOSSIL PLANT**

**PROPOSED DREDGE CELL REPAIR  
SUPPORTING INFORMATION**

Requested Minor Modification to:

**IDL 73-0094**

**April 26, 2005**



**Prepared By**

**Tennessee Valley Authority  
Fossil Engineering Services**

## **Table of Contents**

1. Summary of Approach and Conclusion
2. Description of Principle Design Features
3. Appendix A – Parsons Summary Report (TIMES Model)
4. Appendix B – GeoSyntec Summary Report (Seep/W Model)  
Independent Analysis that confirms general agreement with the  
TIMES Model
5. Appendix C – Hydraulic Calculations (Sump Pond Design)
6. Appendix D - List of Drawings