

**KINGSTON FOSSIL PLANT  
REPLACE KENNEDY WEIR  
TOTAL PROJECT ESTIMATE**

Estimate Number	05290	Option: 0	PCN Number:	KIF531
Plant:	KIF	Revision: 0	Estimate Type:	Detailed
Cost Engineer:	C. I. TONEY	Unit #:	Estimate Accuracy:	+/- 10%
Requesting Engr:	S. M. Haber	Phase: 3	Estimate Issue Date	03/02/2005

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$0
Partner (Non-Manual)		
Other / Sunk Cost		\$29,457
<b><u>Total Phase I</u></b>		<b><u>\$29,457</u></b>
<u>Phase II</u>		
Engineering		\$0
Long Lead Procurement		\$0
Partner ( Non-Manual )		
Other / Other Organizations		\$0
<b><u>Total Phase II</u></b>		<b><u>\$0</u></b>
<u>Phase III</u>		
Construction ( Partner )		
Permanent Material		\$112,375
Labor ( T&L )	6,325.37	\$175,607
Labor ( Non-Manual )	760.00	\$38,000
Equipment		\$64,767
Subcontracts		\$5,000
Partner Fee		\$10,680
Partner Insurance		\$6,408
Escalation		\$0
Construction Risk Dollars		\$0
Other		\$11,010
Total Construction Cost		\$423,847
Engineering		\$19,008
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$17,688
Other / Plant Support		\$10,000
<b><u>Total Phase III</u></b>		<b><u>\$470,543</u></b>
<u>All Phases</u>		
Construction Partner	7,085.37	\$423,847
Long Lead Procurement		\$0
Engineering		\$19,008
Other / Sunk Cost		\$29,457
Other / Plant Support		\$10,000
Total Risk Dollars		\$17,688
<b><u>Total Project Costs</u></b>	<b><u>7,085.37</u></b>	<b><u>\$500,000</u></b>
<b><u>For Information only Total Environmental</u></b>		<b><u>\$0</u></b>
<b><u>For Information only Total Demolition Costs</u></b>		<b><u>\$0</u></b>

Spreadsheet Report  
KIF052900/REPLACE WEIRS

KINGSTON FOSSIL PLANT  
REPLACE KENNEDY WEIR  
TOTAL PROJECT ESTIMATE

Project name KIF052900/REPLACE WEIRS

Engineer Stan Haber

Estimator C. I. TONEY

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Project Sitework

Plant KIF

Estimate # 05290

PCN # KIF531

Requesting Engr S. M. Haber

Option 0

Revision 0

Phase 3

Estimate Type Detailed

Estimate Accuracy +/- 10%

Est. Issue Date 03/02/2005

Funding Type Capital

Outaget(Y/N) N

Basis of Estimate

Scope of work based on preliminary TVA design drawings (10W425-24, 70, 77, 78, 79, and 80) and conversations with Dan Smith, Parsons E & C. Construction quantities are based on provided drawings and quantities sheet provided by engineering.

Project Work Schedule

\*All work based on a forty hour week. Overtime is not included in this estimate.

\*Construction activities: 4 x 10's

\*Anticipated project duration: 36 workable shifts

Note

1. Additional cost shall be incurred by others if excavation encounters solid rock and cannot be removed by conventional means.
2. Approval will be required by engineering for plugging existing weirs. Plug material/grout is based drawing notes, but notes do not detail exact material.
3. Construction drawings should include more detailed dimensions of weir elevations (including existing), dike locations, and weir location.
4. The allowance for the turbidity curtain is based on a standard 200' curtain. Additional cost may be incurred by others if specialized material is required.

Sorted by Location/Activity

Detail summary

Report format

Spreadsheet Report  
KIF05290/REPLACE WEIRS

imate Company

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount
	Erosion Controls	Erect Silt Fence	300.00 lf	0.089	20.57 hrs	519	148	-	-	-	2.53	760
		Erosion Controls			20.57 hrs	519	148	-	-	-	2.53	760
					20.57 hrs	519	148	-	-	-	2.53	760
2	Kennedy Weir Replace	Grout Seal Existing Drains From Kennedy Weir	35.00 cy	4.114	144.00 mh	3,797	2,640	-	1,084	-	214.91	7,522
		Ash Fill (Dike)	10,500.00 cy	910.000	11,540 cd	32,624	-	-	22,847	-	5.30	55,671
		Dewatering (2 each)	1.00 ls	50.000	50.00 cd	21,460	-	-	6,250	-	27,710.00	27,710
		Cut For 36" Diameter RCP And Weirs	1,237.00 cy	0.200	247.40 mh	6,189	-	-	3,093	-	7.50	9,282
		Bedding For 36" RCP Storm Drain Pipe	165.00 ton	0.320	82.50 mh	2,064	1,518	-	275	-	23.36	3,857
		Fill For 36" Diameter RCP Storm Drain Pipe	415.00 cy	0.320	132.80 mh	3,322	3,000	-	3,232	-	15.77	5,544
		Standard TVA Weir Structures	5.00 ea	254.105	1,270.52 mh	33,840	35,000	-	5,500	-	14,866.03	74,340
		36" Diameter RCP Storm Drain Pipe	700.00 lf	0.889	622.22 mh	15,170	35,031	-	3,743	-	77.92	54,344
		Concrete Anti Slop Collar With Water Stop	5.00 ea	3.125	15.63 mh	437	588	-	40	-	212.93	1,065
		Pipe Bolts, 6" Dia Concrete Filled (Embedded In 4" x 1.5 Concrete)	2.00 ea	4.000	24.00 mh	300	100	-	100	-	2,833.54	14,168
		5/8" Eye Bolts With Nut And Washer	2.00 ea	6.000	12.00 mh	300	20	-	100	-	450.10	900
		Steel Pipe Supports (Galvanized Angle 3x3x1/4@5' length)	58.00 ea	1.103	64.00 mh	2,052	725	-	230	-	51.84	3,007
		4" Dia Steel Pipe Galvanized	595.00 lf	1.231	732.45 mh	25,237	7,438	-	6,659	-	66.11	39,333
		Pipe Insulation (For Both Steel & HDPE Pipe)	990.00 lf	0.200	136.00 mh	4,900	5,460	-	1,233	-	16.74	11,383
		4" Dia HDPE IPS DR 11 (Solid Wall)	85.00 lf	0.308	26.16 mh	692	1,063	-	237	-	25.90	2,202
		4" Dia HDPE IPS DR 11 Sparger Pipe	80.00 lf	0.410	32.83 mh	1,132	1,000	-	298	-	30.37	2,429
		4" Dia Steel & HDPE Flanges	2.00 ea	5.500	11.00 mh	379	60	-	100	-	289.51	539
		Install Galvanized Alloy Steel Pipe Clamps	145.00 lf	0.014	2.00 mh	43	1,220	-	-	-	8.71	1,263
		Ash Cut (Dike)	14.00 ea	1.000	14.00 mh	483	140	-	63	-	49.02	666
		Install Turbidity Curtain	2,333.00 cy	910.000	2,560 cd	5,309	2,218	-	2,218	-	3.23	7,527
		(Nonwoven) Geotextile (Installed Underwater)	400.00 sf	1.000,000	1.000 cd	1,622	40	-	655	-	4.30	4,300
		Remove 2 Section Of Wooden Walkway W/4" Rail On Each Side	360.00 in	0.320	115.20 mh	396	528	-	40	-	2.41	964
		QA/QC For Construction Disposal	120.00 sf	0.150	18.00 mh	2,590	3,600	-	1,816	-	23.36	8,409
		Kennedy Weir Replace	1.00 ls		5,987.80 hrs	166,288	112,227	5,000	59,973	-	5,000.00	343,489
					5,987.80 hrs	166,288	112,227	5,000	59,973	-	5,000.00	343,489
XCONST FACILITY	Construct Facilities	Mobilize, Drug Test, Miscellaneous Other, & Demobilize	1.00 ls	317.003	317.00 mh	8,800	4,700	-	4,700	-	13,500.00	13,500
		Construct Facilities			317.00 hrs	8,800	4,700	-	4,700	-	13,500.00	13,500
ZNON MANUAL	Field General Expens	Phase 3 Non Manual	1.00 ls	760.000	760.00 mh	38,000	38,000	-	-	-	38,000.00	38,000
		Field General Expens			760.00 hrs	38,000	38,000	-	-	-	38,000.00	38,000
		ZNON MANUAL			760.00 hrs	38,000	38,000	-	-	-	38,000.00	38,000

Estimate Totals

Labor	213,607	7,065,375	his		
Material	112,375				
Subcontract	5,000	2,923,113	his		
Equipment	64,767				
	395,749				
Small Tools Expense	2,846	0.450	\$/hr	H	
Consumables & Expendables	7,024	4.000	%	C	
Office Supplies & Expense	1,140	3.000	%	C	
	11,010				
Partner Insurance (FY04)	6,403	3.000	%	C	
Partner Award Fee (FY04)	10,660	5.000	%	C	
	17,063				
FFG Proj Engr - Phase 3	2,520	0.847	% @	42.00	A
FFG Civil Engr - Phase 3	2,100	0.705	% @	42.00	A
Parsons Engr - Phase 3	10,800	2.117	% @	72.00	A
FFG Proj Civil Cost - Phase 3	1,008	0.339	% @	42.00	A
FFG Proj Civil Sched - Phase 3	1,008	0.339	% @	42.00	A
FFG Engr Records - Phase 3	672	0.226	% @	42.00	A
CAD Dwg Support - Phase 3	900	0.085	% @	###	A
	19,068				
Phase 1 Other/Sunk Cost	29,457				L
	472,312				
Phase 3 Other/Plant Support	10,000				L
	482,312				
Project Risk	17,688				L
	17,688				
<b>Total</b>	<b>500,000</b>				

05290

**Toney, Calvin L.**

**From:** Haber, Stanley M.  
**Sent:** Tuesday, March 01, 2005 8:11 AM  
**To:** Baugh, James S.  
**Cc:** Davis, Michael D; Lankford, Brian S.; Waldrep, Roger T.; Harless, J. Larry; Toney, Calvin L.; Smith, H. Michael; Franklin, Thomas; Lundy, Dennis L.; Long, S. Scott; Palmer, Patricia A.; Ward, Jeffrey L.  
**Subject:** RE: Needs for KIF Projects Review Meeting: March 16, 2005

Steve,

Sorry about leaving you off of the distribution of my earlier email - my mistake.

As we discussed last Thursday, the project package for the Kennedy Weir needs to be revised and presented at this project review meeting due to the increase in project cost. Scott Long alludes to the revision requirements within the trailing email. The following items need to be completed:

1. A new cost estimate and summary sheet needs to be coordinated with Cost Estimating (Calvin Toney/Larry Harless).
2. The current CPJ needs to be revised to reflect the new cost estimate and level of estimate accuracy. Because this package was a minor project, some special steps need to be taken to ensure that we maintain the project history on this document. Trisch Palmer and Scott Long can provide you guidance on doing this on this.
3. The monthly cash flow forecast for FY05 needs to be revised once the cost estimate summary is complete (Tom Franklin will be able to help you with this).
4. The project schedule needs to be revised; your input on the phase 3 durations for installation need to be provided to Mike Smith. We will need your initials on a copy of the revised schedule for inclusion in the project package.
5. We can get Tom Franklin to generate a PA cover sheet once we complete items 1 through 4.
6. Once the PA cover sheet is completed, you can attach the remaining project package documents (the completed CEC and the Project Review Reformance Impact Checklist) and the package will be ready for signatures.

After we complete items 1 through 6, we will be ready for the project review meeting.

Sorry again about leaving you off of the earlier distribution. Please let me know if you have any other questions.

Stan

-----Original Message-----

**From:** Baugh, James S.  
**Sent:** Tuesday, March 01, 2005 6:30 AM  
**To:** Haber, Stanley M.  
**Subject:** FW: Confirmation: KIF Projects Review Meeting: March 16, 2005

Stan,

What do you need from me and my group to support this meeting?

Thanks,

Steve

03/01/2005

TVA-00029005

-----Original Message-----

**From:** Davis, Michael D  
**Sent:** Monday, February 28, 2005 3:22 PM  
**To:** Ward, Jeffrey L.; Baugh, James S.; Lankford, Brian S.  
**Subject:** FW: Confirmation: KIF Projects Review Meeting: March 16, 2005

FYI

**Michael D. Davis**

**Manager Yard Operations - Projects & Engineering**

Office (423) 751 - 7864  
Mobile (423) 240 - 7909  
FAX (423) 751 -6701

-----Original Message-----

**From:** Haber, Stanley M.  
**Sent:** Monday, February 28, 2005 12:31 PM  
**To:** Deskins, Earl L.; Knight, Patricia F.; Cowser, Daniel J.; Rehberg, Robert L.; Hilton, Susan O.; Tolliver, Sherry D.; Nale, Leslie W.; Nelson, Gary R.; Coffman, Lewis A.  
**Cc:** Halicks, David R.; Marcum, Mark T.; Waldrep, Roger T.; Lundy, Dennis L.; Long, Theresa L.; Waldrep, Roger T.; Davis, Michael D; Ward, Jeffrey L.; Preslar, Jacky D.; Long, S. Scott  
**Subject:** Confirmation: KIF Projects Review Meeting: March 16, 2005

Team,

Per the trailing email, our request for a meeting on March 16, 2005 in Chattanooga to review our projects has been confirmed. Please note the starting time of 3:30 pm.

Stan

-----Original Message-----

**From:** Long, S. Scott  
**Sent:** Monday, February 28, 2005 11:52 AM  
**To:** Haber, Stanley M.  
**Subject:** FW: KIF Projects Review Meeting: Requested Date for Meeting

OK to make it happen.....please note that by waiting until the 16th, please ensure that all components of the project packages are ready for this review meeting on the 16th so there will be no delay in processing if they are approved. I expect to have all the FPG approved projects rolled up by the 17th. Thanks.

Scott Long  
Mgr., Project Development  
Fossil Power Group  
LP 2G-C  
751-7282

-----Original Message-----

**From:** Smith, Deborah J.  
**Sent:** Monday, February 28, 2005 10:59 AM  
**To:** Long, S. Scott  
**Subject:** RE: KIF Projects Review Meeting: Requested Date for Meeting

Masoud said that would be fine. Just schedule it to start about 3:30 p.m. when the FY06 Performance Plan is finished.

-----Original Message-----

**From:** Long, S. Scott  
**Sent:** Monday, February 28, 2005 9:57 AM  
**To:** Smith, Deborah J.  
**Cc:** Haber, Stanley M.  
**Subject:** FW: KIF Projects Review Meeting: Requested Date for Meeting

Debbie, please ask Masoud is this KIF request would be acceptable.

When PAF mentioned before the meeting on cyclones last Friday that they would like to discuss the FY07 projects also, he commented that the FY07 project reviews should be done at the site instead of Chatt.

Scott Long  
Mgr., Project Development  
Fossil Power Group  
LP 2G-C  
751-7282

-----Original Message-----

**From:** Haber, Stanley M.  
**Sent:** Monday, February 28, 2005 8:12 AM  
**To:** Long, S. Scott  
**Cc:** Waldrep, Roger T.; Palmer, Patricia A.; Knight, Patricia F.; Deskins, Earl L.; Cowser, Daniel J.; Tolliver, Sherry D.; Lundy, Dennis L.; Harless, J. Larry; Halicks, David R.; Rehberg, Robert L.  
**Subject:** KIF Projects Review Meeting: Requested Date for Meeting

Scott,

Kingston has requested to have their follow-up meeting to finalize their FY07 projects review on 3/16/05 in Chattanooga. This would be after their meeting that is scheduled for that day with the SVP/Operations at 1:00 pm (the FPG Performance Plan Internal Review/FY2006). Please let me know if this will work.

Thanks.

Stan

Period Name: FEB-05 Budget: FY05 REV BUDGET ANN. BUS. PLAN: FY05 ANN BUS PN

\* MONTH TO DATE \$ \* \*\*\*\*\* YEAR TO DATE \$ \*\*\*\*\* PROJECT TO DATE \$

	Actual	Rev. Budget	Actual	Variance	Actual
KIF531 KIF--REPLACE KENNEDY WEIR					
KIF531A KIF-REPLACE KENNEDY WEIR PH A					
KIF531A-01 FES	2,660.91	5,000.00	3,900.51	-1,099.49	3,900.51
KIF531A-02 PLANT SUPPORT	0.00	1,000.00	0.00	-1,000.00	0.00
KIF531A-03 PARSONS	2,072.11	19,000.00	2,072.11	-16,927.89	2,072.11
Total KIF531A KIF-REPLACE KENNEDY WEIR PH A	4,733.02	25,000.00	5,972.62	-19,027.38	5,972.62
KIF531B KIF-REPLACE KENNEDY WEIR PHB					
KIF531B-01 FES	0.00	8,000.00	0.00	-8,000.00	0.00
KIF531B-02 PLANT SUPPORT	0.00	2,000.00	0.00	-2,000.00	0.00
KIF531B-04 RED ESTIMATE	0.00	0.00	187.50	187.50	187.50
KIF531B-05 PARSONS	0.00	12,000.00	0.00	-12,000.00	0.00
Total KIF531B KIF-REPLACE KENNEDY WEIR PHB	0.00	22,000.00	187.50	-21,812.50	187.50
Total KIF531 KIF--REPLACE KENNEDY WEIR	4,733.02	47,000.00	6,160.12	-40,839.88	6,160.12
Total Report	4,733.02	47,000.00	6,160.12	-40,839.88	6,160.12

*Normal TMD*

*PARSONS*

*167124*



KINGSTON FOSSIL PLANT  
 Replace Kennedy Weir  
 PCN: KIF531  
 Current Approved Phase: 1

FUNCTIONAL ACCOUNT **EC0681**  
 RESPONSIBLE UNIT 18953

LOCATION 450Y

SHORT CODE

肆

PHASE	SHORT CODE	DESCRIPTION	CURRENT BUDGET			ACTUAL TO-DATE AS OF 3/01/05			FORECAST				
			FPEP APPVD PH1 ON 10/14/04.										
			PY	FY05	TOTAL	PY	FY05	TOTAL	PY	FY05	TOTAL		
<b>PHASE 1</b>													
KIF531A-01	001DN47	FE & Project Control	0	5	5	0	4	4	0	5	5	0	5
KIF531A-02	001DN49	Plant Support	0	1	1	0	0	0	0	1	1	0	1
KIF531A-03	001DN4B	Parsons	0	19	19	0	2	2	0	19	19	0	19
		<b>Total Final Engg</b>	<b>0</b>	<b>25</b>	<b>25</b>	<b>0</b>	<b>6</b>	<b>6</b>	<b>0</b>	<b>25</b>	<b>25</b>	<b>0</b>	<b>25</b>
<b>PHASE 2</b>													
KIF531B-01	001DN4C	FE & Project Control	0	13	13	0	0	0	0	13	13	0	13
KIF531B-02	001DN4D	Plant Support	0	5	5	0	0	0	0	5	5	0	5
KIF531B-03	001DN4F	LL Materials	0	20	20	0	0	0	0	20	20	0	20
KIF531B-04	001DN4H	HED Estimate	0	5	5	0	0	0	0	5	5	0	5
KIF531B-05	001DN4J	Parsons	0	82	82	0	0	0	0	82	82	0	82
		<b>Total Final Engg</b>	<b>0</b>	<b>125</b>	<b>125</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>125</b>	<b>125</b>	<b>0</b>	<b>125</b>
<b>PHASE 3</b>													
KIF531C-01	001DN4K	FE & Project Control	0	8	8	0	0	0	0	8	8	0	8
KIF531C-02	001DN4L	Plant Support	0	5	5	0	0	0	0	5	5	0	5
KIF531C-03	001DN4M	HED	0	77	77	0	0	0	0	77	77	0	77
KIF531C-04	001DN4N	Parsons	0	10	10	0	0	0	0	10	10	0	10
		<b>Total Implementation</b>	<b>0</b>	<b>100</b>	<b>100</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>0</b>	<b>100</b>	<b>100</b>	<b>0</b>	<b>100</b>
		<b>TOTAL PROJECT</b>	<b>0</b>	<b>250</b>	<b>250</b>	<b>0</b>	<b>6</b>	<b>6</b>	<b>0</b>	<b>250</b>	<b>250</b>	<b>0</b>	<b>250</b>

KIF531 REPLACE KENNEDY WEIR.xls  
 03/01/2005 6:57 AM

**Toney, Calvin L.**

---

**From:** Smith, Daniel R [Daniel.R.Smith@worleyparsons.com]  
**Sent:** Thursday, February 24, 2005 4:20 PM  
**To:** Hughes, Michael  
**Cc:** Petty, Harold L.; Toney, Calvin L.; Knox, Robert  
**Subject:** FW: KIF - Weir Replacement

Mike, Gary relayed to me some additional comments brought up by Stuart Harris (possibly). We didn't initially include any riprap, because of low velocities. Erosion typically can occur on these ash dikes, but I'm not as concerned about the velocities. However, if everyone concurs that riprap is needed, here are some quantities that can be added to the estimate (although that flies in the face of cost reduction).

Dan

-----Original Message-----

**From:** Melton, Gary  
**Sent:** Thursday, February 24, 2005 4:15 PM  
**To:** Smith, Daniel R  
**Subject:** KIF - Weir Replacement

Dan,

Follow up from today's meeting:

1. Calvin: Add 400 square yards of geotextile (T-1 spec 571 class C) (non-woven needle punched, installed underwater) and 360 tons of 6" D50 riprap to armor the new ash dikes.
2. A detail can be added to the drawing showing the geotextile and riprap.
3. Dan and I discussed the precast manhole sections versus pipe sections for the new weirs and Dan's response is that it is Lynn's decision. It also would be a simple adjustment to the drawing.

Thank You,  
Gary Melton  
WorleyParsons  
423-757-9974

02/28/2005

TVA-00029010

## Toney, Calvin L.

---

**From:** Smith, Daniel R [Daniel.R.Smith@worleyparsons.com]  
**Sent:** Saturday, February 26, 2005 2:38 PM  
**To:** Hughes, Michael  
**Cc:** Melton, Gary; Toney, Calvin L.; Knox, Robert; Petty, Harold L.  
**Subject:** FW: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

Mike, I haven't heard any feedback from last weeks meeting regarding adjustments to the cost estimate. If they decide to install the turbidity curtain, Roy Quinn has estimated about \$4300 (see below). This is higher than the roughly \$3K in the estimate.

Depending on the outcome of the review, this adjustment should be made.

Dan

-----Original Message-----

**From:** Melton, Gary  
**Sent:** Friday, February 25, 2005 8:55 PM  
**To:** Smith, Daniel R  
**Subject:** RE: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

Dan,  
According to Calvin, to install 1,000 sf of turbidity curtain will cost \$3,139.  
Gary

-----Original Message-----

**From:** Smith, Daniel R  
**Sent:** Friday, February 25, 2005 5:05 PM  
**To:** Melton, Gary; 'Hughes, Mike'  
**Subject:** FW: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

Gary, can you compare the cost that Roy Quinn Estimated for the turbidity curtain at KIF to what is in the cost estimate?

Roy estimates \$4300. I can't remember what HED/Calvin had. We will want to be sure to revise if the cost estimate currently has a lower cost than what Roy Quinn has, especially since Roy will install.

Thanks

Dan

-----Original Message-----

**From:** Quinn, James R. [mailto:jrquinn@tva.gov]  
**Sent:** Friday, February 25, 2005 4:15 PM  
**To:** Smith, Daniel R  
**Cc:** Hughes, Michael; Petty, Harold L.  
**Subject:** RE: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

Attached is our estimate. We will have hardware (cable, clamps, etc.) left from the installation we are doing in the ash stilling pond at KIF. Note that I am buying the curtain a little long to ensure ample coverage.

-----Original Message-----

**From:** Smith, Daniel R [mailto:Daniel.R.Smith@worleyparsons.com]  
**Sent:** Friday, February 25, 2005 3:38 PM

To: Quinn, James R.  
Cc: Hughes, Michael; Petty, Harold L.  
Subject: RE: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

I think stainless is better than galvanized, especially in the alkaline environment typically found in these ponds.

If you can put together a cost estimate for materials and installation, and forward to us, we could compare that with what we have in our construction estimate.

-----Original Message-----

From: Quinn, James R. [mailto:jrquinn@tva.gov]  
Sent: Friday, February 25, 2005 2:11 PM  
To: Smith, Daniel R  
Cc: Hughes, Michael; Petty, Harold L.  
Subject: RE: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

Dan,  
Attached is the manufacturer spec. on the materials that we usually install. We use the type II, 22oz vinyl coated curtains for most applications. These DO meet the specs as you required in the performance specs. I am awaiting pricing info from the distributor so we can ensure we fall within you budget target. Our typical installation will include vinyl coated stainless cable and stainless clamps, hardware, etc. You spec vinyl coated galvanized. Is the stainless OK?

<http://www.aerflo.com/index.php?option=content&task=view&id=6&Itemid=26>

Thanks,  
Roy

-----Original Message-----

From: Smith, Daniel R [mailto:Daniel.R.Smith@worleyparsons.com]  
Sent: Wednesday, February 23, 2005 3:14 PM  
To: Quinn, James R.  
Cc: Hughes, Michael; Petty, Harold L.  
Subject: Drawings (DCA's) For Kennedy Weir replacement at KIF, plus turbidity curtain location/draft specification

<html>  
<font face="Arial" style="font-size: 8pt;">\*\*\* WorleyParsons Group Notice \*\*\*  
"This email is confidential. If you are not the intended recipient, you must not disclose or use the information contained in it. If you have received this email in error, please notify us immediately by return email and delete the email and any attachments. Any personal views/opinions expressed by the writer may not necessarily reflect the views/opinions of the company."  
</font>  
</html>

<html>  
<font face="Arial" style="font-size: 8pt;">\*\*\* WorleyParsons Group

Notice \*\*\*

"This email is confidential. If you are not the intended recipient, you must not disclose or use the information contained in it. If you have received this email in error, please notify us immediately by return email and delete the email and any attachments. Any personal views/opinions expressed by the writer may not necessarily reflect the views/opinions of the company."

</font>

</html>

KIF531  
KENNEDY WEIR

PROJECT PACKAGE WAS \$250K

PH1 + PH2 COMBINED ± \$35,000 RIGHT NOW  
(SUNK COST). NOT INCLUDED IN ESTIMATE.

48"  $\phi$  MANHOLE RISERS VS 48"  $\phi$  PIPE WILL  
SAVE APPROX \$10.<sup>00</sup>/LF.

WATER AQUARIUM STALL X 12' WIDE ~ \$30,000  
(TEMPORARY COFFERDAM)

BRIAN Luning

~~MIKE DAVIS~~ - LOOK FOR CONSTRUCTION SAVINGS.

STAN HABER - CHECK ON USE OF MANHOLE RISERS.

STEVE, MIKE, + BRIAN - WILL FIND THE MONEY.

ADD SUNK COST PLUS RIPRAP TO OUTSIDE SLOPE OF DIKE.

- ADD 400 SQ FT (NON WOVEN) GEOTEXTILE (INSTALLED UNDERWATER) ✓
- ADD 360 TN OF 6" D50 RIPRAP TO ARMOR THE NEW ASH DIKE ✓

INCREASE COST OF TURBIDITY CURTAIN \$4,300 VS \$3,139. ✓

39  
1.50 356 -  
2,157,568  
2.65 4,157  
130  
2,129

\$ 166,807

\$ 21.74 <sup>MH</sup> 6,008 MHS

$$5,800 \div 27.76 = 317.00288$$

\$ 60,067

\$ 22.16 <sub>EL</sub> 2,711 EHS

$$5,470 \div 22.16 = 212.09386$$

6,325

**KINGSTON FOSSIL PLANT  
KENNEDY WEIR  
TOTAL PROJECT ESTIMATE**

Estimate Number	05229	Option:	0	PCN Number:	KIF531
Plant:	KIF	Revision:	0	Estimate Type:	Preliminary
Cost Engineer:	C. I. TONEY	Unit #:		Estimate Accuracy:	+/- 20%
Requesting Engr:	S. M. Haber	Phase:	2	Estimate Issue Date	02/15/2005

	<u>Hours</u>	<u>Dollars</u>
<b>Phase I</b>		\$0
Engineering		
Partner (Non-Manual)		\$0
Other / Other Organizations		<u>\$0</u>
	<u>Total Phase I</u>	
<b>Phase II</b>		\$0
Engineering	=	\$0
Long Lead Procurement		
Partner ( Non-Manual )		\$0
Other / Other Organizations		<u>\$0</u>
	<u>Total Phase II</u>	
<b>Phase III</b>		
Construction ( Partner )		\$101,123
Permanent Material		\$171,110
Labor ( T&L )	6,150.71	\$36,900
Labor ( Non-Manual )	738.00	\$62,381
Equipment		\$5,000
Subcontracts		\$10,401
Partner Fee		\$6,240
Partner Insurance		\$0
Escalation		\$0
Construction Risk Dollars		\$10,719
Other		\$403,874
Total Construction Cost		
		\$19,008
Engineering		\$0
Direct plant support + TVA Other Costs		\$118
Project Rounding Dollars		\$10,000
Other / Plant Support		<u>\$433,000</u>
	<u>Total Phase III</u>	
<b>All Phases</b>		
Construction Partner	6,888.71	\$403,874
Long Lead Procurement		\$0
Engineering		\$19,008
Other / Plant Support		\$10,000
Total Rounding Dollars		\$118
		<u>\$433,000</u>
	<u>Total Project Costs</u>	<u>6,888.71</u>
		\$0
	<u>For Information only Total Environmental</u>	\$0
	<u>For Information only Total Demolition Costs</u>	\$0



Spreadsheet Report  
KIF05229/WEIRS

KINGSTON FOSSIL PLANT  
KENNEDY WEIR  
TOTAL PROJECT ESTIMATE

Project name	KIF05229/WEIRS
Engineer	Stan Haber
Estimator	C. I. TONEY
Labor rate table	KIF 40 2005
Equipment rate table	TVA Equipment
Project Plant	Sitework
Estimate #	KIF
PCN #	05229
Requesting Engr	KIF531
Option	S. M. Haber
Revision	0
Phase	0
Estimate Type	2
Estimate Accuracy	Preliminary
Est. Issue Date	4- 20%
Funding Type	02/14/2005
Outage(Y/N)	Capital
Report format	N

Sorted by Location/Activity  
Detail summary

Spreadsheet Report  
KIF05229/WEIRS

imate Company

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount
	Erosion Controls	Erect Silt Fence	300.00 lf	0.069	20.57 mh	519	148	-	93	-	2.53	760
	Erosion Controls	Erosion Controls			20.57 hrs	519	148	-	93	-		760
	01				20.57 hrs	519	148	-	93	-		760
2	Kennedy Weir Replace	Grout Seal Existing Drains From Kennedy Weir	35.00 cy	4.114	144.00 mh	3,797	2,640	-	1,084	-	214.91	7,522
		Ash Fill (Dike)	10,500.00 cy	910.000	11,54 cd	32,824	-	-	22,647	-	58.20	55,071
		Dewatering (2 each)	1,00 lf	50.000	50.00 cd	21,480	-	-	6,250	-	27,730.00	27,730
		Cut For 36" Diameter RCP And Weirs	123.00 cy	0.200	247.40 mh	6,189	1,518	-	3,093	-	79.38	3,897
		Bedding For 36" RCP Storm Drain Pipe	165.00 ton	0.500	82.50 mh	2,064	3,322	-	3,222	-	15.77	5,544
		Fill For 36" Diameter RCP Storm Drain Pipe	415.00 cy	0.320	132.80 mh	3,322	35,000	-	5,500	-	14,668.03	74,340
		Standard TVA Weir Structures	3.00 ea	234.05	1,270.52 mh	33,840	27,930	-	3,743	-	97.78	47,444
		36" Diameter RCP Storm Drain Pipe	700.00 lf	0.868	622.22 mh	15,070	437	-	588	-	212.93	1,065
		Concrete Anvil Sleep Collar With Water Stop	5.00 ea	3.725	15.63 mh	573	13,500	-	95	-	2,833.54	14,168
		Pipe Bolts, 6" Dia Concrete Filled (Embedded In 4" x 1.5" Concrete)	5.00 ea	4.600	24.00 mh	300	500	-	100	-	450.10	900
		Ballast For 36" Diameter Pipe Installation	2.00 ea	6.000	12.00 mh	300	20	-	100	-	10.00	20
		5/8" Eye Bolts With Nut And Washer	2.00 ea	1.103	64.00 mh	2,052	725	-	230	-	51.84	3,007
		1/2" U-Bolts With Nut And Washer	58.00 ea	1.231	732.45 mh	7,438	174	-	6,539	-	88.11	39,333
		Steel Pipe Supports (Galvanized Angle 3x3x1/4@3' length)	595.00 lf	0.200	196.00 mh	25,257	5,460	-	1,233	-	16.74	16,740
		4" Dia Steel Pipe Galvanized	680.00 lf	0.308	26.19 mh	902	1,083	-	237	-	25.90	2,202
		Pipe Insulation (For Both Steel & HDPE Pipe)	85.00 lf	0.410	32.83 mh	1,132	1,000	-	288	-	30.37	2,428
		4" Dia HDPE PS DR 11 (Solid Wall)	80.00 lf	5.500	11.00 mh	379	60	-	100	-	269.51	539
		4" Dia HDPE PS DR 11 Sparger Pipe	2.00 ea	0.074	2.00 mh	43	1,220	-	63	-	49.02	686
		4" Dia Steel & HDPE Flanges	145.00 lf	1.000	14.00 mh	483	140	-	323	-	7.827	7,827
		Install Galvanized Grade 80 Alloy Steel Chain	14.00 ea	910.000	2.56 cd	5,309	2,000	-	328	-	3.14	3,139
		Install Galvanized Alloy Steel Pipe Clamps	2,333.00 cy	2,000.000	0.50 cd	811	2,000	-	328	-	5.43	651
		Ash Cut (Dike)	1,000.00 sf	0.150	16.00 mh	457	-	-	184	-	5,000.00	5,000
		Install Turbidity Curtain	120.00 sf									
		Remove 2 Section Of Wooden Walkway, Weir, Rail On Each Side	1.00 ls									
		O&OC For Construction Disposal										
		Kennedy Weir Replace			5,824.60 hrs	162,081	100,975	5,000	57,788	-	5,000.00	325,854
					5,824.60 hrs	162,091	100,975	5,000	57,788	-		325,854
XCONST FACILITY	Construct Facilities	Mobilize, Drug Test, Miscellaneous Other, & Demobilize	1.00 ls	305.536	305.54 mh	8,500	-	-	4,500	-	13,000.00	13,000
		Construct Facilities			305.54 hrs	8,500	-	-	4,500	-		13,000
		XCONST FACILITY			305.54 hrs	8,500	-	-	4,500	-		13,000
ZNON MANUAL	Field General Expenses	Phase 3 Non Manual	1.00 ls	738.000	738.00 mh	36,900	-	-	-	-	36,900.00	36,900
		Field General Expenses			738.00 hrs	36,900	-	-	-	-		36,900
		ZNON MANUAL			738.00 hrs	36,900	-	-	-	-		36,900

Spreadsheet Report  
KIF/05229/WEIRS

imate Company

Estimate Totals

Labor	206,010	6,888,708	hrs	
Material	101,123			
Subcontract	5,000			
Equipment	62,361	2,877,784	hrs	
	376,514			
Small Tools Expense	2,768	0,450	\$/hr	H
Consumables & Expendables	6,844	4,000	%	C
Office Supplies & Expense	1,107	3,000	%	C
	10,719			
Partner Insurance (FY04)	6,240	3,000	%	C
Partner Award Fee (FY04)	10,401	5,000	%	C
	16,641			
FPG Proj Engr - Phase 3	2,520	0,871	% @ 42.00	A
FPG Civil Engr - Phase 3	2,100	0,726	% @ 42.00	A
Parsons Engr - Phase 3	10,800	2,177	% @ 72.00	A
FPG Proj Critl Cost - Phase 3	1,008	0,348	% @ 42.00	A
FPG Proj Critl Sched - Phase 3	1,008	0,348	% @ 42.00	A
FPG Engr Records - Phase 3	672	0,232	% @ 42.00	A
CAD Dwg Support - Phase 3	900	0,087	% @ ###	A
	19,800	422,882		
Phase 3 Other/Plant Support	10,000			L
	10,000	432,882		
Rounding	118			L
	118	433,000		
<b>Total</b>		<b>433,000</b>		

- HED will perform pre-job briefings each morning and at anytime changes occur in the daily work scope. A post-job briefing will be performed at the completion of the construction project.

#### Project Work Schedule

- All work based on a forty hour week. Overtime is not included in this estimate.
- Construction activities: 4 x 10's
- Anticipated project duration: 36 workable shifts

#### Cost

Total Estimated Cost: **\$374,000**

Thank you for the opportunity to look at your project.  
Submitted: 2/18/05

#### Note

1. Additional cost shall be incurred by others if excavation encounters solid rock and cannot be removed by conventional means.
2. Approval will be required by engineering for plugging existing weirs. Plug material/grout is based drawing notes, but notes do not detail exact material.
3. Construction drawings should include more detailed dimensions of weir elevations (including existing), dike locations, and weir location.
4. The allowance for the turbidity curtain is based on a standard 200' curtain. Additional cost may be incurred by others if specialized material is required.

Kingston Fossil Plant  
Cost Estimate by Heavy Equipment Division  
For  
Kennedy Weir Replacement

Basis of Estimate

Scope of work based on preliminary TVA design drawings (10W425-24, 70, 77, 78, 79, and 80) and conversations with Dan Smith, Parsons E & C. Construction quantities are based on provided drawings and quantities sheet provided by engineering.

Scope of Work

- Any permits, including environmental permits, will be provided to HED prior to construction.
- Mobilization of equipment, personnel, and materials.
- Provide and install erosion control devices as specified on drawings. HED will follow all BMP's during construction activities.
- Install and maintain silt fence at the downstream end of the new weir drains during construction activities.
- Construct bottom ash/fly ash coffer dike as shown on drawings. (10,500 cy)
- Dewater area contained within coffer dike and remove existing fly ash to reach stabilized base for construction of new weirs.
- Stabilize cell base to assure proper support for new weirs.
- Provide and install new weirs, including concrete drain pipe and skimmers, as specified on drawings. Construct concrete anti-seep collars around drain pipe as specified on drawings.
- Bed and backfill around new concrete drain pipe.
- Grade and compact earthen dike to match existing dike.
- Fill dewatered weir area with water to equalize both sides of the coffer dike.
- Remove 140' keyway to allow flow into the new weirs.
- Install a 2' turbidity curtain along the front of the keyway. An allowance has been made for the curtain, but no specifications were provided.
- Install a new slurry pipe from the existing weir area to the new weir keyway. Provide bollards and chains to support the submerged section of perforated pipe. The abandoned 4" pipeline will be used if possible or otherwise removed.
- Plug existing weir with Volclay BentogROUT. A deflated balloon will be placed in the inlet end of the weir and fed through till it reaches a point approx. 100 ft from the discharge end. The balloon will be blown up to block water flow. A metal plate, with a pipe coupling, will be welded to the discharge end the pipe. The pipe coupling will be used to push grout into the pipe, plugging the last 100' of the discharge pipe. The same process will be followed for each existing weir. Engineering approval will be required for this process.
- Demobilization of equipment and personnel. Demobilization includes placing seed and straw on all disturbed areas according to plant environmental guidelines.

- HED will perform pre-job briefings each morning and at anytime changes occur in the daily work scope. A post-job briefing will be performed at the completion of the construction project.

#### Project Work Schedule

- All work based on a forty hour week. Overtime is not included in this estimate.
- Construction activities: 4 x 10's
- Anticipated project duration: 36 workable shifts

#### Cost

Total Estimated Cost: **\$374,000**

Thank you for the opportunity to look at your project.

Submitted: 2/18/05

#### Note

1. Additional cost shall be incurred by others if excavation encounters solid rock and cannot be removed by conventional means.
2. Approval will be required by engineering for plugging existing weirs. Plug material/grout is based drawing notes, but notes do not detail exact material.
3. Construction drawings should include more detailed dimensions of weir elevations (including existing), dike locations, and weir location.
4. The allowance for the turbidity curtain is based on a standard 200' curtain. Additional cost may be incurred by others if specialized material is required.

Knoxton Fossil Plant  
KIF531 (Kennedy Weir)

717-  
Cattlett x 2661

path forward

PL revised  
by Septans

modifications to  
existing permit? (check on Friday)

1. Calculation (Bowers)
2. location map
3. cross section

CEC (Lyn Petty)

MSDS Dan Smith

+ 45 days

(option - phone call)

Milestones (forecast): leave project targets as-is

- |                         |                          |
|-------------------------|--------------------------|
| ✓ revise CRI            | 14 Jan to 20 Jan 05      |
| ✓ Complete final design | 2 Feb 05                 |
| Bowers 45 days          | -                        |
| ✓ Bill of material      | 2 Feb 05                 |
| ✓ initiate CEC          | 31 Jan 05                |
| ✓ final / CEC approved  | 10 Feb 05                |
| pipe delivery           | 16 Mar 05                |
| NA platform delivery    | 15 Apr 05                |
| begin construction      | 14 Feb 05                |
| finish construction     | 31 <del>Feb</del> Mar 05 |
| cost estimate           | 10 Feb 05                |
| ✓ cost estimate         | 10 Feb 05                |
| ✓ Eng input to cost est | 7 Feb 05                 |
| FPEP Approval           | 11 Feb 05                |
| construction            | 14 Feb 05                |
| ✓ DCA issue             | 11 Feb 05                |

(carry to check)

P	S	2008
E		2006
T		
C		
A		

Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Resp Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frcst Mhrs	Actual Mhrs
-------------	----------------------	----------------	-----------------	---------------	-------------	-----------	-----------	----	--------	-----------	------------	-------------

**KIF531 REPLACE KENNEDY WEIR**

*Preliminary Engg (Phase 1)*

A 35	GFKA153101	Replace Kennedy Weir - Parsons Oversight	25OCT04A	02MAR05		119	MSH	HLP	HLP	140.00	151.00	10.00
A 30	GFKA1531PE	Phase 1 Project Engineer Support	25OCT04A	02MAR05		120	SMH	SMH	HLP	20.00	20.00	16.00
A 30	GFKA1531PA	FPEP Phase 1 Authorization	29OCT04A				SMH	SMH	HLP	0.00	0.00	0.00
A 11	GFKA1531PC	Phase 1 Project Controls Support	05NOV04A	02MAR05		120	HMS	DJG	HLP	28.00	28.00	12.00

*Final Engineering (Phase 2)*

D 35	GFKBK531PJ	Revise CPJ	19JAN05A	20JAN05A			MSH	HLP	HLP	0.00	0.00	0.00
D 35	GFKBK531CC	Initiate and Obtain CEC Approval	31JAN05A	28FEB05		242	MSH	HLP	HLP	0.00	0.00	0.00
D 35	GFKBK531DC	Issue DCN KIF-05-1074	02FEB05A	28FEB05		296	MSH	HLP	HLP	0.00	0.00	0.00
D 35	GFKBK531BM	Complete Bills-Of-Material		02FEB05A			MSH	HLP	HLP	0.00	0.00	0.00
D 35	GFKBK531FD	Complete Final Dwg (DCA)		02FEB05A			MSH	HLP	HLP	0.00	0.00	0.00
D 35	GFKBK531CT	Obtain Construction Estimate		11FEB05A			SMH	SMH	HLP	0.00	0.00	0.00
D 35	GFKBK531DI	DCN KIF-05-1074 Issued		28FEB05		289	MSH	HLP	HLP	0.00	0.00	0.00
D 11	GFKBK531CE	Complete Cost Estimate for Kennedy Weir	01MAR05*	02MAR05		297	JLS	JLH	HLP	0.00	0.00	0.00
A T2	GFKBK531ER	ERU Assemble & Issue DCN KIF-05-1074	01MAR05	03MAR05		296	DLL	DLL	RJS	16.00	16.00	0.00
D 30	GFKB1531PA	FPEP Phase 2/3 Authorization	03MAR05	03MAR05*		119	SMH	SMH	HLP	0.00	0.00	0.00
D 11	GFKB1531PC	Phase 2/3 Project Controls Support	04MAR05*	01MAY05		239	HMS	DJG	HLP	40.00	40.00	0.00
D 30	GFKB1531PE	Phase 2/3 Project Engineer Support	04MAR05*	01MAY05		239	SMH	HLP	HLP	40.00	40.00	0.00

*Implementation (Phase 3)*

A T2	GFFCK477RU	ERU Assemble Closure Pkg - DCN KIF-005-1074	04MAR05	05MAR05		296	DLL		RJS	16.00	0.00	0.00
D 35	GFKC153101	Replace Kennedy Weir - Phase 3 Oversight	04MAR05	01MAY05		119	HLP	HLP	HLP	60.00	120.00	0.00
D 35	GFKC1531PT	Project Turnover		01MAY05	29JUL05	119	HLP	HLP	HLP	0.00	0.00	0.00
D 35	GFKCK531CD	DCN KIF-05-1074 Closed		01MAY05		239	MSH	HLP	HLP	0.00	0.00	0.00
D 35	GFKC1531VB	Verify Benefits & Close Project		31MAY05	28OCT05	209	HLP	HLP	HLP	0.00	0.00	0.00

Sheet 144 of 174

TENNESSEE VALLEY AUTHORITY

Layout 70

FHEM

Start Date: 01JAN89

Finish Date: 02AUG13

Data Date: 13FEB05

Run Date: 16FEB05 09:57

© Primavera Systems, Inc.



## Toney, Calvin L.

---

**Subject:** KIF531 (Kennedy Weir): Discuss HED Estimate and Project Cost  
**Location:** LP 2S 904

**Start:** Thu 02/24/2005 1:00 PM  
**End:** Thu 02/24/2005 1:30 PM  
**Show Time As:** Tentative

**Recurrence:** (none)

**Meeting Status:** Not yet responded

**Required Attendees:** Haber, Stanley M.; Baugh, James S.; Davis, Michael D; Lankford, Brian S.; Petty, Harold L.; Toney, Calvin L.; Waldrep, Roger T.; Purkey, Ronald E.; Hedgecoth, Melissa A.; Ward, Jeffrey L.

This meeting is to briefly discuss the HED cost estimate for implementation and to discuss options for proceeding with the project.

---

Stanley Haber has invited you to a MeetingPlace e-Conference (Mtg ID **3838**) on **FEB, 24 2005** at **1:00 PM** **America/New\_York**. If provided, use the following password:

To attend from your PC:

- 1) Launch the "Click to Attend" web link below, or browse to <http://latitude.cha.tva.gov> & enter Mtg ID **3838**. A MeetingPlace web page appears.
- 2) Click Join Voice & enter your phone number
- 3) Click Join Web Conference

Alternatively, call **423-751-2428**. Enter Mtg ID **3838** when prompted.

For more information about this MeetingPlace e-Conference, contact: Stanley Haber,

Click to Attend:  
<http://latitude/attend/FeEkfPmBpDgKjoCbfcNjJIbNmEhkDbKelfioaJnCfKaoKnPldeDkOIEgEk>

# KENNEDY WEIR ASH DIKE FILL

EXCAVATE BY TRACKHOE, LOAD TRUCKS, HAUL, DUMP, SPREAD & COMPACT  
1 MILE ROUNDTRIP (5,280 FT)

1 EA 3-1/2 cy TRACKHOE (CLASS Z26P) ASSUMED OUTPUT = 130 cy/HR  
 No. OF TRUCKS 14 cy (CLASS Z31M)  
 SPOTTING (INCL. WAITING TIME) = 2.00 MIN  
 LOADING  $130 \text{ cy/HR} \div 60 \text{ MIN/HR} = 2.167 \text{ cy/MIN}$   
 TIME TO LOAD 14 cy TRUCK  $\div 2.167 \text{ cy/MIN} = 6.46 \text{ MIN}$   
 UNLOAD, TURN AND DUMP = 2.00 MIN  
 TRAVEL: HAUL 2,640 FT @ 10 MPH = 3.00 MIN  
 RETURN 2,640 FT @ 15 MPH = 2.00 MIN  
15.46 MIN

$$\frac{50 \text{ MIN. HR}}{15.46 \text{ MIN}} = 3.23 \text{ TRIPS/HR} \times 14 \text{ cy/TRIP} = 45.28 \text{ cy/HR/TRUCK}$$

$$\frac{130 \text{ cy/HR}}{45.28 \text{ cy/HR/TRUCK}} = 2.87 \text{ TRUCKS} \text{ use } 3 \text{ TRUCKS REQUIRED}$$

LABOR CREW

EQUIPMENT

0012	1 OEF4	1 (Z20N) D8 DOZER	
024 024 TH 3A	4 OEA4	1 (Z21L) GRADER	
LACA ment	1 OED4	1 (Z25L) COMPACTOR	
	3 TH3A	1 (Z26P) TRACKHOE	✓ 4 pcs
	4 L2C4	3 (Z31M) DUMP TRUCKS	✓
	<u>13 MEN</u>	<u>7 pcs EQPT</u>	

DAILY OUTPUT  $130 \text{ cy} \times 7 \text{ HRS/DAY} = 910 \text{ cy/DAY}$   
 LABOR =  $\frac{104 \text{ MIN/DAY}}{910 \text{ cy/DAY}} = 0.11429 \text{ MH/cy}$ ; EQPT =  $\frac{56 \text{ HR/DAY}}{910 \text{ cy/DAY}} = 0.06154 \text{ @}$

GROUT SEAL STORM DRAIN 24"  $\phi$  <sup>35</sup> ~ cy

- 4 Lac4
- 1 Laf4
- 1 oed4
- 1 oed4

- 1 Z26L
- 1 Z29A

7 men

1 MH/cy x 35 = 35 MH  
 .28571 EH/cy = 10 EHS  
 MAT'L ASSUME \$60/cy = 2.10

- 2 Iwj4
- oed4

---

- Z26L
- Z85h

SEAL WELD 1/4" THICK A-36 STEEL <sup>11/10</sup>  
 EA \$50/EA x 6EA = \$300.00  
 MH 4 MH/EA x 6EA = 24 MHS  
 EH 2.67 EH/EA x 6EA = 16 EHS

COMBINE (GROUT 100' OF EACH OF (3) 24"  $\phi$  CMP DRAIN PIPE) - 35 cy

Reference 050930

MAT'L use \$2,400 TOTAL  
 LABOR use 1.70 MH/cy  
 EQPT use 0.75 EH/cy v. 567

- |        |        |
|--------|--------|
| Crew   |        |
| 1 Laf4 | 1 Z26L |
| 2 Iwj4 | 1 Z29A |
| 4 Lac4 | Z85h   |
| 1 oed4 |        |
| 1 oed4 |        |
| <hr/>  | <hr/>  |
|        | 3 PCS  |

**Toney, Calvin L.**

---

**From:** Smith, Daniel R [Daniel.R.Smith@worleyparsons.com]  
**Sent:** Friday, February 11, 2005 11:50 AM  
**To:** Knox, Robert; Toney, Calvin L.  
**Cc:** Petty, Harold L.; Hughes, Michael; Melton, Gary  
**Subject:** FW: KIF - Kennedy Weir

See below. Maybe (if its not too late), we should add this to the quantity takeoffs. The height of the turbidity curtain is about 6 ft (from 754 to 760), and about 160 ft long, for a total of about 1000 sq ft. The turbidity curtains usually are some type of fabric, with a weight at the bottom (usually a chain), and floats a the top. It is secured by a cable at the top, tied to the sides of the ash dike. It will be hung on the upstream side of the opening cut into the dike.

If we have time, lets add this to the cost estimate. If Lynn want it added to the drawing, we can do that later.

Dan

-----Original Message-----

**From:** Johnson, Lindy P. [mailto:lpjohnson@tva.gov]  
**Sent:** Friday, February 11, 2005 11:23 AM  
**To:** Smith, Daniel R; Campbell, Linda F.; Catlett, James H; Petty, Harold L.; Beasley, Don R.  
**Cc:** Haber, Stanley M.; Bowers, Larry C; Johnson, Lindy P.  
**Subject:** RE: KIF - Kennedy Weir

Lynn & Dan:

Don B asked about getting a turbidity curtain permanently installed outside of the proposed new limestone sparger line to be located between the dikes. This would help us from introducing cenospheres into the stilling pond.

Thanks.

Spreadsheet Report  
KIF/05229WEIRS

KINGSTON FOSSIL PLANT  
KENNEDY WEIR  
TOTAL PROJECT ESTIMATE

Project name KIF/05229WEIRS

Engineer Stan Haber

Estimator C. I. TONEY

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Sitework

KIF

05229

KIF531

S. M. Haber

0

0

2

Preliminary

+/- 20%

02/14/2005

Capital

N

Report format Sorted by Location/Activity

Detail summary

Per Stan Haber

R3 \$ 10pland

P3 15 Johnson 50' by 100'

P3 60 project

P3 PC COST 24

P3 PC SCH 24

Eng Record 6

CAD Drawg 6 DWGS



Spreadsheet Report  
KIF/05229/WEIRS

imate Company

Estimate Totals

Labor	208,010	6,888,708	hrs			
Material	101,123					
Subcontract	51,000					
Equipment	62,381	2,877,784	hrs			
	376,514	376,514				
Engineered Materials - Ph. 2			100,000 %	C		
Adjustment - Engr Materials			(100,000) %	C		
Environmental Costs			100,000 %	C		
Adjustment Environmental			(100,000) %	C		
Demolition Costs			100,000 %	C		
Adjustment Demolition			(100,000) %	C		
Small Tools Expense	2,769		0.450 \$/hr	H		
Consumables & Expendables	6,844		4,000 %	C		
Office Supplies & Expense	1,107		3,000 %	C		
Subcontract Fee	10,719	387,233				
Partner Insurance (FY'04)	6,240		3,000 %	C		
Partner Award Fee (FY'04)	10,401	403,874	5,000 %	C		
FFG Proj Engr - Phase 1	1		0.000 % @ 42.00 A	A		0
FFG Mech Engr - Phase 1	1		0.000 % @ 42.00 A	A		0
FFG Elec Engr - Phase 1	1		0.000 % @ 42.00 A	A		0
FFG Civil Engr - Phase 1	1		0.000 % @ 42.00 A	A		0
FFG Syst Engr - Phase 1	1		0.000 % @ 42.00 A	A		0
Non-TVA Engr - Phase 1	1		0.000 % @ 72.00 A	A		0
FFG Proj Critl Cost - Phase 1	1		0.000 % @ 42.00 A	A		0
FFG Proj Critl Sched - Phase 1	1		0.000 % @ 42.00 A	A		0
FFG Cost Estimating - Phase 1	1		0.000 % @ 42.00 A	A		0
Phase 1 Other/Other Org	9	403,883	0.000 % @ 42.00 A	L		0
FFG Proj Engr - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Mech Engr - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Elec Engr - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Civil Engr - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Syst Engr - Phase 2	1		0.000 % @ 42.00 A	A		0
Non-TVA Engr - Phase 2	1		0.000 % @ 72.00 A	A		0
FFG Proj Critl Cost - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Proj Critl Sched - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Cost Estimating - Phase 2	1		0.000 % @ 42.00 A	A		0
FFG Engr Records - Phase 2	1		0.000 % @ 42.00 A	A		0
Phase 2 Other/Other Org	10	403,883	0.000 % @ 42.00 A	L		0
FFG Proj Engr - Phase 3	1		0.000 % @ 42.00 A	A		0
FFG Mech Engr - Phase 3	1		0.000 % @ 42.00 A	A		0
FFG Elec Engr - Phase 3	1		0.000 % @ 42.00 A	A		0
FFG Civil Engr - Phase 3	1		0.000 % @ 42.00 A	A		0
FFG Syst Engr - Phase 3	1		0.000 % @ 42.00 A	A		0
Non-TVA Engr - Phase 3	1		0.000 % @ 72.00 A	A		0
FFG Proj Critl Cost - Phase 3	1		0.000 % @ 42.00 A	A		0
FFG Proj Critl Sched - Phase 3	1		0.000 % @ 42.00 A	A		0
FFG Engr Records - Phase 3	1		0.000 % @ 42.00 A	A		0
CAD Dwg Support - Phase 3	1		0.000 % @ ### A	A		0
Phase 3 Other/Other Org	10	403,893	0.000 % @ 42.00 A	L		0
Rounding		403,903				
<b>Total</b>		<b>403,903</b>				

**Toney, Calvin L.**








**From:** Smith, Daniel R [Daniel.R.Smith@worleyparsons.com]  
**Sent:** Tuesday, February 08, 2005 7:29 AM  
**To:** Hughes, Michael  
**Cc:** Petty, Harold L.; Toney, Calvin L.; Bowers, Larry C  
**Subject:** Draft permit drawings, QTO, and DCN for Kennedy Weir





Attached please find the draft permit drawings, quantity takeoffs, and DCN for Kennedy Weir replacement. The permit drawings are rather detailed, because they serve a dual purpose due to the brevity of the schedule. Once I receive any comments, the comments will be incorporated into the permit drawings and then placed on a DCA titleblock.

I think a review with the plant is critical due to the short schedule. We presented a number of options and emailed sketches to the team. I received feedback from Lindy, and we worked out what is on these drawings.

The DCN is prepared in pdf format. I am including some additional attachments in Word format, in case they are needed. The engineering form B did not have any yes boxes checked, so I did not include the form B's for the plant, but these are included if determined later to be needed.

Please contact me if you have any questions or comments. I am scheduled to be at ALF on Thursday.

						
10W425-24.pdf (713 KB)	10W425-70.pdf (290 KB)	10W425-77.pdf (686 KB)	10W425-78.pdf (202 KB)	10W425-79.pdf (268 KB)	10W425-80.pdf (166 KB)	DCN 5-1047_dft_020805

			
KIF-05-1074_FORM	KIF-05-1074_FORM	KIF-05-1074_FORM	011805Kennedy
B Fos Ops.doc...	B Fos Plt Mai...	B Plt Sys Eng...	Weir.xls (25 KB...

Please note new email address: Daniel.R.Smith@worleyparsons.com

Daniel R. (Dan) Smith, P.E.

Parsons E & C

633 Chestnut St, Suite 400

Chattanooga, TN 37450

Phone: (423) 757-8088

Fax: (423) 266-0922

Cell: (423) 364-1679

Email: Daniel.R.Smith@parsonsec.com



KIF - Kennedy Weir - PHASE 1 QUANTITIES 3808

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Assumptions/Comments
1.000	Erosion Controls				
1.001	Erect silt fence	lf	300	571	c - For the installation of TVA weirs and drain pipe
2.000	Kennedy Weir Replacement				
2.001	Grout seal existing drains from Kennedy Weir	cy	35		c - Grout 100' of each of (3) 24" dia CMP drain pipes
2.002	Ash fill (dike)	cy	10500	125	c - Assuming 40% increase to ash due underwater placement & consolidation
2.003	Dewatering	ea	2		c - (2) 4" slurry pumps during construction
2.004	Cut for 36" RCP and Weirs	cy	1237		c - #
2.005	Bedding for 36" RCP Storm Drain Pipe	26in	165		c - #1032 crushed stone
2.006	Fill for 36" RCP Storm Drain Pipe	122 1/2" STONE 12" CY	415		c
2.007	Standard TVA Weir Structures	254 1/2" dia 36" ea	5		c
2.008	36" RCP Storm Drain Pipe	254 1/2" dia 36" ea	700		c - Between Dredge Cell and Stilling Pond
2.009	Concrete Anti Seep Collar with water stop	ea	5		c - Install on the 36" dia storm drain pipes (.5 cubic yards of fc = 3000 psi concrete for each collar) (50' of Akqu stop manufactured by CETCO)
2.010	Balloons for 36" dia pipe installation	ea	5		Air compressor for blowing balloons TO INFLATE balloons
2.011	Pipe Bollards	ea	2		c - For temporary plug of 36" dia pipe c - Typical Bollard with 6" STD WT pipe filled with concrete embedded in 4' x 1.5' concrete section. Total length of 6" dia pipe for each bollard is 7'. Total amount of concrete in each bollard is .3 cubic yards
2.012	5/8" Eye Bolts	ea	2		c - With washers and nuts for anchoring chain to the pipe bollard
2.013	Steel Pipe Supports (Galvanized)	ea	58		c - L - 3"x 3"x 1/4" (Assumed Average Length 5') ASTM A36 Steel section 5/16" x 58" ea - 290 LFB
2.014	1/2" U-Bolts	ea	58		c - With washers and nuts attach to pipe supports
2.015	4" dia Steel Pipe (Galvanized)	lf	595		c - Butt weld to existing (or weld flanges and bolt) Assuming tying into existing lime injection pipe
2.016	Pipe insulation (length of pipe)	lf	680		c - Insulation for 4" steel and solid wall HDPE pipe
2.017	4" dia HDPE IPS DR 11	lf	85		c - Solid wall pipe

(256) 762-6401 Kenny Lowery

Kennedy Weir

		If	80		C - With .5" holes on 1.25' centers with end cap butt fusion welded
2.018	4" dia HDPE IPS DR 11 Sparger Pipe	If	145		
2.019	Galvanized Grade 80 Alloy Steel Chain	ea	14		C - \$7.65 per lf (3/8" minimum size, McMaster Carr)
2.020	Galvanized Alloy Steel Pipe Clamps	CY	2333	125	C - Located on 6' centers on the Sparger HDPE
2.021	Ash Cut (dike)	ls	5000		C - North bottom ash dike to allow water to new weirs
2.022	QA/QC for construction of disposal facility				C - Quality control of ash dike construction
2.023					

Assumptions  
 (1) All ash quantities are in bank cubic yards (bcy) - no shrink or swell factors applied  
 (2) Phase 3 Engineering \$10,000 (Inc. TVA over sight and subcontracts)  
 (3) Bottom Ash dike construction will be dipped and hauled from Dredge Cell (equipment - trackhoe, trucks, bulldozer, and compactor).

~~ADD FOR BREACHINGS DIKE~~  
 ADD TURBIDITY CURTAIN 6' x 20' wood with 1' pad on outside  
 Remove 2 sections of wheel necessary  
 (See Detail G 80 Flow Detail (shed & HMC))

\$ 8,500 / 21.68 = 395.5559  
 \$ 1,500 / 21.68 = 70.5640

\$ 162,610  
 57,841  
 5,845 HMC's  
 21,681 / 54  
 3670 E.H.S

6,151 HMC'S

**Toney, Calvin L.**

**From:** Haber, Stanley M.  
**Sent:** Monday, February 14, 2005 3:07 PM  
**To:** Toney, Calvin L.  
**Cc:** Petty, Harold L.; Catlett, James H; Smith, Daniel R.; Lowery, Kenny R.; Knox, Robert; Radford, Larry D.  
**Subject:** KIF531: Kennedy Weir (Insulation Testing - Limestone Slurry Piping)

Calvin,

For your information and use in the cost estimate.

Stan

-----Original Message-----

**From:** Campbell, Linda F.  
**Sent:** Monday, February 14, 2005 2:13 PM  
**To:** Haber, Stanley M.  
**Subject:** Kennedy Weir

Stan,

One of our asbestos workers has tested the insulation of the lime pipe in the past. It is not asbestos, it is fiberglass.  
Please pass this along to anyone who needs it.

Thanks,  
Linda

KIF531 (KENNEDY WEIR)  
Meeting 1-20-05  
2/12/05 [signature]

COMPUTED

DATE

CHECKED

DATE

Phil Carlett }  
Linda Campbell } PLANT  
Missy Hedgecott }

Only weir in system - non <sup>standard</sup> TVA design.  
(Free Water Volume clause)

- Risk of failure due to life of corrugated pipe.


- ACTION ITEM -

Construction will be done by the end of March

RT revised ASAP.

WILL COTTERDAYS WILL BE  
REQUIRED?  
DURING THIS INSTALLATION?  
Bolt out of ash

COST ESTIMATE Due Feb 10, 2005



- NOTES:
1. FOR DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-20.
  2. DRAWINGS 10W425-24 AND -25 DEPICT PHASED CONSTRUCTION OF INITIAL CONSTRUCTION DRAWINGS BEGIN WITH 10W425-26.
  3. FOR INTERIM POND DEVELOPMENT, SEE NOTE 3 ON 10W425-28.

**PRELIMINARY**  
DATE: 5/7/76

REVISED	DATE	BY	REASON

SCALE: 1"=200'

YARD

**PHASE 1 DREDGE CELL  
LATERAL EXPANSION  
DEVELOPMENT PLAN SHEET 1**

DESIGNED BY	DATE	BY	REVISION NO.
CHECKED BY	DATE	BY	REVISION NO.
APPROVED BY	DATE	BY	REVISION NO.

PROJECT: KINGSTON FOSSIL PLANT  
TENNESSEE VALLEY AUTHORITY  
FOSSIL AND HYDRO ENGINEERING

AUTOCAD FILE	SHEET NO.	TOTAL SHEETS	DATE
	36	C	10W425-24

PLOT FACTOR: 1200  
PLOT DATE: 5/7/76  
C.A.D. DRAWING  
DO NOT ALTER MANUALLY

36 | C | 10W425-24

PARSONS	REV. NO.
	0

DATE COMPLETED BY:




10W425-70 36 2 3 4 5 6 7 8 9 10 11 12

**BILL OF MATERIAL**

ITEM	DESCRIPTION	NO. OF	PER	TOTAL
		SPRINGS	SPRINGS	SPRINGS
43	1/2" DIA. 304 STAINLESS STEEL	3	173.00	519.00
44	1/2" DIA. 304 STAINLESS STEEL	1	173.00	173.00
45	1/2" DIA. 304 STAINLESS STEEL	5	375.00	1875.00
46	1/2" DIA. 304 STAINLESS STEEL	23	532.00	12236.00
47	1/2" DIA. 304 STAINLESS STEEL	8	95.00	760.00

**WEIR DISCHARGE \* IN CUBIC FEET PER SECOND**

WEIR FEET	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0
0.0	0.0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0
0.1	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1.0	1.1
0.2	0.2	0.4	0.6	0.8	1.0	1.2	1.4	1.6	1.8	2.0	2.2
0.3	0.3	0.6	1.0	1.4	1.8	2.2	2.6	3.0	3.4	3.8	4.2
0.4	0.4	0.8	1.3	1.8	2.3	2.8	3.3	3.8	4.3	4.8	5.3
0.5	0.5	1.0	1.6	2.1	2.6	3.1	3.6	4.1	4.6	5.1	5.6
0.6	0.6	1.2	1.9	2.5	3.1	3.7	4.3	4.9	5.5	6.1	6.7
0.7	0.7	1.4	2.2	2.9	3.5	4.1	4.7	5.3	5.9	6.5	7.1
0.8	0.8	1.6	2.4	3.2	3.9	4.6	5.3	6.0	6.7	7.4	8.1
0.9	0.9	1.7	2.6	3.4	4.1	4.9	5.6	6.3	7.0	7.7	8.4
1.0	1.0	1.8	2.8	3.6	4.4	5.2	6.0	6.8	7.6	8.4	9.2






**BENT BAR LIST**

BAR MARK	NO.	SIZE	SHAPE	QTY	REMARKS
48-3	10	1/2"	4	EX	
48-4	1	1/2"	5-0	EX	
48-5	1	1/2"	5-0	EX	
48-6	1	1/2"	5-0	EX	

**BENT BAR LIST**

BAR MARK	NO.	SIZE	SHAPE	QTY	REMARKS
48-3	10	1/2"	4	EX	
48-4	1	1/2"	5-0	EX	
48-5	1	1/2"	5-0	EX	
48-6	1	1/2"	5-0	EX	






**BILL OF MATERIAL**

ITEM	DESCRIPTION	NO. OF	PER	TOTAL
		SPRINGS	SPRINGS	SPRINGS
402	CLASS X CONCRETE	9	170.00	1530.00
416	REINFORCING STEEL	170	120.00	20400.00
417	1/2" DIA. 304 STAINLESS STEEL	1	173.00	173.00
418	1/2" DIA. 304 STAINLESS STEEL	1	173.00	173.00
419	1/2" DIA. 304 STAINLESS STEEL	1	173.00	173.00

**TYPE A SPILLWAYS**

BAR MARK	NO.	SIZE	SHAPE	QTY	REMARKS
48-3	10	1/2"	4	EX	
48-4	1	1/2"	5-0	EX	
48-5	1	1/2"	5-0	EX	
48-6	1	1/2"	5-0	EX	






**NOTES:**





- A SECTION OF 120" DIA. CORRUGATED METAL PIPE FULLY COATED, SHALL BE USED FOR THE SKIMMER DEVICE. ALL SEAMS AND JOINTS SHALL BE RIVETED. FABRICATION OF THE PIPE SHALL BE COMPLETE PRIOR TO COATING.
- ONE SECTION OF 48" PIPE SHALL BE INSTALLED DURING INITIAL CONSTRUCTION.
- AS ADDITIONAL SECTIONS OF 48" PIPE ARE ADDED, GROUT THE JOINT TO FORM A STABLE AND WATER TIGHT CONNECTION.
- ALL CONNECTIONS TO BE WELDED.
- FOR SPILLWAY DETAILS SEE STD. DWG. SD-C11.1.
- CAULKING SHALL EXTEND COMPLETELY AROUND THE WEIR AND FORM A WATER TIGHT SEAL.
- WHEN THE WEIR IS INSTALLED THE TOP SHALL BE LEVELED WITH THE USE OF LEVELING BOLTS.
- ALL WELDS BY TIA FIELD SHALL BE MADE AND INSPECTED IN ACCORDANCE WITH TIA CONSTRUCTION SPECIFICATION C28.
- ALL WELDS BY TIA TO HAVE VISUAL INSPECTION.
- ALL SURFACES OF FABRICATED STEEL ITEMS SHALL BE PAINTED IN ACCORDANCE WITH CONSTRUCTION SPECIFICATION G14, PART XIX.
- DEWATER AREA WHERE WEIRS ARE TO BE INSTALLED BY CONSTRUCTING ASH DIKES OR INSTALLING SHEET PILE, AND REMOVING WATER FROM THE INSTALLATION AREA. DESIGN OF ASH DIKES AND/OR SHEET PILE BY TIA FEES.
- PROVIDE ADEQUATE FIRM BASE FOR INSTALLATION OF CONCRETE SPILLWAY BY INSTALLING ROCK BASE OR TENSAR GEOTRID. SELECTION OF TENSAR GEOTRID BY TIA FEES.

**NOTES:**

- ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE T-1 SPECIFICATIONS, UNLESS OTHERWISE NOTED.
- ALL CONCRETE SHALL BE CLASS 'X' IN ACCORDANCE WITH SECTION 400.
- ALL REINFORCEMENT SHALL CONFORM TO ASTM SPECIFICATION A615 GRADE 60, DEFORMED.
- DIMENSIONS SHOWN ARE TO THE CENTERLINE OF REINFORCING BARS, UNLESS OTHERWISE NOTED.
- CONCRETE CLEAR COVER DIMENSIONS ARE AS FOLLOWS:  
3 INCHES FOR FACES CAST AGAINST EARTH OR ROCK;  
2 INCHES FOR ALL OTHER FACES.



**PRELIMINARY**  
DATE: 02/7/05



PARSONS  
TASK COMPLETED BY: [ ]  
REV. NO. [ ]

10W425-70  
R 0

ASH DISPOSAL AREA LATERAL EXPANSION  
WEIR & SKIMMER DETAILS

DATE: 02/7/05

SCALE: 1/2" = 1'-0"

EXCEPT AS NOTED

YARD

DESIGNED BY: [ ]  
CHECKED BY: [ ]  
APPROVED BY: [ ]


KINGSTON FOSSIL PLANT  
TENNESSEE VALLEY AUTHORITY  
FOSSIL AND HERO ENGINEERING

10W425-70  
R 0


PLANT FACTORY  
M, V, W

CAD. DRAWING  
DO NOT ALTER MANUALLY

FRAMEWORK-BASE 26LF x 15FT = 39.05SF  
FRAMEWORK-OUTSIDE WALL 24LF x 4.5FT = 108.05SF  
FRAMEWORK-INSIDE WALL 16LF x 4.5FT = 72.05SF  
219.05SF/BOX




- WEIR REPLACEMENT GENERAL NOTES:
1. FOR DRAWING INDEX & LEGEND SEE 10W425-20
  2. FOR GENERAL NOTES SEE 10W425-26.
  3. AFTER INSTALLATION OF NEW WEIRS, DISCONNECT STORM DRAIN FROM DRAINS CONNECTED TO EXISTING WEIRS. TREMIE GROUT STORM DRAINS TO EXISTING WEIRS. GROUT SHALL BE MANUFACTURED BY CESCO. MIX AND PLACE GROUT RECOMMENDED BY THE MANUFACTURER. VOLCLAY GRANULAR GROUT MAY BE MIXED WITH FLY ASH IN LIEU OF VOLCLAY GRANULAR GROUT. VERIFY FULL PENETRATION TO UNDERWATER. INSTALL TREMIE PIPE & VERIFY FULL PENETRATION TO OUTLET END OF STORM DRAIN. SEAL WELD 1/4" THICK ASB STEEL PLATE TO END OF STORM DRAIN AND GRADUALLY WITHDRAW TREMIE PIPE DURING FILLING. MAINTAIN TREMIE PIPE WITHIN GROUT TO PREVENT THE FORMATION OF AIR POCKETS OR HONEYCOMB AREAS.
  4. NEW DIKE SHOWN IN FINAL CONFIGURATION. SEE DRAWING 10W425-78 FOR DIKE CONSTRUCTION
  5. REMOVE EXISTING WALKWAY (NOT SHOWN) TO EXISTING WEIR. EXISTING WOODEN POLES SHALL BE LEFT IN PLACE AND NOT REMOVED.




**PRELIMINARY**  
DATE: 02/07/95

SCALE: 1" = 50'	YARD	EXCEPT AS NOTED
DREDGE CELL WEIR REPLACEMENT OVERALL PLAN		
DESIGNED BY: J. E. JONES	CHECKED BY: J. E. JONES	DATE: 02/07/95
KINGSTON FOSSIL PLANT TENNESSEE VALLEY AUTHORITY FOSSIL AND IRONWORKS DIVISION		
AUTOCAD: R14	REV: 35	10W425-77
PROJECT NO. 10W425-77		SCALE: 1" = 50'
PROJECT NAME: WEIR REPLACEMENT		DATE: 02/07/95
PROJECT LOCATION: KINGSTON FOSSIL PLANT		PROJECT NO.: 10W425-77
PROJECT OWNER: TENNESSEE VALLEY AUTHORITY		PROJECT NAME: WEIR REPLACEMENT
PROJECT NO.: 10W425-77		PROJECT LOCATION: KINGSTON FOSSIL PLANT
PROJECT OWNER: TENNESSEE VALLEY AUTHORITY		PROJECT NAME: WEIR REPLACEMENT
PROJECT NO.: 10W425-77		PROJECT LOCATION: KINGSTON FOSSIL PLANT
PROJECT OWNER: TENNESSEE VALLEY AUTHORITY		PROJECT NAME: WEIR REPLACEMENT

FALLEN ENDS








- NOTES:
1. FOR WEIR REPLACEMENT GENERAL NOTES, SEE 10W425-77.
  2. REMOVE EXISTING LINE SLUDGE DISCHARGE LINE WHERE IT IS ROUTED FROM THE BANK TO THE EXISTING WEIR. PIPE MAY BE REUSED AT CONSTRUCTOR'S OPTION. OR A NEW LINE MAY BE INSTALLED TO THE EXISTING WEIR. THE NEW LINE TO THE NEW WEIR, NEW PIPE SHALL BE STEEL PIPE TO MATCH DIAMETER AND WALL THICKNESS OF EXISTING DISCHARGE LINE. THE NEW WEIR SHALL BE INSTALLED TO THE EXISTING WEIR. THE NEW WEIR SHALL BE INSTALLED TO THE EXISTING WEIR. THE NEW WEIR SHALL BE INSTALLED TO THE EXISTING WEIR.
  3. WIDE DISCHARGE PIPE IS TO BE SUBMERGED. PIPING SHALL BE HOPE, SOR 11, WELD A STEEL FLANGE ADAPTOR TO THE FABRICATED AS A SPARGER. SEE DETAILS ON 10W425-80.
  4. AFTER COMPLETION OF WEIR INSTALLATION, EXCAVATE THE CENTER OF THE WEIR TO THE STILLING BASIN. ALLOW THE ASH POND TO DISCHARGE TO THE STILLING BASIN.
  5. REMOVE SECTIONS OF DISCHARGE FROM EXISTING WEIR, AND TRIMME GROUT AS DISCUSSED IN NOTE 3 ON 10W425-77.
  6. PIPE AND FITTING USED TO CONSTRUCT HOPE LINE SLUDGE DISCHARGE LINE SHALL BE CLASSIFIED AS 45444C IN ACCORDANCE WITH ASTM D 3360. ALL PIPING AND FITTINGS SHALL BE NEW AND OF THE SAME MATERIAL AND HAVE A MANUFACTURER'S INSTRUCTIONS.
  7. ALL HOPE PIPING AND FITTINGS SHALL BE JOINED BY BUTT FUSION WELDING, IN ACCORDANCE WITH THE MANUFACTURER'S INSTRUCTIONS.
  8. PROVIDE MINIMUM 0.5% SLOPE ON LINE SLURRY PIPE.
  9. INSTALL WEIR AT EL. 760 AS SHOWN. WEIR WILL BE LOWERED TO EL. 759 PRIOR TO GYPSUM/ASH DISPOSAL FACILITY CONSTRUCTION OR OTHER METHODS AS REQUIRED TO PREVENT CAVE-IN. SEE SUBPART P - EXCAVATION, IN ACCORDANCE WITH CSR 25 CFR 1926.
  10. PROTECT EXCAVATIONS BY SHORING, BRACING, SHEET PILING, OR OTHER METHODS AS REQUIRED TO PREVENT CAVE-IN. SEE SUBPART P - EXCAVATION, IN ACCORDANCE WITH CSR 25 CFR 1926.
  11. PRIOR TO REMOVING INSULATION FROM EXISTING LINE SLURRY DISCHARGE PIPE, DETERMINE WHETHER INSULATION CONTAINS ASBESTOS. CONTACT XLP ENVIRONMENTAL PROGRAM ADMINISTRATOR FOR TESTING PROCEDURES AND RECORDS. IF IT CONTAINS ASBESTOS, DISPOSE OF ASBESTOS-CONTAINING MATERIALS IN ACCORDANCE WITH STATE OF TENNESSEE SOLID WASTE REQUIREMENTS.
  12. SPACE SUPPORTS FOR 4" # LINE SLURRY PIPING ON 10' CENTER TO CENTER.

**PRELIMINARY**  
DATE: 02/7/06

DESIGNED BY	DATE	SCALE	EXCEPT AS NOTED
D.R. SMITH	02/07/06	1"=20'	
CHECKED BY	DATE	SCALE	EXCEPT AS NOTED
J. BLANDHORN	02/07/06	1"=20'	
APPROVED BY	DATE	SCALE	EXCEPT AS NOTED
G. WELDON	02/07/06	1"=20'	
APPROVED BY	DATE	SCALE	EXCEPT AS NOTED
K. E. FURCE	02/07/06	1"=20'	
APPROVED BY	DATE	SCALE	EXCEPT AS NOTED
D.L. LUBERT	02/07/06	1"=20'	
<b>DREDGE CELL WEIR REPLACEMENT FINAL DIKE &amp; WEIR LAYOUT</b>			
KINGSTON FOSSIL PLANT TENNESSEE VALLEY AUTHORITY FOSSEL AND HYDRO ENGINEERING			
AUTOCAD R14	REV	36	C
10W425-79			R G
PLOT FACTOR: 800			
W.L.T.V.			
C.A.D. DRAWING			
DO NOT ALTER MANUALLY			



- NOTES:
1. FOR ADDITIONAL NOTES SEE 10W425-78.
  2. CHAIN SHALL BE MESH STRENGTH GRADE #8 CHAIN PLATE SIZE 9/16" x 3/8" x 3500 LB WLL. AG-MASTER-CARR. PART #A457131.
  3. FOR WEIR REPLACEMENT NOTES, SEE 10W425-77.
  4. WATER STOP SHALL BE AWKASTOP GASKET WATERSTOP AS MANUFACTURED BY GAF. INSTALLATION INSTRUCTIONS WITH MANUFACTURER'S INSTALLATION INSTRUCTIONS.
  5. L SECTION SHALL BE GALVANIZED FINISH TOUCH UP PAINT SHALL BE GALVANIZED FINISH TOUCH UP PAINT DURING CONSTRUCTION WITH ZINC RICH PAINT.

- NOTES:
1. FILTER FABRIC FENCE TO BE PLACED PRIOR TO THE START OF ROUGH GRADING.
  2. STEEL POSTS SHALL BE METAL "T" POSTS - 6'-0" LONG.
  3. POSTS SHALL BE PLACED AT 4' INTERVALS MAX.
  4. WIRE FABRIC AND FILTER FABRIC SHALL BE SECURELY BOUND TO POSTS WITH EITHER STAPLES OR WIRE TIES.
  5. CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THAT IS SATISFACTORY TO TVA UNTIL FINAL ACCEPTANCE OF WORK. REMOVE SEDIMENT WHEN SEDIMENT HEIGHT IS ONE-THIRD THE HEIGHT OF THE FENCE.
  6. FILTER FABRIC SHALL BE A CLASS A FABRIC IN ACCORDANCE WITH TVA SPECIFICATION T-1, SECTION 571.

**PRELIMINARY**  
DATE: 02/27/88

SCALE: NOT TO SCALE	YARD
---------------------	------

DREDGE CELL  
WEIR REPLACEMENT  
CROSS SECTIONS AND DETAILS

DESIGNED BY: J.L. HERTZ  
CHECKED BY: J.E. HUBERT  
APPROVED BY: J.E. HUBERT

KINGSTON FOSSIL PLANT  
TENNESSEE VALLEY AUTHORITY  
FOSSIL AND HYDRO ENGINEERING

AUTOCAD R14  
REV: 36  
C 10W425-80  
PLOT FACTORY  
W.T.VA  
DO NOT ALTER MANUALLY

0	PARSONS	REV. NO.	0
1	TASK COMPLETED BY:	REV. NO.	0

**FORM B – MODIFICATION IMPACT REVIEW - FOSSIL OPERATIONS**

1.  DCN or  PIC No. KIF-05-1074 Rev. 0 Parent DCN No. NA (For PIC, else N/A) Page 1 of 1

**PART I – OPERATIONS INPUT TO DCN**

2. PLANT KIF UNIT(s) 1-9 3. CONTINUATION PAGES ATTACHED? \_\_\_\_\_
4. OPERATION ORGANIZATIONS AFFECTED: PROCEDURES  LABELING  TRAINING
5. DOES THE REVIEWER HAVE COMMENTS? YES  NO
6. SPECIAL REQUIREMENTS? YES  NO
7. IS AN OPERATIONS TURNOVER WALKDOWN REQUIRED? YES  NO
8. ARE TEMPORARY ALTERATIONS NECESSARY TO IMPLEMENT THE MODIFICATION? YES  NO
- (If YES, describe and give TAP number on continuation page.)

**PART II – IMPACT OF COMPLETED DCN**

9. LIST PROCEDURES, SOPs, INSTRUCTIONS, AND OPERATOR LETTERS REQUIRING CREATION OR REVISION AS A RESULT OF THIS DCN BEFORE RTO. (Pages can be attached as necessary.)
10. LIST PROCEDURES, SOPs, INSTRUCTIONS, AND OPERATOR LETTERS REQUIRING CREATION OR REVISION AS A RESULT OF THIS DCN BEFORE CLOSURE. (Pages can be attached as necessary.)
11. A. ARE PREFIRE PLANS, FIRE SYSTEMS, RTO, OR FIRE ASSESSMENT ITEMS AFFECTED? YES  NO   
 (If YES, list on continuation sheet.)
- B. IS TRAINING REQUIRED? (If YES, describe on continuation sheet.) YES  NO
- C. IS PLANT COMPONENT IDENTIFICATION LABELING AFFECTED? YES  NO
- D. ARE PUNCHLIST ITEMS INVOLVED? (Items to be completed after RTO but before Closure.) YES  NO
- (The impact of this DCN on Operations/Maintenance is as described above.)

12.	IMPACT REVIEW IS COMPLETE	REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**PART III – LEVEL I ACTIONS (Required to be complete for RTO.)**

13. A. TRAINING REQUIRED FOR RTO COMPLETE? YES  N/A
- B. PROCEDURES, SOPs, INSTRUCTIONS, & DRAWINGS REQUIRED FOR RTO REVISED TO INCORPORATE REDLINE FIELD CHANGES (I.E., AA PICs)? YES  N/A

14.	ACTIONS REQUIRED FOR RTO ARE COMPLETE	REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**PART IV – LEVEL II ACTIONS (Required to be complete for DCN Closure.)**

15. A. TRAINING REQUIRED FOR CLOSURE COMPLETE? YES  N/A
- B. PLANT COMPONENT IDENTIFICATION LABELING COMPLETE? YES  N/A
- C. PROCEDURES/INSTRUCTIONS/SOPs REQD FOR DCN CLOSURE CREATED/REVISED? YES  N/A
- D. TEMPORARY ALTERATIONS REMOVED OR INCORPORATED INTO CONFIG MGMT? YES  N/A
- E. PUNCHLIST ITEMS COMPLETE? YES  N/A

16.	ACTIONS REQUIRED FOR CLOSURE ARE COMPLETE	REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**FORM B - MODIFICATION IMPACT REVIEW - FOSSIL PLANT MAINTENANCE**

1.  DCN or  PIC No. KIF-05-1074 Rev. 0 Parent DCN No. NA Page 1 of       
 (For PIC, else N/A)

**PART I - MAINTENANCE INPUT TO DCN**

2. PLANT KIF UNIT(s) 1-9 3. CONTINUATION PAGES ATTACHED?       
 4. GROUPS AFFECTED: ELEC  I&C  MECH  (Sheet required for each affected)  
 5. COMMENTS?      YES  NO   
 6. SPECIAL REQUIREMENTS? YES  NO

**PART II - IMPACT OF COMPLETED DCN**

7. LIST PROCEDURES, SOPs, INSTRUCTIONS, AND OPERATOR LETTERS REQUIRING CREATION OR REVISION AS A RESULT OF THIS DCN BEFORE RTO. (Pages can be attached as necessary.)  
      
 8. LIST PROCEDURES, SOPs, INSTRUCTIONS, AND OPERATOR LETTERS REQUIRING CREATION OR REVISION AS A RESULT OF THIS DCN BEFORE CLOSURE. (Pages can be attached as necessary.)  
      
 9. A. IS TRAINING REQUIRED? (If YES, describe on continuation sheet.) YES  NO   
 B. ARE NEW PREVENTIVE MAINTENANCE (PM) TASKS REQUIRED? YES  NO   
 C. IS REVISION OF A PM TASK REQUIRED? YES  NO   
 D. ARE NEW/REVISED MSDS DATASHEETS REQUIRED? YES  NO   
 E. ARE SPARE PARTS REQUIRED? YES  NO   
 F. HAVE SPARE PARTS BEEN MADE OBSOLETE BY THIS CHANGE? YES  NO

(The impact of this DCN on Operations/Maintenance is as described above.)

10.	IMPACT REVIEW IS COMPLETE				
		REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**PART III - LEVEL I ACTIONS (Required to be complete for RTO.)**

11. A. PROCEDURES/INSTRUCTIONS REQUIRED FOR RTO REVISED? YES  N/A   
 B. TRAINING REQUIRED FOR RTO COMPLETE? YES  N/A   
 C. SPARE PARTS IN STOCK IN POWER STORES? YES  N/A

12.	ACTIONS REQUIRED FOR RTO ARE COMPLETE				
		REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**PART IV - LEVEL II ACTIONS (Required to be complete for DCN Closure.)**

13. A. PM REQUIREMENTS IDENTIFIED & INPUT SENT TO PM SCHEDULING & TRACKING? YES  N/A   
 B. PROCEDURES/INSTRUCTIONS/SOPs REQD FOR DCN CLOSURE CREATED/REVISED? YES  N/A   
 C. TRAINING REQUIRED FOR CLOSURE COMPLETE? YES  N/A   
 D. SPARE PARTS IN STOCK IN POWER STORES? YES  N/A   
 E. HAVE OBSOLETE SPARE PARTS BEEN SURPLUSSED? YES  N/A

14.	ACTIONS REQUIRED FOR CLOSURE ARE COMPLETE				
		REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**FORM B – MODIFICATION IMPACT REVIEW - PLANT SYSTEMS ENGINEER (SE)**

1.  DCN or  PIC No. KIF-05-1074 Rev. 0 Parent DCN No. NA (For PIC, else N/A) Page 1 of     

**PART I – SYSTEMS ENGINEER INPUT TO DCN**

- 2. PLANT KIF UNIT(s) 1-9
- 3. SYSTEM(S) AFFECTED: \_\_\_\_\_ (Provide review form for each SE affected.)
- 4. COMMENTS?  Y  N \_\_\_\_\_
- 5. SPECIAL REQUIREMENTS?  YES  NO \_\_\_\_\_
- 6. CHANGE WILL CREATE A DIFFERENCE BETWEEN OPERATING UNITS?  YES  NO \_\_\_\_\_

**PART II – IMPACT OF COMPLETED DCN**

- 7. LIST PROCEDURES/INSTRUCTIONS REQUIRING CREATION/REVISION BEFORE RTO. (Pages can be attached as necessary.)
  - 8. LIST PROCEDURE/INSTRUCTIONS REQUIRING CREATION/REVISION BEFORE DCN CLOSURE. (Pages can be attached as necessary.)
  - 9. IS TRAINING REQUIRED?  YES  NO
  - 10. IS ANY TESTING REQUIRED? (If YES, Post Modification Test.)  YES  NO
  - 11. REQUIREMENTS ATTACHED? (Not applicable to Functional Test.)  YES  NO
  - 12. DO THE CHANGES CONTRIBUTE TO FLOW ACCELERATED CORROSION (FAC)? (FPG Only)  YES  NO
- (The impact of this DCN on areas for which SE is responsible is as described above.)

13.	IMPACT REVIEW IS COMPLETE	SE (PRINT NAME)	SIGNATURE	PHONE	DATE
-----	---------------------------	-----------------	-----------	-------	------

**PART III – LEVEL I ACTIONS (Required to be complete for RTO.)**

- 14. A. PROCEDURES/INSTRUCTIONS REQUIRED FOR RTO HAVE BEEN CREATED/REVISED. YES  N/A
- B. RTO TRAINING COMPLETE.
- C. ANY REQUIRED TESTING HAS BEEN COMPLETED OR PUNCHLISTED.
- D. HAS THE FAC COORDINATOR REVIEWED AND ACCEPTED CHANGES?

15.	ACTIONS REQUIRED FOR RTO ARE COMPLETE	SE (PRINT NAME)	SIGNATURE	PHONE	DATE
-----	---------------------------------------	-----------------	-----------	-------	------

**PART IV – LEVEL II ACTIONS (Required to be complete for DCN Closure.)**

- 16. A. PROCEDURES/INSTRUCTION REQUIRED FOR CLOSURE HAVE BEEN CREATED/REVISED. YES  N/A
- B. TRAINING ACTIONS REQUIRED FOR CLOSURE ARE COMPLETE.
- C. POST MODIFICATION OR FUNCTIONAL TESTING COMPLETED.

17.	ACTIONS REQUIRED FOR CLOSURE ARE COMPLETE	SE (PRINT NAME)	SIGNATURE	PHONE	DATE
-----	---	-----------------	-----------	-------	------

TVA/COO		FORM A - DESIGN CHANGE NOTICE				Page 1 of 2	
1. a. DCN Type <input checked="" type="checkbox"/> Base DCN <input type="checkbox"/> PIC for Base/ Parent DCN No.: NA		b. Class Routine Design Change <input checked="" type="checkbox"/> Documentation Only <input type="checkbox"/> Material Equivalency <input type="checkbox"/> c. Advance Authorization <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No		2. DCN No. KIF-05-1074		Rev. 0	
		3. Plant/TL/SUB/ Facility		KIF			
		4. System(s)		14			
		Unit/TL/SUB No.		1-9			
PART I - REQUESTED CHANGE							
5. Authorizing Documents		KIF531					
6. Requested Change or Problem Statement		The weirs that discharge from the active ash pond are a field design rather than a standard TVA engineered design. (See Block 6 continuation)					
7. Initiator's Name (Print)		Organization		Phone		8. Supervisor/Principal Engr	
D.R.Smith		Parsons E&C		(423)757-8088		William Lytle	
						1/27/05	
						Date	
PART II - INITIATION APPROVAL (Skip blocks 9 and 10 for Advance Authorization Approval)							
9. Reviewed INITIATOR'S DEPARTMENT MANAGER		Date		10. Approved ENGRG/OPERATIONS MANAGER		Date	
PART III - APPROVED CHANGE/DETAILED DESIGN							
11. Approved Change Description		<input type="checkbox"/> Planned at Initiation		<input type="checkbox"/> As Issued (If different than planned, line through below and update on continuation sheet.)			
Provide design drawings and details for implementing construction of the weirs.							
12. Advanced Authorization Approval (If applicable, otherwise mark N/A.)		RE or Manager		Date			
13. Does this change contain any assumptions or constraints that require confirmation before RTO?						<input type="checkbox"/> Yes <input type="checkbox"/> No	
14. Does this change address the full scope of the authorizing document?						<input type="checkbox"/> Yes <input type="checkbox"/> No	
15. RE		Phone		Date		16. Civil Lead	
						Date	
17. Electrical/I&C Lead		Date		18. Mechanical Lead		Date	
19. Operations		Date		20. Maintenance		Date	
21. System Engineer		Date		22. Implementing Organization		Date	
23. Telecommunications		Date		25. Plant / Site Manager		Date	
24. Engrg or Site Engrg Manager		Date		26. ISSUE EDMS #			
PART IV - DCN CLOSURE							
27. Facility Manager or Engrg Manager		Date		29. CLOSURE EDMS #			
28. RE Signature for DCN Closure		Date					

Mark "N/A" in any blocks not applicable.  
TVA 40872-FPG [07-2004]

TVA/COO		FORM A - DESIGN CHANGE NOTICE		Page 2 of 2
DCN REVISION LOG				
Revision Number	Effective Date	Pages Affected	Description of Revision	
0	02/11/04	ALL	Initial Issue	
DCN CONTINUATION SHEET				
6. Cont'd Requested Change or Problem Statement	The existing weir configuration and exact location is not known, which inhibits the ability to accurately determine and report pond free water volume in accordance with the plant NPDES requirements. The discharge side of the weirs are equipped with control gates that require manual manipulation and adjustment based on precipitation and dredging activities. This activity is hazardous due to the location, physical requirements for performing work, and risk to employees should equipment failure occur. Equipment failure could also cause a water surge that would likely result in dike overtopping and an REE.			
11. Cont'd Approved Change Description	See Block 11.			
RELATED DCNS REQUIRED TO COMPLETE THIS MODIFICATION				
NA				

**FORM B – MODIFICATION IMPACT REVIEW - ENGINEERING**

1.  DCN or  PIC No. KIF-05-1074 Rev. 0 Parent DCN No. NA (For PIC, else N/A) Page 1 of 1

**PART I – ENGINEERING INPUT TO DCN**

2. PLANT / TL / SUB KIF UNIT(s) 1-9 TL / SUB No. NA  
 3. DESIGN ORGANIZATIONS AFFECTED (One form for each discipline affected.)  
 ELEC  I&C  CIVIL  MECH  TRANSMISSION LINE  TELECOM  SUBSTATION   
 4. DESIGN BASIS DOCUMENTS AFFECTED: NA

**PART II – IMPACT OF COMPLETED DCN**

5. Activities associated with "YES" answers to the following must be addressed in the DCN before issue to support RTO:

	YES	NO
A. ARE PREDECESSOR DCNs / WOs IDENTIFIED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
B. ARE NEW/REVISED PRIMARY/CRITICAL DRAWINGS REQUIRED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
C. ARE UNVERIFIED ASSUMPTIONS IDENTIFIED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
D. ARE SPECIAL REQUIREMENTS IDENTIFIED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
E. ARE POST MOD TEST RESULTS REQUIRED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
F. ARE RELAY SETTING SHEETS CREATED/REVISED AND IMPLEMENTED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
G. DO THE CHANGES CONTRIBUTE TO FLOW ACCELERATED CORROSION (FAC)? (FPG Only)	<input type="checkbox"/>	<input checked="" type="checkbox"/>

6. Activities associated with "YES" answers to the following must be addressed in the DCN before issue to support Closure:

A. ARE VENDOR MANUALS AFFECTED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
B. ARE DESIGN CRITERIA / SYSTEM DESCRIPTIONS AFFECTED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
C. ARE CALCULATIONS / ANALYSES REQUIRED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>
D. ARE OTHER DESIGN OUTPUT DOCUMENTS AFFECTED?	<input type="checkbox"/>	<input checked="" type="checkbox"/>

(The impact of this DCN on Engineering is as described above.)

7. IMPACT REVIEW IS COMPLETE	Daniel R. Smith		757-8088	1/5/04
	REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**PART III – LEVEL I ACTIONS (Required to be complete for RTO.)**

8.

	YES	N/A
A. PREDECESSOR DCNs/ WOs HAVE BEEN RETURNED TO OPERABILITY?	<input type="checkbox"/>	<input type="checkbox"/>
B. HAVE PREVIOUSLY APPROVED (DOCUMENTED ON AA DCNs OR PICs) PRIMARY/CRITICAL DRAWING REDLINES BEEN SUBMITTED TO OPERATIONS AND TAPs WRITTEN?	<input type="checkbox"/>	<input type="checkbox"/>
C. APPLICABLE UNVERIFIED ASSUMPTIONS HAVE BEEN SATISFIED?	<input type="checkbox"/>	<input type="checkbox"/>
D. SPECIAL REQUIREMENTS HAVE BEEN SATISFIED?	<input type="checkbox"/>	<input type="checkbox"/>
E. POST MOD TEST RESULTS HAVE BEEN REVIEWED AND ACCEPTED?	<input type="checkbox"/>	<input type="checkbox"/>
F. RELAY SETTING SHEETS HAVE BEEN CREATED/REVISED AND IMPLEMENTED?	<input type="checkbox"/>	<input type="checkbox"/>
G. HAS THE FAC COORDINATOR REVIEWED AND ACCEPTED CHANGES?	<input type="checkbox"/>	<input type="checkbox"/>

9. ACTIONS REQUIRED FOR RTO ARE COMPLETE				
	REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE

**PART IV – LEVEL II ACTIONS (Required to be complete for DCN Closure.)**

10.

	YES	N/A
A. VENDOR MANUALS HAVE BEEN UPDATED AND SUBMITTED TO DOCUMENT CONTROL?	<input type="checkbox"/>	<input type="checkbox"/>
B. DESIGN CRITERIA / SYSTEM DESCRIPTIONS HAVE BEEN REVISED TO INCLUDE CHANGES?	<input type="checkbox"/>	<input type="checkbox"/>
C. CALCULATIONS/ANALYSES HAS BEEN ISSUED?	<input type="checkbox"/>	<input type="checkbox"/>
D. OTHER DESIGN OUTPUT DOCUMENTS UPDATED?	<input type="checkbox"/>	<input type="checkbox"/>
E. AS-BUILT DRAWINGS HAVE BEEN ISSUED AND ENTERED INTO CONTROLLED STORAGE?	<input type="checkbox"/>	<input type="checkbox"/>

11. ACTIONS REQUIRED FOR CLOSURE ARE COMPLETE				
	REVIEWER (PRINT NAME)	SIGNATURE	PHONE	DATE



**1.0 SCOPE**

- A. **SYSTEM(S): 14**
- B. **FEATURE(S): WEIRS FOR EXISTING ASH POND**
- C. **SCOPE DESCRIPTION: ABANDON THE EXISTING WEIRS AND INSTALL STANDARD TVA ENGINEERED WEIRS THAT REQUIRE NO MANUAL OPERATION OR INTERVENTION.**
- D. **List existing design criteria document(s) with revision number that cover this modification.**  
N/A

**2.0 DESIGN BASIS**

Provide the following information if it applies to this modification; otherwise mark "N/A".

**NOTE:** If the required information can be found in existing design input documents, give the document number, revision number, and applicable section(s).

- A. **FUNCTIONAL REQUIREMENTS: WEIRS DISCHARGE EFFLUENT FROM THE EXISTING ASH POND TO THE STILLING BASIN.**
- B. **OSHA REQUIREMENTS: (1) OSHA 29 CFR 1926, SUBPART P - EXCAVATION  
(2) Check with KIF Environmental Program Administrator [PA(E)], Linda Campbell prior to removing insulation from existing lime discharge pipe. If insulation contains asbestos, removal shall comply with OSHA requirements. Dispose of any asbestos material in accordance with State of Tennessee solid waste requirements.**
- C. **SSC OPERATING ENVIRONMENT: NA**
- D. **ELECTRICAL REQUIREMENTS: NA**
- E. **INSTRUMENTATION REQUIREMENTS: NA**
- F. **PROTECTION AND CONTROL REQUIRMENTS: NA**
- G. **MECHANICAL REQUIREMENTS: NA**
- H. **CIVIL REQUIREMENTS: (SEE ITEM L, INSTALLATION REQUIREMENTS, AND BELOW:**
  - 1. General Notes shown on 10W425-26 are repeated on Appendix 1 of Form C, Modification Criteria.

- I. **TELECOMMUNICATIONS REQUIREMENTS: NA**
- J. **LOGIC FOR OPERATION: NA**
- K. **MAINTENANCE: Inspect at regular intervals to ensure that weirs are operating correctly.**
- L. **INSTALLATION REQUIREMENTS:**
1. Locate and install dikes in accordance with 10W425-78 & 79.
  2. Locate and install new weirs in accordance with 10W425-70 & 79.
  3. For suggested sequence of installing 36 in. dia. concrete pipe, see Attachment 2 to Form C, Modification Criteria.
  4. Remove lime slurry discharge piping from existing weir. Re-utilize piping or discard and install new in accordance with drawings 10W425-79 & 80.
  5. Install HDPE sparger as shown on 10W425-80.
  6. Remove sections of existing weir discharge piping and grout existing pipe remaining in divider dike in accordance with Note 2, 10W425-79.
  7. Remove existing walkway to existing weir.
  8. Following installation of weirs, remove section of dike to allow ash pond to discharge through new weirs.
  9. Disconnect discharge piping from existing weirs and tremie grout sections of existing 24 in. dia. CMP through divider dike with grout.
- See Attachment 1 to Form C for General Notes from drawing 10W425-26.
- M. **HAZARDOUS WASTE REQUIREMENTS: (SEE ITEM B)**  
(Including 29CFR1910.119(1) Management of Change to Highly Hazardous Materials)
- N. **NEPA ENVIRONMENTAL REVIEW COMMITMENTS: SEE CEC 8914.**
- O. **OTHER: NA**  
(e.g., location, security, FME, cleanliness, and Emergency Notification System requirements)

### 3.0 TEST AND INSPECTION REQUIREMENTS

**NOTE:** If the required information can be found in existing TVA general specifications and construction documents, give the document number, revision number, and applicable section(s).

- A. **Component Testing (Including any construction checks):**
- (1) Inspect concrete piping to ensure that joints are secure, and properly attached to weir structure.
  - (2) Determine elevation of weir to ensure it is set at the proper elevation in accordance with the drawings.

(3) Inspect lime slurry discharge piping for leaks after installation.

B. System Testing: NA

C. In-Service Inspection: NA

4.0 OPERABILITY, RELIABILITY, MAINTAINABILITY, & PERFORMANCE ANALYSIS:

NA

5.0 COMMENTS

NA

6.0 REFERENCES AND ATTACHMENTS

A. List of Required Design Input: NA

B. Other References (if required) / Attach IA Summary, sketches, etc.:

NA

7.0. SPECIAL REQUIREMENTS OR UNVERIFIED ASSUMPTIONS (UVA)

A. Engineering UVA's / Special Requirements: NA

B. Non-Engineering Special Requirements: NA

**APPENDIX 1 TO FORM C – DCN KIF-05-1074  
GENERAL NOTES – FROM 10W425-26**

1. FOR DRAWING INDEX AND LEGEND, SEE DRAWING 10W425-20.
2. EXISTING TOPOGRAPHY AND SITE FEATURES OBTAINED FROM A SURVEY PERFORMED BY TVA, DATED OCTOBER 2003. SUPPLEMENTAL SURVEYING FOR PHASE 1 EXPANSION WERE PERFORMED MARCH 2004. EXISTING MONITORING WELL LOCATIONS WERE PROVIDED BY TVA. EXISTING ELEVATION CONTOURS ARE SHOWN AT 1-FOOT INTERVALS UNLESS NOTED OTHERWISE. ELEVATION CONTOURS FOR DREDGE CELL EXPANSION ARE SHOWN AT 2-FOOT INTERVALS UNLESS NOTED OTHERWISE.
3. SURVEY COORDINATES ARE REFERENCED TO TENNESSEE STATE PLANE COORDINATE SYSTEM, NAD 27. COORDINATES FOR UTILITY STRUCTURES AND PIPING ARE TO CENTERLINE OF STRUCTURE OR PIPE UNLESS NOTED OTHERWISE.
4. HORIZONTAL AND VERTICAL CONTROL SHALL BE ESTABLISHED BY USING THE EXISTING BENCHMARK LOCATIONS LISTED ON 10W425-20, AND DEPICTED ON THESE DRAWINGS.  
FOR BENCHMARK DESCRIPTIONS, CONTACT TVA MAPPING, 1101 MARKET ST, CHATTANOOGA, TN 37402.
5. THE ASH POND HAS AN EXISTING STILLING BASIN TO PROVIDE SEDIMENTATION CONTROL DURING CONSTRUCTION AND OPERATION. EROSION CONTROL MEASURES (TEMPORARY SILT FENCING, CHECK DAMS) ARE NOT DEPICTED ON THE DRAWINGS BUT MAY BE UTILIZED BY THE CONSTRUCTOR AND OPERATOR TO CONTROL SEDIMENT DISCHARGE TO THE STILLING BASIN.
6. THE CONSTRUCTOR AND OPERATOR SHALL PROVIDE A MEANS TO CONTROL DUST DURING CONSTRUCTION AND OPERATION. CONTROLS MAY INCLUDE THE USE OF WATER TRUCKS, OR COMMERCIALY AVAILABLE APPLIED SPRAY-ON MEMBRANE EROSION CONTROL PRODUCTS.
7. SECTION NUMBERS REFER DIRECTLY TO TVA SPECIFICATION T-1, UNLESS NOTED OTHERWISE.
8. ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH TVA SPECIFICATION T-1, AND THE FOLLOWING ASH POND EXPANSION DOCUMENTS: OPERATIONS MANUAL; THE CLOSURE/POST CLOSURE PLAN; AND THE QA/QC PLAN.
9. WHERE ENCOUNTERED, VERIFY AMPLE CLEARANCE UNDER OVERHEAD ELECTRICAL LINES FOR CONSTRUCTION EQUIPMENT. CONSTRUCTOR SHALL NOTIFY CONSTRUCTION MANAGER BEFORE ANY WORK STARTS NEAR OVERHEAD ELECTRICAL LINES.
10. THE CONSTRUCTOR IS HEREBY ADVISED THAT THERE MAY UNDERGROUND UTILITIES PRESENT AT THIS SITE WHICH ARE NOT SHOWN ON THESE DRAWINGS. THE CONSTRUCTOR SHALL LOCATE AND VERIFY EXISTING UNDERGROUND UTILITIES THAT MAY NOT BE SHOWN ON THIS DRAWING THAT ARE WITHIN ANY AREA TO BE DISTURBED. THE CONSTRUCTOR SHALL VERIFY THAT ANY UNDERGROUND ELECTRICAL UTILITIES ARE LOCKED OUT/TAGGED OUT AND ARE NOT ACTIVATED PRIOR TO REMOVAL.
11. CONSTRUCTOR SHALL EXERCISE CARE TO PREVENT DAMAGE TO EXISTING MONITORING WELLS AND/OR EXISTING STRUCTURES.
12. DISPOSAL OF DEMOLISHED ITEMS SUCH AS EXISTING STORM SEWER PIPING OR OTHER MISCELLANEOUS ITEMS SHALL BE AS DIRECTED BY TVA.
13. FOR CONSTRUCTION OF THE PHASE 2 BASE AND STARTER DIKE SEE ON DRAWING 10W425-65 AND THE QA/QC PLAN.
14. ELEVATION CONTOURS SHOWN ON THE OUTER SLOPES OF THE PHASE 2 AND 3 EXPANSION ARE FINISHED GRADE.
15. ELEVATIONS SHOWN INSIDE THE PHASE 2 AND 3 STARTER DIKES ARE TO TOP OF THE FLY ASH BASE AS SHOWN ON TYPICAL CROSS SECTION SHOWN ON 10W425-65.

**APPENDIX 2 TO FORM C – DCN KIF-05-1074**

Suggested Procedure for Installing 36 in. dia. concrete pipe from the new weirs to the stilling basin.

Work performed in water within stilling basin. Approximate elevation of water surface in the stilling basin is 754.3.

1. Install silt fence in accordance with drawings.
2. Excavate trench from the downstream side to the approximate crest of the divider dike, so that anti-seep collar and full-length sections of pipe can be installed.
3. Place (dump) 1032 crushed stone bedding in trench, and place pipe. Place pipe plug (balloon) in downstream end of pipe prior to placing in water. Continue filling stone to the waterline. Tamp stone and backfill with excavated material along the length of pipe, maintaining exposure of the upstream end of pipe.
4. Pump water out of excavation. Install waterstop around pipe and place concrete anti-seep collar.
5. While starting item #1, construct cut-off dike inside the ash pond.
6. When all downstream pipes are installed with balloons and anti-seep collars, and water within cutoff pipe is pumped out so that construction can be accomplished in the dry, continue installing 36 in. dia. pipes and weirs.
7. When all weirs are installed, and inspections performed, balloons can be removed, which will flood the interior portion of the dike. Excavate the dike opening, and install piping. Alternately, excavate the opening in the dike then remove the balloons.

**DOCUMENT REQUEST FORM / DCN FORM D**

- These drawings are included in DCN # KIF-05-1074 Rev 0
- These drawings are included in PDL # \_\_\_\_\_ Rev \_\_\_\_\_
- These drawings are not associated with a DCN or PDL # of Drawings: \_\_\_\_\_

PLANT: KIF UNIT(s): 1-9

Project Title/Description: ASH POND DREDGE CELL WEIR REPLACEMENT

PCN or W/O Number: KIF531 IBS Engineering Short Code Number: 001DN4B

Project Eng. (PE) or Program Manager: Stan Haber Address: LP-2 Phone: 751-3838

**Drawings Prepared By:**

TVA	_____	T	VOITH	_____	V
PARSONS	<u>P</u>	P	Other	_____	
MESA	_____	M			
ALSTOM	_____	A			

If drawings are prepared by an outside A/E, please mark code accordingly.

Engineer: D.R. Smith Address: RC-4 AC Phone: 757-8088

Section Supervisor: H.L. Petty Address: LP-2 Phone: 751-6704

Comments / Special Filing Instructions: \_\_\_\_\_

**SUPERVISOR: COMPLETE THIS SECTION FOR ISSUE OF TVA DRAWINGS**

All electronic drawing files for this issue are in folders on J:Drive (\lchachagfp8\lshshr)\Issue\KIF-1074  
This package is released for the Issue Process. The package contains all drawings listed and electronic files have been placed on the file server.

\_\_\_\_\_  
Supervisor Signature

\_\_\_\_\_  
Date

**CONTRACT ADMIN: COMPLETE THIS SECTION FOR RELEASE OF VENDOR DRAWINGS**

All electronic drawing files for this release are in J:Drive (\lchachagfp8\lshshr)\Issue\Plant - Vendor - DCN or PDL # - Rev  
Hardcopies of drawings / documents are provided for scanning where electronic files aren't available.  
See special filing instructions for listed items which are NOT to be inserted into the AutoManager system.

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date

\_\_\_\_\_  
Phone

**FOR RECORDS USE ONLY**

Tracking No. \_\_\_\_\_  
Date AutoCad Files Received: /  
Date Drawings Cleared: /  
Date Drawings Mailed : /  
CC:  
Section Supervisor, address above, Copy of Completed release Sheet and Drawing List (With all DATES)  
Project Engineer, address above, Copy of Completed Release Sheet and Drawing List (With all DATES)  
Program Manager, address above, Copy of Completed Release Sheet and Drawing list (With all DATES)



ENG. RECORDS USE ONLY: Ticket#:

## DOCUMENT REQUEST FORM / DCN FORM D

PDL#: \_\_\_\_\_ UNIT(s): 1-9  
 DCN#: KIF-05-1074 Rev. 0 PCN/WO#: KIF531  
 (Plant Year Seq)

Rev Codes (Dwgs Only)			Doc Codes			DCN REVISION	
<b>A</b> = Test Related <b>B</b> = Design/Eng. Errors <b>C</b> = Vendor Caused <b>D</b> = Planned Project Initial Issues <b>E</b> = Construction Deviation  <b>Format</b> ACAD = AutoCAD H.C. = Hard Copy CAL = Image File	<b>F</b> = Unplanned Scope Changes <b>G</b> = Configuration Different <b>H</b> = Drawing Restoration Only <b>J</b> = As Built  <b>TIF</b> = Image File <b>XLS</b> = Excel File _____ = Other	<b>BOM</b> = Bill of Materials <b>REF</b> = Reference Dwgs <b>V</b> = Vendor Dwgs <b>CN</b> = Calculations <b>SP</b> = Specifications <b>RPT</b> = Reports <b>ENV</b> = Environmental Docs <b>PRM</b> = Permits	<b>A</b> = Architectural Dwgs <b>C</b> = Civil Dwgs <b>E</b> = Electrical Dwgs <b>M</b> = Mechanical Dwgs <b>I</b> = Instrumentation Dwgs <b>P</b> = Protection & Control Dwgs <b>T</b> = Telecomm Dwgs <b>S</b> = Sketches	(Modify as needed) (Modify as needed) (Modify as needed) Put in DCN Folder Issue			
Format	Rev Code	Rev	Sht	Contract No.	Doc Code	Title	ERU Instructions





### Alternate Form D - DCN Package Document List (PDL) for DCAs and ESKs

Code *	Document/DCA/ESK	Rev	Base Drawing	Sheet	Rev	**	Cat	Contract No.	Title or Description

\* Mark a check beside documents included in the DCN package. Other documents maintained in a controlled storage system shall be referenced by a retrievable document or EMDS number.  
\*\* Check mark if anticipated drawing.

**FORM E – COMPONENT UNID DATA SHEET**

NOTE: A listing (e.g., from a database) with similar data may be used in lieu of this form.

1. DCN No.   KIF-05-1074   Rev.   0   Page   1   of   1  

2. PLANT/TL/SUB   KIF   UNIT(s)   1-9   TL/SUB No.                     

Component Data (Use additional sheets as needed)	Action (Check one)			
	New UNID	Delete UNID	Modify UNID	Rename UNID

3. EMPAC UNID (e.g., plant-unit-function-system-loc ID-seq. no.): NA	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. Renamed UNID:				
5. Component Location (e.g., For plants: plant, unit, system, building, elevation, column lines; For Transmission: plant, unit, system, loc ID, seq. no., GPS coordinates or phase location, etc.):				
6. UNID English Description:				
7. Drawing Number:				

3. EMPAC UNID (e.g., plant-unit-function-system-loc ID-seq. no.):	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
4. Renamed UNID:				
5. Component Location (e.g., For plants: plant, unit, system, building, elevation, column lines; For Transmission: plant, unit, system, loc ID, seq. no., GPS coordinates or phase location, etc.):				
6. UNID English Description:				
7. Drawing Number:				

Prepared: _____	Date: _____
Checked: _____	Date: _____

**FORM F – MODIFICATION TURNOVER PACKAGE DATA SHEET**

1. DCN No. KIF-05-1074 Rev. 0 Page 1 of 1

**PART I – SCOPE / DESCRIPTION**

2. PLANT/TL/SUB KIF UNIT(s) 1-9 TL/SUB No. NA

3. SSC INVOLVED NA SYSTEM 14 UNID NA

4. TURNOVER PACKAGE SCOPE/DESCRIPTION (If less than full scope is turned over, indicate the scope included. Include additional data sheets as necessary for other partial scopes until the full scope is turned over.)

**PART II – ACTIONS REQUIRED FOR RETURN TO OPERABILITY (RTO)**

- |   |                          |                          |
|---|--------------------------|--------------------------|
|   | YES                      | N/A                      |
| 5. A. ALL IMPACT ITEMS REQUIRED FOR RTO, AS IDENTIFIED ON IMPACT REVIEW FORMS, HAVE BEEN COMPLETED. COPIES OF IMPACT REVIEW FORMS ARE ATTACHED. | <input type="checkbox"/> | <input type="checkbox"/> |
| B. ALL LEVEL I ACTIONS, AS IDENTIFIED ON THE IMPACT REVIEW FORMS, IF APPLICABLE, HAVE BEEN COMPLETED. (REQUIRED FOR FIELD WORK DCNS ONLY)       | <input type="checkbox"/> | <input type="checkbox"/> |
| C. WORK ORDER IMPLEMENTATION VERIFIED COMPLETE. (REQUIRED FOR FIELD WORK DCNS ONLY)<br>VERIFIED BY IMPLEMENTING ORG.: _____                     | <input type="checkbox"/> | <input type="checkbox"/> |
| D. SPECIAL REQUIREMENTS IMPLEMENTED.  | <input type="checkbox"/> | <input type="checkbox"/> |
| E. POST-MOD TESTING, IF REQUIRED, WAS COMPLETED AND EVALUATED.  | <input type="checkbox"/> | <input type="checkbox"/> |
| 6. SPECIAL CONDITIONS, IF APPLICABLE:   |                          |                          |
| 7. BASED ON A REVIEW OF THE ABOVE DOCUMENTS, RTO OF THE SYSTEM AFFECTED BY THIS DCN IS RECOMMENDED. (N/A IF DOC ONLY DCN.)                      | <input type="checkbox"/> | <input type="checkbox"/> |

RE-SE	DATE	RE-SE- SUPV	DATE	OPERATIONS	DATE

**PART III – ACTIONS REQUIRED FOR DCN CLOSURE**

- |   |                          |                          |
|---|--------------------------|--------------------------|
|   | YES                      | N/A                      |
| 8. ALL IMPACT ITEMS REQUIRED FOR DCN CLOSURE HAVE BEEN COMPLETED. ALL LEVEL II ITEMS HAVE BEEN COMPLETED. | <input type="checkbox"/> | <input type="checkbox"/> |
| 9. BASED ON REVIEW OF THE ABOVE DOCUMENTS, CLOSURE OF THIS DCN IS RECOMMENDED.                            | <input type="checkbox"/> | <input type="checkbox"/> |

RE	DATE	RE SUPV	DATE

# Capital Project Justification Form

**Project Name**

YARD--KIF-REPLACE KENNEDY WEIR

**Project ID**

KIF531

**Rev#**

0

CSF: Manage the environmental and safety impacts TVA's operations have on employees and the region.

## Project Description

**Organization**

Owner: FPG  
Lead: Yard Operations

**Project**

Type: Capital  
Cat: REGULATORY  
Prgm: Environmental Compliance (FPG)

**Location**

Loc: Kingston Fossil Plant

**Estimated Actual****Technical Contact**

Name: HEDGE COTH, MELISSA A  
Phone: 423/751-6426

Start Date: 10/01/2004  
In-Srvc Date: 08/15/2004  
Outage Date:

**Responsible Mgr**

Name: DAVIS, MICHAEL D  
Phone: 423/751-7864

**Problem Description**

The weirs that discharge from the active ash pond to the stilling pond are a field design rather than a TVA standard engineered design. The weir configuration and condition are not known, which inhibits the ability to accurately determine and report pond free water volume in accordance with the plant NPDES permit requirements. The discharge side of the weirs are equipped with control gates that require manual manipulation and adjustment based on precipitation and dredging activities. This activity is hazardous due to the location, physical requirements for performing work, and risk to employees should equipment failure occur. It should be noted that equipment failure could also cause a water surge that would likely result in dike overtopping and an REE.

**Project Scope**

Plug and abandon the existing weirs, remove first sections of existing walkway, and install TVA standard engineered design weirs with access walkways that require no manual intervention or operation. The integrity of the lime injection system will be maintained.

**Performance Measurement**

Ash pond free water volume accurately determined and reported.  
No water surges that result in dike overtopping and REEs as measured for the first 120 days following implementation.  
No reportable employee safety incidents as measured by the first 120 days following project implementation.

**Other Options/Alternatives**

Continue to manually operate the system as-is, placing employees at risk should equipment fail, and risking water surges that might overtop the dike and result in REEs.

**Reason For Change**

New project

**News Release**

N/A

# Capital Project Justification Form

**Project Name**

YARD--KIF-REPLACE KENNEDY WEIR

**Project ID**

KIF531

**Rev#**

0

CSF: Manage the environmental and safety impacts TVA's operations have on employees and the region.

## Project Economic Evaluation

**COST**

SUNK CAPITAL: \$0

SUNK O&M: \$0

REMAINING COST: \$250

TOTAL COST: \$250

ESTIMATE TYPE: Order of Magnitude

**ECONOMIC INDICATORS**

NPV: -\$250.0

PI: 0

IRR: 0.0

SIMPLE PAYBACK: 20

BASE YEAR: 2005

Year	Capital Cost	O&M Cost	Total Benefit	O&M Base Increase	Environmental Cost
<b>SUNK</b>	0	0	0	0	
<b>OUT YEARS</b>	0	0	0	0	
2005	250	0	0	0	0
2006	0	0	0	0	0
2007	0	0	0	0	0
2008	0	0	0	0	0
2009	0	0	0	0	0
2010	0	0	0	0	0
2011	0	0	0	0	0
2012	0	0	0	0	0
2013	0	0	0	0	0
2014	0	0	0	0	0
2015	0	0	0	0	0
2016	0	0	0	0	0
2017	0	0	0	0	0
2018	0	0	0	0	0
2019	0	0	0	0	0
2020	0	0	0	0	0
2021	0	0	0	0	0
2022	0	0	0	0	0
2023	0	0	0	0	0
2024	0	0	0	0	0

# Capital Project Justification Form

**Project Name**

YARD--KIF-REPLACE KENNEDY WEIR

**Project ID**

KIF531

**Rev#**

0

**CSF:** Manage the environmental and safety impacts TVA's operations have on employees and the region.

## I. Project Economic Evaluation

**Cost Assumptions**

1. Abandon existing weirs in place; design, procure materials, and install TVA standard Design Weirs - \$250k

**Risks**

Based upon similar project costs.

**Benefit Assumptions**

1. Ash pond free water volume accurately determined and reported.
2. No water surges leading to dike overtopping and REEs as measured by the first 120 days following project implementation.
3. No reportable employee safety incidents associated with operation or maintenance of the system as measured by the first 120 days following project implementation.

**Risks**

Kingston Fossil Plant  
KIF531 (Kennedy Weir): Project Kick-off Meeting

December 10, 2004

---

**Agenda**

- Introductions
- Opening Comments
- Project Scope
  - a. PJ
  - b. Questions by Darlene Keller
  - c. Project EMP
  - d. Project Checklist
- Project Schedule
- Emergent Work
- Problems/Corrective Actions
- DCNs
  - a. Design Review Meetings (DRMs)
  - b. Approvals
  - c. Closures
- Future Meetings *in Feb as we get ready to go for Ph 2*
- Action Items
- Closing Comments *4/05: be ready for Ph3*



# Capital Project Justification Form

**Project Name**

YARD--KIF-REPLACE KENNEDY WEIR

**Project ID**

KIF531

**Rev#**

0

CSF: Manage the environmental and safety impacts TVA's operations have on employees and the region.

## I. Project Description

**Organization**

Owner: FPG  
Lead: Yard Operations

**Project**

Type: Capital  
Cat: REGULATORY  
Prgm: Environmental Compliance (FPG)

**Location**

Loc: Kingston Fossil Plant

**Estimated Actual**

Start Date: 10/01/2004

**Technical Contact**

Name: HEDGE COTH, MELISSA  
Phone: 423/751-6426

In-Svc Date: 08/15/2004

Outage Date:

**Responsible Mgr**

Name: DAVIS, MICHAEL D  
Phone: 423/751-7864

**Problem Description**

The weirs that discharge from the active ash pond to the stilling pond are a field design rather than a TVA standard engineered design. The weir configuration is not known, which inhibits the ability to accurately determine and report pond free water volume in accordance with the plant NPDES permit requirements. The discharge side of the weirs are equipped with control gates that require manual manipulation and adjustment based on precipitation and dredging activities. This activity is hazardous due to the location, physical requirements for performing work, and risk to employees should equipment failure occur. It should be noted that equipment failure could also cause a water surge that would likely result in dike overtopping and an REE.

**Project Scope**

Abandon the existing weirs and install ~~TVA standard~~ *planned first section of existing walkways* ~~engineered design weirs~~ *with* ~~that~~ *walkways* ~~requires no manual intervention or operation.~~ *MANUAL*

**Performance Measurement**

Ash pond free water volume accurately determined and reported.  
No water surges that result in dike overtopping and REEs as measured for the first 120 days following implementation.  
No reportable employee safety incidents as measured by the first 120 days following project implementation.

**Other Options/Alternatives**

Continue to manually operate the system as-is, placing employees at risk should equipment fail, and risking water surges that might overtop the dike and result in REEs.

**Reason For Change**

New project

**News Release**

N/A

# Capital Project Justification Form

Project Name

YARD--KIF-REPLACE KENNEDY WEIR

Project ID

KIF531

Rev#

0

CSF: Manage the environmental and safety impacts TVA's operations have on employees and the region.

## II. Project Economic Evaluation

Cost Assumptions

1. Abandon existing weirs in place; design, procure materials, and install TVA standard Design Weirs - \$250k

Risks

Based upon similar project costs.

Benefit Assumptions

1. Ash pond free water volume accurately determined and reported.
2. No water surges leading to dike overtopping and REEs as measured by the first 120 days following project implementation.
3. No reportable employee safety incidents associated with operation or maintenance of the system as measured by the first 120 days following project implementation.

Risks

I can't find where I ever sent you my comments on the EMP. After looking at this again, I have a few questions. ① When you say the existing weirs will be "sealed" and abandoned in place, how will they be sealed? With concrete? I would think that the act of sealing these weirs may result in the potential to introduce a pollutant to the water. This should either be addressed in the scope and the control measure reflected in the water section if applicable. My 2nd thought is what type of equipment will be needed to install the new weirs? ② Will there be any equipment that may require fueling near the pond? If so, this needs to be addressed in the SPCC section. I would assume that best management practices would be used to contain fuel and keep any spills from reaching the water. ③ Also, will the installation of the new weirs result in potential turbidity issues? One last comment ④ Where is the lime injection system discharging to now? Will discharging it to the new weir system require any changes to the permit? ⑤

J. Darlene Keller  
SR Regulatory Specialist,  
NEPA & Remediation  
FPG - Environmental Affairs  
423-751-6640

① may get bentonite grout in pond  
insert flex pipe into weir &  
pump in grout plus additional pipe

② normal operating equipment  
use existing BMPs

③ same turbidity from installation?  
water discharge, just engineer

④ question for Lucy Johnson  
- going from 2 to 5 weirs should  
be less turbidity

Need MSDS on grout product

follow up mtg w/

Mike Hughes

Dan Smith

Estimating

D. Keller

L. Campbell

Radford

# Project Review - Performance Impact Checklist

Page 1 of 2

Project Name: Replace Kennedy Weir  
 Location: Kingston

PCN KIF531

PERFORMANCE PARAMETERS	Improve	No Impact	Degrade	COMMENTS
<b>Reliability</b>				
Frequency of failure (MTBF)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Frequency of deratings	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Availability</b>				
Planned outage durations	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Forced outage durations	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Unit deratings (MW and duration)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Repair/replacement time (MTTR)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Frequency of corrective/preventive maintenance	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
MW output (unit capability)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Thermal</b>				
Net heat rate (Btu/kWh) – Identify in the Comments the specific Heat Rate Parameter(s) or process indicator(s) that is(are) affected	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Station service usage	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Customer Requirements</b>				
On-line time (+/- 30 minutes)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
AGC availability	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Net dependable capacity	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Voltage control	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Minimum load	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Unit ramp time	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Cost</b>				
Fuel costs (coal, limestone, chemicals)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Fuel handling costs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Operations labor costs	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<i>easier operation of new Volturno</i>
Maintenance labor costs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Waste disposal costs (solid or hazardous)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Inventory costs	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Other costs (identify in Comments)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Safety</b>				
Public safety	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Employee Safety	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Equipment Safety	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
<b>Other Performance Impacts</b>				
Water chemistry specifications	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
LIST OTHER IMPACTS BELOW				
Environmental (REEs)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Eliminate the risk of REEs from water surges and dike over-topping
Environmental (reporting)	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	Improves calculation and reporting of ash pond free water volume
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	

# Project Review - Performance Impact Checklist

Page 2 of 2

Project Name: Replace Kennedy Weir

PCN KIF531

Location: Kingston

PERFORMANCE PARAMETERS	Improve	No Impact	Degrade	COMMENTS
<b>Environmental</b>				
<b>NOTE: Initiate the project EMP and evaluate the following environmental impacts in conjunction with completing the first column of the EMP.</b>				
Air emissions	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
SO <sub>2</sub>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
NO <sub>x</sub>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Particulate	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Hg	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Quantity of fuel burned	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Ash pond toxicity	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
CEMS /COMS availability	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
NPDES (Water) discharges	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Shoreline/river impacts	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
SPCC/IPP impacts (Fuel, oil, chemical storage)	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
EMP Initiated	-----	-----	-----	YES <input checked="" type="checkbox"/> NO <input type="checkbox"/>
Permitting/Notifications Identified	-----	-----	-----	YES <input type="checkbox"/> NO <input checked="" type="checkbox"/>

PROCEDURE CHANGES	Revisions	No Change	IDENTIFY PROCEDURES
Operations	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Maintenance	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Environmental	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Safety	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

PEOPLE PARAMETERS	Needed	No Impact	COMMENTS
<b>People</b>			
Operations Training	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Maintenance Training	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Environmental Training	<input type="checkbox"/>	<input checked="" type="checkbox"/>	
Manpower availability	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Project Engineer: Stanley M. Haber

Date: 6/23/03

*New weir skimmer  
dwg 10W425-31*

Project Environmental Management Plan Outline

Prepared by: S.M. Haber/R. D. Powell Date: 4/24/04

1. Detail Description of Project:

KIF531 - Replace Kennedy Weir: Scope includes replacement of existing weirs (total of 2; skimmer structure to be removed where applicable, and the weirs sealed and abandoned in place). The water level in the pond will need to be drawn down such that the top of the weir is exposed.

It also includes the design and installation of a new weir system. The new system will use a standard TVA weir/skimmer design. Provisions will be made to route the existing lime injection system to the new weir system. Weirs for the new system will be located in the southeast corner of the main ash pond, close to the stilling pond. The height of the stilling basin weirs will need to be raised as part of this project (final height TBD). Piping (permanent) will be installed across the dike separating the main ash pond from the stilling basin to allow the main ash pond to drain into the stilling basin.

*need ft of pipe & routing for Cost Est.  
el. 760'*

The need for an emergency overflow weir in the dike between the main ash pond and the stilling basin, and an emergency weir on the outer dike from the stilling basin to the intake structure will be assessed.

Sheet piling (temporary) will be installed to allow the area where the new weirs will be installed to be pumped out. The existing weirs and limestone injection system will be left in service until the replacement system is installed and functional.

*finalize in study*

*\* build an "L" shaped ash dike (temp; to be removed partially) front to rear*

*operation of lime system is by plant*

Environmental Concern?

Control Measures to be used

*Valves on pipes would need to be upstream of concrete pipe; may change piping to ductile iron & add platform for ops/maint use a floating platform & anchor (avoids issues w/ drawing & piping & potential H2O cont.)*

YES NO

1. Fugitive Emissions:  YES  NO  Control

2. Open Burning:  YES  NO  Control

3. New Source Review:  YES  NO  Control

4. Other:  YES  NO  Control

B. Water

1. Site / Erosion Control:  YES  NO  Control

2. Sewage:  YES  NO  Control

3. Contaminated Runoff:  YES  NO  Control

Project Environmental Management Plan Outline

	Environmental Concern?		Control Measures to be used
	YES	NO	
4. Process Wastewater (adding pollutants or rerouting flows):	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	___ G R O U T
5. Potentially affect:			
5a. Surface Water:	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	POTENTIAL of Solids ___ G R O U T
5b. Groundwater:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5c. Drinking Water Supply or Potable Water:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5d. Wild or Scenic Rivers or Their Tributaries:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5e. Stream on the Nationwide Rivers Inventory:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5f. Wetlands, Waterflow, Stream Channels, ditches or Stream Banks:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5g. 100-Year Floodplain:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5h. Unique or Aquatic Habitat:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
6. Other: _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
<b>C. Solid Waste</b>			
1. Garbage:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
2. Construction/Demolition Waste:	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	___
3. Clearing Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
4. Sandblasting Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
5. Oil Contaminated Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
6. Other (e.g., sand, glass, etc.): _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
<b>D. Hazardous Waste</b>			
1. Painting Waste (solvents, etc.):	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
2. Sandblasting Waste (Hazardous):	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___
3. Degreasing Solvents:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	___

Appendix A

Project Environmental Management Plan Outline

		Environmental Concern?		Control Measures to be used
		YES	NO	
4.	Corrosive Wastes (acids, caustics):	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
5.	Pesticides:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
6.	Other: _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>E. Asbestos</b>				
1.	Insulation Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
2.	Roofing Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
3.	Floor Tile Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
4.	Other: _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>F. PCB</b>				
1.	Handling & Storage:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
2.	Liquid Waste Disposal:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
3.	Equipment Disposal:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
4.	Contaminated Debris Disposal:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
5.	Other (capacitors, transformers, etc.): _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>G. SPCC/BMP</b>				
1.	Fuel/Lube/Insulating oil Storage:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
2.	Oil Transfer (Procedure):	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
3.	Other: _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>H. Underground Storage Tanks (UST's)</b>				
1.	Contaminated Soil:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
2.	Tank Disposal:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
3.	Other: _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>I. Above-ground Storage Tanks (AST's)</b>				



Project Environmental Management Plan Outline

		Environmental Concern?		Control Measures to be used
		YES	NO	
1.	Contaminated Soil:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
2.	Tank Disposal:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
3.	Other: _____	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>J. Plant or Animal</b>				
1.	Potentially affect:			
	Endangered, threatened, or Special Status Species:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
	Migratory bird populations:	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	_____
	Unique or important terrestrial habitat:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
2.	Potentially take prime or unique farmland out of production:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
3.	Contribute to the spread of exotic or invasive species:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
<b>K. Other:</b>				
1.	Potentially affect:			
	Ecologically critical areas, federal, state, or local park lands, national or state forests, wilderness areas, scenic areas, management wildlife areas, recreational areas, greenways, or trails:	<input type="checkbox"/>		_____
	Historic structures, historic sites, Native American religious or Cultural properties, or archaeological sites:	<input type="checkbox"/>		_____

Appendix A

Page 5 of 6

Project Environmental Management Plan Outline

3.	Environmental Permits/Notifications	Permit Received?		Type	Date of Notification
		Y	N		
A.	Air:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____
B.	Water:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	<u>Discharge point to stilling pool only changed</u>
C.	Hazardous Waste:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____
D.	Asbestos:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____
E.	PCB:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____
F.	UST's / AST's:	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____
G.	Solid Waste:	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____
H.	Other (i.e., Spill Notification):	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____	_____

4.	Employee Training	Required?		Provided / Verified
		Y	N	
A.	Hazardous Waste	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
B.	Asbestos Competent Person	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
C.	Emergency Spill/ Prevention	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
D.	OSHA 1910.120	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____
E.	Other (e.g., Ammonia Awareness):	<input type="checkbox"/>	<input checked="" type="checkbox"/>	_____

5. Emergency Response

Is the Site Emergency Response Plan adequate for this project? If not, a copy of any required additions must be attached to this plan.

Yes  No

Are all environmental concerns addressed in a generic CEC (see Appendix E)? If not, prepare a project-specific CEC.

Yes  No

Do project activities result in environmental concerns?

Yes  No

Are all Appendix E?

Yes  No

Project Environmental Management Plan Outline

If not, prepare a project-specific CEC.

Is a CEC required for this project?

Yes  No

Signatures

Date

Project Initiator/Manager:

\_\_\_\_\_

Site PA(E):

\_\_\_\_\_

Other Signatures:  
(as appropriate)

\_\_\_\_\_

Filed in EDMS

\_\_\_\_\_

## Design Review Meetings

### 10% DESIGN REVIEW

#### Prerequisites

- Preliminary design complete
- Feasibility walkdowns
- DCN cover sheet completed through line 10
- Draft of modification criteria (appendix C)
- Marked up drawings
- Preliminary calculations prepared
- Draft procurement request for LL materials

#### Agenda

- Agreement on scope and approach
- Technical criteria for the task
- Verification of assumptions made during prelim engr
- Special requirements
- Initiate impact review forms

### 50% DESIGN REVIEW

#### Prerequisites

- Completed procure requests for all eng matls (not consumables)
- All drawings prepared and ready for checking
- Completed modification criteria (appendix C)
- Checked calculations

#### Agenda

- Confirmation of scope and approach
- Compatibility of procurement and design schedules
- Critical impact review interfaces
- Technical problems
- Operability, Maintainability, Constructibility
- Testing requirements

#### Hold Point

- Resolve comments before proceeding with final engr design

### 90% DESIGN REVIEW

#### Prerequisites

- Draft of DCN package
- All drawings and documents complete
- All calculations issued
- All impact review forms completed (with schedule for open items)

#### Agenda

- Final constr walkdown w/implementor
- Review DCN pkg
- Discuss mod criteria, special reqmts, testing reqmts, impact review open items and schedule
- Discuss matl delivery, plant support reqmts, implementation schedule
- Assignments for completion of any open items

- Introductions
  
- Review the project basis
  - Systems Background
  - CPJ
    - Problem Description
    - Project Scope
    - Performance Measurement
    - Other Options/Alternatives
  
- Review of notes from 12/10/04 meeting
  - Darlene Keller email
  - Project Impact Checklist
  - EMP
  
- Project Scope and Schedule
  - Scope definition
  - Implementation schedule
  
- Action Items
  
- Next Meeting

**Toney, Calvin L.**

---

**Subject:** KIF531: Discussion of Kennedy Weir Project  
**Location:** Conference Room next to Dennis Lundy's Office

**Start:** Wed 01/19/2005 1:00 PM  
**End:** Wed 01/19/2005 2:30 PM  
**Show Time As:** Tentative

**Recurrence:** (none)

**Meeting Status:** Not yet responded

**Required Attendees:** Haber, Stanley M.; Baugh, James S.; Hedgecoth, Melissa A.; Campbell, Linda F.; Toney, Calvin L.; Petty, Harold L.; Hughes, Michael; Purkey, Ronald E.; Waldrep, Roger T.; Keller, Darlene; Catlett, James H

Please let me know if you will need to call in to participate in this meeting.