

CONSTRUCTION OVERHEAD CALCULATIONS

I. Construction Facilities

In the past Construction Facilities have been estimated as a field overhead line item, although they are accounted (reported) as part of direct feature costs. Construction Facilities will now be estimated separately and in detail as a direct cost. The estimate will NOT prorate these costs back to the direct features. For clarity, a discussion of Construction Facilities will follow.

A. Definition: Construction Facilities are general support activities that benefit more than one direct construction cost account. Examples include (numbers 1-13 are labor items, 14-16 are nonpermanent materials which are listed in estimates as "Other".):

1. Site mobilization
2. Site demobilization
3. Employee processing
4. Maintenance of construction roads, buildings, and facilities
5. General cleanup of project
6. Providing temporary power
7. Providing temporary water
8. Providing temporary air
9. General scaffolding
10. General hauling
11. Providing drinking water
12. Repairing and dispensing small tools
13. Other labor items not listed above
14. Small tools
15. Consumables (i.e. gloves, rags, etc.)
16. Other nonpermanent materials specific to the project

B. Refer to the attached Capital and O&M Cost Estimate - Cost Categories to see that Construction Facility labor is included in "Direct Craft Labor" and Construction Facility material is included in "Other."

II. Field General Expense (Non-Manual Labor)

A. Definition: Field General Expense includes labor costs for non-manual supervision, engineering, inspection, clerical, and administrative salaries and benefits and other expenses necessary for the non-manual work force to operate, such as supplies, office expenses, travel and per diem, vehicles, and other costs.

B. Refer to the attached Capital and O&M Cost Estimate - Cost Categories for directions in estimating Field General Expense

III. Partner Expenses/Charges

Refer to the attached Capital and O&M Cost Estimate - Cost Categories for definitions and directions in estimating Partner Expenses/Charges.

IV. Plant Overhead Charge for Procurement & Handling of Materials

Refer to the attached Capital and O&M Cost Estimate - Cost Categories for definitions and directions in estimating these charges.

7304D

09/03/92

7.1

V. Overheads Which Will NOT Be Included in Project Estimates

- A. Allowance for Funds Used During Construction(AFUDC). See Section 7.2.
- B. TVA Corporate Overheads
- C. TVA Divisional Overheads

OST ESTIMATE PACKAGE

KINGSTON FOSSIL PLANT
(KIF450) GYPSUM PENINSULA DISPOSAL STAGE 1+STAGE 2
PHASE 2 COST ESTIMATE
Ø6Ø47 & Ø6Ø48

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number	06047R3	Option:	0	PCN Number:	KIF450
Plant:	KIF	Revision:	3	Estimate Type:	Preliminary
Cost Engineer:	C. L. Toney	Unit #:		Estimate Accuracy:	+/- 20%
Requesting Engr:	H. L. Petty	Phase:	2	Estimate Issue Date	04/19/2006

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$0
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$0</u>
<u>Phase II</u>		
Engineering		\$330,288
Long Lead Procurement		\$72,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$402,288</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$987,869
Labor (T&L)	56,288.57	\$2,096,180
Labor (Non-Manual)	5,542.96	\$254,790
Equipment		\$1,302,756
Subcontracts		\$285,600
Partner Fee		\$3,439
Partner Insurance		\$2,063
Escalation		\$369,420
Construction Risk Dollars		\$0
Other		\$365,286
Total Construction Cost		\$5,667,403
Engineering		\$209,850
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$0
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$5,877,253</u>
<u>All Phases</u>		
Construction Partner	61,831.53	\$5,667,403
Long Lead Procurement		\$72,000
Engineering		\$540,138
Other / Other Organizations		\$0
Total Risk Dollars		\$0
<u>Total Project Costs</u>	<u>61,831.53</u>	<u>\$6,279,541</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Project name KIF/06047R3/STG 1 GYP PND

Estimator C. L. Toney

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Earthwork

KIF

06047R3

KIF450

S. M. Haber

0

3

2

Preliminary

+/- 20%

04/19/2006

Capital

Cost estimate is based in 2006 dollars.

Revision 3 cost estimate has been revised based on revision 4 estimate provided by HED on 4-18-06.

Revision 2 cost estimate has been revised based on revision 2 estimate provided by HED. Also, contingency for this estimate has been removed.

Revision 1 cost estimate has been revised based on information from Lynn Peety based on revised design & quantities provided by GeoSyniec Consultants.

Short Term Storage. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.

Sorted by Location/Activity

Detail summary

Report format

Location	Activity	Description	Units/Quantity	Subs Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount			
HASE 3 (BOP)	17-Pumps & Pipe	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	84.000	84.00 mh	2,937	60,000	-	-	-	63,244.70	63,245			
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,260.00 cy	0.200	652.00 mh	16,311	-	-	-	-	-	24,461	24,461		
		Bottom Ash Pipe Bedding	112.00 cy	0.500	56.00 mh	1,514	-	-	-	-	-	2,088	2,088		
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.40 mh	19,976	-	92,484	-	-	-	60.77	121,539		
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00 cy	0.320	964.48 mh	24,128	-	-	-	-	-	15.77	47,527		
		Platforms Steel	5.00 ton	60.000	300.00 mh	10,087	-	26,250	-	-	-	7,742.43	38,712		
		17-Pumps & Pipe				2,706.88 hrs	74,953	178,734	-	-	-	43,885	297,572		
		HASE 3 (HED)	18-Electrical	Phase 1 Transformer 200 kva (13.8 KV to 480 V)	1.00 ls	120.000	120.00 mh	4,133	12,000	-	-	-	16,643.28	16,643	
				4/0 600 Volt Cable	200.00 lf	0.100	20.00 mh	708	2,200	-	-	-	14.54	2,908	2,908
				3" Diameter GRC Conduit	200.00 lf	0.619	123.80 mh	4,383	8,140	-	-	-	62.62	12,523	12,523
				13 kv Amp Pole Mount Fuse Disconnect	1.00 ea	12.000	12.00 mh	425	1,500	-	-	-	1,924.86	1,925	1,925
				18-Electrical				275.80 hrs	9,749	23,840	-	-	-	1,924.86	33,999
				xConst Facilities				207.89 mh	5,900	-	-	-	-	9,000.00	9,000
				xConst Facilities				207.89 hrs	5,900	-	-	-	-	9,000.00	9,000
				HASE 3 (HED)	Non-Manual	Phase 3 Non-Manual	1.00 ls	383.000	383.00 hrs	19,150	-	-	-	-	19,150.00
PHASE 3 (BOP)								383.00 hrs	19,150	-	-	-	-	19,150.00	19,150
PHASE 3 (BOP)								3,573.57 hrs	109,712	202,574	-	-	-	47,435	359,722
Construction Labor								53,096.00 mh	2,005,618	-	-	-	-	2,005,617.66	2,005,618
Non Manual Labor								5,159.96 mh	235,640	-	-	-	-	235,640.00	235,640
TVA-HED Subcontracts								-	-	285,600	-	-	-	285,600.00	285,600
Partner Purchased Material								-	-	-	-	-	-	857,295.00	857,295
Construction Heavy Equipment								-	-	-	-	-	-	1,255,321.00	1,255,321
Small Tools						-	-	-	-	-	-	5,310.00	5,310		
Supplies, Consumables & Expendable Tools						-	-	-	-	-	-	15,929.00	15,929		
TVA-HED - Central Command						-	-	-	-	-	-	338,415.00	338,415		
HED Installation						58,257.96 hrs	2,241,258	857,295	285,600	-	-	338,415.00	4,999,128		
PHASE 3 (HED)						58,257.96 hrs	2,241,258	857,295	285,600	-	-	338,415.00	4,999,128		
PHASE 3 (HED)								857,295	285,600	-	-	338,415.00	4,999,128		
PHASE 3 (HED)								857,295	285,600	-	-	338,415.00	4,999,128		

Estimate Totals				Rate	Cost Basis
Description	Amount	Totals	Hours		
Labor	2,350,970		61,831.535 hrs		
Material	1,059,869				
Subcontract	285,600				
Equipment	1,302,756		1,970.471 hrs		
Other	359,654				
Engineered Materials - Ph 2	5,358,849	5,358,849		100.000 %	C
Adjustment - Enar Materials	(72,000)			(100.000) %	C
Small Tools Expense (BOP)	1,435			0.026 \$/hr	H
Consum & Expendables (BOP)	3,622			0.173 %	C
Office Supplies & Exo (BOP)	575			0.226 %	C
Escalation - Craft Labor	5,632	5,364,481			
Escalation - Subcontract	203,329			9.700 %	C
Escalation - Perm Materials	19,421			6.800 %	C
Escalation - HED Equipment	40,275			3.800 %	C
Escalation - Small Tools	75,319			6.000 %	C
Escalation - Consumables	1,914			0.034 \$/hr	H
Escalation - Non-Manual Labor	4,192			0.200 %	C
Escalation - Office Supplies	24,460			9.600 %	C
Partner Insurance (BOP)	510			0.200 %	C
Partner Award Fee (BOP)	369,420	5,733,901			
FPG Proj Enar - Phase 2	2,063			0.088 %	C
FPG Civil Enar - Phase 2	3,439			0.146 %	C
GeoSvntec Enar - Phase 2	5,502	5,739,403			
FPG Proj Enar - Phase 2	4,200		100,000 hrs	0.162 % @ 42.00 A	A
FPG Civil Enar - Phase 2	21,000		500,001 hrs	0.809 % @ 42.00 A	A
GeoSvntec Enar - Phase 2	302,400		4,200,000 hrs	6.793 % @ 72.00 A	A
FPG Proj Cntrl Cost - Phase 2	672		16,002 hrs	0.026 % @ 42.00 A	A
FPG Cost Estimatin - Phase 2	1,680		39,999 hrs	0.065 % @ 42.00 A	A
FPG Enar Records - Phase 2	336		8,001 hrs	0.013 % @ 42.00 A	A
FPG Proj Enar - Phase 3	330,288	6,069,691			
FPG Civil Enar - Phase 3	3,150		75,002 hrs	0.121 % @ 42.00 A	A
GeoSvntec Enar - Phase 3	6,300		149,997 hrs	0.243 % @ 42.00 A	A
Mac Tec QA/QC & Certf - Ph 3	50,400		700,001 hrs	1.132 % @ 72.00 A	A
Total	150,000		2,083,333 hrs	3.369 % @ 72.00 A	A
	209,850	6,279,541			
		6,279,541			

**KINGSTON FOSSIL PLANT
(KIF450) TOTAL BUILDOUT OF GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06048R1 Option: 0 PCN Number: KIF450
 Plant: KIF Revision: 1 Estimate Type: Preliminary
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 20%
 Requesting Engr: S. M. Haber Phase: 2 Estimate Issue Date 01/26/2006

	<u>Hours</u>	<u>Dollars</u>
Phase I		
Engineering		\$0
Partner (Non-Manual)		
Other / Other Organizations		\$0
	<u>Total Phase I</u>	<u>\$0</u>
Phase II		
Engineering		\$0
Long Lead Procurement		\$72,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
	<u>Total Phase II</u>	<u>\$72,000</u>
Phase III		
Construction (Partner)		
Permanent Material		\$2,102,943
Labor (T&L)	146,406.92	\$5,503,636
Labor (Non-Manual)	19,583.00	\$791,950
Equipment		\$2,550,085
Subcontracts		\$754,600
Partner Fee		\$8,858
Partner Insurance		\$5,315
Escalation		\$912,323
Construction Risk Dollars		\$0
Other		\$959,060
Total Construction Cost		\$13,588,770
Engineering		\$419,700
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$2,819,530
Other / Other Organizations		\$0
	<u>Total Phase III</u>	<u>\$16,828,000</u>
All Phases		
Construction Partner	165,989.92	\$13,588,770
Long Lead Procurement		\$72,000
Engineering		\$419,700
Other / Other Organizations		\$0
Total Risk Dollars		\$2,819,530
	<u>Total Project Costs</u>	<u>165,989.92</u>
		<u>\$16,900,000</u>
		<u>\$0</u>
		<u>\$0</u>

**KINGSTON FOSSIL PLANT
(KIF-150) TOTAL BUILDOUT OF GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Project name KIF/06048R1/STG 2 GYP PND

Estimator C. L. Toney

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Project Earthwork

Plant KIF

Estimate # 06048R1

FCR # KIF-150

Requesting Engr S. M. Haber

Option 0

Revision 1

Phase 2

Estimate Type Preliminary

Estimate Accuracy +/- 20%

Est. Issue Date 01/26/2006

Funding Type Capital

Notes
Cost estimate is based in 2006 dollars.

Revision 1 cost estimate has been revised based on info from Lynn Petty based on revised design & quantities provided by GeoSynetic Consultants.

Gypsum Long Term Rim Ditch Stack. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.

Sorted by 'Location/Activity'
'Detail' summary

Report format

Spreadsheet Report
KIF/06048R1/STG 2 GYP PND

Estimate Company

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount		
PHASE 3 (BOP)	17-Pumps & Pipe Ph 1	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	84.000	84.000 mh	2,937	60,000	-	308	-	63,244.70	63,244.70		
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,260.00 cy	0.200	652.000 mh	16,311	-	-	8,150	-	-	24,461	24,461	
		Donor Ash Pipe Bedding	112.000 cy	0.500	56.000 mh	1,514	-	-	574	-	-	18,655	18,655	
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.400 mh	19,976	-	92,484	-	9,080	-	60,777	121,539	
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.000 cy	0.320	964.480 mh	24,126	-	-	-	23,998	-	15,777	47,527	
		Platform Steel	5.000 ton	60.000	300.000 mh	10,087	-	26,250	-	2,376	-	7,742.43	38,712	
		17-Pumps & Pipe Ph 1	2,706.88 hrs	-	-	74,953	-	178,734	-	43,885	-	-	297,572	
		18-Electrical Ph 1	Phase 1 Transformer 200 kva (13.8 kV to 480 V)	1.00 ls	120.000	120.000 mh	4,193	-	12,000	-	450	-	16,643.28	16,643.28
			4/0 600 Volt Cable	200.00 lf	0.100	20.000 mh	708	-	2,200	-	-	-	14,54	2,908
			3" Diameter GRC Conduit	200.00 lf	0.619	123.800 mh	4,383	-	8,140	-	-	-	62,62	12,523
			13 kV Amp Pole Mount Fuse Disconnect	1.00 ea	12.000	12.000 mh	425	-	1,500	-	-	-	1,924.86	1,925
			18 Electrical Ph 1	275.80 hrs	-	-	9,709	-	23,840	-	450	-	-	33,999
		xConst Facilities	Mobilize Drug Test, Miscellaneous Other, & Demobilize	1.00 ls	207.883	207.889 mh	5,900	-	-	-	3,100	-	9,000.00	9,000
			xConst Facilities	207.889 hrs	-	-	5,900	-	-	-	3,100	-	-	9,000
		PHASE 3 (HED)	zNon-Manual	Phase 3 Non Manual	1.00 ls	383.000	383.000 hrs	19,150	-	-	-	-	19,150.00	19,150
PHASE 3 (BOP)	3,573.57 hrs			-	-	109,712	202,574	-	47,435	-	-	359,722		
Construction Labor (Phase 1) Mhs Limited To Timberline Program	1.00 ls			76,830.266	76,830.27 mh	2,926,849	-	-	-	2,926,849	-	2,926,849		
Construction Labor (Phase 2) Balance Of Mhs Required For Estimate	1.00 ls			66,386.078	66,386.08 mh	2,486,225	-	-	-	2,486,225	-	2,486,225		
Non Manual Labor	1.00 ls			19,200.000	19,200.00 mh	772,800	-	-	-	772,800	-	772,800		
TVA-HED Subcontracts	1.00 ls			-	-	-	754,600	-	-	-	-	754,600	754,600	
Partner Purchased Material	1.00 ls			-	-	-	1,972,369	-	-	-	-	1,972,369	1,972,369	
Construction Heavy Equipment	1.00 ls			-	-	-	-	-	-	2,502,650	-	2,502,650	2,502,650	
Small Tools	1.00 ls			-	-	-	-	-	-	14,322	-	14,322	14,322	
Supplies, Consumables & Expendable Tools	1.00 ls			-	-	-	-	-	-	42,965	-	42,965	42,965	
TVA-HED - Central Command	1.00 ls			-	-	-	-	-	-	891,284	-	891,284	891,284	
HED Install Ph1-Ph2	1.00 ls			-	-	-	-	-	-	2,502,650	-	2,502,650	2,502,650	
PHASE 3 (HED)	162,416.34 hrs			-	-	6,185,874	1,972,369	754,600	2,502,650	948,571	-	12,364,064		
PHASE 3 (HED)	162,416.34 hrs			-	-	6,185,874	1,972,369	754,600	2,502,650	948,571	-	12,364,064		

Estimate Totals

Description	Amount	Totals	Hours	Rate	Cost Basis
			##### hrs		
Labor	6,295.586				
Material	2,174.943				
Subcontract	754.600				
Equipment	2,550.085		1,970.471 hrs		
Other	948.571				
Engineered Materials - Ph 2	12,723.785	12,723.785		100.000 %	C
Adjustment - Enor Materials	(72.000)			(100.000) %	C
Small Tools Expense (BOP)	2.596			0.018 \$/hr	H
Consum & Expendables (BOP)	6.453			0.117 %	C
Office Supplies & Exp (BOP)	1,441			0.182 %	C
	10,490	12,734.275			
Escalation - Craft Labor	533.853			9.700 %	C
Escalation - Subcontract	52.067			6.900 %	C
Escalation - Perm Materials	82.648			3.800 %	C
Escalation - HED Equipment	150.159			6.000 %	C
Escalation - Small Tools	4.978			0.034 \$/hr	H
Escalation - Consumables	11.007			0.200 %	C
Escalation - Non-Manual Labor	76.027			9.600 %	C
Escalation - Office Supplies	1,584			0.200 %	C
	912.323	13,646.598			
Partner Insurance (BOP)	5.315			0.084 %	C
Partner Award Fee (BOP)	8,858			0.141 %	C
	14,173	13,660.771			
FPG Proj Enar - Phase 3	6,300		150,005 hrs	0.090 % @ 42.00 A	A
FPG Civil Enar - Phase 3	12,600		299,994 hrs	0.181 % @ 42.00 A	A
GeoSvntec Enar - Phase 3	100,799		1,399,992 hrs	0.843 % @ 72.00 A	A
Mac Tec QA/QC & Certf - Ph 3	300,000		7,142,862 hrs	4.303 % @ 42.00 A	A
	419,699	14,080.470			
Contingency Ttl Project @ 20%	2,819,530				L
	2,819,530	16,900.000			
Total		16,900.000			

ESTIMATE INPUT/OUTPUT

PCN Number: PCN Description: KIF - Gypsum Disposal Area - Peninsula - Stage 1

Current Phase: 1 Phase Request: 2 Date: 11/17/2005

	Phase I		Phase II		Phase III		Prin/RE Engr
	Hours	\$	Hours	\$	Hours	\$	
Project Engr		\$0	100	\$4,200	75	\$3,150	
Mech Engr		\$0		\$0		\$0	
Elec Engr I		\$0		\$0		\$0	
Elec Engr II		\$0		\$0		\$0	
Civil Engr		\$0	500	\$21,000	150	\$6,300	
Air, Gas, Wtr, Yard Systems		\$0		\$0		\$0	
Comb Proc, Wtr Treatment		\$0		\$0		\$0	
Steam Cycle Systems		\$0		\$0		\$0	
Other Systems Engr (specify)		\$0		\$0		\$0	
Non-TVA Engr		\$0	4200	\$302,400	700	\$50,400	
Other Orgs (specify) (MacTec QA/QC & certification)		\$0		\$0		\$150,000	
Project Controls Scheduling		\$0		\$0		\$0	
Project Controls Cost		\$0	16	\$672		\$0	
Cost Estimating		\$0	40	\$1,680		\$0	
Engr Records		\$0	8	\$336		\$0	
CAD Dwg Support-Enter # Dwgs:	0	\$0	4864	\$330,288	925	\$ 209,850	
Sub Totals:							
Project Totals:	5,789	Hours	\$540,138	Dollars			

Long Lead Material - Dollars

Print

Save As...

KIF Gypsum on Peninsula
Phase 1 - Gypsum Long Term Rim Ditch Stack

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
7.00	Gypsum Stack Peninsula (7/00 through 18/00)				
7.01	Clear and Grub	ac	30		C - Tree line only
7.02	Clear and grub	cy	100,000		C - 62 acres - Phase 1 & Stormwater Pond area
7.03	Strip 1 ft vegetation and topsoil - spoil at stockpile				
8.00	Erosion Controls / Stormwater Pond				
8.01	Erect silt fence	lf	5,400		C -
8.02	Cut for stormwater runoff ponds	cy	25,851		C -
8.03	Fill for stormwater runoff ponds	cy	99,550	119,460	C - gross fill volume; subtract cut to obtain net fill volume
8.04	Drop inlet to the Pond	ea	2		
8.05	Inlet pipes to the Pond (2 - 48 in dia RCP)	lf	100		
8.06	Riprap for stormwater runoff pond (if needed)	ton	8,102		C - Pond perimeter = 2588 ft @ midslope, 57 ft slope length
8.07	CMP for Emergency Spillway (2 x 36 in dia)	lf	120		C
9.00	Relocated Access Roads				Assume 6000' long road, 20 ft wide
9.01	Bottom Ash	cy	2,300		C - 6" bottom ash
9.02	Crushed stone base	ton	2,200		C - 4" stone with an assumed unit weight = 110 pcf
9.03	Crushed stone base - parking lot	ton	275		C - Assume 100 ft x 100 ft w/6 in crushed stone (110 pcf)
10.00	Fencing (Excluding Dewatering Facility)				
10.01	New fencing (including grounding)	lf	200		C - Assume chain link fence to block road only
10.02	Gates	ea	2		C - 1 @ each end
11.00	Seed/Mulch				
11.01	Seed/Mulch disturbed areas	ac	25		C - Disturbed areas include areas outside perimeter road, stormwater pond, and relocated access road
12.00	Borrow Area Development				
12.01	Clear and Grub	ac	34		C
12.02	Erect silt fence	lf	5,000		C
12.03	Temporary perimeter ditch	cy			C
12.04	Additional items related to stormwater management	ls	1		C
13.00	Gypsum Disposal Facility Construction				
13.01	Earthwork cut	cy	259,932	431,912	C - to shape base in phase 1 gypsum stack area
13.02	Proofroll/subgrade	ac	52		C - Phase 1 area
13.03	Earthwork fill	cy	315,546	377,635	C - subtract cut and fill volume to get the net volume
13.04	Geologic buffer	cy	227,163	274,480	C - B' thick geologic buffer
13.05	8 oz nonwoven geotextile for centerline underdrain	sy	63,600		C - W rapped around pipe bedding, includes 10% waste & overlap
13.06	36" depth crushed stone (110 pcf)	ton	37,900		C - 1530' long, 150' wide, 3' deep
13.07	12-in. dia HDPE centerline underdrain piping	lf	10,360		C - 6 pipes @ 1726' long each

DIFF 53,263cy
LONG

MARK 44,386cy

[Handwritten signature]

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
13.08	24-in Phase 2 discharge pipe	lf	1,726		C - 5 tees, 2 elbows, 6 caps
13.09	HDPE Fittings	ea	13		C -
13.10	Drainage pipe from sump to stormwater pond	lf	580		C -
13.11	Lift Station to stormwater pond	ea	1		C - North of stormwater pond
13.12	Drop inlet for diversion pipes	ea	3		C - 3 - 48 in dia Reinforced concrete pipe
13.13	Diversion pipes beneath stormwater pond	lf	1,830		C -
13.14	Flood Gate	ea	3		C - Assume 6" base layer - length 8250 ft, 20' wide roadway around perimeter soil dike and storm water pond
13.15	Perimeter road - bottom ash base	cy	3,100		C - Assume 4" stone layer around perimeter w/unit wt = 110 pcf
13.16	Perimeter road - crushed stone	ton	3,100		
14.00	Gypsum Stack Operation				
14.01	6" dia perforated HDPE perimeter toe underdrains	lf			O&M
14.02	crushed stone surrounding pipe (110 pcf)	ton			O&M
14.03	8-oz nonwoven geotextile for perimeter underdrain	sy			O&M - Wrapped around stone envelope
14.04	6" dia solid HDPE SDR 17 lateral outlet pipes	lf			O&M
14.05	Wet Cast Gypsum Dike	cy			O&M - From crown elevation of initial soil berm to 850
14.06	Cut Rim Ditches	cy			O&M
14.07	Gypsum Disposal Stack (wet sluice)	cy			O&M
14.08	Life of Gypsum Disposal Stack	yr			O&M -
15.00	Construction parking				
15.01	Earthwork cut	bcy			C
15.02	Earthwork fill	bcy			C
15.03	Crushed stone base - parking lot	ton	620		C - Assume 150' x 150' area w/6" crushed stone @ 110 pcf
16.00	Engineering				
16.01	Engineering	ls	1		Assume 10% of construction cost
17.00	Lift Stations				
17.01	underdrain lift station	ea	1		See 10W427-24
17.02	Stormwater lift station	ea	1		See 10W427-25
18.00	Electrical				

Notes:

- 1 C - Capital cost
- 2 O&M - Operation and Maintenance Cost
- 3 Prior to construction, the contractor shall verify material quantities based on construction drawings.

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 1 Gypsum Disposal Facility Pond Construction
Revision #04

04/18/06

Mr. Calvin Toney,

We thank you for the opportunity to provide this estimate for the TVA - Kingston (Phase 1) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings @50% Design.

The TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 10,400 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Construct construction parking area.
- Cut approximately 88,500 CY of clay for storm-water runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Install 12 lf of 72” Outlet Structure.
- Install 14 lf of 48” riser.
- Install 150 lf of 48” principle spillway.
- Pour concrete “anti-seep” collars at all joints.
- Allowance - Clean out Gypsum Stack storm-water runoff pond as needed. (approximately 1,000 cy)
- Clear and Grub approximately 30 acres at Gypsum Stack Peninsula. (Includes clear cut logging as well with clearing support by HED).
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Borrow Area Development”:

- Clear and Grub approximately 34 acres at borrow site.
- Clear cut all timber on approximately 34 acres for clay borrow site.
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Haul / Access Roads”:

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 1.5 miles of roadway.
- Build Gypsum Disposal Facility Access Roadways with 2,200 TN of new stone.
- Build Gypsum Disposal Facility Access Roadways with 2,760 CY of Bottom Ash.

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

- Install Fence and gates at road. (200 lf w/ 1 personnel and 1 swing gate.)

“Disposal Facility Construction”:

- Proof-roll all Gypsum Stack sub-grade. (52 acres)
- Install geologic buffer. Over-excavate 3’ depth in Gypsum Stack liner area (approximately 52 acres), then re-place and re-compact liner material. (272,596 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 431,918 cy)
- Install centerline underdrain piping inside new Gypsum Stack (10,360 lf).
- Install 63,600 sy of non-woven geotextile fabric in new centerline underdrain.
- Install 37,900 tn of 36” deep crushed stone in new centerline underdrain.
- Install Perimeter road with 6” of Bottom Ash topped with 4” of crushed stone. (1 mile of 20’ wide roadway)
- Install 48” RCP Phase 2 Discharge Pipe. (1,726 lf)
- Install drainage pipe from sump to stormwater pond. (580 lf)
- Install 48” RCP diversion pipes beneath stormwater pond. (1,830 lf)
- Install perimeter road bottom ash. (3,700 cy)
- Install perimeter road crushed stone. (3,100 tn)

“Clarifications to Estimated Scope of Work”:

- No “rock removal / excavation” costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.
- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All “Bank Cubic Yard” quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes 2 weeks contingency for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for Fence Contractor, TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed, Geotechnical Engineers to provide compaction test results as required, and mulching of tree stumps, laps, etc. after clearing of trees is completed.
- Seed and Mulch all disturbed areas outside dikes. (approximately 25 acres) is included.

“Schedule”:

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 11 months from start of project as

TVA – HEAVY EQUIPMENT DIVISION
 933 OLD FERRY ROAD
 SPRING CITY, TENNESSEE 37381
 PH: (423) 365-8739 FAX: (423) 365-8705

stated on "Estimate Summary" sheet provided with this estimate.

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$4,999,128.00 Lump Sum

Thank You,
Brad Workman
TVA - HED
(931) 320-1044

cc: Larry Radford
TVA - HED

Kenny Lowery
TVA - HED

TVA - HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029097

06047R3

HED ESTIMATE SUMMARY

REV # 4

0

LOCATION: KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 1

PRINT DATE: 18-Apr-06
ESTIMATE DATE: 17-Mar-06

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 1)

WORKSCOPE: DEVELOP BORROW AREA, DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 1 OF GYPSUM POND.

DURATION: ***11 MONTHS FOR PHASE 1 ROAD CONSTRUCTION / POND CONSTRUCTION.*** WITH 2 WEEKS CONTINGENCY FOR WEATHER

ESTIMATE PHASE		TYPE OF FUNDING
2		CAPITAL > 100K

PREPARED BY: B. WORKMAN (HED)

1. TVA-HED LABOR COSTS		Comments
Craft Augmented Labor	MANHOURS	53098 <i>\$31,712.01</i>
	COST	\$2,005,618
Non-Manual Labor	MANHOURS	5,160 <i>\$45,646.50</i>
	COST	\$235,640
Contingency 0.00%	MANHOURS	0
	COST	\$0
SUBTOTAL TVA-HED LABOR		
	MANHOURS	58,258
	COST	\$2,241,258
2. TVA-HED OTHER COSTS		
TVA-HED Subcontracts		\$285,600
TVA-HED Subcontract Fee		\$0
Travel & Living Expenses		See "Non-Manual Labor"
TVA-HED Material Purchases		\$0
HED Other Costs		\$0
Contingency 0%		\$0
SUBTOTAL TVA-HED OTHER		\$285,600
TOTAL TVA-HED COSTS		\$2,526,858
3. ITEMS MANAGED BY TVA-HED		
Permanent Materials		\$857,295
Heavy Equipment		\$1,255,321
Tagged & 3rd Party Rental Equipment		\$0
Small Tools		\$5,310
Supplies, Consumables & Expendable Tools		\$15,929
Office Supplies & Expenses		\$0
Other TVA-HED Costs		\$0
TVA subcontracts (By Others)		\$0
Partner or OCIP Insurance		\$0
TVA-HED - Overhead	10.00%	\$338,415
Contingency 0%		\$0
SUBTOTAL TVA-HED MANAGED		\$2,472,270
TOTAL TVA-HED COSTS		\$4,999,128

APPROVALS: ESTIMATE TOTAL 4,999,128

_____	_____
TVA-HED Estimator	Date:
_____	_____
TVA - Project Manager	Date:
_____	_____
TVA - Project Engineer	Date:
_____	_____
TVA - Site Environmental Engineer	Date:

A	B	C	D	E	F	G	H	I	J	K	L	M	N
MAT. CODE	CODE WDRK ORDER	CODE	ACT 50%	CODE CRFT	DESCRIPTION	QTY	UNIT	MAN MH	WAGE RATE	TOTAL LABOR	MATERIAL	TOTAL MATERIAL	
GYPSUM POND CONSTRUCTION (PHASE I)													
CLEAR AND GRUB													
	102			OEA	CLEAR FOR BORROW @ PENINSULA, SED. PONDS, DIKES		AC	80	\$40.00				
	100			OEA	STRIP TOPSOIL	100000	CY	0.055	5500	\$40.00		\$220,000	
EROSION CONTROLS / SEED & MULCH													
	103			OEA	TRENCH FOR EROSION CONTROL FENCING	5400	LF	0.025	135	40		\$5,400	
	103			LBJ	INSTALL SILT FENCING / STRAW BALES	5400	LF	0.12	648	26		\$16,848	
	103			LBJ	SEED / MULCH DISTURBED AREAS	25	AC	40	1000	26		\$26,000	
	103			TMW	HAUL STRAW AND SILT FENCE ALONG PROJECT AREA	5400	LF	0.0183	98.82	32		\$3,162	
STORMWATER RUNOFF POND CONSTRUCTION													
	100			OEA	GROSS CUT / FILL FOR STORMWATER RUNOFF PONDS	119460	CY	0.065	7765	\$40.00		\$310,596	
	105			OEA	RIP RAP FOR PONDS	8102	TN	0.05	405	\$40.00		\$16,204	
	105			OEA	72" DIA. CMP FOR OUTLET STRUCTURE	12	LF	2	24	\$40.00		\$960	
	105			OEA	48" DIA CMP FOR RISER FOR OUTLET STRUCTURE	14	LF	2	28	\$40.00		\$1,120	
	105			LBJ	CUT HOLES IN RISER	6	EA	2	12	\$26.00		\$312	
	105			OEA	48" CMP OUTLET PIPE (PRINCIPLE SPILLWAY)	100	LF	1	100	\$40.00		\$4,000	
	105			LBJ	CONCRETE FOR RISER BASE	9	CY	2	18	\$26.00		\$468	
	105			LBJ	ANTI-SEEP COLLARS	6	CY	4	24	\$26.00		\$624	
	105			OEA	PIPE BEDDING - #57 STONE	40	TN	2	80	\$40.00		\$3,200	
	100			OEA	CLEAN OUT STORMWATER RUNOFF POND	1000	CY	0.065	65	\$40.00		\$2,600	
BUILD / RELOCATE ACCESS ROADS													
	101			OEA	BOTTOM ASH CUT / HAUL / FILL	2760	CY	0.065	179	\$40.00		\$7,176	
	104			OEA	CRUSHED STONE BASE	2200	TN	0.025	55	\$40.00		\$2,200	
	104			OEA	CRUSHED STONE BASE - PARKING LOT	280	TN	0.025	7	\$40.00		\$280	
FENCING - SEE SUBCONTRACTS SECTION													
FENCING - SEE SUBCONTRACTS SECTION													EA
BORROW AREA DEVELOPMENT													
	102			OEA	CLEAR AND GRUB	34	AC	30	1020	\$40.00		\$40,800	
	103			OEA	TRENCH FOR EROSION CONTROL FENCING	5000	LF	0.025	125	\$40.00		\$5,000	
	103			LBJ	INSTALL SILT FENCING / STRAW BALES		LF	0.125		\$26.00			
	100			OEA	EXCAVATE TEMPORARY PERIMETER DITCH		CY	0.065		\$40.00			
	100			OEA	CUT FOR STORMWATER RUNOFF PONDS		CY	0.065		\$40.00			
	100			OEA	FILL FOR STORM WATER PONDS		CY	0.065		\$40.00			
	106			OEA	72" DIA. CMP FOR OUTLET STRUCTURE		LF	2		\$40.00			
	106			OEA	48" DIA CMP FOR RISER FOR OUTLET STRUCTURE		LF	2		\$40.00			
	106			LBJ	CUT HOLES IN RISER		EA	2		\$26.00			
	106			OEA	48" CMP OUTLET PIPE (PRINCIPLE SPILLWAY)		LF	1		\$40.00			
	106			LBJ	CONCRETE FOR RISER BASE		CY	2		\$26.00			
	106			LBJ	ANTI-SEEP COLLARS		CY	4		\$26.00			
	106			OEA	PIPE BEDDING - #57 STONE		TN	2		\$40.00			
	106			OEA	CLEAN OUT STORMWATER RUNOFF POND		CY	0.065		\$40.00			
DISPOSAL FACILITY CONSTRUCTION													
	100			OEA	EARTHWORK CUT - SHAPE BASE INSIDE GYPSUM STACK	431918	CY	0.03	12958	\$40.00		\$518,302	
	100			OEA	EARTHWORK FILL FROM BORROW AREA		CY	0.03		\$40.00			
	100			OEA	PROOFROLL SUBGRADE	52	AC	3	156	\$40.00		\$6,240	
	100			OEA	CUT AND RE-COMPACT LINER (GEOLOGIC BUFFER)	272596	CY	0.035	9541	\$40.00		\$381,634	
	107			LBJ	INSTALL 8" HDPE CENTERLINE UNDERDRAIN PIPE	10358	LF	0.08	829	\$26.00		\$21,545	
	107			OEA	CUT FOR UNDERDRAIN SYSTEM		CY	0.073		\$40.00			
	107			LBJ	INSTALL GEOTEXTILE - 8OZ NON-WOVEN FOR CL UNDERDRAIN	63600	SY	0.0063	398	\$26.00		\$10,335	
	107			OEA	INSTALL 36" DEPTH 1081 CRUSHED STONE	37900	TN	0.04	1516	\$40.00		\$60,640	
	107			LBJ	INSTALL UNDERDRAIN PIPING (12" DIA. HDPE)	10360	LF	0.08	829	\$26.00		\$21,549	
	107			LBJ	24" PHASE 2 DISCHARGE PIPE INSTALLATION	1728	LF	0.08	138	\$24.40		\$3,368	
	107			LBJ	INSTALL HDPE FITTINGS FOR UNDERDRAIN PIPING	13	EA	0.1	1	\$26.00		\$34	
	107			OEA	EXCAVATE SURFACE WATER DIVERSION DITCH		CY	0.07		\$40.00			
	107			TM3	HAUL EXCAVATED SPOILS FROM DITCH AND STOCKPILE		CY	0.027		\$32.00			
	107			OEA	RIP RAP DIVERSION DITCH		TN	0.05		\$40.00			
	107			OEA	DRAINAGE PIPE FROM SUMP TO STORMWATER POND	580	LF	0.1	58	\$40.00		\$2,320	
	107				LIFT STATION	1	LOT			\$10,000		\$10,000	
	107			OEA	DIVERSION PIPE BENEATH STORMWATER POND	1830	LF	0.07	128	\$36.21		\$4,639	
	101			OEA	INSTALL 2.5" THICK BOTTOM ASH DRAINAGE LAYER		CY	0.065		\$40.00			
	101			OEA	INSTALL 6" THICK FLY ASH LAYER (MIX)		CY	0.065		\$40.00			
	101			OEA	PERIMETER ROAD SURFACING - BOTTOM ASH	3700	CY	0.065	241	\$40.00		\$9,820	
	104			OEA	PERIMETER ROAD SURFACING - CRUSHED STONE	3100	TN	0.025	78	\$40.00		\$3,100	
	107			OEA	INSTALL RIP RAP DITCH		TN	0.02		\$40.00			
	107			LBJ	INSTALL 8 OZ NON-WOVEN GEOTEXTILE (IF RIP RAP IS USED)		SY	0.0063		\$26.00			
CONSTRUCTION PARKING													
	100			OEA	EARTHWORK CUT		CY	0.04		\$40.00			
	100			OEA	EARTHWORK FILL		CY	0.04		\$40.00			
	104			OEA	CRUSHED STONE BASE	650	TN	0.03	20	\$40.00		\$780	
"ALLOWANCE" FOR PUMP STATION POND													
				OEA	PUMP STATION QUANT'S. NOT PROVIDED AT THIS TIME	2	MEN	80	160	\$40.00		\$6,400	
				TM3	HAUL MATERIAL OUT	2	MEN	80	160	\$29.27		\$4,683	
											PHASE I TOTALS		
											EARTHWORK 925,026		
											ASH 6,460		
											RIP RAP 8102		
											#57 STONE 40		
											CR. STONE 44130		
											FABRIC 63,600		
											SILT FENCE 10,400		
ADD ABOVE THIS LINE IF NECESSARY							PRE-OUTAGE DIRECT						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE							SUBTOTALS :		44498		\$1,732,138		
OUTAGE - DIRECT CRAFT													
GYPSUM POND CONSTRUCTION (PHASE I)													

A	B	C	D	E	F	G	H	I	J	L	M	N
1	2	3				CRAFT LABOR	UNIT	MAN	WAGE	TOTAL	MATERIAL	TOTAL
CODE	WORK ORDER	CODE	ACT	CODE	DESCRIPTION	QTY	UNIT	MH	HOURS	RATE	LABOR	MATERIAL
ADD ABOVE THIS LINE IF NECESSARY						OUTAGE DIRECT						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :						
POST OUTAGE - DIRECT CRAFT												
GYPSUM POND CONSTRUCTION (PHASE 1)												
ADD ABOVE THIS LINE IF NECESSARY						POST OUTAGE DIRECT						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :						
TOTALS - DIRECT CRAFT						44498		\$1,732,138				
SUPPORT CRAFT												
(QTY & UNITS MUST BE INCLUDED FOR EA. LINE ITEM)												
PRE-OUTAGE - SUPPORT CRAFT												
GENERAL FOREMAN / SUPPORT CRAFT (1 YR)												
942		OEA			OPERATOR FOREMAN	1	MEN		1720	\$46.00	\$79,120	
942		LBJ			LABORER FOREMAN	1	MEN		1720	\$29.00	\$49,880	
902		TM3			TEAMSTER TO WATER ROADS / SUPPORT MANPOWER	1	MEN		1720	\$32.00	\$55,040	
902		LBJ			LABORER GENERAL SUPPORT / OFFICE	2	MEN		3440	\$26.00	\$89,440	
ADD ABOVE THIS LINE IF NECESSARY						PRE-OUTAGE SUPPORT						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :		8600		\$273,480		
OUTAGE - SUPPORT CRAFT												
ADD ABOVE THIS LINE IF NECESSARY						OUTAGE SUPPORT						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :						
POST-OUTAGE - SUPPORT CRAFT												
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :						
MOBILIZATION OF CRAFT												
	901	AWJ			ADMINISTRATIVE TIME		MEN	2		\$33.79		
	901	AWJ			SAFETY MEETING		MEN	3		\$33.79		
	901	AWJ			DRUG TEST		MEN	1		\$33.79		
	901	ABJ			ADMINISTRATIVE TIME		MEN	2		\$27.44		
	901	ABJ			SAFETY MEETING		MEN	3		\$27.44		
	901	ABJ			DRUG TEST		MEN	1		\$27.44		
	901	BMJ			ADMINISTRATIVE TIME		MEN	2		\$52.60		
	901	BMJ			SAFETY MEETING		MEN	3		\$52.60		
	901	BMJ			DRUG TEST		MEN	1		\$52.60		
	901	CAJ			ADMINISTRATIVE TIME		MEN	2		\$32.26		
	901	CAJ			SAFETY MEETING		MEN	3		\$32.26		
	901	CAJ			DRUG TEST		MEN	1		\$32.26		
	901	ELJ			ADMINISTRATIVE TIME		MEN	2		\$39.71		
	901	ELJ			SAFETY MEETING		MEN	3		\$39.71		
	901	ELJ			DRUG TEST		MEN	1		\$39.71		
	901	IWJ			ADMINISTRATIVE TIME		MEN	2		\$37.63		
	901	IWJ			SAFETY MEETING		MEN	3		\$37.63		
	901	IWJ			DRUG TEST		MEN	1		\$37.63		
	901	LBJ			ADMINISTRATIVE TIME		MEN	2		\$24.40		
	901	LBJ			SAFETY MEETING		MEN	3		\$24.40		
	901	LBJ			DRUG TEST		MEN	1		\$24.40		
	901	OEA			ADMINISTRATIVE TIME		MEN	2		\$36.21		
	901	OEA			SAFETY MEETING		MEN	3		\$36.21		
	901	OEA			DRUG TEST		MEN	1		\$36.21		
	901	PAJ			ADMINISTRATIVE TIME		MEN	2		\$28.98		
	901	PAJ			SAFETY MEETING		MEN	3		\$28.98		
	901	PAJ			DRUG TEST		MEN	1		\$28.98		
	901	MWJ			ADMINISTRATIVE TIME		MEN	2		\$36.24		
	901	MWJ			SAFETY MEETING		MEN	3		\$36.24		
	901	MWJ			DRUG TEST		MEN	1		\$36.24		
	901	PFJ			ADMINISTRATIVE TIME		MEN	2		\$39.89		
	901	PFJ			SAFETY MEETING		MEN	3		\$39.89		
	901	PFJ			DRUG TEST		MEN	1		\$39.89		
	901	SMJ			ADMINISTRATIVE TIME		MEN	2		\$40.98		
	901	SMJ			SAFETY MEETING		MEN	3		\$40.98		
	901	SMJ			DRUG TEST		MEN	1		\$40.98		
	901	TMW			ADMINISTRATIVE TIME		MEN	2		\$28.38		
	901	TMW			SAFETY MEETING		MEN	3		\$28.38		
	901	TMW			DRUG TEST		MEN	1		\$28.38		
ADD ABOVE THIS LINE IF NECESSARY						CONSTR FAC & MOB						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :						
MISCELLANEOUS CONSTRUCTION FACILITIES												
ADD ABOVE THIS LINE IF NECESSARY						MISC. CONSTR FAC						
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :						
TOTAL SUPPORT CRAFT LABOR						8600		\$273,480		13.64%		
TOTAL DIRECT CRAFT LABOR						44498		\$1,732,138		86.36%		
LABOR SUMMARY						53098		\$2,005,618				
GRAND TOTAL CRAFT LABOR												
SUBCONTRACTS - HED												

1	A	B	C	D	E	F	G	H	I	J	L	M	N
2	MAT.	CODE	CODE	ACT	CODE		UNIT	MAN	WAGE		TOTAL	MATERIAL	TOTAL
3	CODE	WORKORDER		SCH	CRFI	DESCRIPTION	QTY	UNIT	HOURS	RATE	LABOR		MATERIAL
398			HED	HED	HCOST	RUBBER TIRE BACKHOE	172	1ST	N/A	120	\$20,640		
399			HED	HED	HCOST	PORTALET (3 EA)	10	MO	N/A	300	\$3,000		
400			HED	HED	HCOST	FOREMAN TRUCK (2 EA)	43	WK	N/A	160	\$6,880		
401			HED	HED	HCOST	WATER TRUCK	172	1ST	N/A	130	\$22,360		
402			HED	HED	HCOST	WATER TRUCK	172	1ST	N/A	130	\$22,360		
403			HED	HED	HCOST	MULE	172	1ST	N/A	28	\$4,816		
404			HED	HED	HCOST	MULE	172	1ST	N/A	28	\$4,816		
405			HED	HED	HCOST	789 - BACKDUMP	50	1ST	N/A	300	\$15,000		
406			HED	HED	HCOST	770 - BACKDUMP	50	1ST	N/A	300	\$15,000		
407			HED	HED	HCOST	FUEL TRUCK	172	1ST	N/A	33	\$5,676		
408			HED	HED	HCOST	MECHANICS TRUCK	172	WK	N/A	200	\$34,400		
422						TOTAL - HEAVY EQUIPMENT					\$1,255,321		
423													
821													
823						ADD ABOVE THIS LINE IF NECESSARY							
824						DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE							
825						TOTAL - TAGGED TOOLS							
826	END	END	END	END	END	END	END	END	END	END	END	END	END

Staff

INGSTON		****SUMMARY****		RUN DATE:		19-Apr-06						
YPSUM POND CONSTRUCTION (PHASE 1)		TRAVEL & LIVING EXPENSES (Relocation, Per Diem, Expenses, Month)										
TOTAL STAFF DOLLARS				\$55,728								
TOTAL STAFF MANHOURS				\$235,640								
				5160								
TAFFING	RATE	RELOCATE/ PER DIEM EXPENSES	MONTHLY TRIPS HOME	OUTAGE DOLLARS	NON-OUTAGE DOLLARS	TOTAL STAFF DOLLARS	PRE-OUTAGE		OUTAGE		POST-OUT	
							DUR (WKS)	DUR (WKS)	DUR (WKS)	DUR (WKS)	DUR (WKS)	MANHO
ITE MANGER	\$67.65	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
ENERAL SUPT.	\$63.90	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
ILER SUPT	\$49.90	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
LECT SUPT	\$49.90	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
IECHANICAL SUPT	\$49.90	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
IVIL SUPT	\$46.00	\$37,152	\$0	\$0	\$158,240	\$158,240	86	86	86	3440	3440	0
QUIPMENT MECHANIC	\$45.00	\$18,576	\$0	\$0	\$77,400	\$77,400	43	43	43	1720	1720	0
OST SPECIALIST	\$37.72	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
STIMATING MGR	\$55.65	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
IELD TECH SPECLST	\$48.73	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
IELD ADMIN MGR.	\$32.65	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
VSULATION SERV MGR.	\$51.94	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
EAD FIELD ADMIN MGR	\$44.15	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
ATERIAL COORD.	\$22.26	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
AYROLL/TIMEKEEPER	\$22.08	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
IA/QC INSPECTOR	\$44.52	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
AFETY COORDINATOR	\$40.73	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
AFETY SUPERVISOR	\$48.23	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
SCHEDULE ANALYST	\$50.45	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
SCHEDULELER	\$41.55	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
SECRETARY	\$25.00	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
ITE PROJ CTRL MGR	\$51.65	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
TECH SUPPORT	\$26.09	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
TIMEKEEPER	\$16.32	\$0	\$0	\$0	\$0	\$0	40	40	40	0	0	0
TOTALS		\$55,728	\$0	\$0	\$235,640	\$235,640	5160	5160	5160	0	0	0

**GYPSUM POND CONSTRUCTION (PHASE 1)
KINGSTON
PHASE 1**

0
0

CRAFT	Pre-outage				Outage			P Post Outage			
ASBESTOS WORKER	ABJ	0	0	0	0	0	0	0	0	0	0
BRICKLAYER	BLJ	0	0	0	0	0	0	0	0	0	0
BOILERMAKER GENERAL FOREMAN	BMG				0			0			0
BOILERMAKER FOREMAN	BMF				0			0			0
BOILERMAKER	BMJ	0	0	0	0	0	0	0	0	0	0
CONCRETE MASON	CMJ	0	0	0	0	0	0	0	0	0	0
CARPENTER FOREMAN	CAF				0			0			0
CARPENTERS	CAJ	0	0	0	0	0	0	0	0	0	0
ELECTRICAL GENERAL FOREMAN	ELG				0			0			0
ELECTRICAL FOREMAN	ELF				0			0			0
ELECTRICAL	ELJ	0	0	0	0	0	0	0	0	0	0
INSULATOR GENERAL FOREMAN	AWG				0			0			0
INSULATOR FOREMAN	AWF				0			0			0
INSULATOR	AWJ	0	0	0	0	0	0	0	0	0	0
IRONWORKER FOREMAN	IWF				0			0			0
IRONWORKER	IWJ	0	0	0	0	0	0	0	0	0	0
MILLWRIGHT FOREMAN	MWF				0			0			0
MILLWRIGHT	MWJ	0	0	0	0	0	0	0	0	0	0
LABOR FOREMAN	LBF				1087			0			1086.758
LABOR	LBJ	3896.3	5160	0	9056.3	0	0	0	0	0	9056.32
OPERATOR	OEA	40342	1720	0	42062	0	0	0	0	0	42062.4
PAINT FOREMAN	PAF				0			0			0
PAINTER	PAJ	0	0	0	0	0	0	0	0	0	0
PIPEFITTER GENERAL FOREMAN	PFG				0			0			0
PIPE FOREMAN	PFF				0			0			0
PIPEFITTER	PFJ	0	0	0	0	0	0	0	0	0	0
SHEETMETAL FOREMAN	SMF				0			0			0
SHEETMETAL	SMJ	0	0	0	0	0	0	0	0	0	0
TRUCK DRIVER	TM3	160	1720	0	1880	0	0	0	0	0	1880
TEAMISTER	TMW	98.82	0	0	98.82	0	0	0	0	0	98.82
TOTAL		44498	8600	0	1087	0	0	0	0	0	54184

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06047R3 ~~ELT~~ Option: 0 PCN Number: KIF450
 Plant: KIF Revision: 3 Estimate Type: Preliminary
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 20%
 Requesting Engr: S. M. Haber Phase: 2 Estimate Issue Date 04/18/2006

	<u>Hours</u>	<u>Dollars</u>
<u>Phase I</u>		
Engineering		\$0
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$0</u>
<u>Phase II</u>		
Engineering		\$330,288
Long Lead Procurement		\$72,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$402,288</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$987,869
Labor (T&L)	91,272.01	\$3,495,526
Labor (Non-Manual)	5,542.96	\$254,790
Equipment		\$1,302,756
Subcontracts		\$285,600
Partner Fee		\$5,486
Partner Insurance		\$3,291
Escalation		\$509,145
Construction Risk Dollars		\$0
Other		\$519,216
Total Construction Cost		\$7,363,679
Engineering		\$209,850
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$0
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$7,573,529</u>
<u>All Phases</u>		
Construction Partner	96,814.97	\$7,363,679
Long Lead Procurement		\$72,000
Engineering		\$540,138
Other / Other Organizations		\$0
Total Risk Dollars		\$0
<u>Total Project Costs</u>	<u>96,814.97</u>	<u>\$7,975,817</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

Spreadsheet Report
KIF06047R3/STG 1 GYP PND

KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE

Project name KIF06047R3/STG 1 GYP PND
 Estimator C. L. Toney
 Labor rate table KIF 40 2005
 Equipment rate table TVA Equipment
 Project Earthwork
 Plant KIF
 Estimate # 06047R3
 PCN # KIF450
 Requesting Engr S. M. Haber
 Option 0
 Revision 0
 Phase 2
 Estimate Type Preliminary
 Estimate Accuracy +/- 20%
 Est. Issue Date 04/18/2006
 Funding Type Capital

Notes
 Cost estimate is based in 2006 dollars.
 Revision 3 cost estimate has been revised based on revised estimate provided by HED on 4-17-06.
 Revision 2 cost estimate has been revised based on revised estimate provided by HED. Also, contingency for this estimate has been removed.
 Revision 1 cost estimate has been revised based on information from Lynn Peaty based on revised design & quantities provided by GeoSyntec Consultants.
 Short Term Storage. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.
 Report format Sorted by Location/Activity
 Detail summary

Spreadsheet Report
KIF/06047R3/STG 1 GYP PND

Inmate Company

Location	Activity	Description	Material Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount		
IASE 3 (BOP)	17-Pumps & Pipe	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	84.000	84.00 mh	2,957	60,000	-	308	-	63,244.70	63,245		
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,250.00 cy	0.500	652.00 mh	16,311	-	-	8,150	-	-	24,461	24,461	
		Bonum Ash Pipe Bedding	112.00 cy	0.500	56.00 mh	1,514	-	-	574	-	-	2,088	2,088	
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.40 mh	19,976	-	92,484	-	9,080	-	60,771	121,539	
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00 cy	0.320	964.48 mh	24,128	-	-	-	23,998	-	15,771	47,527	
		Platforms Steel	5.00 ton	60.000	300.00 mh	10,087	-	26,250	-	2,376	-	7,742.43	35,712	
		17-Pumps & Pipe				2,706.88 hrs	74,953	178,734	-	43,885	-	-	297,572	
		18-Electrical				120.00 mh	4,198	12,000	-	450	-	-	16,643	
		Phase 1 Transformer 200 kva (13.8 kv to 480 v)	1.00 ls	8.100	20.00 mh	708	-	2,200	-	14.54	-	-	2,908	
		4/0 600 Volt Cable	200.00 lf	0.619	123.80 mh	4,363	-	8,140	-	62.62	-	12,523	12,523	
		3" Diameter GRC Conduit	200.00 lf	1.000	12.00 mh	435	-	1,500	-	-	-	1,924.86	1,925	
		13 kv Amp Pole Mount Fuse Disconnect	1.00 ea	12.000	275.90 hrs	9,709	-	23,940	-	450	-	-	33,999	
		18-Electrical				1.00 ls	207.893	5,900	-	3,100	-	-	9,000.00	9,000
		XConst Facilities				207.893	207.89 hrs	5,900	-	3,100	-	-	9,000.00	9,000
		IASE 3 (HED)	HED Installation	Phase 3 Non Manual	1.00 ls	383.000	383.00 mh	19,150	-	-	-	-	18,150.00	18,150
zNon-Manual					383.00 hrs	19,150	-	-	-	-	-	18,150.00	18,150	
PHASE 3 (BOP)					3,573.57 hrs	109,712	-	202,574	-	47,435	-	-	359,722	
Construction Labor	1.00 ls			88,081.434	88,081.43 mh	3,404,964	-	-	-	-	-	3,404,964.00	3,404,964	
Non Manual Labor	1.00 ls			5,159.962	5,159.96 mh	235,640	-	-	-	-	-	235,640.00	235,640	
TVA-HED Subcontracts	1.00 ls			-	-	-	-	285,600	-	-	-	285,600.00	285,600	
Partner Purchased Material	1.00 ls			-	-	-	-	-	285,600	-	-	285,600.00	285,600	
Construction Heavy Equipment	1.00 ls			-	-	-	-	-	-	-	-	867,295.00	867,295	
Small Tools	1.00 ls			-	-	-	-	-	-	-	-	1,255,321.00	1,255,321	
Supplies, Consumables & Expendable Tools	1.00 ls			-	-	-	-	-	-	-	8,809	8,809.00	8,809	
TVA-HED - Central Command	1.00 ls			-	-	-	-	-	-	-	26,424	26,424.00	26,424	
HED Installation						93,241.40 hrs	3,640,604	857,295	285,600	285,600	1,255,321	478,350	6,552,403	
PHASE 3 (HED)						93,241.40 hrs	3,640,604	857,295	285,600	285,600	1,255,321	478,350	6,552,403	

Estimate Totals			Cost Basis		
Description	Amount	Hours	Rate	Rate	Cost Basis
Labor	3,750,316	96,814,969 hrs			
Material	1,059,869				
Subcontract	285,600				
Equipment	1,302,756	1,970,471 hrs			
Other	513,583				
Engineered Materials - Ph 2	6,912,124	6,912,124	100.000 %		C
Adjustment - Enor Materials	(72,000)		(100.000) %		C
Small Tools Expense (BOP)	1,436		0.016 \$/hr		H
Consum & Exoendables (BOP)	3,622		0.104 %		C
Office Supplies & Exp (BOP)	575		0.226 %		C
Escalation - Craft Labor	5,633	6,917.757	9.700 %		C
Escalation - Subcontract	339,066		6.800 %		C
Escalation - Perm Materials	19,421		3.800 %		C
Escalation - HED/Equipment	40,275		6.000 %		C
Escalation - Small Tools	75,319		0.034 \$/hr		H
Escalation - Consumables	3,103		0.200 %		C
Escalation - Non-Manual Labor	6,991		9.600 %		C
Escalation - Office Supplies	24,460		0.200 %		C
Partner Insurance (BOP)	509,145	7,426,902	0.068 %		C
Partner Award Fee (BOP)	3,291		0.146 %		C
FPG Proj Enar - Phase 2	5,486				
FPG Civil Enar - Phase 2	8,777	7,435,679			
GeoSvntec Enar - Phase 2	4,200				
FPG Proj Cntrl Cost - Phase 2	21,000	100,000 hrs	0.103 % @ 42.00 A		A
FPG Cost Estimating - Phase 2	302,400	500,001 hrs	0.516 % @ 42.00 A		A
FPG Enar Records - Phase 2	672	4,199,998 hrs	4.338 % @ 72.00 A		A
FPG Proj Enar - Phase 3	1,680	16,004 hrs	0.017 % @ 42.00 A		A
FPG Civil Enar - Phase 3	336	40,004 hrs	0.041 % @ 42.00 A		A
GeoSvntec Enar - Phase 3	330,288	7,997 hrs	0.008 % @ 42.00 A		A
Mac Tec QA/OC & Certif - Ph 3	3,150	75,003 hrs	0.077 % @ 42.00 A		A
Total	7,975,817	149,995 hrs	0.155 % @ 42.00 A		A
		700,001 hrs	0.723 % @ 72.00 A		A
		2,083,332 hrs	2.152 % @ 72.00 A		A
		7,975,817			

KIBAD Gypsum Disposal St 91 (06047R3)
 06047R3 CLT

HED ESTIMATE SUMMARY

REV# 3

0

LOCATION: KINGSTON
 SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 1

PRINT DATE: 17-Apr-06
 ESTIMATE DATE: 17-Mar-06

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 1)

WORKSCOPE: DEVELOP BORROW AREA, DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 1 OF GYPSUM POND.

DURATION: ***11 MONTHS FOR PHASE 1 ROAD CONSTRUCTION / POND CONSTRUCTION.*** WITH 2 WEEKS CONTINGENCY FOR WEATHER

ESTIMATE PHASE	TYPE OF FUNDING
2	CAPITAL > 100K

PREPARED BY: B. WORKMAN (HED) Comments

1. TVA-HED LABOR COSTS		Comments
Craft Augmented Labor	MANHOURS	88081 <i>389,657.10</i> Includes all aspects of Phase 1 work.
	COST	\$3,404,964 Based on FY 2005 labor rates.
Non-Manual Labor	MANHOURS	5,160 <i>45,666.67</i> Supervisor and (2) Mechanics full time.
	COST	\$285,640 Includes Hourly Rates & Per Diem for both men.
Contingency 0.00%	MANHOURS	0
	COST	\$0
SUBTOTAL TVA-HED LABOR	MANHOURS	93,241
	COST	\$3,640,604

2. TVA-HED OTHER COSTS		Comments
TVA-HED Subcontracts	\$285,600	Survey / Layout / Fence Cont./ Compac. Testing
TVA-HED Subcontract Fee	\$0	
Travel & Living Expenses	See "Non-Manual Labor"	
TVA-HED Material Purchases	\$0	
HED Other Costs	\$0	
Contingency 0%	\$0	
SUBTOTAL TVA-HED OTHER	\$285,600	
TOTAL TVA-HED COSTS	\$3,926,204	

3. ITEMS MANAGED BY TVA-HED		Comments
Permanent Materials	\$857,295	Per Quantities Provided by Parsons E & C.
Heavy Equipment	\$1,255,321	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment	\$0	
Small Tools	\$8,808	
Supplies, Consumables & Expendable Tools	\$26,424	
Office Supplies & Expenses	\$0	
Other TVA-HED Costs	\$0	
TVA subcontracts (By Others)	\$0	
Partner or OCIP Insurance	\$0	
TVA-HED - Overhead 10.00%	\$478,350	
Contingency 0%	\$0	
SUBTOTAL TVA-HED MANAGED	\$2,626,198	
TOTAL TVA-HED COSTS	\$6,552,403	

APPROVALS: ESTIMATE TOTAL 6,552,403

TVA-HED Estimator	Date:
TVA - Project Manager	Date:
TVA - Project Engineer	Date:
TVA - Site Environmental Engineer	Date:

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 1 Gypsum Disposal Facility Pond Construction
Revision #03

04/17/06

Mr. Calvin Toney,

We thank you for the opportunity to provide this estimate for the TVA - Kingston (Phase 1) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings @50% Design.

The TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 10,400 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Construct construction parking area.
- Cut approximately 88,500 CY of clay for storm-water runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Install 12 lf of 72” Outlet Structure.
- Install 14 lf of 48” riser.
- Install 150 lf of 48” principle spillway.
- Pour concrete “anti-seep” collars at all joints.
- Allowance - Clean out Gypsum Stack storm-water runoff pond as needed. (approximately 1,000 cy)
- Clear and Grub approximately 30 acres at Gypsum Stack Peninsula. (Includes clear cut logging as well with clearing support by HED).
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Borrow Area Development”:

- Clear and Grub approximately 34 acres at borrow site.
- Clear cut all timber on approximately 34 acres for clay borrow site.
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Haul / Access Roads”:

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 1.5 miles of roadway.
- Build Gypsum Disposal Facility Access Roadways with 2,200 TN of new stone.
- Build Gypsum Disposal Facility Access Roadways with 2,760 CY of Bottom Ash.

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

- Install Fence and gates at road. (200 lf w/ 1 personnel and 1 swing gate.)

“Disposal Facility Construction”:

- Proof-roll all Gypsum Stack sub-grade. (52 acres)
- Install geologic buffer. Over-excavate 3’ depth in Gypsum Stack liner area (approximately 52 acres), then re-place and re-compact liner material. (272,596 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 431,918 cy)
- Install centerline underdrain piping inside new Gypsum Stack (10,360 lf).
- Install 63,600 sy of non-woven geotextile fabric in new centerline underdrain.
- Install 37,900 tn of 36” deep crushed stone in new centerline underdrain.
- Install Perimeter road with 6” of Bottom Ash topped with 4” of crushed stone. (1 mile of 20’ wide roadway)
- Install 48” RCP Phase 2 Discharge Pipe. (1,726 lf)
- Install drainage pipe from sump to stormwater pond. (580 lf)
- Install 48” RCP diversion pipes beneath stormwater pond. (1,830 lf)
- Install perimeter road bottom ash. (3,700 cy)
- Install perimeter road crushed stone. (3,100 tn)

“Clarifications to Estimated Scope of Work”:

- No “rock removal / excavation” costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.
- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All “Bank Cubic Yard” quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes 2 weeks contingency for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for Fence Contractor, TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed, Geotechnical Engineers to provide compaction test results as required, and mulching of tree stumps, laps, etc. after clearing of trees is completed.
- Seed and Mulch all disturbed areas outside dikes. (approximately 25 acres) is included.

“Schedule”:

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 11 months from start of project as

TVA – HEAVY EQUIPMENT DIVISION
 933 OLD FERRY ROAD
 SPRING CITY, TENNESSEE 37381
 PH: (423) 365-8739 FAX: (423) 365-8705

stated on "Estimate Summary" sheet provided with this estimate.

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$6,552,403.00 Lump Sum

Thank You,
Brad Workman
TVA - HED
(931) 320-1044

cc: Larry Radford
TVA - HED

Kenny Lowery
TVA - HED

TVA - HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029116

A	B	C	D	E	F	G	H	I	J	K	L	M	N	
1					CRAFT LABO			MATERIAL		TOTAL		TOTAL		
2	MAT.	CODE	CODE	ACT	CODE	UNIT	MAN	WAGE	TOTAL			TOTAL		
3	CODE	WORK ORDER	SCN	CRAFT	DESCRIPTION	QTY	UNIT	HR	RATE	LABOR			MATERIAL	
116	ADD ABOVE THIS LINE IF NECESSARY					OUTAGE DIRECT								
117	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :								
118	POST OUTAGE - DIRECT CRAFT													
119	GYPSUM POND CONSTRUCTION (PHASE 1)													
120	ADD ABOVE THIS LINE IF NECESSARY					POST OUTAGE DIRECT								
121	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :								
122	TOTALS - DIRECT CRAFT													
123							79481			\$3,131,484				
124	SUPPORT CRAFT													
125	(QTY & UNITS MUST BE INCLUDED FOR EA. LINE ITEM)													
126	PRE-OUTAGE - SUPPORT CRAFT													
127	GENERAL FOREMAN / SUPPORT CRAFT (1 YR)													
128		942		OE	OPERATOR FOREMAN	1	MEN	1720	\$46.00			\$79,120		
129		942		LB	LABORER FOREMAN	1	MEN	1720	\$29.00			\$49,880		
130		902		TM	TEAMSTER TO WATER ROADS / SUPPORT MANPOWER	1	MEN	1720	\$32.00			\$55,040		
131		902		LB	LABORER GENERAL SUPPORT / OFFICE	2	MEN	3440	\$26.00			\$89,440		
132	ADD ABOVE THIS LINE IF NECESSARY					PRE-OUTAGE SUPPORT								
133	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :			8600		\$273,480			
134	OUTAGE - SUPPORT CRAFT													
135	ADD ABOVE THIS LINE IF NECESSARY					OUTAGE SUPPORT								
136	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :								
137	POST-OUTAGE - SUPPORT CRAFT													
138	ADD ABOVE THIS LINE IF NECESSARY					SUBTOTALS :								
139	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :								
140	MOBILIZATION OF CRAFT													
141		901		AW	ADMINISTRATIVE TIME		MEN	2		\$33.79				
142		901		AW	SAFETY MEETING		MEN	3		\$33.79				
143		901		AW	DRUG TEST		MEN	1		\$33.79				
144		901		AB	ADMINISTRATIVE TIME		MEN	2		\$27.44				
145		901		AB	SAFETY MEETING		MEN	3		\$27.44				
146		901		AB	DRUG TEST		MEN	1		\$27.44				
147		901		BM	ADMINISTRATIVE TIME		MEN	2		\$52.60				
148		901		BM	SAFETY MEETING		MEN	3		\$52.60				
149		901		BM	DRUG TEST		MEN	1		\$52.60				
150		901		CA	ADMINISTRATIVE TIME		MEN	2		\$32.26				
151		901		CA	SAFETY MEETING		MEN	3		\$32.26				
152		901		CA	DRUG TEST		MEN	1		\$32.26				
153		901		EL	ADMINISTRATIVE TIME		MEN	2		\$39.71				
154		901		EL	SAFETY MEETING		MEN	3		\$39.71				
155		901		EL	DRUG TEST		MEN	1		\$39.71				
156		901		IW	ADMINISTRATIVE TIME		MEN	2		\$37.63				
157		901		IW	SAFETY MEETING		MEN	3		\$37.63				
158		901		IW	DRUG TEST		MEN	1		\$37.63				
159		901		LB	ADMINISTRATIVE TIME		MEN	2		\$24.40				
160		901		LB	SAFETY MEETING		MEN	3		\$24.40				
161		901		LB	DRUG TEST		MEN	1		\$24.40				
162		901		OE	ADMINISTRATIVE TIME		MEN	2		\$36.21				
163		901		OE	SAFETY MEETING		MEN	3		\$36.21				
164		901		OE	DRUG TEST		MEN	1		\$36.21				
165		901		PA	ADMINISTRATIVE TIME		MEN	2		\$28.98				
166		901		PA	SAFETY MEETING		MEN	3		\$28.98				
167		901		PA	DRUG TEST		MEN	1		\$28.98				
168		901		MW	ADMINISTRATIVE TIME		MEN	2		\$36.24				
169		901		MW	SAFETY MEETING		MEN	3		\$36.24				
170		901		MW	DRUG TEST		MEN	1		\$36.24				
171		901		PF	ADMINISTRATIVE TIME		MEN	2		\$39.89				
172		901		PF	SAFETY MEETING		MEN	3		\$39.89				
173		901		PF	DRUG TEST		MEN	1		\$39.89				
174		901		SM	ADMINISTRATIVE TIME		MEN	2		\$40.98				
175		901		SM	SAFETY MEETING		MEN	3		\$40.98				
176		901		SM	DRUG TEST		MEN	1		\$40.98				
177		901		TM	ADMINISTRATIVE TIME		MEN	2		\$28.38				
178		901		TM	SAFETY MEETING		MEN	3		\$28.38				
179		901		TM	DRUG TEST		MEN	1		\$28.38				
180	ADD ABOVE THIS LINE IF NECESSARY					CONSTR FAC & MOB								
181	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :								
182	MISCELLANEOUS CONSTRUCTION FACILITIES													
183	ADD ABOVE THIS LINE IF NECESSARY					MISC. CONSTR FAC								
184	DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE					SUBTOTALS :								
185	LABOR SUMMARY						8600			\$273,480			8.03%	
186							79481			\$3,131,484			91.97%	
187	GRAND TOTAL CRAFT LABOR						88081			\$3,404,964				
188	SUBCONTRACTS - HED													

A	B	C	D	E	F	G	H	I	J	L	M	N	
1	2	3	4	5	6	7	8	9	10	11	12	13	
MAT. CODE	CODE	CODE	ACT. CODE	CODE	DESCRIPTION	QTY.	UNIT	UNIT	MAN. HOURS	WAGE RATE	TOTAL LABOR	TOTAL MATERIAL	
CODE	WORK ORDER	SCH.	CRET										
		HED	HED	HCOST	RUBBER TIRE BACKHOE	172	1ST	N/A	120		\$20,640		
399		HED	HED	HCOST	PORTALET (3 EA)	10	MO	N/A	300		\$3,000		
400		HED	HED	HCOST	FOREMAN TRUCK (2 EA)	43	WK	N/A	160		\$6,880		
401		HED	HED	HCOST	WATER TRUCK	172	1ST	N/A	130		\$22,360		
402		HED	HED	HCOST	WATER TRUCK	172	1ST	N/A	130		\$22,360		
403		HED	HED	HCOST	MULE	172	1ST	N/A	28		\$4,816		
404		HED	HED	HCOST	MULE	172	1ST	N/A	28		\$4,816		
405		HED	HED	HCOST	769 - BACKDUMP	50	1ST	N/A	300		\$15,000		
406		HED	HED	HCOST	770 - BACKDUMP	50	1ST	N/A	300		\$15,000		
407		HED	HED	HCOST	FUEL TRUCK	172	1ST	N/A	33		\$5,676		
408		HED	HED	HCOST	MECHANICS TRUCK	172	WK	N/A	200		\$34,400		
422													
423													
821													
823													
824													
825													
826													
ADD ABOVE THIS LINE IF NECESSARY													
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						TOTAL - HEAVY EQUIPMENT						\$1,255,321	
TAGGED TOOLS													
END	END	END	END	END	END	END	END	END	END	END	END	END	

GYPSUM POND CONSTRUCTION (PHASE 1)

GYPSUM POND CONSTRUCTION (PHASE 1)

KINGSTON

KINGSTON

W.O.#

0

PA #

0

#	QT	DESCRIPTION	COST	TOTAL
63600	SY	8 oz GEOTEXTILE FABRIC - NON-WOVEN	\$1.33	\$84,588.00
1000	LB	KY-31 FESCUE SEED	\$1.20	\$1,200.00
750	LB	PERINNEAL RYE GRASS SEED	\$1.45	\$1,087.50
500	LB	15-15-15 FERTILIZER	\$0.32	\$160.00
30	ROLL	CURLEX	\$48.00	\$1,440.00
20716	LF	12" HDPE UNDERDRAIN PIPING	\$4.76	\$98,608.16
580	LF	12" HDPE PIPE BENEATH STORMWATER POND (ASSUMED)	\$10.00	\$5,800.00
800	EA	STRAW BALES	\$3.90	\$3,120.00
8102	TN	6"-12" RIP RAP	\$11.50	\$93,173.00
40	TN	#57 STONE	\$10.00	\$400.00
44130	TN	CRUSHED STONE	\$10.00	\$441,300.00
3556	LF	48" RCP	\$18.90	\$67,208.40
1	LS	PIPE	\$22,000.00	\$22,000.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
30	ROLL	TYPE "C" SILT FENCE FABRIC	\$455.00	\$13,650.00
130	HUN	WIRE MESH	\$72.00	\$9,360.00
3050	EA	"T" POSTS	\$4.00	\$12,200.00
1	LS	MISC TOOLS / WIRE	\$2,000.00	\$2,000.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
				\$0.00
TOTAL				\$857,295.06

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06047R2 Option: 0 PCN Number: KIF450
 Plant: KIF Revision: 2 Estimate Type: Preliminary
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 20%
 Requesting Engr: S. M. Haber Phase: 2 Estimate Issue Date 03/23/2006

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$0
Partner (Non-Manual)		\$0
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$0</u>
<u>Phase II</u>		
Engineering		\$330,288
Long Lead Procurement		\$72,000
Partner (Non-Manual)		\$0
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$402,288</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$795,806
Labor (T&L)	62,861.57	\$2,354,566
Labor (Non-Manual)	5,542.96	\$254,790
Equipment		\$1,302,756
Subcontracts		\$285,600
Partner Fee		\$5,486
Partner Insurance		\$3,291
Escalation		\$387,925
Construction Risk Dollars		\$0
Other		\$374,549
Total Construction Cost		\$5,764,770
Engineering		\$209,850
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$0
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$5,974,619</u>
<u>All Phases</u>		
Construction Partner	68,404.53	\$5,764,770
Long Lead Procurement		\$72,000
Engineering		\$540,138
Other / Other Organizations		\$0
Total Risk Dollars		\$0
<u>Total Project Costs</u>	<u>68,404.53</u>	<u>\$6,376,908</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Project name KIF/06047R2/STG 1 GYP PND

Estimator C. L. Toney

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Project Earthwork

Plant KIF

Estimate # 06047R2

PCN # KIF450

Requesting Engr S. M. Haber

Option 0

Revision 2

Phase Preliminary

Estimate Accuracy +/- 20%

Est. Issue Date 03/23/2006

Funding Type Capital

Cost estimate is based in 2006 dollars.

Revision 2 cost estimate has been revised based on revised estimate provided by HED. Also, contingency for this estimate has been removed.

Revision 1 cost estimate has been revised based on information from Lynn Petty based on revised design & quantities provided by GeoSyntec Consultants.

Short Term Storage. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.

Sorted by Location/Activity
Detail summary

Report format

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount		
IASE 3 (BOP)	17-Pumps & Pipe	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	84.000	84.00 mh	2,897	60,000	-	308	-	63,244.70	63,245		
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,260.00 cy	0.200	652.00 mh	16,311	-	-	3,150	-	-	24,461	24,461	
		Bottom Ash Pipe Bedding	112.00 cy	0.500	56.00 mh	1,514	-	-	-	574	-	18.85	2,088	
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.00 mh	19,976	-	92,484	-	9,090	-	60.77	121,539	
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00 cy	0.325	984.48 mh	24,128	-	-	-	23,998	-	15.77	47,527	
		Platforms Steel	5.00 ton	60.000	300.00 mh	10,087	-	26,250	-	2,376	-	7,742.43	39,712	
		17-Pumps & Pipe	2,706.88 hrs	74,953	-	-	-	179,734	-	43,885	-	-	297,572	
		18-Electrical	Phase 1 Transformer 200 kva (13.8 kv to 480 v)	1.00 ls	120.000	120.00 mh	4,193	12,000	-	-	450	-	16,643.28	16,643
			4/0-600 Volt Cable	200.00 lf	0.100	20.00 mh	708	2,000	-	-	-	-	14.54	2,908
			3" Diameter GRC Conduit	200.00 lf	0.619	123.80 mh	4,383	8,140	-	-	-	-	62.82	12,523
			13 kv Amp Pole Mount Fuses Disconnect	1.00 ea	12.000	12.00 mh	425	1,500	-	-	-	-	1,924.86	1,925
			18-Electrical	275.80 hrs	9,709	23,840	-	-	-	-	450	-	-	33,995
		XConst Facilities	Mobilia, Drug Test, Miscellaneous Other, & Demobilize	1.00 ls	207.893	207.89 mh	5,900	-	-	-	3,100	-	9,000.00	9,000
			XConst Facilities	207.89 hrs	5,900	-	-	-	-	-	3,100	-	-	9,000
		zNon-Manual	Phase 3 Non Manual	1.00 ls	383.000	383.00 mh	19,150	-	-	-	-	-	19,150.00	19,150
zNon-Manual	383.00 hrs		19,150	-	-	-	-	-	-	-	-	19,150		
IASE 3 (HED)	HED Installation	PHASE 3 (BOP)	3,573.57 hrs	109,712	-	-	202,574	-	47,435	-	-	359,722		
		Construction Labor	1.00 ls	59,671.000	59,671.00 mh	2,264,004	-	-	-	-	-	2,264,004.00	2,264,004	
		Non Manual Labor	1.00 ls	5,159.962	5,159.96 mh	235,640	-	-	-	-	-	235,640.00	235,640	
		TVA-HED Subcontracts	1.00 ls	-	-	-	285,600	-	-	-	-	285,600.00	285,600	
		Partner Purchased Material	1.00 ls	-	-	-	665,232	-	-	-	-	665,232.00	665,232	
		Construction Heavy Equipment	1.00 ls	-	-	-	1,255,321	-	-	-	-	1,255,321.00	1,255,321	
		Small Tools	1.00 ls	-	-	-	5,967	-	-	-	-	5,967.00	5,967	
		Supplies, Consumables & Expendable Tools	1.00 ls	-	-	-	17,901	-	-	-	-	17,901.00	17,901	
		TVA-HED - Central Command	1.00 ls	-	-	-	345,048	-	-	-	-	345,048.00	345,048	
		HED Installation	64,830.96 hrs	2,499,644	64,830.96 hrs	-	-	665,232	285,600	1,255,321	368,916	-	3,669,916	
		PHASE 3 (HED)	64,830.96 hrs	2,499,644	64,830.96 hrs	-	-	665,232	285,600	1,255,321	368,916	-	3,669,916	

Estimate Totals

Description	Amount	Totals	Hours	Rate	Cost Basis
Labor	2,609,356		68,404,535 hrs		
Material	867,806				
Subcontract	285,600				
Equipment	1,302,756		1,970,471 hrs		
Other	368,916				
Engineered Materials - Ph 2	5,434,434	5,434,434			
Adjustment - Enar Materials	72,000				
	(72,000)				
		5,434,434			
Small Tools Exoense (BOP)	1,436			0.023 \$/hr	C
Consum & Exoendables (BOP)	3,622			0.154 %	C
Office Supplies & Exp (BOP)	575			0.226 %	C
	5,633	5,440,067			
Escalation - Craft Labor	228,393			9.700 %	C
Escalation - Subcontract	19,421			6.800 %	C
Escalation - Perm Materials	32,977			3.800 %	C
Escalation - HED Equipment	75,319			6.000 %	C
Escalation - Small Tools	2,137			0.034 \$/hr	H
Escalation - Consumables	4,709			0.200 %	C
Escalation - Non-Manual Labor	24,460			9.600 %	C
Escalation - Office Supplies	510			0.200 %	C
	387,926	5,827,993			
Partner Insurance (BOP)	3,291			0.126 %	C
Partner Award Fee (BOP)	5,486			0.210 %	C
	8,777	5,836,770			
FPG Pro Enar - Phase 2	4,200		100,001 hrs	0.146 % @ 42.00 A	A
FPG Civil Enar - Phase 2	21,000		500,003 hrs	0.731 % @ 42.00 A	A
GeoSvntec Enar - Phase 2	302,400		4,199,997 hrs	6.140 % @ 72.00 A	A
FPG Pro Cntrl Cost - Phase 2	672		16,000 hrs	0.023 % @ 42.00 A	A
FPG Cost Estimativa - Phase 2	1,680		40,003 hrs	0.058 % @ 42.00 A	A
FPG Enar Records - Phase 2	336		8,003 hrs	0.012 % @ 42.00 A	A
	330,288	6,167,058			
FPG Pro Enar - Phase 3	3,150		74,999 hrs	0.110 % @ 42.00 A	A
FPG Civil Enar - Phase 3	6,300		149,997 hrs	0.219 % @ 42.00 A	A
GeoSvntec Enar - Phase 3	50,400		699,997 hrs	1.023 % @ 72.00 A	A
Mac Tec QA/QC & Certf - Ph 3	150,000		2,083,335 hrs	3.046 % @ 72.00 A	A
	209,850	6,376,908			
Total		6,376,908			

06047R2 cym 06047R1

Toney, Calvin L.

From: Workman, Brad
Sent: Monday, March 20, 2006 9:19 AM
To: Toney, Calvin L.
Cc: Radford, Larry D.; Stewart, David W.; Lowery, Kenny R.; Jones, Sonja R.; Pentecost, Tina S.; Nathan, Larry B.; Baugh, James S.
Subject: HED - Kingston Gypsum Pond Construction Estimate - Rev02
Importance: High

Calvin,

I have attached the revised Kingston - Gypsum Pond (Phase 1) Construction estimate. You will still need to escalate from 2005 wage rates to forecasted year of construction. I am still working on the Phase 2 number. Please review and comment.

2008 #'s

Thank you,
Brad Workman
TVA - HED
(931) 320-1044

KIFASU GYPSUM DISPOSAL STG 1 (06047R2)

6047
6048

06047R2

HED ESTIMATE SUMMARY

REV #

2

0

LOCATION: KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 1

PRINT DATE: 20-Mar-06
ESTIMATE DATE: 17-Mar-06

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 1)

WORKSCOPE: DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL
ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 1 OF GYPSUM POND.

DURATION: ***10 MONTHS FOR PHASE 1 ROAD CONSTRUCTION / POND CONSTRUCTION.***

ESTIMATE PHASE		TYPE OF FUNDING	
2		CAPITAL > 100K	

PREPARED BY: B. WORKMAN (HED)

			Comments
1. TVA-HED LABOR COSTS			
Craft Augmented Labor	MANHOURS	59671	Includes all aspects of Phase 1 work. Based on FY 2005 labor rates.
	COST	\$2,264,004	
Non-Manual Labor	MANHOURS	5,160	Supervisor and (2) Mechanics full time. Includes Hourly Rates & Per Diem for both men.
	COST	\$235,640	
Contingency 0.00%	MANHOURS	0	
	COST	\$0	
SUBTOTAL TVA-HED LABOR		MANHOURS 64,831	
		COST \$2,499,644	
2. TVA-HED OTHER COSTS			
TVA-HED Subcontracts		\$285,600	Survey / Layout / Fence Cont./ Compac. Testing
TVA-HED Subcontract Fee		\$0	
Travel & Living Expenses		See "Non-Manual Labor"	
TVA-HED Material Purchases		\$0	
HED Other Costs		\$0	
Contingency 0%		\$0	
SUBTOTAL TVA-HED OTHER		\$285,600	
TOTAL TVA-HED COSTS		\$2,785,244	
3. ITEMS MANAGED BY TVA-HED			
Permanent Materials		\$665,232	Per Quantities Provided by Parsons E & C.
Heavy Equipment		\$1,255,321	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment		\$0	
Small Tools		\$5,967	
Supplies, Consumables & Expendable Tools		\$17,901	
Office Supplies & Expenses		\$0	
Other TVA-HED Costs		\$0	
TVA subcontracts (By Others)		\$0	
Partner or OCIP Insurance		\$0	
TVA-HED - Overhead	10.00%	\$345,048	
Contingency 0%		\$0	
SUBTOTAL TVA-HED MANAGED		\$2,289,469	
TOTAL TVA-HED COSTS		\$5,074,713	

APPROVALS: ESTIMATE TOTAL 5,074,713

ESC TO 2008 DOLLARS

TVA-HED Estimator

TVA - Project Manager

TVA - Project Engineer

TVA - Site Environmental Engineer

Date:

Date:

Date:

Date:

PCN Number: PCN Description: KIF - Gypsum Disposal Area - Peninsula - Stage 1
 Current Phase: 1 Phase Request: 2 Date: 11/17/2005

	Phase I		Phase II		Phase III		Prin/RE/Engr
	Hours	\$	Hours	\$	Hours	\$	
Project Engr		\$0	100	\$4,200	75	\$3,150	
Mech Engr		\$0		\$0		\$0	
Elec Engr I		\$0		\$0		\$0	
Elec Engr II		\$0		\$0		\$0	
Civil Engr		\$0	500	\$21,000	150	\$6,300	
Air, Gas, Wtr, Yard Systems		\$0		\$0		\$0	
Comb Proc, Wtr Treatment		\$0		\$0		\$0	
Steam Cycle Systems		\$0		\$0		\$0	
Other Systems Engr (specify)		\$0		\$0		\$0	
Non-TVA Engr		\$0	4200	\$302,400	700	\$50,400	
Other Orgs (specify) (MacTec QA/QC & certification)		\$0		\$0		\$150,000	
Project Controls Scheduling		\$0		\$0		\$0	
Project Controls Cost		\$0	16	\$672		\$0	
Cost Estimating		\$0	40	\$1,680		\$0	
Engr Records			8	\$336		\$0	
CAD Dwg Support-Enter # Dwgs:						\$0	
Sub Totals:	0	\$0	4864	\$330,288	925	\$ 209,850	
Project Totals:	5,789	Hours	\$540,138	Dollars			

Long Lead Material - Dollars

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 1 Gypsum Disposal Facility Pond Construction
Revision #02

03/17/06

Mr. Calvin Toney,

We thank you for the opportunity to provide the following estimate for the TVA - Kingston (Phase 1) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings, as well as meetings with TVA Project Managers and TVA Engineering.

The understood TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 7,150 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Construct construction parking area.
- Cut approximately 43,223 CY of clay for stormwater runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Install 12 lf of 72” Outlet Structure.
- Install 14 lf of 48” riser.
- Install 150 lf of 48” principle spillway.
- Pour concrete “anti-seep” collars at all joints.
- Allowance - Clean out Gypsum Stack stormwater runoff pond as needed. (approximately 1,000 cy)

“Haul / Access Roads”:

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 1.5 miles of roadway.
- Build Gypsum Disposal Facility Access Roadways with 2,200 TN of new stone.
- Build Gypsum Disposal Facility Access Roadways with 1,956 CY of Bottom Ash.
- Install Fence and gates at road. (200 lf w/ 1 personnel and 1 swing gate.)

“Disposal Facility Construction”:

- Proof-roll all Gypsum Stack sub-grade. (50 acres)
- Over-excavate 3’ depth in Gypsum Stack liner area (approximately 50 acres), then re-place and re-compact liner material. (211,362 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 337,228 cy)

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029133

- Install centerline underdrain piping inside new Gypsum Stack.
- Install 58,282 sy of non-woven geotextile fabric in new centerline underdrain.
- Excavate and install 4,000 lf total of 8" HDPE underdrain piping around perimeter of Stack.
- Install 14,260 tn of 12" deep crushed stone in new centerline underdrain.
- Install Perimeter road with 6" of Bottom Ash topped with 4" of crushed stone. (1 mile of 20' wide roadway)
- Install rip-rap diversion ditch (approximately 12,000 tn).

“Clarifications to Estimated Scope of Work”:

- Allowance Included – 15% Double handling of liner material foreseen as risk due to unsuitable soil for liner construction encountered during over-excavation. This cost is included in estimate.
- No “rock removal / excavation” costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.
- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All “Bank Cubic Yard” quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes contingencies for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for Fence Contractor, TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed and Geotechnical Engineers to provide compaction test results as required.
- Seed and Mulch all disturbed areas outside dikes. (approximately 16 acres) is included.
- If and when proof-roll tests fail, we will over-excavate on a T&M basis above this estimated cost to get sub-grade back to passing proof-roll status.

“Schedule”:

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 10 months from start of project as stated on “Estimate Summary” sheet provided with this estimate.

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$5,074,713.00 Lump Sum

Thank You,
Brad Workman
TVA HED
(931) 320-1044

cc: Kenny Lowery
TVA - HED
(256) 762-6401

TVA - HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029135

HED ESTIMATE SUMMARY

HED ESTIMATE SUMMARY
REV # 2

0

LOCATION: -KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 1

PRINT DATE: 22-Mar-06
ESTIMATE DATE: 17-Mar-06

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 1)

WORKSCOPE: DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL
ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 1 OF GYPSUM POND.

DURATION: ***10 MONTHS FOR PHASE 1 ROAD CONSTRUCTION / POND CONSTRUCTION.***

ESTIMATE PHASE	2	TYPE OF FUNDING	
		CAPITAL > 100K	

PREPARED BY: B. WORKMAN (HED)

1. TVA-HED LABOR COSTS			Comments
Craft Augmented Labor	MANHOURS	59671	Includes all aspects of Phase 1 work.
	COST	\$2,264,004	Based on FY 2005 labor rates.
Non-Manual Labor	MANHOURS	5,160	Supervisor and (2) Mechanics full time.
	COST	\$235,640	Includes Hourly Rates & Per Diem for both men.
Contingency 0.00%	MANHOURS	0	
	COST	\$0	
SUBTOTAL TVA-HED LABOR		64,831	
	COST	\$2,499,644	
2. TVA-HED OTHER COSTS			
TVA-HED Subcontracts		\$285,600	Survey / Layout / Fence Cont./ Compac. Testing
TVA-HED Subcontract Fee		\$0	
Travel & Living Expenses		See "Non-Manual Labor"	
TVA-HED Material Purchases		\$0	
HED Other Costs		\$0	
Contingency 0%		\$0	
SUBTOTAL TVA-HED OTHER		\$285,600	
TOTAL TVA-HED COSTS		\$2,785,244	
3. ITEMS MANAGED BY TVA-HED			
Permanent Materials		\$665,232	Per Quantities Provided by Parsons E & C.
Heavy Equipment		\$1,255,321	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment		\$0	
Small Tools		\$5,967	
Supplies, Consumables & Expendable Tools		\$17,901	
Office Supplies & Expenses		\$0	
Other TVA-HED Costs		\$0	
TVA subcontracts (By Others)		\$0	
Partner or OCIP Insurance		\$0	
TVA-HED - Overhead 10.00%		\$345,048	
Contingency 0%		\$0	
SUBTOTAL TVA-HED MANAGED		\$2,289,469	
TOTAL TVA-HED COSTS		\$5,074,713	

APPROVALS: ESTIMATE TOTAL 5,074,713

TVA-HED Estimator	Date:
TVA - Project Manager	Date:
TVA - Project Engineer	Date:
TVA - Site Environmental Engineer	Date:

LINE NO	A	B	C	D	E	F	G	H	I	J	K	L	M	N
1	MAT	CODE	CODE	ACT	CODE	DESCRIPTION	QTY	UNIT	UNIT	MAN	WAGE	TOTAL	MATERIAL	TOTAL
2	CODE	WORK ORDER	SCH	CRIT					HR	PER HOUR		LABOR		MATERIAL
GYPSUM POND CONSTRUCTION (PHASE 1)														
CLEAR AND GRUB														
102	OE				OE	CLEAR FOR BORROW @ PENINSULA, SED. PONDS, DIKES	30	AC	80	2400	17.60	\$96,000		
100	OE				OE	STRIP TOPSOIL	100000	CY	0.055	5500	\$40.00	\$220,000		
EROSION CONTROLS / SEED & MULCH														
103	OE				OE	TRENCH FOR EROSION CONTROL FENCING	7150	LF	0.025	179	\$40.00	\$7,150		
103	LB				LB	INSTALL SILT FENCING / STRAW BALES	7150	LF	0.12	858	\$26.00	\$22,300		
103	LB				LB	SEED / MULCH DISTURBED AREAS	16	AC	40	640	\$26.00	\$16,640		
103	TM				TM	HAUL STRAW AND SILT FENCE ALONG PROJECT AREA	7150	LF	0.0183	131	\$32.00	\$4,187		
STORMWATER RUNOFF POND CONSTRUCTION														
100	OE				OE	GROSS CUT / FILL FOR STORMWATER RUNOFF PONDS	43223	CY	0.065	2809	\$40.00	\$112,380		
105	OE				OE	RIP RAP FOR PONDS	8182	TN	0.05	405	\$40.00	\$16,204		
105	OE				OE	72" DIA. CMP FOR OUTLET STRUCTURE	12	LF	2	24	\$40.00	\$960		
105	OE				OE	48" DIA CMP FOR RISER FOR OUTLET STRUCTURE	14	LF	2	28	\$40.00	\$1,120		
105	LB				LB	CUT HOLES IN RISER	6	EA	2	12	\$26.00	\$312		
105	OE				OE	48" CMP OUTLET PIPE (PRINCIPLE SPILLWAY)	150	LF	1	150	\$40.00	\$6,000		
105	LB				LB	CONCRETE FOR RISER BASE	9	CY	2	18	\$26.00	\$468		
105	LB				LB	ANTI-SEEP COLLARS	6	CY	4	24	\$26.00	\$624		
105	OE				OE	PIPE BEDDING - #57 STONE	40	TN	2	80	\$40.00	\$3,200		
100	OE				OE	CLEAN OUT STORMWATER RUNOFF POND	1000	CY	0.065	65	\$40.00	\$2,600		
BUILD ACCESS ROADS														
101	OE				OE	BOTTOM ASH CUT / HAUL / FILL	2593	CY	0.065	169	\$40.00	\$6,742		
104	OE				OE	CRUSHED STONE BASE	2566	TN	0.025	64	\$40.00	\$2,566		
104	OE				OE	CRUSHED STONE BASE - PARKING LOT	275	TN	0.025	7	\$40.00	\$275		
FENCING - SEE SUBCONTRACTS SECTION														
						FENCING - SEE SUBCONTRACTS SECTION				EA				
BORROW AREA DEVELOPMENT														
102	OE				OE	CLEAR AND GRUB		AC	80		\$40.00			
103	OE				OE	TRENCH FOR EROSION CONTROL FENCING		LF	0.025		\$40.00			
103	LB				LB	INSTALL SILT FENCING / STRAW BALES		LF	0.125		\$26.00			
100	OE				OE	EXCAVATE TEMPORARY PERMETER DITCH		CY	0.085		\$40.00			
100	OE				OE	CUT FOR STORMWATER RUNOFF PONDS		CY	0.055		\$40.00			
100	OE				OE	FILL FOR STORM WATER PONDS		CY	0.055		\$40.00			
106	OE				OE	72" DIA. CMP FOR OUTLET STRUCTURE		LF	2		\$40.00			
106	OE				OE	48" DIA CMP FOR RISER FOR OUTLET STRUCTURE		LF	2		\$40.00			
106	LB				LB	CUT HOLES IN RISER		EA	2		\$26.00			
106	OE				OE	48" CMP OUTLET PIPE (PRINCIPLE SPILLWAY)		LF	1		\$40.00			
106	LB				LB	CONCRETE FOR RISER BASE		CY	2		\$26.00			
106	LB				LB	ANTI-SEEP COLLARS		CY	4		\$26.00			
106	OE				OE	PIPE BEDDING - #57 STONE		TN	2		\$40.00			
106	OE				OE	CLEAN OUT STORMWATER RUNOFF POND		CY	0.065		\$40.00			
DISPOSAL FACILITY CONSTRUCTION														
100	OE				OE	EARTHWORK CUT - SHAPE BASE INSIDE GYPSUM STACK	337228	CY	0.03	10117	\$40.00	\$404,673		
100	OE				OE	EARTHWORK FILL FROM BORROW AREA	89714	CY	0.03	2691	\$40.00	\$107,657		
100	OE				OE	PROOFROLL SUBGRADE	45	AC	3	135	\$40.00	\$5,400		
100	OE				OE	CUT AND RE-COMPACT LINER	211362	CY	0.035	7398	\$40.00	\$295,907		
100	OE				OE	(ALLOWANCE FOR DOUBLE HANDLING - 15% OF LINER MATERIAL)	31704	CY	0.035	1110	\$40.00	\$44,386		
107	LB				LB	INSTALL 6" HDPE CENTERLINE UNDERDRAIN PIPE	10358	LF	0.08	829	\$26.00	\$21,545		
107	OE				OE	CUT FOR UNDERDRAIN SYSTEM		CY	0.073		\$40.00			
107	LB				LB	INSTALL GEOTEXTILE - 80Z NON-WOVEN FOR CL UNDERDRAIN	58282	SY	0.0063	364	\$26.00	\$9,471		
107	OE				OE	INSTALL 12" DEPTH 1081 CRUSHED STONE	14260	TN	0.6	8556	\$40.00	\$342,240		
107	LB				LB	INSTALL UNDERDRAIN PIPING (8" DIA. HDPE)	10358	LF	0.08	829	\$26.00	\$21,545		
107	LB				LB	INSTALL HDPE FITTINGS FOR UNDERDRAIN PIPING	13	EA	0.1	1	\$26.00	\$34		
107	OE				OE	EXCAVATE SURFACE WATER DIVERSION DITCH	43333	CY	0.07	3033	\$40.00	\$121,332		
107	TM				TM	HAUL EXCAVATED SPOILS FROM DITCH AND STOCKPILE	43333	CY	0.027	1170	\$32.00	\$37,440		
107	OE				OE	RIP RAP DIVERSION DITCH	12000	TN	0.05	600	\$40.00	\$24,000		
107	OE				OE	DRAINAGE PIPE FROM SUMP TO STORMWATER POND	580	LF	0.1	58	\$40.00	\$2,320		
107	OE				OE	LIFT STATION		1 LOT				\$10,000		
107	OE				OE	DIVERSION PIPE BENEATH STORMWATER POND	560	LF	0.07	41	\$36.21	\$1,470		
101	OE				OE	INSTALL 2.5" THICK BOTTOM ASH DRAINAGE LAYER		CY	0.065		\$40.00			
101	OE				OE	INSTALL 6" THICK FLY ASH LAYER (MIX)		CY	0.065		\$40.00			
101	OE				OE	PERIMETER ROAD SURFACING - BOTTOM ASH	2616	CY	0.065	170	\$40.00	\$6,802		
104	OE				OE	PERIMETER ROAD SURFACING - CRUSHED STONE	2592	TN	0.025	65	\$40.00	\$2,592		
107	OE				OE	INSTALL RIP RAP DITCH		TN	0.02		\$40.00			
107	LB				LB	INSTALL 8 OZ NON-WOVEN GEOTEXTILE (IF RIP RAP IS USED)		SY	0.0663		\$26.00			
CONSTRUCTION PARKING														
100	OE				OE	EARTHWORK CUT		CY	0.04		\$40.00			
100	OE				OE	EARTHWORK FILL		CY	0.04		\$40.00			
104	OE				OE	CRUSHED STONE BASE	744	TN	0.03	22	\$40.00	\$893		
"ALLOWANCE" FOR PUMP STATION POND														
97	OE				OE	PUMP STATION QUANT'S. NOT PROVIDED AT THIS TIME		2 MEN	80	160	\$40.00	\$6,400		
98	TM				TM	HAUL MATERIAL OUT		2 MEN	80	160	\$29.27	\$4,683		
PHASE 1 TOTALS EARTHWORK 857,609 ASH 5,209 RIP RAP 20102 #57 STONE 40 CR. STONE 20437 FABRIC 58,282 SILT FENCE 7,150														
ADD ABOVE THIS LINE IF NECESSARY										PRE-OUTAGE DIRECT				
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE										SUBTOTALS		51071		\$1,990,524
OUTAGE - DIRECT CRAFT														
GYPSUM POND CONSTRUCTION (PHASE 1)														

INCREASE FOR STAFF AUGMENTED LABOR PLUS POSSIBLY 5% INCREASE FOR MATERIAL

A	B	C	D	E	F	G	H	I	J	K	L	M	N
MAT CODE	CODE WORK ORDER	CODE	ACT SCH	CODE CRT	DESCRIPTION	QTY	UNIT	MAN HOURS	WAGE RATE	TOTAL LABOR	MATERIAL	TOTAL MATERIAL	
ADD ABOVE THIS LINE IF NECESSARY						OUTAGE DIRECT							
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :							
POST OUTAGE - DIRECT CRAFT													
GYPSUM POND CONSTRUCTION (PHASE 1)													
ADD ABOVE THIS LINE IF NECESSARY						POST OUTAGE DIRECT							
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :							
TOTALS - DIRECT CRAFT						51071				\$1,990,524			
SUPPORT CRAFT													
(QTY & UNITS MUST BE INCLUDED FOR EA. LINE ITEM)													
PRE-OUTAGE - SUPPORT CRAFT													
GENERAL FOREMAN / SUPPORT CRAFT (1 YR)													
	942		OEA		OPERATOR FOREMAN	1	MEN	1720	\$46.00	\$79,120			
	942		LBJ		LABORER FOREMAN	1	MEN	1720	\$29.00	\$49,880			
	902		TM3		TEAMSTER TO WATER ROADS / SUPPORT MANPOWER	1	MEN	1720	\$32.00	\$55,040			
	902		LBJ		LABORER GENERAL SUPPORT / OFFICE	2	MEN	3440	\$26.00	\$89,440			
ADD ABOVE THIS LINE IF NECESSARY						PRE-OUTAGE SUPPORT							
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :			8600		\$273,480		
OUTAGE - SUPPORT CRAFT													
ADD ABOVE THIS LINE IF NECESSARY						OUTAGE SUPPORT							
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :							
POST-OUTAGE - SUPPORT CRAFT													
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :							
MOBILIZATION OF CRAFT													
	901		AWJ		ADMINISTRATIVE TIME		MEN	2	\$33.79				
	901		AWJ		SAFETY MEETING		MEN	3	\$33.79				
	901		AWJ		DRUG TEST		MEN	1	\$33.79				
	901		ABJ		ADMINISTRATIVE TIME		MEN	2	\$27.44				
	901		ABJ		SAFETY MEETING		MEN	3	\$27.44				
	901		ABJ		DRUG TEST		MEN	1	\$27.44				
	901		BMJ		ADMINISTRATIVE TIME		MEN	2	\$52.60				
	901		BMJ		SAFETY MEETING		MEN	3	\$52.60				
	901		BMJ		DRUG TEST		MEN	1	\$52.60				
	901		CAJ		ADMINISTRATIVE TIME		MEN	2	\$32.26				
	901		CAJ		SAFETY MEETING		MEN	3	\$32.26				
	901		CAJ		DRUG TEST		MEN	1	\$32.26				
	901		ELJ		ADMINISTRATIVE TIME		MEN	2	\$39.71				
	901		ELJ		SAFETY MEETING		MEN	3	\$39.71				
	901		ELJ		DRUG TEST		MEN	1	\$39.71				
	901		IWJ		ADMINISTRATIVE TIME		MEN	2	\$37.63				
	901		IWJ		SAFETY MEETING		MEN	3	\$37.63				
	901		IWJ		DRUG TEST		MEN	1	\$37.63				
	901		LBJ		ADMINISTRATIVE TIME		MEN	2	\$24.40				
	901		LBJ		SAFETY MEETING		MEN	3	\$24.40				
	901		LBJ		DRUG TEST		MEN	1	\$24.40				
	901		OEA		ADMINISTRATIVE TIME		MEN	2	\$36.21				
	901		OEA		SAFETY MEETING		MEN	3	\$36.21				
	901		OEA		DRUG TEST		MEN	1	\$36.21				
	901		PAJ		ADMINISTRATIVE TIME		MEN	2	\$28.98				
	901		PAJ		SAFETY MEETING		MEN	3	\$28.98				
	901		PAJ		DRUG TEST		MEN	1	\$28.98				
	901		MWJ		ADMINISTRATIVE TIME		MEN	2	\$36.24				
	901		MWJ		SAFETY MEETING		MEN	3	\$36.24				
	901		MWJ		DRUG TEST		MEN	1	\$36.24				
	901		PFJ		ADMINISTRATIVE TIME		MEN	2	\$39.89				
	901		PFJ		SAFETY MEETING		MEN	3	\$39.89				
	901		PFJ		DRUG TEST		MEN	1	\$39.89				
	901		SMJ		ADMINISTRATIVE TIME		MEN	2	\$40.98				
	901		SMJ		SAFETY MEETING		MEN	3	\$40.98				
	901		SMJ		DRUG TEST		MEN	1	\$40.98				
	901		TMW		ADMINISTRATIVE TIME		MEN	2	\$28.38				
	901		TMW		SAFETY MEETING		MEN	3	\$28.38				
	901		TMW		DRUG TEST		MEN	1	\$28.38				
ADD ABOVE THIS LINE IF NECESSARY						CONSTR FAC & MOB							
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :							
MISCELLANEOUS CONSTRUCTION FACILITIES													
ADD ABOVE THIS LINE IF NECESSARY						MISC. CONSTR FAC							
DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE						SUBTOTALS :							
LABOR SUMMARY													
TOTAL SUPPORT CRAFT LABOR								8600		\$273,480		12.08%	
TOTAL DIRECT CRAFT LABOR								51071		\$1,990,524		87.92%	
GRAND TOTAL CRAFT LABOR								59671		\$2,264,004			
SUBCONTRACTS - HED													

A	B	C	D	E	F	G	H	I	J	K	L	M	N
1	2	3											
MAT. CODE	CODE	CODE	ACT SCH	CODE CRFT	DESCRIPTION	QTY	UNIT	UNIT MH	MAN HOURS	WAGE RATE	TOTAL LABOR	MATERIAL	TOTAL MATERIAL
		PSUB1			HCOST: ENGINEERING - DENSITY / COMPACTION TESTING - QA/QC						\$130,000		
		PSUB2			HCOST: TVA SURVEYING / LAYOUT						\$24,000		
		PSUB3			HCOST: SUNBELT PUMPS & SETUP (DE-WATER)						\$100,000		
		PSUB4			HCOST: FENCE CONTRACTOR						\$11,600		
		PSUB5			HCOST: STUMP / TREE GRINDING FOR MULCH						\$20,000		
		PSUB6			HCOST:								
		PSUB7			HCOST:								
TOTAL - SUBCONTRACTS - HED											\$285,600		
SUBCONTRACTS - TVA (OTHERS)													
TOTAL - SUBCONTRACTS - TVA (OTHERS)													
MATERIALS - HED PURCHASE													
		TMTL			HCOST: SEE MATERIALS LIST								
		TMTL									\$665,232		
TOTAL - MATERIALS - HED PURCHASE											\$665,232		
MATERIALS - TVA (OTHERS) PURCHASE													
TOTAL - MATERIALS - TVA (OTHERS)													
NON-MANUAL LABOR													
STAFFING (See Staff Plan for Details)													
		950		STF	NON PROJECT SPECIFIC STAFF (SUPERVISION) SEE STAFF SHEET				5180		\$235,640		
		950X		HCOST:	TRAVEL & LIVING EXPENSES								
TOTAL - NON MANUAL LABOR											\$235,640		
OTHER COSTS - MANAGED BY HED													
		STLS	STLS		HCOST: SMALL TOOLS	59671	MHRS			\$0.10	\$5,967		
		CONS	CONS		HCOST: CONSUMABLES	59671	MHRS			\$0.30	\$17,901		
		OSUP	OSUP		HCOST: OFFICE SUPPLIES AND EXPENSES								
					HCOST: OTHER HED COSTS								
					OTHER TVA COSTS								
TOTAL COST MANAGED BY HED											\$23,868		
TVA HEAVY EQUIPMENT													
Note: 1st SHIFT rate shown - 2nd shift rate is a lookup													
CLEARING AND GRUBBING													
	102		HED		HCOST: 245 CAT TRACKHOE W/ 3 1/2 CY BUCKET	20	1ST		N/A	479	\$9,580		
	102		HED		HCOST: D8 W/ RIPPER	20	1ST		N/A	475	\$9,500		
	102		HED		HCOST: LR 322 CAT TRACHOE	20	1ST		N/A	485	\$9,700		
	102		HED		HCOST: KAWASAKI MULE	20	1ST		N/A	28	\$560		
EARTHWORK EQUIPMENT													
	100		HED		HCOST: 637 SCRAPER - DBL	110	1ST		N/A	593	\$65,230		
	101		HED		HCOST: 638 SCRAPER - DBL	110	1ST		N/A	593	\$65,230		
	102		HED		HCOST: 639 SCRAPER - DBL	110	1ST		N/A	593	\$65,230		
	103		HED		HCOST: 640 SCRAPER - DBL	110	1ST		N/A	593	\$65,230		
	104		HED		HCOST: 641 SCRAPER - DBL	110	1ST		N/A	593	\$65,230		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: 631 SCRAPER	110	1ST		N/A	455	\$50,050		
	100		HED		HCOST: DBK	110	1ST		N/A	332	\$36,520		
	100		HED		HCOST: DBK	110	1ST		N/A	332	\$36,520		
	100		HED		HCOST: 20 TON SHEEPFOOT ROLLER	110	1ST		N/A	200	\$22,000		
	101		HED		HCOST: 21 TON SHEEPFOOT ROLLER	110	1ST		N/A	200	\$22,000		
	100		HED		HCOST: 20 TON SMOOTHDRUM ROLLER	110	1ST		N/A	200	\$22,000		
	100		HED		HCOST: 20 TON SMOOTHDRUM ROLLER	110	1ST		N/A	200	\$22,000		
	100		HED		HCOST: DBN	110	1ST		N/A	294	\$32,340		
	100		HED		HCOST: DBN	110	1ST		N/A	294	\$32,340		
ASH WORK EQUIPMENT													
	101		HED		HCOST: 637 SCRAPER - DBL	15	1ST		N/A	593	\$8,895		
	102		HED		HCOST: 638 SCRAPER - DBL	15	1ST		N/A	594	\$8,910		
	103		HED		HCOST: 639 SCRAPER - DBL	15	1ST		N/A	595	\$8,925		
	104		HED		HCOST: 640 SCRAPER - DBL	15	1ST		N/A	596	\$8,940		
	105		HED		HCOST: 641 SCRAPER - DBL	15	1ST		N/A	597	\$8,955		
	106		HED		HCOST: 642 SCRAPER - DBL	15	1ST		N/A	598	\$8,970		
	101		HED		HCOST: 631 SCRAPER	15	1ST		N/A	455	\$6,825		
	101		HED		HCOST: 631 SCRAPER	15	1ST		N/A	455	\$6,825		
	101		HED		HCOST: 631 SCRAPER	15	1ST		N/A	455	\$6,825		
	101		HED		HCOST: 631 SCRAPER	15	1ST		N/A	455	\$6,825		
	101		HED		HCOST: 631 SCRAPER	15	1ST		N/A	455	\$6,825		
	101		HED		HCOST: 631 SCRAPER	15	1ST		N/A	455	\$6,825		
	101		HED		HCOST: 20 TON SMOOTHDRUM ROLLER	15	1ST		N/A	200	\$3,000		
	101		HED		HCOST: 270 TRACKHOE	15	1ST		N/A	280	\$4,200		
	101		HED		HCOST: 320 TRACKHOE - LONGSTICK	15	1ST		N/A	600	\$9,000		
	101		HED		HCOST: DBK	15	1ST		N/A	332	\$4,980		
	101		HED		HCOST: DBN	15	1ST		N/A	294	\$4,410		
ERECT SILT FENCE													
	103		HED		HCOST: AIR COMPRESSOR	20	1ST		N/A	150	\$3,000		
	103		HED		HCOST: TRENCHER - DITCH WITCH	20	1ST		N/A	250	\$5,000		
GENERAL SUPPORT EQUIPMENT													
		HED	HED		HCOST: SUPERVISOR TRUCK	43	WK		N/A	140	\$6,020		
		HED	HED		HCOST: CREW TRAILER (2 EA)	172	1ST		N/A	25	\$4,300		
		HED	HED		HCOST: TOOL TRAILER	172	1ST		N/A	14	\$2,408		
		HED	HED		HCOST: CREW TRUCK	43	WK		N/A	140	\$6,020		
		HED	HED		HCOST: TRACKHOE	43	WK		N/A	300	\$12,900		
		HED	HED		HCOST: MOTOR GRADER	43	WK		N/A	210	\$9,030		

1	A	B	C	D	E	F	G	H	I	J	L	M	N
2	MAT.	CODE	CODE	ACT	CODE						CRAFT LABO		
3	CODE	WORK ORDER		SCH	CRT	DESCRIPTION	QTY	UNIT	MH	HOURS	WAGE RATE	TOTAL LABOR	TOTAL MATERIAL
398			HED	HED	HCOST	RUBBER TIRE BACKHOE	172	1ST		N/A	120	\$20,640	
399			HED	HED	HCOST	PORTALET (3 EA)	10	MO		N/A	300	\$3,000	
400			HED	HED	HCOST	FOREMAN TRUCK (2 EA)	43	WK		N/A	160	\$6,880	
401			HED	HED	HCOST	WATER TRUCK	172	1ST		N/A	130	\$22,360	
402			HED	HED	HCOST	WATER TRUCK	172	1ST		N/A	130	\$22,360	
403			HED	HED	HCOST	MJLE	172	1ST		N/A	28	\$4,816	
404			HED	HED	HCOST	MJLE	172	1ST		N/A	28	\$4,816	
405			HED	HED	HCOST	769 - BACKDUMP	50	1ST		N/A	300	\$15,000	
406			HED	HED	HCOST	770 - BACKDUMP	50	1ST		N/A	300	\$15,000	
407			HED	HED	HCOST	FUEL TRUCK	172	1ST		N/A	33	\$5,676	
408			HED	HED	HCOST	MECHANICS TRUCK	172	WK		N/A	200	\$34,400	
422													
423						TOTAL - HEAVY EQUIPMENT						\$1,255,321	
821													
823						ADD ABOVE THIS LINE IF NECESSARY							
824						DO NOT DELETE THIS LINE UNLESS DELETING PRE-OUTAGE SECTION OF ESTIMATE							
825						TOTAL - TAGGED TOOLS							
826	END	END	END	END	END		END	END	END	END	END	END	

Staff

NGSTON	YPSUM POND CONSTRUCTION (PHASE 1)	RELOCATE/		MONTHLY	TOTAL		PRE-OUTAGE	OUTAGE	POST-OUT	RUN DATE:	22-Mar-06				
		PER DIEM	EXPENSES		STAFF	DOLLARS						DUR (WKS)	DUR (WKS)	DUR (WKS)	MANHO
				****SUMMARY****											
		TRAVEL & LIVING EXPENSES (Relocation, Per Diem, Expenses, Month)				\$55,728									
		TOTAL STAFF DOLLARS				\$235,640									
		TOTAL STAFF MANHOURS				5160									
TAFFING	RATE	RELOCATE/	MONTHLY	OUTAGE	NON-OUTAGE	TOTAL	PRE-OUTAGE	OUTAGE	POST-OUT						
		PER DIEM	TRIPS	DOLLARS	DOLLARS	STAFF	DUR (WKS)	DUR (WKS)	DUR (WKS)						
		EXPENSES	HOME	DOLLARS	DOLLARS	DOLLARS	40	40	40						
ITE MANGER	\$67.65	\$0	\$0	\$0	\$0	\$0									
ENERAL SUPT.	\$63.90	\$0	\$0	\$0	\$0	\$0									
OILER SUPT	\$49.90	\$0	\$0	\$0	\$0	\$0									
LECT SUPT	\$49.90	\$0	\$0	\$0	\$0	\$0									
ECHANICAL SUPT	\$49.90	\$0	\$0	\$0	\$0	\$0									
IVIL SUPT	\$46.00	\$37,152	\$0	\$0	\$158,240	\$158,240	86			3440					
QUIPMENT MECHANIC	\$45.00	\$18,576	\$0	\$0	\$77,400	\$77,400	43			1720					
OST SPECIALIST	\$37.72	\$0	\$0	\$0	\$0	\$0									
STIMATING MGR	\$55.65	\$0	\$0	\$0	\$0	\$0									
IELD TECH SPECILST	\$48.73	\$0	\$0	\$0	\$0	\$0									
IELD ADMIN MGR.	\$32.65	\$0	\$0	\$0	\$0	\$0									
ISULATION SERV MGR.	\$51.94	\$0	\$0	\$0	\$0	\$0									
EAD FIELD ADMIN MGR	\$44.15	\$0	\$0	\$0	\$0	\$0									
ATERIAL COORD.	\$22.26	\$0	\$0	\$0	\$0	\$0									
AYROLL/TIMEKEEPER	\$22.08	\$0	\$0	\$0	\$0	\$0									
A/QC INSPECTOR	\$44.52	\$0	\$0	\$0	\$0	\$0									
AFETY COORDINATOR	\$40.73	\$0	\$0	\$0	\$0	\$0									
AFETY SUPERVISOR	\$48.23	\$0	\$0	\$0	\$0	\$0									
CHEDULE ANALYST	\$50.45	\$0	\$0	\$0	\$0	\$0									
CHEDULER	\$41.55	\$0	\$0	\$0	\$0	\$0									
ECRETARY	\$25.00	\$0	\$0	\$0	\$0	\$0									
ITE PROJ CTRL MGR	\$51.65	\$0	\$0	\$0	\$0	\$0									
ECH SUPPORT	\$26.09	\$0	\$0	\$0	\$0	\$0									
IMEKEEPER	\$16.32	\$0	\$0	\$0	\$0	\$0									
OTALS		\$55,728	\$0	\$0	\$235,640	\$235,640				5160					

GYPSUM POND CONSTRUCTION (PHASE 1)

KINGSTON

PHASE 1

0

0

CRAFT

		Pre-outage			Outage			P Post Outage				
ASBESTOS WORKER	ABJ	0	0	0	0	0	0	0	0	0	0	0
BRICKLAYER	BLJ	0	0	0	0	0	0	0	0	0	0	0
BOILERMAKER GENERAL FOREMAN	BMG				0			0			0	0
BOILERMAKER FOREMAN	BMF				0			0			0	0
BOILERMAKER	BMJ	0	0	0	0	0	0	0	0	0	0	0
CONCRETE MASON	CMJ	0	0	0	0	0	0	0	0	0	0	0
CARPENTER FOREMAN	CAF				0			0			0	0
CARPENTERS	CAJ	0	0	0	0	0	0	0	0	0	0	0
ELECTRICAL GENERAL FOREMAN	ELG				0			0			0	0
ELECTRICAL FOREMAN	ELF				0			0			0	0
ELECTRICAL	ELJ	0	0	0	0	0	0	0	0	0	0	0
INSULATOR GENERAL FOREMAN	AWG				0			0			0	0
INSULATOR FOREMAN	AWF				0			0			0	0
INSULATOR	AWJ	0	0	0	0	0	0	0	0	0	0	0
IRONWORKER FOREMAN	IWF				0			0			0	0
IRONWORKER	IWJ	0	0	0	0	0	0	0	0	0	0	0
MILLWRIGHT FOREMAN	MWF				0			0			0	0
MILLWRIGHT	MWJ	0	0	0	0	0	0	0	0	0	0	0
LABOR FOREMAN	LBF				1048			0			0	1048.181
LABOR	LBJ	3574.8	5160	0	8734.8	0	0	0	0	0	0	8734.843
OPERATOR	OEA	46036	1720	0	47756	0	0	0	0	0	0	47755.57
PAIN FOREMAN	PAF				0			0			0	0
PAINTER	PAJ	0	0	0	0	0	0	0	0	0	0	0
PIPEFITTER GENERAL FOREMAN	PFG				0			0			0	0
PIPE FOREMAN	PFF				0			0			0	0
PIPEFITTER	PFJ	0	0	0	0	0	0	0	0	0	0	0
SHEETMETAL FOREMAN	SMF				0			0			0	0
SHEETMETAL	SMJ	0	0	0	0	0	0	0	0	0	0	0
TRUCK DRIVER	TM3	1330	1720	0	3050	0	0	0	0	0	0	3049.991
TEAMISTER	TMW	130.85	0	0	130.85	0	0	0	0	0	0	130.845
TOTAL		51071	8600	0	1048	0	0	0	0	0	0	60719

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06047R1 Option: 0 PCN Number: KIF450
 Plant: KIF Revision: 1 Estimate Type: Preliminary
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 20%
 Requesting Engr: S. M. Haber Phase: 2 Estimate Issue Date 01/26/2006

	Hours	Dollars
Phase I		
Engineering		\$0
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$0</u>
Phase II		
Engineering		\$330,288
Long Lead Procurement		\$72,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$402,288</u>
Phase III		
Construction (Partner)		
Permanent Material		\$795,806
Labor (T&L)	80,020.84	\$3,017,411
Labor (Non-Manual)	11,583.00	\$469,950
Equipment		\$1,522,370
Subcontracts		\$440,600
Partner Fee		\$4,736
Partner Insurance		\$2,841
Escalation		\$498,933
Construction Risk Dollars		\$0
Other		\$484,006
Total Construction Cost		\$7,236,653
Engineering		\$209,850
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$1,551,209
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$8,997,712</u>
All Phases		
Construction Partner	91,603.84	\$7,236,653
Long Lead Procurement		\$72,000
Engineering		\$540,138
Other / Other Organizations		\$0
Total Risk Dollars		\$1,551,209
<u>Total Project Costs</u>	<u>91,603.84</u>	<u>\$9,400,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Project name KIF/06047R1/STG 1 GYP PND

Estimator C. L. Toney

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Earthwork

KIF

06047R1

KIF450

S. M. Haber

0

1

2

Preliminary

+/- 20%

01/26/2006

Capital

Notes

Cost estimate is based in 2006 dollars.

Revision 1 cost estimate has been revised based on information from

Lynn Peily based on revised design & quantities provided by GecSyntec

Consultants.

Short Term Storage. Construction earthwork portion of estimate

provided by HED. Remainder provided by ESS Group.

Sorted by Location/Activity

Detail summary

Report format

Sorted by Location/Activity

Detail summary

Spreadsheet Report
KIF/06047R1/STG 1 GYP PND

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Slip Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount				
HASE 3 (BOP)	17-Pumps & Pipe	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	84.000	84.00 mh	2,937	80,000	-	-	308	63,244.70	63,245				
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,260.00 cy	0.200	652.00 mh	16,311	-	-	-	8,150	7.50	24,461	24,461			
		Bottom Ash Pipe Bedding	112.00 cy	0.500	56.00 mh	1,514	-	-	-	574	18.65	2,088	2,088			
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.40 mh	19,976	-	92,484	-	9,080	60.77	121,539	121,539			
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00 cy	0.320	964.48 mh	23,128	-	-	-	23,398	15.77	47,527	47,527			
		Platforms Steel	5.00 ton	60.000	300.00 mh	10,087	-	26,250	-	23,376	7,742.43	38,712	38,712			
		17-Pumps & Pipe				2,706.88 hrs	74,963	178,734	-	43,885	-	297,572	297,572			
		18-Electrical	Phase 1 Transformer 200 kva (13.8 kV to 480 V)	4/0 600 Volt Cable	1.00 ls	120.000	120.00 mh	4,193	12,000	-	450	-	16,643.28	16,643		
				3" Diameter GRC Conduit	200.00 lf	0.619	123.80 mh	708	2,200	-	-	-	14.56	2,908	2,908	
				13 kV Amp Pole Mount Fuse Disconnect	1.00 ea	12.000	12.00 mh	425	8,140	-	-	-	82.62	12,963	12,963	
				18-Electrical				275.80 hrs	9,709	23,840	-	450	-	1,925	33,999	33,999
				18-Electrical				207.89 hrs	5,930	-	-	3,100	-	9,000.00	9,000	
		xConst Facilities	Mobilize, Drop Test, Miscellaneous Other, & Demobilize	xConst Facilities	1.00 ls	207.893	207.89 hrs	5,930	-	-	3,100	-	9,000.00	9,000		
				xConst Facilities				5,930	-	-	3,100	-	9,000.00	9,000		
		HASE 3 (HED)	zNon-Manual	Phase 3 Non Manual	1.00 ls	383.000	383.00 mh	19,150	-	-	-	-	19,150.00	19,150		
zNon-Manual						19,150	-	-	-	-	-	19,150.00	19,150			
PHASE 3 (BOP)						109,712	202,574	-	47,495	-	-	359,772	359,772			
PHASE 3 (BOP)						3,573.57 hrs	109,712	202,574	-	47,495	-	359,772	359,772			
HED Installation	Construction Labor			Non Manual Labor	1.00 ls	76,830.266	76,830.27 mh	2,926,849	-	-	-	-	2,926,849.00	2,926,849		
				TVA-HED Subcontracts	1.00 ls	11,200.000	11,200.00 mh	450,800	-	-	-	-	-	450,800.00	450,800	
				Partner Purchased Material	1.00 ls	-	-	-	665,232	440,600	-	-	-	1,105,832.00	1,105,832	
				Construction Heavy Equipment	1.00 ls	-	-	-	-	-	-	-	-	-	-	
				Small Tools	1.00 ls	-	-	-	-	-	-	-	-	-	-	
HED Installation	TVA-HED - Central Command			Supplies, Consumables & Expendable Tools	1.00 ls	-	-	-	-	-	-	-	-	-		
		TVA-HED - Central Command	1.00 ls	-	-	-	-	-	-	-	-	-	-			
		HED Installation	1.00 ls	-	-	-	665,232	440,600	-	-	-	1,105,832.00	1,105,832			
		HED Installation				88,030.27 hrs	3,377,649	665,232	440,600	1,474,935	479,081	6,437,497	6,437,497			
		PHASE 3 (HED)				88,030.27 hrs	3,377,649	665,232	440,600	1,474,935	479,081	6,437,497	6,437,497			

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Slip Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount				
HASE 3 (HED)	17-Pumps & Pipe	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	84.000	84.00 mh	2,937	80,000	-	-	308	63,244.70	63,245				
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,260.00 cy	0.200	652.00 mh	16,311	-	-	-	8,150	7.50	24,461	24,461			
		Bottom Ash Pipe Bedding	112.00 cy	0.500	56.00 mh	1,514	-	-	-	574	18.65	2,088	2,088			
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.40 mh	19,976	-	92,484	-	9,080	60.77	121,539	121,539			
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00 cy	0.320	964.48 mh	23,128	-	-	-	23,398	15.77	47,527	47,527			
		Platforms Steel	5.00 ton	60.000	300.00 mh	10,087	-	26,250	-	23,376	7,742.43	38,712	38,712			
		17-Pumps & Pipe				2,706.88 hrs	74,963	178,734	-	43,885	-	297,572	297,572			
		18-Electrical	Phase 1 Transformer 200 kva (13.8 kV to 480 V)	4/0 600 Volt Cable	1.00 ls	120.000	120.00 mh	4,193	12,000	-	450	-	16,643.28	16,643		
				3" Diameter GRC Conduit	200.00 lf	0.619	123.80 mh	708	2,200	-	-	-	14.56	2,908	2,908	
				13 kV Amp Pole Mount Fuse Disconnect	1.00 ea	12.000	12.00 mh	425	8,140	-	-	-	82.62	12,963	12,963	
				18-Electrical				275.80 hrs	9,709	23,840	-	450	-	1,925	33,999	33,999
				18-Electrical				207.89 hrs	5,930	-	-	3,100	-	9,000.00	9,000	
		xConst Facilities	Mobilize, Drop Test, Miscellaneous Other, & Demobilize	xConst Facilities	1.00 ls	207.893	207.89 hrs	5,930	-	-	3,100	-	9,000.00	9,000		
				xConst Facilities				5,930	-	-	3,100	-	9,000.00	9,000		
		HASE 3 (HED)	zNon-Manual	Phase 3 Non Manual	1.00 ls	383.000	383.00 mh	19,150	-	-	-	-	19,150.00	19,150		
zNon-Manual						19,150	-	-	-	-	-	19,150.00	19,150			
PHASE 3 (BOP)						109,712	202,574	-	47,495	-	-	359,772	359,772			
PHASE 3 (BOP)						3,573.57 hrs	109,712	202,574	-	47,495	-	359,772	359,772			
HED Installation	Construction Labor			Non Manual Labor	1.00 ls	76,830.266	76,830.27 mh	2,926,849	-	-	-	-	2,926,849.00	2,926,849		
				TVA-HED Subcontracts	1.00 ls	11,200.000	11,200.00 mh	450,800	-	-	-	-	-	450,800.00	450,800	
				Partner Purchased Material	1.00 ls	-	-	-	665,232	440,600	-	-	-	1,105,832.00	1,105,832	
				Construction Heavy Equipment	1.00 ls	-	-	-	-	-	-	-	-	-	-	
				Small Tools	1.00 ls	-	-	-	-	-	-	-	-	-	-	
HED Installation	TVA-HED - Central Command			Supplies, Consumables & Expendable Tools	1.00 ls	-	-	-	-	-	-	-	-	-		
		TVA-HED - Central Command	1.00 ls	-	-	-	-	-	-	-	-	-	-			
		HED Installation	1.00 ls	-	-	-	665,232	440,600	-	-	-	1,105,832.00	1,105,832			
		HED Installation				88,030.27 hrs	3,377,649	665,232	440,600	1,474,935	479,081	6,437,497	6,437,497			
		PHASE 3 (HED)				88,030.27 hrs	3,377,649	665,232	440,600	1,474,935	479,081	6,437,497	6,437,497			

Estimate Totals				Rate	Cost Basis
Description	Amount	Totals	Hours		
Labor	3,487,361		91,603,839 hrs		
Material	867,806				
Subcontract	440,600				
Equipment	1,522,370		1,970,471 hrs		
Other	479,081				
Engineered Materials - Ph 2	6,797,218	6,797,218		100.000 %	C
Adjustment - Enor Materials	72,000			(100.000) %	C
	(72,000)				
Small Tools Expense (BOP)	1,185			0.015 \$/hr	H
Consum & Expendables (BOP)	2,960			0.098 %	C
Office Supplies & Exp (BOP)	779			0.166 %	C
	4,924	6,802,142			
Escalation - Craft Labor	292,689			9.700 %	C
Escalation - Subcontract	29,961			6.800 %	C
Escalation - Perm Materials	32,977			3.800 %	C
Escalation - HED Equipment	88,496			6.000 %	C
Escalation - Small Tools	2,721			0.034 \$/hr	H
Escalation - Consumables	6,035			0.200 %	C
Escalation - Non-Manual Labor	45,115			9.600 %	C
Escalation - Office Supplies	940			0.200 %	C
	498,934	7,301,076			
Partner Insurance (BOP)	2,841			0.081 %	C
Partner Award Fee (BOP)	4,736			0.136 %	C
	7,577	7,308,653			
FPG Pro Enar - Phase 2	4,200		100.004 hrs	0.109 % @ 42.00 A	A
FPG Civil Enar - Phase 2	21,000		500.001 hrs	0.546 % @ 42.00 A	A
GeoSvntec Enar - Phase 2	302,400		4,199,999 hrs	4.585 % @ 72.00 A	A
FPG Pro Cntrl Cost - Phase 2	672		16,003 hrs	0.017 % @ 42.00 A	A
FPG Cost Estimatin - Phase 2	1,680		40,003 hrs	0.044 % @ 42.00 A	A
FPG Enar Records - Phase 2	336		7,997 hrs	0.009 % @ 42.00 A	A
	330,288	7,638,941			
FPG Pro Enar - Phase 3	3,150		74,996 hrs	0.082 % @ 42.00 A	A
FPG Civil Enar - Phase 3	6,300		150,001 hrs	0.164 % @ 42.00 A	A
GeoSvntec Enar - Phase 3	50,400		700,000 hrs	0.764 % @ 72.00 A	A
Mac Tec QA/QC & Certif - Ph 3	150,000		2,083,337 hrs	2.274 % @ 72.00 A	A
	209,850	7,848,791			
Contingency TH Protect @ 20%	1,551,209	9,400,000			L
	1,551,209	9,400,000			
Total		9,400,000			

**KINGSTON FOSSIL PLANT
(KIF450) TOTAL BUILDOUT OF GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06048R1 Option: 0 PCN Number: KIF450
 Plant: KIF Revision: 1 Estimate Type: Preliminary
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 20%
 Requesting Engr: S. M. Haber Phase: 2 Estimate Issue Date 01/26/2006

	<u>Hours</u>	<u>Dollars</u>
Phase I		
Engineering		\$0
Partner (Non-Manual)		
Other / Other Organizations		\$0
		<u>\$0</u>
Phase II		
Engineering		\$0
Long Lead Procurement		\$130,430
Partner (Non-Manual)		
Other / Other Organizations		\$0
		<u>\$130,430</u>
Phase III		
Construction (Partner)		
Permanent Material		\$2,287,846
Labor (T&L)	151,483.69	\$5,648,301
Labor (Non-Manual)	20,192.00	\$822,400
Equipment		\$2,623,914
Subcontracts		\$754,600
Partner Fee		\$9,104
Partner Insurance		\$5,463
Escalation		\$939,048
Construction Risk Dollars		\$0
Other		\$959,376
Total Construction Cost		\$14,050,052
Engineering		\$419,700
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$2,899,818
Other / Other Organizations		\$0
		<u>\$17,369,570</u>
All Phases		
Construction Partner	171,675.69	\$14,050,052
Long Lead Procurement		\$130,430
Engineering		\$419,700
Other / Other Organizations		\$0
Total Risk Dollars		\$2,899,818
		<u>\$17,500,000</u>
		\$0
		\$0

Removed pump, pipe + electrical for second pond from this estimate. See markup on estimate.

**KINGSTON FOSSIL PLANT
(KIF450) TOTAL BUILDOUT OF GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

KIF/0604BR1/STG 2 GYP PND

C. L. Toney

KIF 40 2005

TVA Equipment

Earthwork

KIF

0604BR1

KIF450

S. M. Haber

0

1

2

Preliminary

+/- 20%

01/26/2006

Capital

Cost estimate is based in 2006 dollars.

Revision 1 cost estimate has been revised based on info from Lynn Peily based on revised design & quantities provided by GeoSynlec Consultants.

Gypsum Long Term Flim Ditch Stack. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.

Sorted by 'Location/Activity'
'Detail' summary

Project name

Estimator

Labor rate table

Equipment rate table

Project Plant

Estimate #

PCN #

Requesting Engr

Revision

Phase

Estimate Type

Estimate Accuracy

Est. Issue Date

Funding Type

Notes

Report format

Spreadsheet Report
KIP706049R1/STG 2 GYP PND

timate Company

Location	Activity	Description	Takeoff Quantity	Labor Productivity	Labor Quantity	Labor Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount	
HASE 3 (BOP)	17-Pumps & Pipe Ph 1 <i>Armed Perjan Petty</i> <i>1/31/06</i>	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00 ea	64.000	64.00 mh	2,937	60,000	-	300	-	63,244.70	63,245	
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,260.00 cy	0.200	652.00 mh	16,311	8,150	-	514	-	-	24,451	24,451
		Bottom Ash Pipe Bedding	112.00 cy	0.500	56.00 mh	1,514	757	-	-	-	-	18.65	2,098
		18" Diameter Discharge HDPE Pipe, SDR11	2,000.00 lf	0.325	650.40 mh	19,978	9,980	92,484	-	-	-	60.77	121,539
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00 cy	0.320	964.48 mh	24,128	23,398	-	-	-	-	15.77	47,557
		Platform Steel	5.00 ton	60.000	300.00 mh	10,887	300.00	25,250	-	-	-	7,742.43	38,712
		17-Pumps & Pipe Ph 1				2,706.88 hrs	74,953	176,734	-	-	-	-	297,572
		50 HP Submersible Pump For Phase 2 Stormwater Pond	1.00 ea	54.000	54.00 mh	1,888	38,000	40,093.20	-	205	-	40,393	40,393
		Structural Excavation For 12" Diameter Pipe (4,500 lf)	5,250.00 cy	0.200	1,050.00 mh	26,288	13,125	-	-	-	-	7.50	39,393
		Bottom Ash Pipe Bedding	167.00 cy	0.500	83.50 mh	2,257	856	3,114	-	-	-	18.65	3,114
		12" Diameter Discharge HDPE Pipe, SDR11	4,500.00 lf	0.175	788.40 mh	24,214	11,006	31,000	-	-	-	6.77	79,663
		Structural Backfill For 12" Diameter Pipe (4,500 lf)	4,362.00 cy	0.320	1,395.84 mh	39,643	38,443	76,008	-	-	-	15.77	76,008
		Platform Steel	5.00 ton	60.000	300.00 mh	10,887	2,376	35,712	-	-	-	7,742.43	35,712
		17-Pumps & Pipe Ph 2				3,860.54 hrs	104,357	166,673	-	-	-	-	393,041
		HASE 3 (BOP)	18-Electrical Ph 1 <i>Armed Perjan Petty</i> <i>1/31/06</i>	Phase 1 Transformer 200 kva (13.8 kV to 480 v)	1.00 ls	120.000	120.00 mh	4,193	12,000	-	450	-	16,643.28
40 600 Volt Cable	200.00 lf			0.100	20.00 mh	708	2,200	-	-	-	14.54	2,908	
3" Diameter GRC Conduit	200.00 lf			0.619	123.80 mh	4,383	8,140	62.62	-	-	66.62	12,523	
13 kV Amp Pole Mount Fuse Disconnect	1.00 ea			12.000	12.00 mh	425	1,500	-	-	-	-	1,925	1,925
18-Electrical Ph 1						275.80 hrs	23,840	-	-	450	-	1,924.86	33,999
Phase 1 Transformer 200 kva (13.8 kV to 480 v)	1.00 ls			120.000	120.00 mh	4,193	12,000	-	-	450	-	16,643.28	16,643
40 600 Volt Cable	200.00 lf			0.100	20.00 mh	708	2,200	-	-	-	-	14.54	2,908
3" Diameter GRC Conduit	200.00 lf			0.619	123.80 mh	4,383	8,140	62.62	-	-	-	66.62	12,523
13 kV Amp Pole Mount Fuse Disconnect	1.00 ea			12.000	12.00 mh	425	1,500	-	-	-	-	1,925	1,925
No 6 15 kvolt Overhead Cable	4,500.00 lf			0.080	360.00 mh	12,746	42,390	-	-	-	-	12.25	55,136
Poles Between Ponds (Assumed 40 Wood Poles w/4 Cross Arm)	15.00 ea			16.000	240.00 mh	8,152	8,420	-	-	-	-	1,243.27	16,849
18-Electrical Ph 2						875.80 hrs	30,607	74,660	-	-	-	-	107,784
Mobilize, Drug Test, Miscellaneous Other, & Demobilize	1.00 ls			548.330	548.33 mh	15,600	15,600	-	-	8,400	-	24,000.00	24,000
XConst Facilities						1.00 ls	548.33 hrs	15,600	-	8,400	-	-	24,000.00
2Non-Manual						1.00 ls	992.000	49,600	-	-	-	49,600.00	49,600
PHASE 3 (BOP)				9,259.35 hrs	284,627	445,907	-	-	121,264	-	657,997		
PHASE 3 (HED)	HED Instail Ph1+Ph2	Construction Labor (Phase 1) Mh's Limited To Timberline Program	1.00 ls	76,830.266	76,830.27 mh	2,926,849	-	-	-	-	2,926,849.00	2,926,849	
		Construction Labor (Phase 2) Balance Of Mh's Required For Estimate	1.00 ls	66,386.078	66,386.08 mh	2,486,225	-	-	-	-	-	2,486,225.00	2,486,225
		Non-Manual Labor	1.00 ls	19,200.000	19,200.00 mh	772,800	-	-	-	-	-	772,800.00	772,800
		TVA-HED Subcontracts	1.00 ls	-	-	-	-	-	754,600	-	-	754,600.00	754,600
		Partner Purchased Material	1.00 ls	-	-	-	-	-	-	-	-	1,972,369.00	1,972,369
		Construction Heavy Equipment	1.00 ls	-	-	-	-	-	-	-	-	2,502,650.00	2,502,650
		Small Tools	1.00 ls	-	-	-	-	-	-	-	-	14,322.00	14,322
		Supplies, Consumables & Expendable Tools	1.00 ls	-	-	-	-	-	-	-	-	42,965.00	42,965
		TVA-HED - Central Command	1.00 ls	-	-	-	-	-	-	-	-	891,284.00	891,284
		HED Instail Ph1+Ph2				1.00 ls	162,416.34 hrs	6,185,874	1,972,369	754,600	2,502,650	948,571	12,364,064
		PHASE 3 (HED)				162,416.34 hrs	6,185,874	1,972,369	754,600	2,502,650	948,571	12,364,064	

Estimate Totals

Description	Amount	Totals	Hours	Rate	Cost Basis
			##### hrs		
Labor	6,470,701				
Material	2,418,276				
Subcontract	754,600				
Equipment	2,623,914		4,985,891 hrs		
Other	948,571				
Engineered Materials - Ph 2	13,216,062	13,216,062		100.000 %	C
Adjustment - Enor Materials	(130,430)	13,216,062		(100.000) %	C
Small Tools Expense (BOP)	2,686			0.018 \$/hr	H
Consum & Expendables (BOP)	6,623			0.117 %	C
Office Supplies & Exp (BOP)	1,497			0.182 %	C
	10,806	13,226,868			
Escalation - Craft Labor	547,885			9.700 %	C
Escalation - Subcontract	52,067			6.900 %	C
Escalation - Perm Materials	91,894			3.800 %	C
Escalation - HED Equipment	150,159			6.000 %	C
Escalation - Small Tools	5,150			0.034 \$/hr	H
Escalation - Consumables	11,297			0.200 %	C
Escalation - Non-Manual Labor	78,950			9.600 %	C
Escalation - Office Supplies	1,645			0.200 %	C
	939,047	14,165,915			
Partner Insurance (BOP)	5,463			0.084 %	C
Partner Award Fee (BOP)	9,104			0.141 %	C
	14,567	14,180,482			
FPG Prol Enar - Phase 3	6,300		149,993 hrs	0.087 % @ 42.00 A	A
FPG Civil Enar - Phase 3	12,600		300,003 hrs	0.175 % @ 42.00 A	A
GeoSvntec Enar - Phase 3	100,800		1,399,998 hrs	0.815 % @ 72.00 A	A
Mac Tec QA/QC & Certf - Ph 3	300,000		7,142,859 hrs	4.161 % @ 42.00 A	A
	419,700	14,600,182			
Contingency Ttl Project @ 20%	2,899,818				L
	2,899,818	17,500,000			
Total		17,500,000			

Toney, Calvin L.

From: Petty, Harold L.
Sent: Friday, January 20, 2006 7:45 AM
To: Toney, Calvin L.
Cc: Purkey, Ronald E.; Hughes, Michael
Subject: FW: One final item

Calvin:

Here are the revised capital construction quantities for the gypsum disposal area at Kingston on the peninsula.

The file is tabbed so there is one tab for phase I and another tab for phase 1&2.

The goal is to revise the estimate we had done with Dan's quantities before Thanksgiving but using these quantities.

We need the estimate back from you next Friday.

Thanks,
Lynn

-----Original Message-----

From: Neil Davies [mailto:NDavies@GeoSyntec.com]
Sent: Friday, January 20, 2006 12:10 AM
To: Petty, Harold L.
Subject: One final item

Here is the quantity take for the cost estimate. We will bring hard copies with us.

Thanks.

Neil

R. Neil Davies, C.Eng., MICE, P.E.
Principal/Branch Manager

GeoSyntec Consultants, Inc.
1255 Roberts Blvd. Suite 200
Kennesaw, GA 30144

phone: 678-202-9500
direct: 678-202-9545
fax: 678-202-9501

www.geosyntec.com

PRELIMINARY

KIF Gypsum on Peninsula
Phase 1 - Gypsum Long Term Rim Ditch Stack

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
7.00	Gypsum Stack Peninsula (7.00 through 18.00)				
7.01	Clear and grub	ac	30		C - Tree line only
7.02	Clear and grub	cy	100,000		C - 62 acres - Phase 1 & Stormwater Pond area
7.03	Strip 1 ft vegetation and topsoil - spoil at stockpile				
8.00	Erosion Controls/Ponds				
8.01	Erect silt fence	lf	7,150		C -
8.02	Cut for stormwater runoff ponds	cy	5,339		C -
8.03	Fill for stormwater runoff ponds	cy	43,223		C - gross fill volume; subtract cut to obtain net fill volume
8.04	Riprap for stormwater runoff pond (if needed)	ton	8,102		C - Pond perimeter = 2588 ft @ midslope, 57 ft slope length
8.05	CMP for outlet structure (assume 72 in dia)	lf	12		C
8.06	CMP for riser for outlet structure (assume 48 in dia)	lf	14		C
8.07	CMP outlet pipe (principal spillway - assume 48 in)	lf	150		C
8.08	Concrete for riser base (assume 7' x 7' x 2')	cy	5		C
8.09	Anti-seep collars (assume concrete)	ea	3		C -
8.10	Pipe bedding	ton	20		C
9.00	Access Roads				Assume 7000' long road, 20 ft wide
9.01	Bottom Ash	cy	2,593		C - 6" bottom ash
9.02	Crushed stone base	ton	2,566		C - 4" stone with an assumed unit weight = 110 pcf
9.03	Crushed stone base - parking lot	ton	275		C - Assume 100 ft x 100 ft w/6 in crushed stone (110 pcf)
10.00	Fencing (Excluding Dewatering Facility)				
10.01	New fencing (including grounding)	lf	200		C - Assume chain link fence to block road only
10.02	Gates	ea	2		C - 1 @ each end
11.00	Seed/Mulch				
11.01	Seed/Mulch disturbed areas	ac	16		C - Area outside perimeter berm, 100' width
12.00	Borrow Area Development				
12.01	Clear and Grub	ac	34		C
12.02	Erect silt fence	lf	5,000		C
12.03	Temporary perimeter ditch	cy			C
12.04	Additional items related to stormwater management	ls	1		C
13.00	Gypsum Disposal Facility				
13.01	Disposal Facility Construction				
13.01	Earthwork cut	cy	281,023		C - to shape base in gypsum stack area

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
13.02	Profile subgrade	ac	45		C - Phase 1 area
13.03	Earthwork fill from borrow area	cy	74,762		C - Net fill = 355784 (gross fill) - 281,023 (cut)
13.04	Cut and Recompact liner	cy	176,135		C - 3' compacted clay liner
13.05	8 oz nonwoven geotextile for centerline underdrain	sy	58,282		C - Wrapped around pipe bedding, includes 10% waste & overlap
13.06	12" depth 1081 crushed stone (110 pcf)	ton	14,260		C - 1726' long, 150' wide, 1' deep
13.07	8-in. dia HDPE centerline underdrain piping	lf	10,358		C - 6 pipes @ 1711' long each
13.08	Perimeter underdrain pipe	lf	4,000		C - at toe of soil starter berm
13.09	HDPE Fittings	ea	13		C - 5 tees, 2 elbows, 6 caps
13.10	Surface water diversion ditch	lf	3,000		C - From gypsum dewatering facility to river discharge point east of Phase II disposal area
13.11	Riprap for diversion ditch (assume D ₅₀ = 6 in)	ton	12,000		C - Assumes 10 ft deep w/9 ft bottom width & 3:1 side slopes
13.12	Drainage pipe from sump to stormwater pond	lf	580		C -
13.13	Lift Station to stormwater pond	ea	1		C -
13.14	Drop inlet	ea	1		C - North of stormwater pond
13.15	Diversion pipe beneath stormwater pond	lf	800		C -
13.16	Perimeter road - bottom ash base	cy	2,180		C - Assume 6" base layer - 1.1 mile, 20' wide roadway around perimeter on soil starter berm surface
13.17	Perimeter road - crushed stone	ton	2,160		C - Assume 4" stone layer around perimeter w/unit wt = 110 pcf
14.00	Gypsum Stack Operation				
14.01	6" dia perforated HDPE perimeter toe underdrains	lf			O&M
14.02	1081 crushed stone surrounding pipe (110 pcf)	ton			O&M
14.03	8-oz nonwoven geotextile for perimeter underdrain	sy			O&M - Wrapped around stone envelope
14.04	6" dia solid HDPE SDR 17 lateral outlet pipes	lf			O&M
14.05	Wet Cast Gypsum Dike	cy			O&M - From crown elevation of initial soil berm to 850
14.06	Cut Rim Ditches	cy			O&M
14.07	Gypsum Disposal Stack (wet sluice)	cy			O&M
14.08	Life of Gypsum Disposal Stack	yr			O&M - Assume 547,500 cu. yds. per year settled gypsum (@ 67 pcf)
15.00	Construction parking				
15.01	Earthwork cut	bcy			C
15.02	Earthwork fill	bcy			C
15.03	Crushed stone base - parking lot	ton	620		C - Assume 150' x 150' area w/6" crushed stone @ 110 pcf
16.00	Engineering				

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
16.01	Engineering	ls	1		Assume 10% of construction cost
17.00	Lift Station				
17.01	Phase 1 Pond	ea	1		
18.00	Electrical				

Notes:

- 1 C - Capital cost
- 2 O&M - Operation and Maintenance Cost
- 3 This preliminary estimate of quantities was based on conceptual drawings presented as part of the project planning document (PPD). These quantities will be updated upon the completion of the final design drawings. Prior to construction, it is the responsibility of the contractor to verify the material quantities based on final design drawings.

Toney, Calvin L.

From: Workman, Brad
Sent: Wednesday, January 25, 2006 7:27 PM
To: Toney, Calvin L.
Cc: Petty, Harold L.; Radford, Larry D.; Oliver, Don; Lowery, Kenny R.; Jones, Sonja R.; Stewart, David W.
Subject: KIF - Gypsum Pond Const. Estimate - Phase 1

Calvin,

Please review the attached Rev 01 - Phase 1 - KIF Gypsum Pond construction estimate. If you have questions or comments, please call.

Thanks,
Brad Workman
TVA - HED
(931) 320-1044

0647R1

0647R1

HED ESTIMATE SUMMARY

REV#

ESTIMATE SUMMARY

0

LOCATION: KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 1

PRINT DATE: 25-Jan-06
ESTIMATE DATE: 10-Nov-05

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 1)

WORKSCOPE: DEVELOP SOIL BORROW AREA, DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 1 OF GYPSUM POND.

DURATION: 1.35 YEARS OR (70 WEEKS) IF CLEARED, THEN SITE WORK BEGINS. INCLUDES 4 WEEKS OVERALL FOR BAD WEATHER.
 6 MONTHS FOR CLEARING OF TREES BY LOGGING COMPANY
 10 MONTHS FOR BORROW AREA DEVELOPMENT / ROAD CONSTRUCTION / POND CONSTRUCTION

PHASE	TYPE OF FUNDING
2	CAPITAL > 100K

PREPARED BY: B. WORKMAN (HED)

			Comments
1. TVA-HED LABOR COSTS			
Craft Augmented Labor	MANHOURS	76830	Includes all aspects of Phase 1 work.
	COST	\$2,926,849	Based on FY 2005 labor rates.
Non-Manual Labor	MANHOURS	11,200	Supervisor and (2) Mechanics full time for 1.35 years.
	COST	\$450,800	Includes Hourly Rates & Per Diem for both men.
Contingency 0.00%	MANHOURS	0	
	COST	\$0	
SUBTOTAL TVA-HED LABOR	MANHOURS	88,030	
	COST	\$3,377,649	
2. TVA-HED OTHER COSTS			
TVA-HED Subcontracts		\$440,600	Survey / Layout / Fence Cont./ Compac. Testing / Mulch Grinding Cont.
TVA-HED Subcontract Fee		\$0	
Travel & Living Expenses		See "Non-Manual Labor"	
TVA-HED Material Purchases		\$0	
HED Other Costs		\$0	
Contingency 0%		\$0	
SUBTOTAL TVA-HED OTHER		\$440,600	
TOTAL TVA-HED COSTS		\$3,818,249	
3. ITEMS MANAGED BY TVA-HED			
Permanent Materials		\$665,232	Per Quantities Provided by Parsons E & C.
Heavy Equipment		\$1,474,935	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment		\$0	
Small Tools		\$7,683	
Supplies, Consumables & Expendable Tools		\$23,049	
Office Supplies & Expenses		\$0	
Other TVA-HED Costs		\$0	
TVA subcontracts (By Others)		\$0	
Partner or OCIP Insurance		\$0	
TVA-HED - Central Command 10.00%		\$448,348	
Contingency 0%		\$0	
SUBTOTAL TVA-HED MANAGED		\$2,619,247	
TOTAL TVA-HED COSTS		\$6,437,497	

APPROVALS: ESTIMATE TOTAL 6,437,497

ESC TO 2008 DOLLARS

TVA-HED Estimator

TVA - Project Manager

TVA - Project Engineer

TVA - Site Environmental Engineer

Date:

Date:

Date:

Date:

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 1 Gypsum Disposal Facility Pond Construction

01/25/06

Mr. Calvin Toney,

We thank you for the opportunity to provide the following estimate for the TVA - Kingston (Phase 1) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings.

The understood TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 7,150 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Construct construction parking area.
- Cut approximately 43,223 CY of clay for stormwater runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Install 12 lf of 72” Outlet Structure.
- Install 14 lf of 48” riser.
- Install 150 lf of 48” principle spillway.
- Pour concrete “anti-seep” collars at all joints.
- Allowance - Clean out Gypsum Stack stormwater runoff pond as needed. (approximately 1,000 cy)
- Clear and Grub approximately 30 acres at Gypsum Stack Peninsula. (Includes clear cut logging as well).
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Borrow Area Development”:

- Clear and Grub approximately 34 acres at borrow site.
- Clear cut all timber on approximately 34 acres for clay borrow site.
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Haul / Access Roads”:

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 1.5 miles of roadway.
- Build Gypsum Disposal Facility Access Roadways with 2,200 TN of new stone.
- Build Gypsum Disposal Facility Access Roadways with 1,956 CY of Bottom Ash.
- Install Fence and gates at road. (200 lf w/ 1 personnel and 1 swing gate.)

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029161

“Disposal Facility Construction”:

- Proof-roll all Gypsum Stack sub-grade. (50 acres)
- Over-excavate 3' depth in Gypsum Stack liner area (approximately 50 acres), then re-place and re-compact liner material. (211,362 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 337,228 cy)
- Install centerline underdrain piping inside new Gypsum Stack.
- Install 58,282 sy of non-woven geotextile fabric in new centerline underdrain.
- Excavate and install 4,000 lf total of 8" HDPE underdrain piping around perimeter of Stack.
- Install 14,260 tn of 12" deep crushed stone in new centerline underdrain.
- Install Perimeter road with 6" of Bottom Ash topped with 4" of crushed stone. (1 mile of 20' wide roadway)
- Install rip-rap diversion ditch (approximately 12,000 tn).

“Clarifications to Estimated Scope of Work”:

- Allowance Included – 15% Double handling of liner material foreseen as risk due to unsuitable soil for liner construction encountered during over-excavation. This cost is included in estimate.
- No “rock removal / excavation” costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.
- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All “Bank Cubic Yard” quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes contingencies for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for Fence Contractor, TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed, Geotechnical Engineers to provide compaction test results as required, and mulching of tree stumps, laps, etc. after clearing of trees is completed.
- Seed and Mulch all disturbed areas outside dikes. (approximately 16 acres) is included.

“Schedule”:

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 1.35 years from start of project as stated on “Estimate Summary” sheet provided with this estimate.

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$6,437,497.00 Lump Sum

Thank You,
Kenny Lowery
TVA HED
(256)762-6401

cc: Brad Workman
TVA - HED
(931) 320-1044

TVA - HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

PRELIMINARY

KIF Gypsum on Peninsula
Phases 1 & 2 - Gypsum Long Term Rim Ditch Stack

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
7.00	Gypsum Stack Peninsula (7.00 through 18.00)				
7.01	Clear and Grub	ac	35		C - Tree line only
7.02	Clear and grub	cy	193,600		C - 120 acre area for entire site
7.03	Strip 1 ft vegetation and topsoil - spoil at stockpile				
8.00	Erosion Controls / Ponds				
8.01	Erect silt fence	lf	11,870		C - 2 stages (around Phase 1 and later around Phase 2)
8.02	Cut for stormwater runoff ponds	cy	5,339		C -
8.03	Fill for stormwater runoff ponds	cy	43,223		C - gross fill volume; subtract cut to obtain net fill volume
8.04	Riprap for stormwater runoff pond (if needed)	ton	8,102		C - Pond perimeter = 2588 ft @ midslope, 57 ft slope length
8.05	CMP for outlet structure (assume 72 in dia)	lf	12		C
8.06	CMP for riser for outlet structure (assume 48 in dia)	lf	14		C
8.07	CMP outlet pipe (principal spillway - assume 48 in)	lf	150		C
8.08	Concrete for riser base (assume 7' x 7' x 2')	cy	5		C
8.09	Anti-seep collars (assume concrete)	ea	3		C -
8.10	Pipe bedding	ton	20		C
9.00	Access Roads				Assume 7000' long road, 20 ft wide
9.01	Bottom Ash	cy	2,593		C - 6" bottom ash
9.02	Crushed stone base	ton	2,566		C - 4" stone with an assumed unit weight = 110 pcf
9.03	Crushed stone base - parking lot	ton	275		C - Assume 100 ft x 100 ft w/6 in crushed stone (110 pcf)
10.00	Fencing (Excluding Dewatering Facility)				
10.01	New fencing (including grounding)	lf	200		C - Assume chain link fence to block road only
10.02	Gates	ea	2		C - Personnel
11.00	Seed/Mulch				
11.01	Seed/Mulch disturbed areas	ac	27		C - Area outside perimeter berm (100' width)
12.00	Borrow Area Development				
12.01	Clear and Grub	ac	34		C
12.02	Erect silt fence	lf	5,000		C
12.03	Temporary perimeter ditch	cy			C
12.04	Additional items related to stormwater management	ls	1		C
13.00	Gypsum Disposal Facility				
13.01	Disposal Facility Construction	cy	588,673		C - to shape base in gypsum stack area
13.01	Earthwork cut				

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
13.02	Proofroll subgrade	ac	100		C - Phase 1 & 2 areas
13.03	Earthwork fill from borrow area	cy	145,344		C - Net fill = 734,016 (gross fill) - 588,673 (cut)
13.04	Cut and Recompact liner	cy	328,693		C - 3' compacted clay liner: = 176,135 (P1) + 152,558 (P2)
13.05	8 oz nonwoven geotextile for centerline underdrain	sy	730,110		C - Wrapped around pipe bedding, includes 10% waste & overlap
13.06	12" depth 1081 crushed stone (110 pcf)	ton	27,350		C - 3315' long, 150' wide, 1' deep
13.07	8-in. dia HDPE centerline underdrain piping	lf	19,890		C - 6 pipes @ 3315' long each
13.08	Perimeter underdrain pipe	lf	6,000		C - at top of soil starter berm
13.09	HDPE Fittings	ea	13		C - 5 tees, 2 elbows, 6 caps
13.10	Surface water diversion ditch	lf	4,435		C - From gypsum dewatering facility to river discharge point east of Phase II disposal area
13.11	Riprap for diversion ditch (assume D ₅₀ = 6 in)	ton	18,000		C - Assumes 10 ft deep w/9 ft bottom width & 3:1 side slopes
13.12	Drainage pipe from sump to stormwater pond	lf	580		C -
13.13	Lift Station to stormwater pond	ea	1		C -
13.14	Drop inlet	ea	1		C - North of stormwater pond
13.15	Diversion pipe beneath stormwater pond	lf	800		C -
13.16	Perimeter road - bottom ash base	cy	3,755		C - Assume 6" base layer - 1.92 mile, 20' wide roadway around perimeter on soil starter berm surface
13.17	Perimeter road - crushed stone	ton	3,717		C - Assume 4" stone layer around perimeter w/unit wt = 110 pcf
14.00	Gypsum Stack Operation				
14.01	6" dia perforated HDPE perimeter toe underdrains	lf			O&M
14.02	1081 crushed stone surrounding pipe (110 pcf)	ton			O&M
14.03	8-oz nonwoven geotextile for perimeter underdrain	sy			O&M - Wrapped around stone envelope
14.04	6" dia solid HDPE SDR 17 lateral outlet pipes	lf			O&M
14.05	Wet Cast Gypsum Dike	cy			O&M - From crown elevation of initial soil berm to 850
14.06	Cut Rim Ditches	cy			O&M
14.07	Gypsum Disposal Stack (wet sluice)	cy			O&M
14.08	Life of Gypsum Disposal Stack	yr			O&M - Assume 547,500 cu. yds. per year settled gypsum (@ 67 pcf) **
15.00	Construction parking				
15.01	Earthwork cut	bcy			C
15.02	Earthwork fill	bcy			C
15.03	Crushed stone base - parking lot	ton	275		C - Assume 100' x 100' area w/6" crushed stone @ 110 pcf
16.00	Engineering				
16.01	Engineering	ls	1		Assume 10% of construction cost

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
17.00	Lift Station				
17.01	Phase 1 Pond	ea	1		
18.00	Electrical				

Notes:

- 1 C - Capital cost
- 2 O&M - Operation and Maintenance Cost
- 3 This preliminary estimate of quantities was based on conceptual drawings presented as part of the Project Planning Document (PPD). These quantities will be updated upon the completion of the final design drawings. Prior to construction, it is the responsibility of the contractor to verify the material quantities based on final design drawings.

Toney, Calvin L.

Toney, Calvin L.

From: Workman, Brad
Sent: Wednesday, January 25, 2006 7:29 PM
To: Toney, Calvin L.
Cc: Petty, Harold L.; Radford, Larry D.; Lowery, Kenny R.; Oliver, Don; Jones, Sonja R.; Stewart, David W.
Subject: KIF - ~~Gypsum Pond Const. Estimate - Phase 2~~

Calvin,

Please review the attached Rev 01 - Phase 2 - KIF Gypsum Pond construction estimate. If you have questions or comments, please call.

Thanks,
Brad Workman
TVA - HED
(931) 320-1044

01/26/2006

TVA-00029168

HED ESTIMATE SUMMARY

REV# 1 ESTIMATE SUMMARY

\$6048 R1

ADD PHASE 1 FOR TOTAL BUILDOUT

LOCATION: KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 2

PRINT DATE: 25-Jan-06
ESTIMATE DATE: 10-Nov-05

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 2)

WORKSCOPE: DEVELOP SOIL BORROW AREA, DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 2 OF GYPSUM POND.

DURATION: 0.83 YEARS OR (45 WEEKS) IF CLEARED, THEN SITE WORK BEGINS. INCLUDES 6 WEEKS OVERALL FOR BAD WEATHER.
1 MONTH FOR CLEARING OF TREES BY LOGGING COMPANY
9 MONTHS FOR BORROW AREA DEVELOPMENT / ROAD CONSTRUCTION / POND CONSTRUCTION

PHASE	TYPE OF FUNDING
2	CAPITAL > 100K

PREPARED BY: B. WORKMAN (HED)

				Comments
1. TVA-HED LABOR COSTS				
Craft Augmented Labor	<i>\$37.80</i>	MANHOURS <i>143216</i>	<i>66386 + 76830</i>	Includes all aspects of Phase 1 work.
		COST <i>5413874</i>	<i>\$2,486,225 + 2926449</i>	Based on FY 2005 labor rates.
Non-Manual Labor	<i>\$40.25</i>	MANHOURS <i>15200</i>	<i>8,000 + 11200</i>	Supervisor and Mechanic full time for 1.35 years.
		COST <i>772900</i>	<i>\$322,000 + 450,800</i>	Includes Hourly Rates & Per Diem for both men.
Contingency	0.00%	MANHOURS	0	
		COST	\$0	
SUBTOTAL TVA-HED LABOR		MANHOURS <i>162416</i>	<i>74,386 + 88050</i>	
		COST <i>6,185,874</i>	<i>\$2,808,225 + 3,377,649</i>	
2. TVA-HED OTHER COSTS				
TVA-HED Subcontracts	<i>754,600</i>		<i>\$314,000 + 440,600</i>	Survey / Layout / Fence Cont. / Compac. Testing / Mulch Grinding Cont.
TVA-HED Subcontract Fee			\$0	
Travel & Living Expenses			See "Non-Manual Labor"	
TVA-HED Material Purchases			\$0	
HED Other Costs			\$0	
Contingency	0%		\$0	
SUBTOTAL TVA-HED OTHER	<i>754,600</i>		<i>\$314,000 + 440,600</i>	
TOTAL TVA-HED COSTS	<i>6,940,474</i>		<i>\$3,122,225 + 3,818,249</i>	
3. ITEMS MANAGED BY TVA-HED				
Permanent Materials	<i>1977,369</i>		<i>\$1,307,137 + 665,232</i>	Per Quantities Provided by Parsons E & C.
Heavy Equipment	<i>2502650</i>		<i>\$1,027,715 + 1474935</i>	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment			\$0	
Small Tools	<i>14322</i>		<i>\$6,639 + 7683</i>	
Supplies, Consumables & Expendable Tools	<i>42765</i>		<i>\$19,916 + 23049</i>	
Office Supplies & Expenses			\$0	
Other TVA-HED Costs			\$0	
TVA subcontracts (By Others)			\$0	
Partner or OCIP Insurance			\$0	
TVA-HED - Overhead	<i>891,284</i>	10.00%	<i>\$442,936 + 448,348</i>	
Contingency		0%	\$0	
SUBTOTAL TVA-HED MANAGED	<i>547,3589</i>		<i>\$2,804,342 + 2,619247</i>	
TOTAL TVA-HED COSTS	<i>12,362,064</i>		<i>\$5,926,567 + 6,435,497</i>	

APPROVALS: ESTIMATE TOTAL 5,926,567

ESC TO 2,008 DOLLARS

TVA-HED Estimator

TVA - Project Manager

TVA - Project Engineer

TVA - Site Environmental Engineer

Date:

Date:

Date:

Date:

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 2 Gypsum Disposal Facility Pond Construction

01/25/06

Mr. Calvin Toney,

We thank you for the opportunity to provide the following estimate for the TVA - Kingston (Phase 2) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings.

The understood TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 4,720 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Clear and Grub approximately 5 acres at Gypsum Stack Peninsula. (Includes clear cut logging as well).
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.

“Haul / Access Roads”:

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 1.5 miles of roadway.

“Disposal Facility Construction”:

- Over-excavate 3’ depth in Gypsum Stack liner area, then re-place and re-compact liner material. (approximately 183,070 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 369,180 cy)
- Install 9,532 lf of centerline underdrain piping inside new Gypsum Stack.
- Install 671,828 sy of non-woven geotextile fabric in new centerline underdrain.
- Excavate and install 2,000 lf total of 8” HDPE underdrain piping around perimeter of Stack.
- Install 13,090 tn of 12” deep crushed stone in new centerline underdrain.
- Install remaining perimeter road with 6” of Bottom Ash topped with 4” of crushed stone. (1 mile of 20’ wide roadway)
- Install rip-rap diversion ditch (approximately 6,000 tn)

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029170

“Clarifications to Estimated Scope of Work”:

- Allowance Included – 15% Double handling of liner material foreseen as risk due to unsuitable soil for liner construction encountered during over-excavation. This cost is included in estimate.
- No “rock removal / excavation” costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.
- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All “Bank Cubic Yard” quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes contingencies for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed, Geotechnical Engineers to provide compaction test results as required, and mulching of tree stumps, laps, etc. after clearing of trees is completed.
- Seed and Mulch all disturbed areas outside dikes. (approximately 11 acres) is included.

“Schedule”:

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 13 months from start of project as stated on “Estimate Summary” sheet provided with this estimate.

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$5,926,567.00 Lump Sum

Thank You,
Kenny Lowery
TVA HED
(256)762-6401

cc: Brad Workman
TVA – HED
(931) 320-1044

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA - HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

**KINGSTON FOSSIL PLANT
(KIF450) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06047 Option: 0 PCN Number: KIF450 (Gypsum Disposal)
 Plant: KIF Revision: 0 Estimate Type: Preliminary
 Cost Engineer: C. L. Toney Unit #: Estimate Accuracy: +/- 20%
 Requesting Engr: S. M. Haber Phase: 2 Estimate Issue Date 11/17/2005

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$0
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$0</u>
<u>Phase II</u>		
Engineering		\$330,288
Long Lead Procurement		\$72,000
Partner (Non-Manual)		
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$402,288</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$885,084
Labor (T&L)	96,962.57	\$3,693,018
Labor (Non-Manual)	7,583.00	\$346,750
Equipment		\$1,906,627
Subcontracts		\$340,600
Partner Fee		\$5,486
Partner Insurance		\$3,291
Escalation		\$574,309
Construction Risk Dollars		\$0
Other		\$545,660
Total Construction Cost		\$8,300,825
Engineering		\$209,850
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$1,787,037
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$10,297,712</u>
<u>All Phases</u>		
Construction Partner	104,545.57	\$8,300,825
Long Lead Procurement		\$72,000
Engineering		\$540,137
Other / Other Organizations		\$0
Total Risk Dollars		\$1,787,037
<u>Total Project Costs</u>	<u>104,545.57</u>	<u>\$10,700,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
(KIF-150) STAGE 1 GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Project name KIF/06047/STG 1 GYP POND

Estimator C. L. Toney

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Project Earthwork

Plant KIF

Estimate # 06047

PCN # KIF450

Requesting Engr S. M. Haber

Revision 0

Phase 2

Estimate Type Preliminary

Estimate Accuracy +/- 20%

Est. Issue Date 11/21/2005

Funding Type Capital

Cost estimate is based in 2008 dollars.

Short Term Storage. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.

Sorted by 'Location/Activity'
'Detail' summary

Report format

Spreadsheet Report
KIF/06047/STG 1 GYP POND

Location	Activity	Description	Takeoff Quantity	Units	Labo. Productivity	Labo. Quantity	Labo. Amount	Material Amount	Sub Amount	Equip Amount	Other Amount	Total Cost/Unit	Total Amount	
HASE 3 (BOP)	17-Pumps & Pipe	100 HP Submersible Pump For Phase 1 Stormwater Pond	1.00	ea	64.000	84.00	2,937	60,000	-	-	308	63,244.70	63,245	
		Structural Excavation For 18" Diameter Pipe (2,000 lf)	3,200.00	cy	0.200	652.00	16,311	-	-	-	8,150	7,50	24,461	
		Bottom Ash Pipe Bedding	112.00	cy	0.500	56.00	1,514	-	-	-	574	18,65	2,098	
		18" Diameter Discharge HDPE Pipe SDR11	2,000.00	lf	0.325	650.00	19,976	96,484	-	-	9,080	60,77	121,639	
		Structural Backfill For 18" Diameter Pipe (2,000 lf)	3,014.00	cy	0.320	964.48	24,128	-	-	-	23,398	15,77	47,527	
		Platforms Steel	300.00	mh	60.000	2,706.88	10,087	26,250	-	-	2,376	7,742.43	38,712	
		17-Pumps & Pipe	5.00	ton	60.000	2,706.88	74,953	178,734	-	-	45,985	-	297,572	
		18-Electrical	Phase 1 Transformer 200 kv (13.8 kv to 480 v)	1.00	ls	120.000	120.00	4,193	12,000	-	-	450	16,643.28	16,643
		40 600 Volt Cable	200.00	lf	0.100	20.00	708	2,200	-	-	-	14,54	2,908	
		3" Diameter GRC Conduit	200.00	lf	0.619	123.80	4,393	9,140	-	-	-	62.62	12,563	
HASE 3 (HED)	HED Installation	13 kv Amp Pole Mount Fuse Disconnect	1.00	ea	12.000	275.80	9,709	23,840	-	-	460	1,924.86	33,999	
		18-Electrical	18-Electrical	207.893	207.89	5,900	5,900	-	-	3,100	9,000.00	9,000		
		Mobilize, Drug Test, Miscellaneous Other, & Demobilize	207.893	207.89	5,900	5,900	-	-	3,100	9,000.00	9,000			
		XConst Facilities	XConst Facilities	207.893	207.89	5,900	5,900	-	-	3,100	9,000.00	9,000		
		zNon-Manual	zNon-Manual	383.000	383.00	19,150	19,150	-	-	-	19,150.00	19,150		
		PHASE 3 (BOP)	PHASE 3 (BOP)	109.712	109.712	3,602,456	3,602,456	-	-	-	3,602,456.00	3,602,456		
		Construction Labor	Construction Labor	83,772.000	83,772.00	3,602,456	3,602,456	-	-	-	3,602,456.00	3,602,456		
		Non Manual Labor	Non Manual Labor	7,200.000	7,200.00	327,600	327,600	-	-	-	327,600.00	327,600		
		TVA-HED Subcontracts	TVA-HED Subcontracts	1.00	ls	1.00	1.00	-	-	340,600	340,600.00	340,600		
		Partner Purchased Material	Partner Purchased Material	1.00	ls	1.00	1.00	-	754,510	-	754,510.00	754,510		
HASE 3 (HED)	HED Installation	Construction Heavy Equipment	1.00	ls	1.00	1.00	-	-	-	1,859,192.00	1,859,192			
		Small Tools	1.00	ls	1.00	1.00	-	-	-	9,377	9,377			
		Supplies, Consumables & Expandable Tools	1.00	ls	1.00	1.00	-	-	-	28,131	28,131			
		TVA-HED - Central Command	TVA-HED - Central Command	1.00	ls	1.00	1.00	-	-	-	502,517	502,517		
		HED Installation	HED Installation	100,972.00	100,972.00	3,930,056	3,930,056	-	-	340,600	1,859,192	7,424,383		
		PHASE 3 (HED)	PHASE 3 (HED)	100,972.00	100,972.00	3,930,056	3,930,056	-	-	340,600	1,859,192	7,424,383		
		Construction Heavy Equipment	Construction Heavy Equipment	1.00	ls	1.00	1.00	-	-	-	1,859,192.00	1,859,192		
		Small Tools	Small Tools	1.00	ls	1.00	1.00	-	-	-	9,377	9,377		
		Supplies, Consumables & Expandable Tools	Supplies, Consumables & Expandable Tools	1.00	ls	1.00	1.00	-	-	-	28,131	28,131		
		TVA-HED - Central Command	TVA-HED - Central Command	1.00	ls	1.00	1.00	-	-	-	502,517	502,517		

Estimate Totals

Labor	4,039,768	104,545.573	hrs						
Material	957,084								
Subcontract	340,600								
Equipment	1,906,627	1,970.471	hrs						
Other	540,025								
	7,784,104	7,784,104			72.75%				
Engineered Materials - Ph 2	72,000								C
Adjustment - Enr Materials	(72,000)								C
	7,784,104				72.75%				
Small Tools Expense (BOP)	1,436								H
Consum & Expendables (BOP)	3,623								C
Office Supplies & Exp (BOP)	573								C
	5,634	7,789,738			72.86%				
Escalation - Craft Labor	358,223								C
Escalation - Subcontract	23,501								C
Escalation - Firm Materials	36,369								C
Escalation - HED Equipment	111,552								H
Escalation - Small Tools	3,297								C
Escalation - Consumables	7,386								C
Escalation - Non-Manual Labor	33,288								C
Escalation - Office Supplies	694								C
	574,310	8,364,048			78.17%				
Partner Insurance (BOP)	3,291								C
Partner Award Fee (BOP)	5,486								C
	8,777	8,372,825			78.25%				
FPG Proj Engr - Phase 2	4,200								42.00 A
FPG Civil Engr - Phase 2	21,000								42.00 A
Parsons Engr - Phase 2	302,400								72.00 A
FPG Proj Cntrl Cost - Phase 2	672								42.00 A
FPG Cost Estimating - Phase 2	1,660								42.00 A
FPG Engr Records - Phase 2	332								42.00 A
	330,266	8,703,113			81.34%				
FPG Proj Engr - Phase 3	3,150								42.00 A
FPG Civil Engr - Phase 3	6,300								42.00 A
Parsons Engr - Phase 3	50,400								72.00 A
Mac Tec QA/QC & Cert - Ph 3	150,000								72.00 A
	209,850	8,912,963			83.30%				
Contingency TII Project @ 20%	1,787,037								L
	1,787,037	10,700,000			100.00%				
Total		10,700,000							

Page 3
11/17/2005 10:13 AM

**KINGSTON FOSSIL PLANT
(KIF450) TOTAL BUILDOUT OF GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Estimate Number 06048	Option: 0	PCN Number: KIF450 (Gypsum Disposal)
Plant: KIF	Revision: 0	Estimate Type: Preliminary
Cost Engineer: C. L. Toney	Unit #:	Estimate Accuracy: +/- 20%
Requesting Engr: S. M. Haber	Phase: 2	Estimate Issue Date 11/17/2005

<u>Phase I</u>	<u>Hours</u>	<u>Dollars</u>
Engineering		\$0
Partner (Non-Manual)		\$0
Other / Other Organizations		\$0
<u>Total Phase I</u>		<u>\$0</u>
<u>Phase II</u>		
Engineering		\$0
Long Lead Procurement		\$130,430
Partner (Non-Manual)		\$0
Other / Other Organizations		\$0
<u>Total Phase II</u>		<u>\$130,430</u>
<u>Phase III</u>		
Construction (Partner)		
Permanent Material		\$1,457,845
Labor (T&L)	209,833.35	\$8,024,608
Labor (Non-Manual)	17,872.00	\$817,640
Equipment		\$4,224,969
Subcontracts		\$594,600
Partner Fee		\$12,441
Partner Insurance		\$7,465
Escalation		\$1,229,302
Construction Risk Dollars		\$0
Other		\$1,124,680
Total Construction Cost		\$17,493,550
Engineering		\$419,700
Direct plant support + TVA Other Costs		\$0
Project Risk Dollars		\$3,656,320
Other / Other Organizations		\$0
<u>Total Phase III</u>		<u>\$21,569,570</u>
<u>All Phases</u>		
Construction Partner	227,705.35	\$17,493,550
Long Lead Procurement		\$130,430
Engineering		\$419,700
Other / Other Organizations		\$0
Total Risk Dollars		\$3,656,320
<u>Total Project Costs</u>	<u>227,705.35</u>	<u>\$21,700,000</u>
<u>For Information only Total Environmental</u>		<u>\$0</u>
<u>For Information only Total Demolition Costs</u>		<u>\$0</u>

**KINGSTON FOSSIL PLANT
(KIF450) TOTAL BUILDOUT OF GYPSUM POND
PHASE 2 APPROVAL COST ESTIMATE**

Project name KIF06048/STG 2 GYP POND

Estimator C. L. Toney

Labor rate table KIF 40 2005

Equipment rate table TVA Equipment

Earthwork

KIF

06048

KIF450

S. M. Haber

0

2

Preliminary

+/- 20%

11/21/2005

Capital

Cost estimate is based in 2008 dollars.

Gypsum Long Term Rtn Ditch Stack. Construction earthwork portion of estimate provided by HED. Remainder provided by ESS Group.

Notes

Report format

Sorted by Location/Activity
Detail summary

Spreadsheet Report
KIF/06048/STG 2 GYP POND

Estimate Totals

	227,705,350	hrs	
Labor	8,842,248		
Material	1,588,275		
Subcontract	554,600		
Equipment	4,224,869		
Other	1,110,961		
	16,360,156	75.39%	C
Engineered Materials - Ph 2	130,430		
Adjustment - Enor Materials	(130,430)		
	16,360,156	75.39%	C
Small Tools Expense (BOP)	3,720	0.018 \$/hr	H
Consum & Expendables (BOP)	9,409	0.117 %	C
Office Supplies & Exp (BOP)	1,458	0.182 %	C
	16,374,773	75.46%	C
Escalation - Craft Labor	778,387	9.700 %	C
Escalation - Subcontract	41,027	6.900 %	C
Escalation - Perm Materials	60,354	3.800 %	C
Escalation - HED Equipment	246,222	6.000 %	C
Escalation - Small Tools	7,134	0.084 \$/hr	H
Escalation - Consumables	16,049	0.200 %	C
Escalation - Non-Manual Labor	78,409	9.600 %	C
Escalation - Office Supplies	1,635	0.200 %	C
	1,229,301	81.12%	C
Partner Insurance (BOP)	7,465	0.084 %	C
Partner Award Fee (BOP)	12,441	0.141 %	C
	19,906	81.22%	C
FPG Prof Enor - Phase 3	6,300	0.066 % @	42.00 A
FPG Civil Enor - Phase 3	12,600	0.132 % @	42.00 A
Parsons Enor - Phase 3	100,800	0.615 % @	72.00 A
Mac Tec O&MOC & Cent - Ph 3	300,000	3.137 % @	42.00 A
	419,700	83.15%	A
Contingency Till Project @ 20%	3,656,320		L
	3,656,320	100.00%	L
Total	21,700,000		

Message

Toney, Calvin L.

From: Petty, Harold L.
Sent: Thursday, November 03, 2005 1:42 PM
To: Smith, Daniel R.; Lowery, Kenny R.; Toney, Calvin L.; Bowers, Larry C; Workman, Brad
Cc: Purkey, Ronald E.; Radford, Larry D.; Latsch, Mitchell D.
Subject: KIF - Gypsum Peninsula - coordination highlights

Here's a bullet list of what we talked about in today's meeting.

Dan Smith is to resend the drawings (as a .pdf file) and the quantities to Brad Workman & Kenny Lowery.

Kenny Lowery and Brad Workman (HED) are estimating the gypsum storage area heavy earthwork (civil construction per the quantities that Dan is providing. Two estimates are expected. **Stage 1** - (expected construction) building the partial pond on the side closest to the plant and dewatering area. The **Stage 2** estimate is really a total build out of the entire footprint. HED's input to Calvin is due to him Nov. 10th (but can be read as in his hands the morning of Nov 14th.)

Dan (WorleyParsons) is finishing up the other input (electrical, mechanical, some civil) that includes the pumps, xformers, pump platforms, discharge line pipe, etc. That is due to Calvin on the same timeframe - Nov. 10th (but can be read as in his hands the morning of Nov 14th.).

Further to that end we identified a point (coordinates later) of where the power will be supplied to by Advatech. That serves as an interface point location to identify scope of who does what and where.....

Calvin will roll up the estimate the week of Nov 14th (he is out of the office Nov. 18th) giving him time to ask questions for clarification, etc. His roll up will be complete Nov 21st.

We also discussed the blanket underdrain and need for speedy resolution.

Our next coordination meeting will be Wednesday 11/9/05 at 10 am. I'll send out a meeting notice. Anyone who cannot attend can call in via phone.

Thanks,
Lynn

- ENGR Follup -

J F M A M J J A S O N D J F M A M J J A S O N D J F M A M J J A S O N D A

CONTACT TDOT RE: TURNING LANE HWY 70

FY 06 MECH ENG SUPP - KINGSTON 6- 9 FGD ADDITION
 FY 06 FIRE PROT SUPP-KINGSTON 6- 9 FGD ADDITION
 FY 06 AGW&S SUPP-KINGSTON 6- 9 FGD ADDITION
 FY 06 CIVIL SUPP-KINGSTON 6- 9 FGD ADDITION
 FY 06 ELECT SUPP-KINGSTON 6- 9 FGD ADDITION
 FY 06 CIVIL SUPP-KINGSTON 6- 9 FGD ADDITION
 FY 06 KIF450 U6-9 FGD ADD-PROJECT CONTROL SUPPORT
 FY 06 KIF450 U6-9 FGD -COST ESTIMATING SUPPORT

50 DEVELOP SWPPP (FGD/LHF CONSTRUCT PERMIT)

KIF450
 KENINSULA

U3 FGD - ELECTRICAL - REVIEW APS STUDY

PAF200-U3 FGD - ELECT- REVIEW ARC FLASH STUDY
 PAF200 ELECT- REVW RELAY COORD.FOR 12B(ABSORBER)
 PAF200 ELECT- REVW RELAY COORD.FOR 406 AREA (L-S)
 PAF200 ELECT- UPS FAT IN RHODE ISLAND
 PAF200 ELECT- REVW PAF ELECT CALC'S (RESUBMITTAL)
 PAF200 ELECT- REVW CONTACTOR GROUNDING DEVICE

SCOD	Activity ID	Forecast Start	Forecast Finish	Finish Target
15 A 001DQ13	VRRESKIFC1	15JUL05A	30AUG05A	
11 A 001DQ13	VRRESKIFZ4	03OCT05A	30SEP06	
39 A 001DNL4	VRRESSYSAG	03OCT05A	30SEP06	
39 A 001DNL4	VRRESSYSAH	03OCT05A	30SEP06	
35 A 001DQ13	VRRESSYSAI	03OCT05A	30SEP06	
36 A 001DQ13	VRRESSYSAJ	03OCT05A	30SEP06	
35 A 001B9NF	VRRESSYSAK	03OCT05A	30SEP06	
15 A 001DQ14	VRRESKIFPM	27FEB06*	09JUN06	
15 A 001DQ13	VRRESKIFCE	03NOV05A	29SEP06	

VRKIFSWP00 17NOV05* 06JAN06

PAF--U3 FGD ADDITION

Phase A Preliminary Engineering

37 A 001B9NF	VRPAF200E0	25MAY05A	01JUL05A	
37 A 001B9NF	VRPAF200E1	25JUL05A	05AUG05A	
37 A 001B9NF	VRPAF200E2	25JUL05A	05AUG05A	
37 A 001B9NF	VRPAF200E3	25JUL05A	05AUG05A	
37 A 001B9NF	VRPAF200E5	16AUG05A	17AUG05A	
37 A 001B9NF	VRPAF200E6	29AUG05A	06SEP05A	
37 A 001B9NF	VRPAF200E4	14NOV05*	18NOV05	

35 A 001B9NF	VRRESPAFC2	29SEP03A	26SEP04A	
35 A 001B9NF	VRRESPAFC3	29SEP03A	26SEP04A	

Start Date	08AUG00	Early Bar
Finish Date	30NOV07	Progress Bar
Data Date	06NOV05	Critical Activity
Run Date	03NOV05 13:25	

FHEM - GENA	TENNESSEE VALLEY AUTHORITY	Sheet 4 of 5
Classic Schedule Layout	Revision	Checked
	Date	Approved

Toney, Calvin L.

KIF450

From: Smith, Daniel R (Chattanooga) [Daniel.R.Smith@worleyparsons.com]

Sent: Sunday, October 30, 2005 7:26 PM

To: Toney, Calvin L.; Radford, Larry D.

Cc: Petty, Harold L.; Hughes, Michael

Larry/Calvin, attached please find quantity takeoffs for the peninsula site at KIF. We will need two estimates; one for Phase 1 and another for Phase 2. Information for pumps will be provided later.

Lynn, I will probably need to schedule a meeting shortly if Larry and Calvin need to discuss. Larry, who will do the estimating for HED?

Thanks

Daniel R. (Dan) Smith, PE
Supervising Civil Engineer
WorleyParsons
633 Chestnut St., Suite 400 Ph (423)757-8088
Chattanooga, TN 37450 Fax (423)266-0922
Email: daniel.r.smith@worleyparsons.com

STAGE 1
Phase 1

KIFASD
DOLLARS 11/07/2005

PRELIMINARY

Gypsum on Peninsula
ase 1 - Gypsum Pond (Short-term Storage)

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
7.00	Gypsum Stack Peninsula (7.00 through 18.00)				See Note 1 at end of table
7.01	Clear and Grub	ac	25		C - Treeline only
7.02	Clear and grub				C - 52 ac entire site, place soil on site approximately 1 mile roundtrip.
7.03	Strip 1 ft vegetation and topsoil - spoil at stockpile	bcy	83,893		
8.00	Erosion Controls / Ponds				C - 6 ft post spacing, trench bottom of fence, 10% hay bales
8.01	Erect silt fence	lf	5,875		C - Phase 1 Pond: 6 ac 17' deep. Place as fill in gypsum stack area
8.02	Cut for stormwater runoff ponds	bcy	130,250		C - No fill will be required for Pond 1 b/c it lies in cut
8.03	Fill for stormwater runoff ponds	bcy	0		C - Combined - 1 ft deep along inside slope
8.04	Riprap for stormwater runoff pond	ton	2,713		C
8.05	72 in dia cmp for outlet structure	lf	12		C
8.06	48 in dia cmp for riser for outlet structure	lf	14		C
8.07	Cut holes in riser	ea	6		C
8.08	48 in dia cmp outlet pipe (principle spillway)	lf	300		C
8.09	(2) Concrete for riser base (assume 7ft x 7 ft x 2 ft)	cy	9		C - Assume 1.5 cy concrete per collar
8.10	Anti-seep collars (assume concrete)	ea	14		C
8.11	Pipe bedding - #57 stone	ton	40		C - Assume 2 ft sediment, 67 cy/ac depth x 40 ac
8.12	Clean out stormwater runoff pond	bcy	2,680		Assume 1 mile of roadway (5280 ft); road is 20 ft wide
9.00	Access Roads				C - Assume 6 in bottom ash
9.01	Bottom Ash	bcy	1956		C - Assume 4 inch stone (1032), 110 pcf
9.02	Crushed stone base	ton	1917		C - Assume 100 x 100 ft w/ 6 in crushed stone (110 pcf)
9.03	Crushed stone base	ton	275		
10.00	Fencing (Exclude De-watering Facility)				C - Assume chain link fence to block road only - no perimeter fence
10.01	New fencing (including grounding)	lf	200		C - personnel
10.02	Gates, swinging	ea	1		C - 20 ft wide
10.03	Gates, sliding, w/ motorized operator	ea	1		
11.00	Seed/Mulch				C - Areas outside dike
11.01	Seed/Mulch disturbed areas	ac	12		

12.00	Borrow Area Development								
12.01	Clear and grub	ac	8						C
12.02	Erect silt fence	lf	3,000						C
12.03	Temporary perimeter ditch	bcy	1,450						C
12.04	Cut for stormwater runoff ponds	bcy	1,106						C
12.05	Fill for stormwater runoff ponds	bcy	222						C
12.06	Fill for stormwater runoff structure	lf	12						C
12.07	72 in dia cmp for outlet structure	lf	20						C
12.08	48 in dia cmp for riser for outlet structure	ea	5						C
12.09	Cut holes in riser	lf	200						C
12.10	48 in dia cmp outlet pipe (principle spillway)	lf	9						C
12.10	(2) Concrete for riser base (assume 7ft x 7 ft x 2 ft)	cy	20						C - Assume 1.5 cy concrete per collar
12.11	Anti-seep collars (assume concrete)	ea	25						C - Assumed Unit wt = 125 pcf
12.12	Pipe bedding - #57 stone	ton	3,226						C
12.13	Clean out stormwater runoff pond	bcy							
13.00	Gypsum Disposal Facility								
13.01	Disposal Facility Construction								
13.01	Earthwork cut	bcy	251,537						C - to shape base in gypsum stack area
13.02	Earthwork fill from borrow area	bcy	254,073						C - Remaining fill from onsite borrow area. 635860- (251537+130250)=254073 Haul Length = 2.2 miles roundtrip
13.03	Additional spoil material	bcy	0						C
13.04	Proofroll subgrade	ac	50						C - Over excavate 3' and recompact to build liner
13.05	Cut and recompact liner	bcy	215,556						C - 8 in dia HDPE, SDR = 17, perforated
13.06	Perimeter underdrain pipe	lf	5,250						C
13.07	Cut for Underdrain system	cy	1,000						C - Wrapped around pipe bedding
13.08	Geotextile 8 oz nonwoven for underdrain	sy	7,500						C - Initial bedding for underdrain piping
13.09	6" depth 1081 crushed stone (110 pcf)	ton	495						C
13.10	Underdrain piping (8" dia HDPE)	lf	9000						C
13.11	HDPE Fittings for underdrain piping	ea	65						C
13.12	2.5' thick bottom ash drainage layer	bcy	179,630						C - Mix
13.13	6" Fly ash layer	bcy	35,926						C - 6 in bottom ash topped w/ 4 in stone - 1 mi of roadway 20 ft wide
13.14	Perimeter road surfacing - bottom ash	cy	1956						C - Assumed Unit wt = 110pcf - 1 miles of roadway
13.15	Perimeter road surfacing - crushed stone	ton	1917						C - Assume 2 ft deep riprap, 5165 lf ditch, Unit wt = 110 pcf
13.16	Riprap Ditch (D50 = 6 in)	ton	41,475						C - Assume ditch has 9 ft bottom width, 10 ft depth and 3:1 side slopes
13.17	8oz nonwoven geotextile (if riprap is used)	sy	41,894						

14.00	Gypsum on Peninsula Disposal Cost				
15.00	Construction parking				
15.01	Earthwork cut	bcy	833		C
15.02	Earthwork fill	bcy	300		C
15.03	Crushed stone base	ton	675		C - Assume 150 x 150 ft x 6 in thick crushed stone base
16.00	Engineering				
16.01	Engineering	ls			C - Take 10% of construction cost (see Dan Smith to confirm engineering cost).
17.00	Pump Station				
17.01	Phase 1 Pond				Later
17.02	Phase 2 Pond				Later
18.00	Electrical				See Electrical takeoffs

Notes:
 . Item #7 corresponds to Gypsum Disposal at the Peninsula. This numbering system matched the one used for the comparative study done in December '04.

2 - Capital cost
 O&M - Operation and Maintenance cost

Red means that these O&M quantities DO NOT need to be estimated.
 Yellow means that these quantities will be provided later

PH 2 - Approval

06/17

Toney, Calvin L.

From: Workman, Brad
Sent: Monday, November 14, 2005 12:04 PM
To: Toney, Calvin L.
Cc: Petty, Harold L.; Radford, Larry D.; Lowery, Kenny R.; Stewart, David W.
Subject: HED - KIF Phase 1 Gypsum Pond Construction Estimate

Calvin,
I have attached KIF Gypsum Pond Const. Estimate and Detailed Estimate Summary. If you have questions or comments, please give me a call.

Thank you,
Brad Workman
TVA - HED
(931) 320-1044

Page 1 of 1

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 1 Gypsum Disposal Facility Pond Construction

11/14/05

Mr. Calvin Toney,

We thank you for the opportunity to provide the following estimate for the TVA - Kingston (Phase 1) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings.

The understood TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 8,875 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Construct construction parking area.
- Cut approximately 156,300 CY of clay for stormwater runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Install 12 lf of 72” Outlet Structure.
- Install 14 lf of 48” riser.
- Install 2,713 TN of Rip Rap 1’ deep inside slope of pond.
- Install 300 lf of 48” principle spillway.
- Pour concrete “anti-seep” collars at all joints.
- Allowance - Clean out Gypsum Stack stormwater runoff pond as needed. (approximately 3,216 cy)
- Clear and Grub approximately 25 acres at Gypsum Stack Peninsula. (Includes clear cut logging as well).
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.
- Seed / Mulch approximately 12 acres outside Gypsum Disposal Facility dikes.

“Borrow Area Development”:

- Clear and Grub approximately 8 acres at borrow site.
- Clear cut all timber on approximately 8 acres for clay borrow site.
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.
- Strip approximately 83,893 CY of topsoil from the stated 8 acre borrow area, haul and spoil at Gypsum Disposal Facility site approximately ½ mile away from borrow area.
- Excavate temporary ditch on perimeter of borrow area. (approximately 1,740 CY of material to be excavated).

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029189

- Cut approximately 1,327 CY of clay for stormwater runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Install 12 lf of 72" Outlet Structure.
- Install 20 lf of 48" riser.
- Install 200 lf of 48" principle spillway.
- Pour concrete "anti-seep" collars at all joints.
- Allowance - Clean out borrow area stormwater runoff pond as needed. (approximately 3,871 cy)

"Haul / Access Roads":

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 1.5 miles of roadway.
- Build Gypsum Disposal Facility Access Roadways with 2,200 TN of new stone.
- Build Gypsum Disposal Facility Access Roadways with 1,956 CY of Bottom Ash.
- Install Fence and gates at road. (200 lf w/ 1 personnel and 1 swing gate.)

"Disposal Facility Construction":

- Proof-roll all Gypsum Stack sub-grade. (50 acres)
- Over-excavate 3' depth in Gypsum Stack liner area (approximately 50 acres), then re-place and re-compact liner material. (258,667 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 301,844 cy)
- Cut, haul and compact clay fill from borrow area inside Gypsum Stack dike base. (approximately 304,888 cy)
- Excavate and install 14,250 lf total of 8" HDPE underdrain piping around perimeter of Stack.
- Install approximately 495 ton of underdrain bedding stone.
- Wrap pipe bedding stone with 7,500 SY of 8 oz. geotextile for underdrain.
- Install 2.5' thick Bottom Ash drainage layer. (approximately 215,556 cy)
- Install 6" thick Fly Ash layer over Bottom Ash (mix). (approximately 43,111 cy)
- Install Perimeter road with 6" of Bottom Ash topped with 4" of crushed stone. (1 mile of 20' wide roadway)
- Excavate and install 2' deep rip-rap stone on 8oz. geotextile in Gypsum Stack Perimeter Ditch. (approximate ditch dimensions - 1 mile long x 10' deep x 9' wide bottom. Estimate assumes ditch will be constructed with fill dirt from borrow area while constructing stack dikes. No typical detail provided. Approximately 41,475 ton of rip-rap, and 41,894 SY of 8oz geotextile material.)

"Clarifications to Estimated Scope of Work":

- Allowance Included - 15% Double handling of liner material foreseen as risk due to unsuitable soil for liner construction encountered during over-excavation. This cost is included in estimate.
- No "rock removal / excavation" costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.

TVA - HEAVY EQUIPMENT DIVISION
 933 OLD FERRY ROAD
 SPRING CITY, TENNESSEE 37381
 PH: (423) 365-8739 FAX: (423) 365-8705

- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All "Bank Cubic Yard" quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes contingencies for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for Fence Contractor, TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed, Geotechnical Engineers to provide compaction test results as required, and mulching of tree stumps, laps, etc. after clearing of trees is completed.
- Seed and Mulch all disturbed areas outside dikes. (approximately 12 acres)

"Schedule":

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 1 ½ years from start of project as stated on "Estimate Summary" sheet provided with this estimate.

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$7,424,383.00 Lump Sum

Thank You,
Kenny Lowery
TVA HED
(256)762-6401

cc: Brad Workman
(931) 320-1044

TVA - HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

HED ESTIMATE SUMMARY

REV# 0

0

LOCATION: KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 1

PRINT DATE: 14-Nov-05
ESTIMATE DATE: 10-Nov-05

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 1)

WORKSCOPE: DEVELOP SOIL BORROW AREA, DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, BUILD HAUL ROADS, BUILD ACCESS ROADS, BUILD CONSTRUCTION PARKING AREA, BUILD PHASE 1 OF GYPSUM POND.

DURATION: 1.5 YEARS OR (76 WEEKS) IF CLEARED, THEN SITE WORK BEGINS. INCLUDES 4 WEEKS OVERALL FOR BAD WEATHER.

8 MONTHS FOR CLEARING OF TREES BY LOGGING COMPANY

1 YEAR FOR BORROW AREA DEVELOPMENT / ROAD CONSTRUCTION / POND CONSTRUCTION.

PHASE	TYPE OF FUNDING
2	CAPITAL > 100K

PREPARED BY: B. WORKMAN (HED)

1. TVA-HED LABOR COSTS			Comments
Craft Augmented Labor	MANHOURS	93772	Includes all aspects of Phase 1 work. Based on FY 2005 labor rates.
	COST	\$3,602,456	
Non-Manual Labor	MANHOURS	7,200	Supervisor and Mechanic full time for 1.5 years. Includes Hourly Rates & Per Diem for both men.
	COST	\$327,600	
Contingency 0.00%	MANHOURS	0	
	COST	\$0	
SUBTOTAL TVA-HED LABOR	MANHOURS	100,972	
	COST	\$3,930,056	
2. TVA-HED OTHER COSTS			
TVA-HED Subcontracts		\$340,600	Survey / Layout / Fence Cont. / Compac. Testing / Mulch Grinding Cont.
TVA-HED Subcontract Fee		\$0	
Travel & Living Expenses		See "Non-Manual Labor"	
TVA-HED Material Purchases		\$0	
HED Other Costs		\$0	
Contingency 0%		\$0	
SUBTOTAL TVA-HED OTHER		\$340,600	
TOTAL TVA-HED COSTS		\$4,270,656	
3. ITEMS MANAGED BY TVA-HED			
Permanent Materials		\$754,510	Per Quantities Provided by Parsons E & C.
Heavy Equipment		\$1,859,192	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment		\$0	
Small Tools		\$9,377	
Supplies, Consumables & Expendable Tools		\$28,131	
Office Supplies & Expenses		\$0	
Other TVA-HED Costs		\$0	
TVA subcontracts (By Others)		\$0	
Partner or OCIP Insurance		\$0	
TVA-HED - Central Command	10.00%	\$502,517	
Contingency 0%		\$0	
SUBTOTAL TVA-HED MANAGED		\$3,153,727	
TOTAL TVA-HED COSTS		\$7,424,383	

APPROVALS: ESTIMATE TOTAL 7,424,383 LS

ESCALATE TO 2008 DOLLARS

_____	_____
TVA-HED Estimator	Date:
_____	_____
TVA - Project Manager	Date:
_____	_____
TVA - Project Engineer	Date:
_____	_____
TVA - Site Environmental Engineer	Date:

Toney, Calvin L.

Toney, Calvin L.

From: Smith, Daniel R (Chattanooga) [Daniel.R.Smith@worleyparsons.com]
Sent: Monday, November 14, 2005 5:08 PM
To: Toney, Calvin L.
Cc: Workman, Brad; Lowery, Kenny R.; Petty, Harold L.; Hughes, Michael
Subject: KIF Peninsula - Speadsheets with electrical and pumps added


Attached are updated QTO for pumps, piping, and electrical components. A separate tab has been set up. This file name is the same as it was before, so it will overwrite any previous files. Only the electrical and pump info has been added in the separate tab – nothing else has been added.

Daniel R. (Dan) Smith, PE
Supervising Civil Engineer
WorleyParsons
633 Chestnut St., Suite 400 Ph (423)757-8088
Chattanooga, TN 37450 Fax (423)266-0922
Email: daniel.r.smith@worleyparsons.com

*** WORLEYPARSONS GROUP NOTICE ***

"This email is confidential. If you are not the intended recipient, you must not disclose or use the information contained in it. If you have received this email in error, please notify us immediately by return email and delete the email and any attachments. Any personal views/ opinions expressed by the writer may not necessarily reflect the views/ opinions of the company."

PE 22009 (1) 79
 6" BA bedding 27 cft
 3 x DS x 200 = 112 cys
 27 cft
 BACKFILL = 3,260 cys - (112 cys + 131 cys) = 3014 cys



$\frac{1}{2} (16+2) \times 5 \times 450 = 5,250$
 27 cft
 6" BA bedding 2,054 cys = 16 cys
 BACKFILL 5,250 cys (16 + 131 cys) = 147 cys
 4,952 cys

Page 1 of 1
 BA FILL 2226L
 12 B1M
 22 PDT

PE 22009 (1) 79
 6" BA bedding 27 cft
 3 x DS x 200 = 112 cys
 27 cft
 BACKFILL = 3,260 cys - (112 cys + 131 cys) = 3014 cys

ITEM	DESCRIPTION	UNITS	QUANTITY	Comments/Assumptions
17.00	Pumps & Pipe Phase 1 100 hp pump for Phase 1 Stormwater Pond	ea	1	
17.01	18 in dia discharge HDPE pipe SDR 11 @ 344.04' / 18'	lf	2000	Bury 3.5 ft deep with bottom ash bedding
17.02	Platform steel	ton	5	
17.03	Pumps & Pipe Full buildout 50 hp pump for Phase 2 stormwater Pond	ea	1	
17.04	12 in dia discharge HDPE Pipe SDR 11 @ 22,192' / 12'	lf	1724500	Bury 3.5 ft deep with bottom ash bedding
17.05	Platform steel	ton	5	
18.00	Electrical Phase 1			
18.01	Phase 1 Transformer 200kva	LS	\$8,000	13.8 kV to 480 v underground
18.02	4 / 0 600 volt Cable @ 3.03' @ 0.06	lf	200	underground
18.03	3 in dia conduit	lf	200	underground
18.04	13 kV 15 amp pole mount fuse disconnect	ea	1	
18.05	Electrical Full buildout Phase 1 Transformer 200kva	LS	\$8,000	13.8 kV to 480 v underground
18.06	4 / 0 600 volt Cable	lf	200	underground
18.07	3 in dia conduit	lf	200	underground
18.08	13 kV 15 amp pole mount fuse disconnect	ea	1	aboveground - see below
18.09	No 6 15 kvolt overhead cable	lf	4500	Assume 300 ft spacing - aboveground on poles
18.10	Poles between ponds	ea	15	
18.11				
18.12				
18.13				
18.14				

1 cft
 2000 cft
 1724500 cft
 3014 cft
 7 MEN

FOR 50HP 54mi A FOR ESTIMATE me \$3K
 FOR 100HP 84mi/EA FOR ESTIMATE me \$2K
 (Factor 1.6)

Cast iron single stage vertical sump pumps

Mounted on steel support plate and supplied with cast iron strainer, 1750 RPM drip-proof motor, using a 20-ton hydraulic crane with 70' boom and small tools.

800 GPM, 6" discharge, 70' head, 20 HP	pj@28.5	Ea	4270.00	736.00	64.40	5070.40
1000 GPM, 6" discharge, 70' head, 30 HP	pj@28.5	Ea	4510.00	736.00	64.40	5310.40
1600 GPM, 8" discharge, 70' head, 50 HP	pj@33.6	Ea	12100.00	868.00	75.90	13043.90
2000 GPM, 8" discharge, 70' head, 60 HP	pj@37.3	Ea	9130.00	963.00	84.30	10177.30
Add for each extra column assembly 60" or less	---@10.0	Ea	--	--	23.00	23.00
Add for general purpose copper coated float switch	---@6.00	Ea	125.00	--	--	125.00
Add for 24" square steel sump cover	---@4.00	Ea	133.00	--	--	133.00
Add for 36" square steel sump cover	---@6.00	Ea	111.00	--	--	111.00
Add for 48" square steel sump cover	---@8.00	Ea	309.00	--	--	309.00
Add for 60" square steel sump cover	---@11.0	Ea	681.00	--	--	681.00
Add for 72" square steel sump cover	---@15.0	Ea	854.00	--	--	854.00

Submersible sump pumps, 15' head, 1-1/2" discharge

Using small tools.

15 gallons per minute	nb@1.67	Ea	91.00	50.60	.78	142.38
42 gallons per minute	nb@1.67	Ea	238.00	50.60	.78	289.38
52 gallons per minute	nb@2.00	Ea	444.00	60.50	.94	505.44

CSI 15-146, Submersible pumps

CSI 15-146	Craft@Hrs	Unit	Material	Labor	Equip	Total
Installed in wells to 180' (55m) deep, using a 20-ton hydraulic crane with 70' boom and small tools.						
250 to 770 gallons per hour	nt@12.2	Ea	425.00	322.00	66.60	813.60
550 to 1,600 gallons per hour	nt@14.0	Ea	553.00	369.00	76.40	998.40
800 to 2,200 gallons per hour	nt@14.0	Ea	966.00	369.00	76.40	1411.40

Submersible pump rental

using a 20-ton hydraulic crane with 70' boom and small tools.

2", per day	---@---	Day	--	--	32.00	32.00
2", per week	---@---	Week	--	--	102.00	102.00
2", per month	---@---	Mo	--	--	287.00	287.00
4", per day	---@---	Day	--	--	72.00	72.00
4", per week	---@---	Week	--	--	230.00	230.00
4", per month	---@---	Mo	--	--	659.00	659.00

Well pumps, 6" discharge

Using a 20-ton hydraulic crane with 70' boom and small tools.

50 to 125 gallons per hour, for wells, 50-150' deep	nt@20.0	Ea	1280.00	528.00	109.00	1917.00
15 to 135 gallons per hour, for wells, 200-500' deep	nt@28.0	Ea	1820.00	739.00	153.00	2712.00

CSI 15-147, Pneumatic ejectors

CSI 15-147	Craft@Hrs	Unit	Material	Labor	Equip	Total
Electronic level controls, inlet and outlet check valves, gate valves, and standard cross connections. Costs exclude air compressor, air receiver, and air piping and fittings. See CSI 15-310 for submersible sewage ejectors, using a 20-ton hydraulic crane with 70' boom and small tools.						
30 gallons per hour	nt@14.0	Ea	12100.00	369.00	76.40	12545.40
50 gallons per hour	nt@15.6	Ea	12100.00	412.00	85.20	12597.20

100 gallons per hour	nt@18.7	Ea	14500.00	493.00	102.00	15095.00	Ea
150 gallons per hour	nt@21.5	Ea	16900.00	567.00	117.00	17584.00	Ea
200 gallons per hour	nt@28.0	Ea	21800.00	739.00	153.00	22692.00	Ea
250 gallons per hour	nt@35.0	Ea	24200.00	923.00	191.00	25314.00	Ea
300 gallons per hour	nt@56.0	Ea	30300.00	1480.00	306.00	32086.00	Ea
Add for cast iron receivers	---@---	%	20.00	--	--	--	--
Add for mechanical level control	---@---	%	20.00	--	--	--	--

CSI 15-148, Pneumatic pumps

CSI 15-148	Craft@Hrs	Unit	Material	Labor	Equip	Total
Excludes air compressor cost, using small tools.						
Pumping unit, oil and gear lubrication	nb@1.67	Ea	884.00	50.60	.78	935.38
Pumping unit, grease	nb@1.67	Ea	1240.00	50.60	.78	1291.38

Pneumatic powered pumping unit accessories

Using small tools, using small tools.

Hose reel, 1,000 PSI, oil and lubrication	nb@1.25	Ea	602.00	37.80	.59	640.39
Hose reel, 5,000 PSI, grease	nb@1.25	Ea	692.00	37.80	.59	730.39



Add a little power to these material costs

The figures above are from a time and money saving construction cost manuals from Craftsman Book Company. Over 50 cost estimating databases are available and all come with the popular National Estimator program.

National Estimator helps you compile estimates and bids for any construction project

National Estimator lets you use these costs to create estimates for new construction, repair and remodeling, commercial and industrial projects. Copy and paste and anything you see here into your estimate. Then add overhead and profit and print the bid – or turn your bid into an invoice that goes out in a window envelope. It's quick, easy and flexible.

Find out more about using these cost estimates with the National Estimator program:

[Click here](#) for more information on getting these cost estimates in book form and CD-ROM

[Click here](#) for more information on getting these costs as a download on the Web.

National Estimator includes the following features:

Prints estimates and saves estimates to disk.

Add any percent for overhead, profit and sales tax. Plus, show or hide markup and unit costs.

Change, copy, revise or delete an estimate at any time.

Use your own labor rates and man-hour estimates.

Export to Excel, Word, QuickBooks Pro and others

Organize estimates by division with subtotals.

Turn estimates into invoices

No need to be connected to the Web when estimating.

Includes an extensive help system and free phone support.

CD-ROM includes the Watch Me video on disk.

✓ - Transformer 200KVA 13.8kv to 480V
 Mater \$12,000/ea
 Lab 120 mhrs /ea Crew 6 Journeymen

✓ - 4/0 600V Cable 200lf
 * Assumed 4w/ground
 Mater \$10 /lf
 Lab 0.1 mhrs /lf Crew 6 Journeymen

✓ - 3" GRC 200lf
 Mater \$37 /lf
 Lab 0.619 mhrs /lf Crew 6 Journeymen

✓ - 13KV 15amp pole mount fuse disconnect
 Mater \$1500/ea
 Lab 12 mhrs/ea Crew 6 Journeymen

✓ - #6 15kv 4500lf
 * Assumed 3 conductor
 3 single conductor runs
 Mater \$3.14/lf * 3 * 4500 = \$42,390
 Labor 0.08 mhrs * 4500 = 360 mhrs

✓ - Poles between ponds 15ea
 Mater \$502/ea eq \$100/ea
 Labor 12 mhrs/ea
 * Assumed 40' wood pole with 4' cross arm

PCN Number: **PCN Description:** KIF - Gypsum Disposal Area - Peninsula - Stage 1
Current Phase: 1 **Phase Request:** 2 **Date:** 11/17/2005

	Phase I		Phase II		Phase III		Prin/RE Engr
	Hours	\$	Hours	\$	Hours	\$	
Project Engr		\$0	100	\$4,200	75	\$3,150	
Mech Engr		\$0		\$0		\$0	
Elec Engr I		\$0		\$0		\$0	
Elec Engr II		\$0	500	\$21,000	150	\$6,300	
Civil Engr		\$0		\$0		\$0	
Air, Gas, Wtr, Yard Systems		\$0		\$0		\$0	
Comb Proc, Wtr Treatment		\$0		\$0		\$0	
Steam Cycle Systems		\$0		\$0		\$0	
Other Systems Engr (specify)		\$0	4200	\$302,400	700	\$50,400	
Non-TVA Engr		\$0		\$0		\$150,000	
Other Orgs (specify) (MacTec QA/QC & certification)		\$0		\$0		\$0	
Project Controls Scheduling		\$0	16	\$672		\$0	
Project Controls Cost		\$0	40	\$1,680		\$0	
Cost Estimating		\$0	8	\$336		\$0	
Engr Records		\$0		\$0		\$0	
CAD Dwg Support-Enter # Dwgs:	0	\$0	4864	\$330,288	925	\$ 209,850	
Sub Totals:							
Project Totals:	5,789	Hours	\$540,138	Dollars			

Long Lead Material - Dollars

Toney, Calvin L.

From: Smith, Daniel R (Chattanooga) [Daniel.R.Smith@worleyparsons.com]
Sent: Wednesday, November 16, 2005 9:37 PM
To: Toney, Calvin L.
Cc: Petty, Harold L.
Subject: estimated engineering cost for peninsula engineering

Phase 2 Engineering (including permit prep) for Worley Parsons \$300,000 (total all of Phase 2). This is the same for both Phase 2 and full buildout.

Phase 3 Engineering costs for WP Phase 1 - \$50,000 (assume 10 hrs/week @ 50 weeks @ \$100/hr)
Phase 3 Engineering costs for WP Full buildout - \$100,000

QA/QC costs Phase 1 - \$100,000
QA/QC costs full buildout - \$200,000

Certification costs - \$50,000 (phase 1)
Certification costs - \$100,000 (full buildout)

Daniel R. (Dan) Smith, PE
Supervising Civil Engineer
WorleyParsons
633 Chestnut St., Suite 400 Ph (423)757-8088
Chattanooga, TN 37450 Fax (423)266-0922
Email: daniel.r.smith@worleyparsons.com

*** WORLEYPARSONS GROUP NOTICE ***

"This email is confidential. If you are not the intended recipient, you must not disclose or use the information contained in it. If you have received this email in error, please notify us immediately by return email and delete the email and any attachments. Any personal views/ opinions expressed by the writer may not necessarily reflect the views/ opinions of the company."

Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Respon Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frst Mhrs	Actual Mhrs	2006	2008
30 Z4FBK439R2	Review Total Proj & Submit Phase 3 Approval Pkg	01NOV04A	03NOV04A			SMH	SMH	RJS		0.00	0.00	0.00		
32 Z4FBK439S0	KIF439: 50% Design Review	05NOV04A				S	HMP	RJS		0.00	0.00	0.00		
32 Z4FBK439MT	Manufacture & Ship LL Material	05NOV04A	04MAR05A			RJS	HMP	RJS		0.00	0.00	0.00		
32 Z4FBK43990	KIF439: 100% Design Review	07JAN05A				RJS	HMP	RJS		0.00	0.00	0.00		
32 Z4FBK439ER	Issue Pkg to Eng	07JAN05A				RJS	HMP	RJS		0.00	0.00	0.00		
T2 Z4FBK439AP	ERU Assemble & Issue DCN KIF-04-1067	12JAN05A	13JAN05A			DLL	DLL	RJS	TS2RU	16.00	0.00	0.00		
32 Z4FBK439D	DCN KIF-04-1067 Issued	04MAR05A				RJS	HMP	RJS		0.00	0.00	0.00		
30 Z4FBK439PC	Final Engineering Complete					SMH	SMH	RJS		0.00	0.00	0.00		
Phase C Implementation														
30 Z4FCK439A1	Issue Partner PA	26OCT04A	26OCT04A			SMH	SMH	RJS		0.00	0.00	0.00		
30 Z4FCK439P3	FPEP Phase 3 Approval	06JAN05A	06JAN05A			SMH	SMH	RJS		0.00	0.00	0.00		
30 Z4FCK439PE	KIF439: Phase 3 Project Engr / Cntrl Support	06JAN05A	17AUG05A			SMH	SMH	RJS	TS2CT, TS2PC, FSWT	84.00	84.00	84.00		
32 Z4FC439SY	KIF439: Phase 3 Sys-Engr Support	26JAN05A	15APR05A			RJS	HMP	RJS	FSWT	40.00	51.00	51.00		
32 Z4FCK439LL	LL Material Delivery Complete	04MAR05A	04MAR05A			RJS	HMP	RJS		0.00	0.00	0.00		
30 Z4FCK439OT	OUTAGE X832 - 48 DAYS	05MAR05A	15APR05A			SMH	SMH	RJS		0.00	0.00	0.00		
30 Z4FCK439PT	Project Turnover		15APR05A	21APR05		SMH	SMH	RJS		0.00	0.00	0.00		
32 Z4FCK439CD	Closure Process of DCN KIF-04-1067	22APR05A	20MAY05A			DLL	HMP	RJS	FSWT, TS2CD	24.00	0.00	0.00		
T2 Z4FCK439RU	ERU Assemble Closure Pkg - DCN KIF-04-1067	20MAY05A	23MAY05A			DLL		RJS	TS2RU	15.00	0.00	0.00		
32 Z4FCK439DC	DCN KIF-04-1067 CLOSED		23MAY05A			RJS	HMP	RJS		0.00	0.00	0.00		
30 Z4FCK439PC	Verify Benefits & Close Project		17AUG05A	19AUG05		SMH	SMH	RJS		0.00	0.00	0.00		

KIF439 APPROVALS

FULLS APPROVALS

KIF450 U6-9 FGD (Gypsum/Peninsula Storage Area,


Phase A Preliminary Engineering

Req TAO For Parsons - Mike Hughes (HLP)
 Scoping Discussion

DIFAGYP20	Req TAO For Parsons - Mike Hughes (HLP)	01APR05A		HLP	MSH	0.00	0.00	0.00
DIFAGYP22	Scoping Discussion	01APR05A		HLP	MSH	0.00	0.00	0.00

Sheet 103 of 178

FHEM



Start Date: 01JAN89
 Finish Date: 15OCT14
 Start Date: 09OCT05
 End Date: 12OCT05 08:09

TENNESSEE VALLEY AUTHORITY

Layout 70

S E C	Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Resp Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frct Mhrs	Actual Mhrs	2006	2008
	DIFAGYP18	Map of Survey - Scope to Surveying (HLP)		08APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP17	Scope of Drilling to MATEC (HLP)		11APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP12	RSO&E Survey of Holes- Predrill (Phy Layout HLP)		18APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP31	CEC for Drilling (Generic #5259) (HLP)		20APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP15	Issue MATEC TAO (HLP)		25APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP16	Receive MATEC Proposal (HLP)		25APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP13	RSO&E Prepare Hydrogeo Workplan (Hank Julian)		26APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP11	Env Aff Meet /TDEC - Hydrogeo Wkpln-(Amos/Larry)		27APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP14	MACTEC Start Drilling (HLP)		28APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP07	RSO&E Begin Hydrogeo Report (Draft) (H Julian)		29APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP21	LOA for RSO&E (HLP)		29APR05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP09	LOA for GeoProbe (HLP)		03MAY05A				HLP	MSH		0.00	0.00	0.00		
	DIFAGYP06	RSO&E Receive Prelim MACTEC Rept (TVA) (HLP)		20JUN05A			HLP	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP19	Phase 1B: Issue TAO to Parsons (HLP)		15JUL05A			HLP	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP25	Carrier Site Visit	20JUL05A	21JUL05A			MSH	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP04	RSO&E Complete Draft to Environ Aff -Hank Julian		23AUG05A			MSH	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP05	RSO&E Complete Draft to Parsons -Hank Julian		23AUG05A			MSH	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP10	Receive Final Mactec Lab Results		26AUG05A			MSH	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP03	Hydro Geo Final Internal Review -Enviro Aff		29AUG05A			ALS	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP35	Part I Application (Larry Bowers-Begin Package)		01SEP05A			MSH	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP30	Nuyt update meeting		23SEP05A			MSH	HLP	MSH		0.00	0.00	0.00		
	DIFAGYP37	NOD Response by Environmental Affairs	01OCT05A	30MAR06			29	MSH	HLP	MSH	0.00	0.00	0.00		
	DIFAGYP41	Site Meeting to Review MATEC Report -Steve Baugh	05OCT05A	05OCT05A				BSL	JSB	MSH	0.00	0.00	0.00		
	DIFAGYP32	Preliminary Footprint Drawing to JPT		10OCT05A			200	MSH	HLP	MSH	0.00	0.00	0.00		

Sheet 104 of 178

TENNESSEE VALLEY AUTHORITY
Layout 70

FHEM

01JAN89 Early Bar

15OCT14 Progress Bar

09OCT05 Critical Activity

12OCT05 08:09

© Primavera Systems, Inc.


S E C	Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Resp Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frcst Mhrs	Actual Mhrs	2006		2008
														Jan	Dec	Jan
35	DIFAGYP33	JPT Meeting - Status	19OCT05*			191	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP02	Final Hydrogeo Report to Envir Aff (Hank Julian)	28OCT05*			172	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP34	Quantity Takeoffs to Radford/Toney	28OCT05*			182	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP01	State Receives Hydro Geo Report	07NOV05			172	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP36	ESTIMATES PREPARED TOTAL ESTIMATE Final Estimate back from Radford/Toney	15NOV05*	15NOV05*		168	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP38	Final Footprint Study Drawing	15NOV05*			164	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP39	PPD Preliminary to JPT	20NOV05*			159	MSH	HLP	MSH		0.00	0.00	0.00			
35	DIFAGYP40	Final PPD	01DEC05*			148	MSH	HLP	MSH		0.00	0.00	0.00			
	DIFAGYP08	State Approves Hydro Geo Report	15APR06*			13		HLP	MSH		0.00	0.00	0.00			
30	DIFAGYPPC	Preliminary Engineering Complete (Phase 1B)	15APR06			13	SMH	HLP	MSH		0.00	0.00	0.00			
Phase B Final Engineering																
A 50	DIFBGYP10	Part I Application to TDEC	21OCT05*			375	MSH	HLP	MSH		0.00	0.00	0.00			
A 35	DIFBGYP05	10% Design Review	12DEC05*			4	SMH	HLP	MSH		0.00	0.00	0.00			
A 35	DIFBHP15	Send Drawings to Plant 1 Week Prior to 50% Mtg	06MAR06*			665	SMH	HLP	MSH		0.00	0.00	0.00			
A 35	DIFBGYP20	50% Design Review Meeting	15MAR06*			656	SMH	HLP	MSH		0.00	0.00	0.00			
A 50	DIFBGYP28	Part II Application to TDEC	16MAY06*			168	SMH	HLP	MSH		0.00	0.00	0.00			
A 50	DIFBGYP30	ARAP/404 Permit Application	16MAY06*			168	SMH	HLP	MSH		0.00	0.00	0.00			
A	DIFBGYP35	ARAP/404 Permit Issued	01MAY07*			244	SMH	HLP	MSH		0.00	0.00	0.00			
A	DIFBGYP40	TDEC Issues Solid Waste Permit	15OCT07*			77	SMH	HLP	MSH		0.00	0.00	0.00			
A 35	DIFBGYP45	100% Design Review Meeting	15DEC07*			16	SMH	HLP	MSH		0.00	0.00	0.00			
E																
A 39	VRRESKIF69	FY 05 AG&WS SUPPORT - KINGSTON 6-9 FGD ADDITION	17JAN05A	30SEP05A			GTM	REJ	TJM	FSAG, FSAGS	500.00	38.00	38.00			
A 35	VRRESKIFC0	FY 05 CIVIL SUPPORT - KINGSTON 6-9 FGD ADDITION	04MAR05A	30SEP05A			VJD	HLP	TJM	FDCEA	50.00	32.00	32.00			
A 31	VRRESKIFZ1	FY 05 MECH ENG SUPP - KINGSTON 6-9 FGD ADDITION	16MAY05A	30SEP05A			MDL	DLD	TJM	FDMEA	200.00	184.00	184.00			

Sheet 105 of 178

TENNESSEE VALLEY AUTHORITY

Layout 70

FHEM



Start Date: 01JAN89
 Finish Date: 15OCT14
 Data Date: 09OCT05
 Run Date: 12OCT05 08:09

Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Resp Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frct Mhrs	Actual Mhrs
A 33	VRRESKIFZ2 FY 05 I&C ENG SUPP- KINGSTON 6-9 FGD ADDITION	06JUN05A	23SEP05A			RDG	RCO	TJM	FDEE2D	200.00	4.00	4.00
A 35	VRRESKIFC1 CONTACT TDOOT RE: TURNING LANE HWY 70	15JUL05A	30AUG05A			VJD	HLP	TJM		0.00	0.00	0.00
A 31	VRRESKIFZ4 FY 06 MECH ENG SUPP - KINGSTON 6- 9 FGD ADDITION	03OCT05A	30SEP06		-1	MDL	DLG	TJM	FDMEA	800.00	800.00	0.00
A 39	VRRESSYAG FY 06 FIRE PROT SUPP-KINGSTON 6- 9 FGD ADDITION	03OCT05A	30SEP06		0	NCR	REJ	TJM	FSAGFP	200.00	200.00	0.00
A 39	VRRESSYSAH FY 06 AGW&S SUPP-KINGSTON 6- 9 FGD ADDITION	03OCT05A	30SEP06		0	GTM	REJ	TJM	FSAG	2,000.00	2,000.00	0.00
A 35	VRRESSYSAI FY 06 CIVIL SUPP-KINGSTON 6- 9 FGD ADDITION	03OCT05A	30SEP06		0	HLP	HLP	TJM	FDCEA	1,000.00	1,000.00	0.00
A 36	VRRESSYSAJ FY 06 ELECT SUPP-KINGSTON 6- 9 FGD ADDITION	03OCT05A	30SEP06		0	RJM	MAS	TJM	FDEE2A	600.00	600.00	0.00

KIF451 - U1-4 SELECT CATALYTIC REDUC(SCR)

Phase B Final Engineering

Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Resp Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frct Mhrs	Actual Mhrs
A 28	Z5FBK45126 JPT Review Scope & Schedule	30MAY01A	31MAY01A					JLL		0.00	0.00	0.00
A 28	Z5FBK451FA Receive FPEP Approval (Final Engr & Const)		30MAY01A					JLL		0.00	0.00	0.00
A 28	Z5FBK45128 Final Engr Authorization	01OCT01A	01JUN01A					JLL		0.00	0.00	0.00
A 28	Z5FBK45100 PE SUPPORT FOR U1-4SCR	01OCT01A	23MAY03A			JLL	VWD	JLL	FDME2S, FDME2	1,620.00	369.00	369.00
A 37	Z5FBK45118 ELECTRICAL SUPPORT FOR U1-4 SCR	01OCT01A	23MAY03A			RDG		JLL	FDME2S, FDME2	1,700.00	369.00	369.00
A 35	Z5FBK4518C Phase 2 Civil Support for U1-4 SCR	01OCT01A	23MAY03A			SLW		JLL		35.00	35.00	35.00
A 11	Z5FBK4518P PCS Support for U1-4 SCR	01OCT01A	23MAY03A			MHS	RHT	JLL		400.00	296.00	296.00
A 39	Z5FBK451AB AG&W SYSTEMS Support for Phase 2	01OCT01A	23MAY03A			JG	REJ	JLL	FSAG, FSWT	400.00	296.00	296.00
A T2	Z5FBK451RU KIF451 U1-4 SCR ERU DCN ISSUE	01OCT01A	23MAY03A			MHS	JS	JLL	TSZRU	1,368.00	1,043.00	1,043.00
A 31	Z5FBK45119 Mech Support U1-4 SCR	03SEP02A	23MAY03A			CPW	CPW	JLL	FDME2, FDMEB	985.00	1,077.00	1,077.00

Phase C Implementation

Activity ID	Activity Description	Forecast Start	Forecast Finish	Finish Target	Total Float	Resp Engr	Prin Engr	RE	Res ID	Bdgt Mhrs	Frct Mhrs	Actual Mhrs
A 11	Z5FGK451#P PCS Support for U1-4 SCR 03	01OCT01A	28SEP03A			MHS	RHT	JLL	TS2PC	1,000.00	271.50	271.50
A 28	Z5FGK451P# PE SUPPORT FOR U1-4SCR 03	01OCT01A	28SEP03A			JLL	VWD	JLL	FDEE1, FDME2S	800.00	2,043.50	2,043.50
A 35	Z5FGK4518C Phase 3 Civil Support for U1-4 SCR	01OCT01A	02MAR04A			SLW	SLW	JLL	FDCEB	50.00	16.00	16.00
A 31	Z5FGK451#1 Mech Support U1-4 SCR 03	03SEP02A	28SEP03A			CPW	CPW	JLL	FDME2, FDME2S	0.00	440.00	440.00

Start Date 01JAN89
 Finish Date 15OCT14
 Data Date 09OCT05
 Run Date 12OCT05 08:09

Legend:
 Early Bar
 Progress Bar
 Critical Activity

FHEM

TENNESSEE VALLEY AUTHORITY
 Layout 70

© Primavera Systems, Inc.

PRELIMINARY

IF Gypsum on Peninsula
hase 2 - Gypsum Long Term Rim Ditch Stack

ITEM	DESCRIPTION	UNITS	QUANTITY	T-1 Spec	Comments/Assumptions
7.00	Gypsum Stack Peninsula (7.00 through 18.00)				See Note 1 at end of table
7.01	Clear and Grub				
7.02	Clear and grub	ac	35		C - Tree line only
7.03	Strip 1 ft vegetation and topsoil - spoil at stockpile	bcy	193,600		C - 120 ac entire site, place soil on site approximately 1 mile roundtrip
8.00	Erosion Controls / Ponds				
8.01	Erect silt fence	lf	9,250		C - 6 ft post spacing, trench bottom of fence, 10% hay bales
8.02	Cut for stormwater runoff ponds	bcy	170,970		C - 2 ponds, Phase 1 Pond: 6 ac 17' deep, Phase 2 Pond: 6 ac 10' deep. Place as fill in gypsum stack area.
8.03	Fill for stormwater runoff ponds	bcy	16,425		C - Fill for dikes around Phase 2 pond
8.04	Riprap for stormwater runoff pond	ton	2,713		C - Combined - 1 ft deep along inside slope
8.05	72 in dia cmp for outlet structure	lf	12		C
8.06	48 in dia cmp for riser for outlet structure	lf	14		C
8.07	Cut holes in riser	ea	6		C
8.08	48 in dia cmp outlet pipe (principle spillway)	lf	300		C
8.09	(2) Concrete for riser base (assume 7ft x 7 ft x 2 ft)	cy	9		C
8.10	Anti-seep collars (assume concrete)	ea	14		C - Assume 1.5 cy concrete per collar
8.11	Pipe bedding - #57 stone	ton	40		C
8.12	Clean out stormwater runoff pond	bcy	7,150		C - Assume 2 ft sediment, 67 cy/ac depth x 110 ac
9.00	Access Roads				Assume 1.3 miles of roadway (7000 ft); road is 20 ft wide
9.01	Bottom Ash	bcy	2593		C - Assume 6 in bottom ash
9.02	Crushed stone base	ton	2541		C - Assume 4 inch stone (1032), 110 pcf
9.03	Crushed stone base - parking lot	ton	275		C - Assume 100 x 100 ft w/ 6 in crushed stone (110 pcf)
10.00	Fencing (Exclude De-watering Facility)				
10.01	New fencing (including grounding)	lf	200		C - Assume chain link fence to block road only - no perimeter fence
10.02	Gates, swinging	ea	1		C - personnel
10.03	Gates, sliding, w/ motorized operator	ea	1		C - 20 ft wide
11.00	Seed/Mulch				
11.01	Seed/Mulch disturbed areas	ac	25		C - Areas outside dike

12.00	Borrow Area Development					
12.01	Clear and grub	ac	33			C
12.02	Erect silt fence	lf	3,000			C
12.03	Temporary perimeter ditch	bcy	2,900			C - 15 acres of runoff
12.04	Cut for temporary stormwater runoff ponds	bcy	4,422			C - 33 acres*134 cy/ac
12.05	Fill for temporary stormwater runoff ponds	bcy	884			C
12.06	72 in dia cmp for outlet structure	lf	12			C
12.07	48 in dia cmp for riser for outlet structure	lf	20			C
12.08	Cut holes in riser	ea	5			C
12.09	48 in dia cmp outlet pipe (principle spillway)	lf	200			C
12.10	(2) Concrete for riser base (assume 7ft x 7 ft x 2 ft)	cy	9			C - Assume 1.5 cy per collar
12.11	Anti-seep collars (assume concrete)	ea	20			C - Assumed Unit wt = 125 pcf
12.12	Pipe bedding - #57 stone	ton	25			C - Assume 2ft sediment, 67 cy/ac @ 33 ac
12.13	Clean out stormwater runoff pond	bcy	4,422			
13.00	Gypsum Disposal Facility					
13.01	Disposal Facility Construction					
13.01	Earthwork cut	bcy	357,647			C - to shape base in gypsum stack area
13.02	Earthwork fill from borrow area	bcy	899,679			C - Remaining fill from onsite borrow area, 1428296- (357647+170970)=899679 Haul Length = 2 miles roundtrip
13.03	Additional spoil material	bcy	0			C
13.04	Proofroll subgrade	ac	100			C - Over excavate 3' and recompact to build liner
13.05	Cut and recompact liner	bcy	445,944			C - 8 in dia HDPE, SDR = 17, perforated
13.06	Perimeter underdrain pipe	lf	8,220			C
13.07	Cut for Underdrain system	cy	2,667			C - Wrapped around pipe bedding
13.08	Geotextile 8oz nonwoven, for underdrain	sy	20,000			C - Initial bedding for underdrain piping
13.09	6" depth 1081 crushed stone (110 pcf)	ton	1,320			C
13.10	Underdrain piping (8" dia HDPE)	lf	24,000			
13.11	HDPE Fittings for underdrain piping	ea	65			
13.12	2.5' thick bottom ash drainage layer	bcy	371,620			C - Mix
13.13	6" Fly ash layer	bcy	74,324			C - 6 in bottom ash topped w/ 4 in stone - 1.6 mi of roadway 20 ft wide
13.14	Perimeter road surfacing - bottom ash	cy	3130			C - Assumed Unit wt = 110pcf - 1.6 miles of roadway
13.15	Perimeter road surfacing - crushed stone	ton	3067			C - Assume riprap 2 ft depth, 8055 lf ditch, Unit wt = 110 pcf
13.16	Riprap Ditch (D50 = 6 in)	ton	64,682			C - Assume ditch has 9 ft bottom width, 10 ft depth and 3:1 side slopes
13.17	8 oz nonwoven geotextile (if riprap is used)	sy	65,335			Spread the O&M Cost Over the Life of the Stack
14.00	Gypsum on Peninsula Disposal Cost					

15.00	Construction parking				
15.01	Earthwork cut	bcy	833		C
15.02	Earthwork fill	bcy	300		C
15.03	Crushed stone base	ton	675		C - Assume 150 x 150 ft x 6 in thick crushed stone base
16.00	Engineering				
16.01	Engineering	ls			C - Take 10% of construction cost (see Dan Smith to confirm engineering cost).
17.00	Pump Station				
17.01	Phase 1 Pond				Later
17.02	Phase 2 Pond				Later
18.00	Electrical				See Electrical takeoffs

Notes:
 . Item #7 corresponds to Gypsum Disposal at the Peninsula. This numbering system matched the one used for the comparative study done in December '04.

)- Capital cost
)&M - Operation and Maintenance cost

Red means that these O&M quantities DO NOT need to be estimated.
 Yellow means that these quantities will be provided later

PHASE 2 APPROVAL
PLPAB

Toney, Calvin L.

From: Workman, Brad
Sent: Monday, November 14, 2005 12:07 PM
To: Toney, Calvin L.
Cc: Petty, Harold L.; Lowery, Kenny R.; Radford, Larry D.; Stewart, David W.
Subject: HED - KIF Phase 2 Gypsum Pond Construction estimate

Calvin,

I have attached the Phase 2 estimate for the KIF Gypsum Pond Construction. You will need to add this estimate total to the Phase 1 estimate total provided to obtain the total "full buildout" number. If you have questions or comments, please give me a call.

Thank you,
Brad Workman
TVA - HED
(931) 320-1044

TVA – Heavy Equipment Division
Estimate for
Kingston – Phase 2 Gypsum Disposal Facility Pond Construction

11/14/05

Mr. Calvin Toney,

We thank you for the opportunity to provide the following estimate for the TVA - Kingston (Phase 2) Gypsum Disposal Facility Pond Construction. The below estimate is based upon the provided Parsons Engineering quantities and Preliminary drawings.

The understood TVA-HED Scope of Work for the project is as follows:

“Erosion Controls / SWPPP”:

- Provide all technical support, supervision, labor, equipment and materials to join together all the various phases of the work and deliver a complete project.
- Install a total of approximately 9,375 lf of Type “C” silt fence w/ 10% estimated for straw bales.
- Construct construction parking area.
- Cut approximately 47,928 CY of clay for Stormwater Runoff Pond construction and haul to Gypsum Disposal Facility for new construction use.
- Allowance - Clean out Gypsum Stack stormwater runoff pond as needed. (approximately 3,216 cy)
- Clear and Grub approximately 10 acres at Gypsum Stack Peninsula. (Includes clear cut logging as well).
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.
- Seed / Mulch approximately 13 acres outside Gypsum Disposal Facility dikes.

“Borrow Area Development”:

- Clear and Grub approximately 25 acres at borrow site.
- Clear cut all timber on approximately 25 acres for clay borrow site.
- Mulch with grinder all remaining stumps and tree laps not carried off site by Logging Company.
- Strip approximately 109,707 CY of topsoil from the stated 25 acre borrow area, haul and spoil at Gypsum Disposal Facility site approximately ½ mile away from borrow area.
- Excavate temporary ditch on perimeter of borrow area. (approximately 1,740 CY of material to be excavated).
- Cut approximately 3,979 CY of clay for stormwater runoff pond construction and haul to Gypsum Disposal Facility for new construction use.
- Allowance - Clean out borrow area stormwater runoff pond as needed. (approximately 1,435 cy)

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

TVA-00029209

“Haul / Access Roads”:

- Build / Improve & maintain haul roads to and from the borrow sites (Clay and Bottom Ash) consisting of approximately 0.3 miles of roadway.
- Build Gypsum Disposal Facility Access Roadways with 1,213 TN of new stone.
- Build Gypsum Disposal Facility Access Roadways with 764 CY of Bottom Ash.

“Disposal Facility Construction”:

- Proof-roll all Gypsum Stack sub-grade. (50 acres)
- Over-excavate 3' depth in Gypsum Stack liner area (approximately 50 acres), then re-place and re-compact liner material. (276,466 cy)
- Cut existing clay inside Gypsum Stack area to shape base inside Gypsum Stack area. (approximately 127,332 cy)
- Cut, haul and compact clay fill from borrow area inside Gypsum Stack dike base. (approximately 774,727 cy)
- Excavate and install 17,970 lf total of 8" HDPE underdrain piping around perimeter of Stack.
- Install approximately 825 ton of underdrain bedding stone.
- Wrap pipe bedding stone with 12,500 SY of 8 oz. geotextile for underdrain.
- Install 2.5' thick Bottom Ash drainage layer. (approximately 230,388 cy)
- Install 6" thick Fly Ash layer over Bottom Ash (mix). (approximately 46,078 cy)
- Install Perimeter road with 6" of Bottom Ash topped with 4" of crushed stone. (0.5 miles of 20' wide roadway)
- Excavate and install 2' deep rip-rap stone on 8oz. geotextile in Gypsum Stack Perimeter Ditch. (approximate ditch dimensions – 3,055 lf x 10' deep x 9' wide bottom. Estimate assumes ditch will be constructed with fill dirt from borrow area while constructing stack dikes. No typical detail provided. Approximately 23,207 ton of rip-rap, and 23,441 SY of 8oz geotextile material.)

“Clarifications to Estimated Scope of Work”:

- Allowance Included – 15% Double handling of liner material foreseen as risk due to unsuitable soil for liner construction encountered during over-excavation. This cost is included in estimate.
- No “rock removal / excavation” costs are included in cost estimate or project schedule duration.
- All craft / supervisor labor wage rates are FY 2005 wage rates.
- All equipment rates are TVA - HED FY 2005 equipment rates utilizing TVA - HED heavy equipment.
- All “Bank Cubic Yard” quantities provided are escalated 20% for compaction / shrinkage.
- Estimate includes contingencies for inclement weather.
- Estimate assumes TVA - HED to be sole General Contractor responsible for said Gypsum Stack Construction scope of work.
- Estimate includes sub-contract costs for Fence Contractor, TVA Surveyors to provide layout, and project control points during various stages of the work for the identified schedule duration as needed, Geotechnical Engineers to provide

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

compaction test results as required, and Mulching Contractor of tree stumps, laps, required and slash etc. after clearing of trees is completed is included.

- Seed and Mulch all disturbed areas outside dikes. (approximately 13 acres)

“Schedule”:

All work is currently estimated for 4 – 10 hour shifts per work week with no overtime included.

Individual project schedules end dates per activity shall vary from one to another. We propose to complete all work identified above within 1 ¾ years from start of project as stated on “Estimate Summary” sheet provided with this estimate.

If you have questions regarding this work as estimated, please feel free to contact us at the below numbers.

Total Estimated Cost - \$8,083,776.00 Lump Sum

Thank You,
Kenny Lowery
TVA HED
(256) 762-6401

cc: Brad Workman
(931) 320-1044

TVA – HEAVY EQUIPMENT DIVISION
933 OLD FERRY ROAD
SPRING CITY, TENNESSEE 37381
PH: (423) 365-8739 FAX: (423) 365-8705

HED ESTIMATE SUMMARY

HED ESTIMATE SUMMARY
REV# 0

*ADD TO PHASE 1
FOR TOTAL BUDGET*

LOCATION: KINGSTON
SHORT CODE: KENNY LOWERY

UNIT NO: PHASE 2

PRINT DATE: 14-Nov-05
ESTIMATE DATE: 10-Nov-05

PROJECT DESCRIPTION: GYPSUM POND CONSTRUCTION (PHASE 2)

WORKSCOPE: DEVELOP SOIL BORROW AREA, DEWATER BOTTOM ASH POND BORROW AREA, PERFORM EROSION CONTROL WORK PER STANDARD SWPPP, MAINTAIN HAUL
HAUL ROADS, MAINTAIN ACCESS ROADS, BUILD PHASE 2 OF GYPSUM POND.

DURATION: 1.75 YEARS OR (88 WEEKS) IF CLEARED, THEN SITE WORK BEGINS. INCLUDES 5 WEEKS OVERALL FOR BAD WEATHER.
4 MONTHS FOR CLEARING OF TREES BY LOGGING COMPANY
1.5 YEARS FOR PHASE 2 BORROW AREA DEVELOPMENT / POND CONSTRUCTION.

PHASE	TYPE OF FUNDING
2	CAPITAL > 100K

PREPARED BY: B. WORKMAN (HED)

1. TVA-HED LABOR COSTS			Comments
Craft Augmented Labor	MANHOURS <i>201,506</i>	107794 + 93,772	Includes all aspects of Phase 2 work. Based on FY 2005 labor rates.
	COST <i>778,938</i>	\$4,186,925 + 360,245	
Non-Manual Labor	MANHOURS <i>6,930</i>	9,680 + 7,200	Supervisor and Mechanic full time for 1.5 years. Includes Hourly Rates & Per Diem for both men.
	COST <i>78,040</i>	\$440,440 + 327,600	
Contingency	0.00% MANHOURS	0	
	COST	\$0	
SUBTOTAL TVA-HED LABOR	MANHOURS <i>218,436</i>	117,474 + 100,972	
	COST <i>8,557,871</i>	\$4,627,365 + 3,930,506	
2. TVA-HED OTHER COSTS			
TVA-HED Subcontracts	<i>594,600</i>	\$254,000 + 340,600	Survey / Layout / Fence Cont / Compac. Testing / Much Grinding Cont.
TVA-HED Subcontract Fee		\$0	
Travel & Living Expenses		See "Non-Manual Labor"	
TVA-HED Material Purchases		\$0	
HED Other Costs		\$0	
Contingency	0%	\$0	
SUBTOTAL TVA-HED OTHER	<i>594,600</i>	\$254,000 + 340,600	
TOTAL TVA-HED COSTS	<i>9,152,021</i>	\$4,881,365 + 4,270,656	
3. ITEMS MANAGED BY TVA-HED			
Permanent Materials	<i>1,142,368</i>	\$387,858 + 754,510	Per Quantities Provided by Parsons E & C.
Heavy Equipment	<i>4,103,705</i>	\$2,244,513 + 1,859,192	Based on FY 2005 (HED) Equipment Rates.
Tagged & 3rd Party Rental Equipment		\$0	
Small Tools	<i>20,156</i>	\$10,779 + 9,377	
Supplies, Consumables & Expendable Tools	<i>60,469</i>	\$32,338 + 28,131	
Office Supplies & Expenses		\$0	
Other TVA-HED Costs		\$0	
TVA subcontracts (By Others)		\$0	
Partner or OCIP Insurance		\$0	
TVA-HED - Central Command	<i>1,029,439</i>	10.00% \$526,922 + 502,517	
Contingency	0%	\$0	
SUBTOTAL TVA-HED MANAGED	<i>6,356,138</i>	\$3,202,411 + 3,153,727	
TOTAL TVA-HED COSTS	<i>15,508,159</i>	\$8,083,776 + 7,424,383	

APPROVALS: ESTIMATE TOTAL \$8,083,776 LS

ESCALATE TO 2008 DOLLARS

_____	TVA-HED Estimator	_____	Date:
_____	TVA - Project Manager	_____	Date:
_____	TVA - Project Engineer	_____	Date:
_____	TVA - Site Environmental Engineer	_____	Date:

PCN Number:

PCN Description: KIF - Gypsum Disposal Area - Peninsula - Stage 2 Full Build Out

Current Phase: 1

Phase Request: 2

Date: 11/17/2005

	Phase I		Phase II		Phase III		Prin/RE Engr
	Hours	\$	Hours	\$	Hours	\$	
Project Engr		\$0	0	\$0	150	\$6,300	
Mech Engr		\$0		\$0		\$0	
Elec Engr I		\$0		\$0		\$0	
Elec Engr II		\$0		\$0		\$0	
Civil Engr		\$0	0	\$0	300	\$12,600	
Air, Gas, Wtr, Yard Systems		\$0		\$0		\$0	
Comb Proc, Wtr Treatment		\$0		\$0		\$0	
Steam Cycle Systems		\$0		\$0		\$0	
Other Systems Engr (specify)		\$0		\$0		\$0	
Non-TVA Engr		\$0	0	\$0	1400	\$100,800	
Other Orgs (specify) (MacTec QA/QC & certification)		\$0		\$0		\$300,000	
Project Controls Scheduling		\$0		\$0		\$0	
Project Controls Cost		\$0	0	\$0		\$0	
Cost Estimating		\$0	0	\$0		\$0	
Engr Records			0	\$0		\$0	
CAD Dwg Support-Enter # Dwgs:							\$0
Sub Totals:	0	\$0	0	\$0	1850	\$ 419,700	
Project Totals:	1,850	Hours	\$419,700	Dollars			

Long Lead Material - Dollars

Print

Save As...

Toney, Calvin L.

Toney, Calvin L.

From: Smith, Daniel R (Chattanooga) [Daniel.R.Smith@worleyparsons.com]
Sent: Wednesday, November 16, 2005 9:37 PM
To: Toney, Calvin L.
Cc: Petty, Harold L.
Subject: estimated engineering cost for peninsula engineering

Phase 2 Engineering (including permit prep) for Worley Parsons \$300,000 (total all of Phase 2). This is the same for both Phase 2 and full buildout.

Phase 3 Engineering costs for WP Phase 1 - \$50,000 (assume 10 hrs/week @ 50 weeks @ \$100/hr)
Phase 3 Engineering costs for WP Full buildout - \$100,000

QA/QC costs Phase 1 - \$100,000
QA/QC costs full buildout - \$200,000

Certification costs - \$50,000 (phase 1)
Certification costs - \$100,000 (full buildout)

Daniel R. (Dan) Smith, PE
Supervising Civil Engineer
WorleyParsons
633 Chestnut St., Suite 400 Ph (423)757-8088
Chattanooga, TN 37450 Fax (423)266-0922
Email: daniel.r.smith@worleyparsons.com

***** WORLEYPARSONS GROUP NOTICE *****

"This email is confidential. If you are not the intended recipient, you must not disclose or use the information contained in it. If you have received this email in error, please notify us immediately by return email and delete the email and any attachments. Any personal views/ opinions expressed by the writer may not necessarily reflect the views/ opinions of the company."