US Army Corps
of Engineers
Hydrologic Engineering Center

HEC-ResSim

Reservoir System Simulation

User's Manual

Version 2.0
September 2003

Approved for Public Release

CPD-82

REPORT DOCUMENTATION PAGE

Form Approved
OMB No. 0704-0188

Public reporting burden for this collection of information is estimated to average 1 hour per response, including the time for reviewing instructions, searching existing data sources, gathering and maintaining the date needed, and completing and reviewing the collection of information. Send comments regarding this burden estimate or any other aspect of this collection of information, including suggestions for reducing this burden, to Washington Headquarters Services, Directorate for Information Operations and Reports, 1215 Jefferson Davis Highway, Suite 1204, Arlington, VA 22202-4302, and to the Office of Management and Budget, Paperwork Reduction Project (0704-0188), Washington, DC 20503.

1. AGENCY USE ONLY *(Leave blank)*	2. REPORT DATE	3. REPORT TYPE AND DATES COVERED
	September 2003	Computer Program Documentation

4. TITLE AND SUBTITLE
HEC-ResSim User's Manual

5. FUNDING NUMBERS

6. AUTHOR(S)
Joan D. Klipsch

7. PERFORMING ORGANIZATION NAME(S) AND ADDRESS(ES)
US ARMY CORPS OF ENGINEERS
HYDROLOGIC ENGINEERING CENTER (HEC)
609 Second Street
Davis, CA 95616-4687

8. PERFORMING ORGANIZATION REPORT NUMBER
CPD-82

9. SPONSORING / MONITORING AGENCY NAME(S) AND ADDRESS(ES)

10. SPONSORING / MONITORING AGENCY REPORT NUMBER

11. SUPPLEMENTARY NOTES
Also, see HEC-ResSim Quick Start Guide, CPD-82a

12a. DISTRIBUTION / AVAILABILITY STATEMENT
Distribution is unlimited.

12b. DISTRIBUTION CODE

13. ABSTRACT *(Maximum 200 words)*

The U.S. Army Corps of Engineers' Hydrologic Engineering Center's Reservoir System Simulation (HEC-ResSim) is a computer program comprised of a graphical user interface (GUI) and a computational program to simulate reservoir operations. Included are data storage and management capabilities and graphics and reporting facilities. HEC's Data Storage System (HEC-DSS) is used for storage and retrieval of input and output time series data.

14. SUBJECT TERMS
HEC-ResSim, Reservoir Simulation, computer program

15. NUMBER OF PAGES 426

16. PRICE CODE

17. SECURITY CLASSIFICATION OF REPORT	18. SECURITY CLASSIFICATION OF THIS PAGE	19. SECURITY CLASSIFICATION OF ABSTRACT	20. LIMITATION OF ABSTRACT
UNCLASSIFIED	UNCLASSIFIED	UNCLASSIFIED	UNLIMITED

HEC-ResSim

Reservoir System Simulation

User's Manual

Version 2.0
September 2003

US Army Corps of Engineers
Institute for Water Resources
Hydrologic Engineering Center
609 Second Street
Davis, CA 95616-4687

(530) 756-1104
(530) 756-8250 FAX
www.hec.usace.army.mil

HEC Reservoir System Simulation, HEC-ResSim Software Distribution and Availability Statement

The HEC-ResSim executable code and documentation are public domain software that were developed by the Hydrologic Engineering Center for the U.S. Army Corps of Engineers. The software was developed with United States Federal Government resources and is, therefore, in the public domain. This software can be downloaded for free from the HEC website (http://www.hec.usace.army.mil). HEC cannot provide technical support for this software to non-Corps users. See our software vendor list (on our web page) to locate organizations that provide the program, documentation, and support services for a fee. However, we will respond to all documented instances of program errors. Documented errors are bugs in the software due to programming mistakes, not model problems due to user-entered data.

HEC-ResSim User's Manual

Table of Contents

Page

List of Tables ix

List of Figures x

List of Appendices xix

History and Acknowledgments xx

Chapter **Page**

1 Introduction
1.1 ResSim Modules 1-1
1.1.1 Watershed Setup Module 1-2
1.1.2 Reservoir Network Module 1-2
1.1.3 Simulation Module 1-3
1.2 About this Manual 1-3

2 ResSim Concepts
2.1 Starting ResSim 2-2
2.2 Recognizing Common Screen Components 2-3
2.2.1 Menu Bar 2-3
2.2.2 Module List 2-5
2.3 Watershed Setup Module 2-6
2.4 Reservoir Network Module 2-10
2.5 Simulation Module 2-13
2.6 Opening an Existing Watershed 2-15
2.7 Understanding Schematic Elements 2-16
2.7.1 Stream Alignment 2-17
2.7.2 Other Watershed Elements 2-17
2.7.3 Reservoir Network Schematic 2-18
2.7.4 Using Shortcut Menus 2-19
2.8 Printing and Exporting Reports 2-19
2.8.1 Printing Reports 2-19
2.8.2 Print Preview 2-22
2.8.3 Exporting Reports to a File 2-23

3 Creating and Managing Watersheds
3.1 Recognizing Watershed Setup Screen Components 3-1
3.1.1 Menu Bar 3-2
3.1.2 Configuration Selector and Lock/Unlock 3-3
3.1.3 Map (Mouse) Tools 3-4

Table of Contents (continued)

Chapter Page

3.2 Using Shortcut Menus 3-6
3.3 Watershed Creation 3-6
3.3.1 Defining a Watershed Location 3-6
3.3.2 Creating a New Watershed 3-8
3.3.3 Specifying Units of Measure 3-9
3.3.4 Specifying Time Zone 3-9
3.4 Setting Up New Map Layers 3-9
3.4.1 Importing Maps into ResSim 3-9
3.4.2 Adding a New Map Layer 3-12
3.4.3 Specifying the Geographic Referencing and Coordinate System 3-13

4 Working with Layers
4.1 Understanding Layers 4-1
4.1.1 Time-Series Icon Layer 4-1
4.1.2 Study Layer 4-1
4.1.3 Stream Alignment Layer 4-2
4.1.4 Map Layers 4-2
4.2 Exploring the Layer Selector 4-2
4.2.1 The Layer Selector Menus 4-3
4.2.2 The Layer Selector "Tree" 4-4
4.2.3 Controlling Layer Display 4-5
4.2.4 Viewing Layer Legend 4-6
4.3 Controlling Layer Organization 4-6
4.3.1 Configuring Toolbar Icons to Control Layers 4-7
4.3.2 Adding Map Layers 4-8
4.3.3 Removing Map Layers 4-8
4.3.4 Using Layer Selector Shortcut Menus 4-9
4.4 Viewing and Configuring Layer Properties 4-10
4.4.1 Study Layer Properties 4-11
4.4.2 Stream Alignment Layer Properties 4-14
4.4.3 Map Layers Properties 4-15

5 Working with the Stream Alignment
5.1 Creating a New Stream Alignment 5-2
5.2 Editing an Existing Stream Alignment 5-5
5.2.1 Moving Vertices of a Stream Element 5-5
5.2.2 Adding Vertices to a Stream Element 5-6
5.2.3 Deleting Vertices from a Stream Element 5-6
5.2.4 Editing a Stream Element 5-6
5.2.5 Renaming a Stream Element 5-8
5.2.6 Deleting a Stream Element 5-8
5.2.7 Inserting a Stream Node 5-9
5.2.8 Editing a Stream Node 5-9
5.2.9 Deleting a Stream Node 5-10

Table of Contents (continued)

Chapter Page

5.2.10 Moving a Stream Junction 5-10
5.2.11 Editing a Stream Junction 5-11
5.2.12 Reversing the Direction of a Stream 5-11
5.2.13 Disconnecting a Stream Element....5-12
5.3 Importing a Stream Alignment....5-12
5.4 Exporting a Stream Alignment....5-14
5.5 Configuring Stream Alignment Display Properties 5-15
5.6 Saving the Stream Alignment....5-16
5.7 Listing of Streams....5-16

6 Creating Watershed Elements
6.1 Creating a Reservoir 6-1
6.1.1 Editing Reservoir Data (Watershed Setup)....6-2
6.1.2 Renaming a Reservoir 6-3
6.1.3 Removing a Reservoir from a Configuration....6-4
6.1.4 Deleting a Reservoir 6-4
6.1.5 Adding Configuration Notes for a Reservoir 6-4
6.2 Creating a Levee....6-5
6.2.1 Editing Levee Data....6-5
6.2.2 Renaming a Levee....6-7
6.2.3 Removing a Levee from a Configuration 6-7
6.2.4 Deleting a Levee 6-8
6.2.5 Adding Configuration Notes for a Levee 6-8
6.3 Creating a Diversion....6-9
6.3.1 Editing Diversion Data 6-10
6.3.2 Renaming a Diversion....6-10
6.3.3 Disconnecting a Diversion 6-11
6.3.4 Removing a Diversion from a Configuration 6-11
6.3.5 Deleting a Diversion....6-11
6.3.6 Adding Configuration Notes for a Diversion....6-12
6.4 Creating Channel Modifications 6-12
6.4.1 Editing Channel Modification Data....6-13
6.4.2 Renaming a Channel Modification 6-13
6.4.3 Removing a Channel Modification from a Configuration....6-14
6.4.4 Deleting a Channel Modification 6-14
6.4.5 Adding Configuration Notes for Channel Modifications....6-14
6.5 Creating Off-Channel Storage Areas 6-15
6.5.1 Editing Off-Channel Storage Data 6-15
6.5.2 Renaming an Off-Channel Storage Area 6-16
6.5.3 Removing an Off-Channel Storage Area from a Configuration....6-16
6.5.4 Deleting an Off-Channel Storage Area 6-17
6.5.5 Adding Configuration Notes for an Off-Channel Storage Area....6-17

Table of Contents (continued)

Chapter Page

6.6 Creating "Other" Projects 6-18
6.6.1 Editing "Other" Project Data 6-18
6.6.2 Renaming "Other" Projects 6-19
6.6.3 Removing "Other" Projects from a Configuration 6-19
6.6.4 Deleting "Other" Projects 6-20
6.6.5 Adding Configuration Notes for "Other" Projects 6-20
6.7 Configuring Project Display Properties 6-20
6.8 Defining Computation Points 6-21
6.8.1 Editing Computation Point Data 6-21
6.8.2 Renaming a Computation Point and Editing the Description 6-23
6.8.3 Deleting a Computation Point 6-23
6.9 Working with Time-Series Icons 6-24

7 Creating Watershed Configurations
7.1 Adding Watershed Configurations 7-1
7.2 Adding and Removing Projects from Configurations 7-3
7.2.1 Adding Projects to a Configuration 7-4
7.2.2 Removing Projects from a Configuration 7-4
7.3 Adding Configuration Notes 7-5
7.4 Making a Copy of a Configuration 7-5
7.5 Deleting a Configuration 7-6
7.6 Saving Configuration Data 7-6
7.7 Listing Configurations 7-6

8 Developing a Reservoir Network
8.1 Recognizing Reservoir Network Screen Components 8-2
8.1.1 Menu Bar 8-3
8.1.2 Network, Configuration, and Lock/Unlock 8-5
8.1.3 Map (Mouse) Tools 8-5
8.1.4 Display Area 8-6
8.2 Defining a Reservoir Network 8-7
8.2.1 Creating a New Reservoir Network 8-7
8.2.2 Opening an Existing Reservoir Network 8-8
8.3 Making the Network Editable 8-8
8.4 Adding Routing Reaches 8-9
8.4.1 Drawing Routing Reaches 8-9
8.4.2 Renaming Routing Reaches 8-10
8.4.3 Deleting Routing Reaches 8-10
8.5 Viewing Network Reports 8-11
8.5.1 Viewing the Reservoir List 8-11
8.5.2 Viewing the Reach List 8-11
8.5.3 Viewing the Junction List 8-12
8.5.4 Viewing the Diversion List 8-12
8.5.5 Viewing Advanced Reports 8-13
8.6 Updating a Reservoir Network 8-14

Table of Contents (continued)

Chapter Page

9 Editing Junction, Reach, and Diversion Data
9.1 Editing Junction Properties ... 9-1
9.1.1 Junction Editor: Info Tab ... 9-2
9.1.2 Junction Editor: Local Flow Tab ... 9-3
9.1.3 Junction Editor: Rating Curve Tab ... 9-4
9.1.4 Junction Editor: Observed Data Tab ... 9-5
9.2 Editing Reach Properties ... 9-6
9.2.1 Reach Editor: Routing Tab ... 9-7
9.2.1.1 Coefficient Routing Method ... 9-7
9.2.1.2 Muskingum Routing Method ... 9-8
9.2.1.3 Muskingum-Cunge 8-pt Channel Routing Method ... 9-9
9.2.1.4 Muskingum-Cunge Prismatic Channel Routing Method ... 9-11
9.2.1.5 Modified Puls Routing Method ... 9-13
9.2.1.6 SSARR Routing Method ... 9-14
9.2.2 Reach Editor: Losses Tab ... 9-16
9.2.3 Reach Editor: Observed Data Tab ... 9-17
9.3 Editing Diversion Properties ... 9-18
9.3.1 Diversion Editor: Diversion Tab ... 9-19
9.3.1.1 Constant Diversion Method ... 9-19
9.3.1.2 Monthly Varying Diversion Method ... 9-20
9.3.1.3 Seasonal Diversion Method ... 9-21
9.3.1.4 Function of Flow Diversion Method ... 9-22
9.3.1.5 Function of Pool Elevation Diversion Method ... 9-23
9.3.1.6 Time-Series Diversion Method ... 9-24
9.3.2 Diversion Editor: Routing Tab ... 9-25
9.3.3 Diversion Editor: Losses Tab ... 9-25
9.3.4 Diversion Editor: Observed Data Tab ... 9-26

10 Defining Physical Components of Reservoirs
10.1 Accessing the Reservoir Editor ... 10-2
10.2 Using the Reservoir Editor to Define Physical Components ... 10-2
10.3 Specifying Physical Components of a Reservoir ... 10-3
10.4 Specifying Reservoir Pool Losses ... 10-4
10.5 Defining Physical Features of a Dam ... 10-4
10.6 Adding Leakage to a Dam ... 10-5
10.7 Adding Outlet Groups ... 10-6
10.8 Defining Controlled Outlets ... 10-7
10.8.1 Adding Controlled Outlets ... 10-7
10.8.2 Adding a Power Plant to a Controlled Outlet ... 10-8
10.9 Adding Uncontrolled Outlets ... 10-9
10.10 Adding Tailwater Elevation ... 10-10
10.11 Defining Physical Components of a Diverted Outlet ... 10-11

Table of Contents (continued)

Chapter Page

10.12 Renaming, Deleting, and Removing Reservoir Components 10-12
10.12.1 Renaming Reservoir Components 10-12
10.12.2 Deleting Reservoir Components 10-13
10.12.3 Removing Reservoir Parameters 10-14
10.13 Editing Reservoir Physical Data 10-14
10.14 Editing Pool Physical Data 10-15
10.14.1 Editing Pool Evaporation Data 10-16
10.14.2 Editing Pool Seepage 10-17
10.15 Editing Dam Leakage 10-18
10.16 Editing Controlled Outlet Physical Data 10-19
10.17 Editing Power Plant Physical Data 10-21
10.17.1 Editing Capacity Data for a Power Plant 10-21
10.17.2 Editing Efficiency Data for a Power Plant 10-22
10.17.2.1 Constant Efficiency Method 10-22
10.17.2.2 Function of Reservoir Elevation Efficiency Method 10-23
10.17.2.3 Function of Release Efficiency Method 10-24
10.17.2.4 Function of Operating Head Efficiency Method 10-25
10.17.3 Editing Station Use Data for a Power Plant 10-26
10.17.3.1 Constant Station Use Method 10-26
10.17.3.2 Function of Release Station Use Method 10-27
10.17.4 Editing Hydraulic Losses Data for a Power Plant 10-28
10.17.4.1 Constant Hydraulic Losses Method 10-28
10.17.4.2 Function of Release Hydraulic Losses Method 10-29
10.18 Editing Uncontrolled Outlet Physical Data 10-30
10.19 Editing Tailwater Elevation Physical Data 10-31
10.20 Viewing Composite Release Capacity Tables 10-33
10.20.1 Reservoir Composite Release Capacity Table 10-33
10.20.2 Dam Composite Release Capacity Table 10-34
10.20.3 Diverted Outlet Composite Release Capacity Table 10-34
10.20.4 Outlet Group Composite Release Capacity Table 10-34
10.21 Reservoir Editor: Observed Data Tab 10-35

11 Defining Reservoir Operations Data
11.1 Reservoir Editor's Operations Tab 11-2
11.2 Reservoir Operation Sets 11-3
11.2.1 Creating a New Operation Set 11-3
11.2.2 Renaming an Operation Set 11-4
11.2.3 Copying an Operation Set 11-5
11.2.4 Deleting an Operation Set 11-5
11.2.5 Editing an Operation Set 11-6

Table of Contents (continued)

Chapter Page

11.3 Reservoir Operation Zones 11-6
11.3.1 Renaming and Describing Operation Zones 11-7
11.3.2 Adding a New Reservoir Storage Zone 11-7
11.3.3 Defining Operation Zones 11-8
11.3.4 Deleting Operation Zones 11-9
11.4 Understanding Reservoir Operation Rules 11-10
11.4.1 Release Decision Process 11-10
11.4.2 Using Existing Rules 11-11
11.4.3 Removing Rules 11-11
11.4.4 Deleting Rules 11-11
11.4.5 Prioritizing Rules 11-11
11.4.6 Renaming Rules 11-11
11.5 Defining Reservoir Operation Rules 11-12
11.5.1 Adding a New Operation Rule to a Zone 11-13
11.5.2 Adding an Existing Rule to a Zone 11-14
11.5.3 Defining a Release Function Rule 11-14
11.5.4 Defining a Downstream Control Function Rule 11-19
11.5.5 Defining a Tandem Operation Rule 11-21
11.5.6 Defining an Induced Surcharge Rule 11-22
11.5.7 Defining a Flow Rate of Change Limit Rule 11-26
11.5.8 Defining an Elevation Rate of Change Limit Rule 11-27
11.5.9 Defining Hydropower Rules 11-29
11.5.9.1 Hydropower – Schedule 11-29
11.5.9.2 Hydropower – Time Series Requirement 11-30
11.5.9.3 Hydropower – Power Guide Curve 11-31
11.5.9.4 Hour of Day Weighting Factors 11-33
11.5.9.5 Day of Week Weighting Factors 11-34
11.6 Common Options for Rule Definition 11-35
11.6.1 Interpolation Method 11-35
11.6.2 Hour of Day Multiplier 11-37
11.6.3 Day of Week Multiplier 11-38
11.6.4 Rising / Falling Condition 11-39
11.6.5 Seasonal Variation 11-40
11.7 Editing the Reservoir Decision Interval 11-41
11.8 Selecting the Reservoir Guide Curve 11-42
11.9 Adjusting the Guide Curve for Flood Control Credit Storage 11-43

12 Defining Reservoir Systems
12.1 Concept of Reservoir Systems 12-1
12.1.1 Implicit System Storage Balance Method 12-2
12.1.2 Explicit System Storage Balance Method 12-5
12.2 Overview of the Reservoir System Editor 12-9
12.3 Accessing the Reservoir System Editor 12-10
12.4 Reservoir System Editor Menu Items 12-10
12.5 Defining a New Reservoir System 12-11

Table of Contents (continued)

Chapter Page

12.6 Selecting Reservoirs for the System 12-12
12.7 Defining a System Storage Balance Operation Set 12-13
12.8 Defining Reservoir System Zones 12-14
12.9 Configuring System Storage Balance 12-15
12.10 General System Operation Notes 12-17

13 Defining Alternatives
13.1 Preparing to Develop Alternatives 13-1
13.2 Accessing the Alternative Editor 13-1
13.3 Creating a New Alternative 13-2
13.4 Selecting a Reservoir Operation Set 13-3
13.5 Selecting a Reservoir System Storage Balance Operation Set 13-4
13.6 Selecting Lookback Type 13-5
13.7 Associating Time-Series Data with a Location 13-5
13.8 Defining Observed Data 13-7
13.9 Saving an Alternative 13-8

14 Running Simulations
14.1 Recognizing Simulation Screen Components 14-1
14.1.1 Menu Bar 14-2
14.1.2 Map (Mouse) Tools 14-4
14.1.3 Simulation Control Panel 14-5
14.1.4 Display Area 14-5
14.2 Creating a Simulation 14-6
14.3 Working with Existing Simulations 14-7
14.3.1 Opening an Existing Simulation 14-8
14.3.2 Editing a Simulation 14-9
14.4 Computing a Simulation 14-9
14.4.1 Setting the Active Alternative 14-9
14.4.2 Computing the Simulation 14-10
14.5 Reviewing Simulation Results 14-11
14.5.1 Viewing Compute Logs 14-11
14.5.2 Using Plots and Tables 14-13
14.5.2.1 Features of Plots 14-13
14.5.2.2 Customizing Plots 14-14
14.5.2.3 Creating User-Defined Plots 14-15
14.5.2.4 Viewing Data in Tabular Form 14-17
14.5.2.5 Printing and Exporting Plots and Tables 14-18
14.5.3 Viewing Summary Reports 14-18
14.5.3.1 Reservoir Summary Reports 14-18
14.5.3.2 Flow Summary Reports 14-19
14.5.3.3 Power Summary Reports 14-20
14.5.3.4 Gate Summary Reports 14-21
14.5.3.5 Stage Summary Reports 14-22
14.5.3.6 Release Decision Reports 14-23
14.5.3.7 Network Reports 14-23

Table of Contents (continued)

Chapter **Page**

14.6 Calibrating the Model and Editing Data 14-24
14.6.1 Using the ResSim Editor Interface 14-24
14.6.2 Editing Alternative Lookback, Time Series, and Observed Data 14-25
14.6.3 Editing Release Override Values 14-25
14.6.4 Setting Compute Options 14-29
14.7 Managing Simulation Data 14-30
14.7.1 Saving Data *to* the Base Directory 14-30
14.7.2 Replacing Data *from* the Base Directory 14-31
14.8 Using HEC-DssVue 14-32

List of Tables

Table Number **Page**

1.1 Summary of Contents of HEC-ResSim User's Manual 1-4

3.1 Map Layer Formats Supported by ResSim 3-10

12.1 Explicit System Storage Balance 12-7

List of Figures

Figure Number Page

1.1 ResSim Module Concepts 1-1

2.1 ResSim Information Screen 2-2
2.2 ResSim Main Window 2-2
2.3 File Menu 2-4
2.4 View Menu 2-4
2.5 Tools Menu 2-4
2.6 Help Menu 2-5
2.7 Watershed Setup Module 2-6
2.8 Reservoir Network Module 2-10
2.9 Simulation Module 2-13
2.10 Tools Menu, Options Dialog Box, General Tab: Reload last Watershed at Startup 2-15
2.11 Open Watershed Dialog Box 2-16
2.12 Stream Alignment 2-17
2.13 Reservoir 2-17
2.14 Levee 2-17
2.15 Diversion 2-17
2.16 Channel Modification 2-17
2.17 Off-Channel Storage 2-17
2.18 Other Project 2-17
2.19 Computation Points 2-18
2.20 Impact Areas 2-18
2.21 Time-Series Icons 2-18
2.22 Reservoir Network Schematic 2-19
2.23 Selecting a Report 2-20
2.24 Select Print from Report's File Menu 2-20
2.25 Select Print from Report's Shortcut Menu 2-20
2.26 Printing Properties, Page Tab 2-21
2.27 Printing Properties, Header/Footer Tab 2-21
2.28 Printing Properties, Table Title Tab 2-21
2.29 System Print Dialog Box 2-22
2.30 Select Print Preview from Report's Shortcut Menu 2-22
2.31 Print Preview Dialog Box 2-23
2.32 Select Export from the Report's File Menu 2-23
2.33 Select Export from Report's Shortcut Menu 2-24
2.34 Table Export Options Dialog Box 2-24
2.35 System Save Browser (for Saving a File) 2-25

3.1 Watershed Setup Module Main Window 3-2
3.2 File Menu 3-2
3.3 Edit Menu 3-3
3.4 Watershed Menu 3-3
3.5 Reports Menu 3-3

List of Figures (continued)

Figure Number **Page**

3.6 Reservoir Shortcut Menu....3-6
3.7 HEC-ResSim Options Dialog Box....3-7
3.8 Add Watershed Location Dialog Box....3-7
3.9 Create New Watershed Dialog Box....3-8
3.10 Layer Selector Dialog Box....3-12
3.11 Open File Dialog Box to Add Map Layer....3-12
3.12 Geographic Region Dialog Box....3-13

4.1 Layer Selector....4-2
4.2 Layers Menu - Layer Selector....4-3
4.3 Edit Menu - Layer Selector....4-3
4.4 Edit Menu - Allow Layer Editing Turned Off and No Layer Selected....4-3
4.5 Maps Menu - Layer Selector....4-4
4.6 View Menu - Layer Selector....4-4
4.7 Layer Selector - Layers Expanded....4-5
4.8 Layer Selector - Map Legend for Reservoirs....4-6
4.9 Toolbar Button Editor....4-7
4.10 Layer Selector Shortcut Menu for the Stream Alignment Layer....4-9
4.11 Layer Selector Shortcut Menu for a Map Layer....4-10
4.12 Drawing Properties Editor - Reservoir Tab....4-11
4.13 Drawing Properties Editor - Levees Tab....4-12
4.14 Drawing Properties Editor - Diversions Tab....4-12
4.15 Drawing Properties Editor - Channel Modification Tab....4-13
4.16 Drawing Properties Editor - Computation Point Tab....4-13
4.17 Drawing Properties Editor - Impact Area Tab....4-14
4.18 Stream Alignment Properties Editor....4-14
4.19 USGS Digital Line Graph Editor for Digital Line Graph (DLG) Map Layer....4-15

5.1 Stream Alignment....5-1
5.2 Stream Elements....5-1
5.3 Stream Nodes....5-1
5.4 Stream Junctions....5-1
5.5 Relationship of Line Segments, Stream Elements, and Stream Alignment....5-2
5.6 Drawing a Stream Element....5-3
5.7 Create New Stream Dialog Box....5-4
5.8 Connect Stream Reaches Dialog Box....5-4
5.9 Stream Junction....5-4
5.10 Moving Stream Element Vertices....5-5
5.11 Stream Alignment Shortcut Menu....5-6
5.12 Stream Editor....5-7
5.13 Enter Description Dialog Box - Stream Element....5-7
5.14 Name Stream Dialog Box....5-8

List of Figures (continued)

Figure Number **Page**

5.15 Confirmation Message when Deleting a Stream Element 5-8
5.16 Stream Node Shortcut Menu 5-9
5.17 Stream Node Editor 5-9
5.18 Confirm Delete of Stream Node 5-10
5.19 Moving a Stream Junction 5-10
5.20 Stream Junction Shortcut Menu 5-11
5.21 Stream Junction Editor 5-11
5.22 Confirm Reverse Direction of Stream Element 5-12
5.23 Import Stream Alignment Dialog Box 5-13
5.24 Choose Shapefile Dialog Box 5-13
5.25 Save File Browser 5-15
5.26 Stream Alignment Properties Dialog Box 5-15
5.27 List of Streams in Stream Alignment 5-16

6.1 Reservoir Elements in Watershed Setup Module 6-1
6.2 Name New Reservoir Dialog Box 6-2
6.3 Reservoir Editor 6-3
6.4 Warning Message when Renaming Reservoir 6-3
6.5 Confirm Removal of Reservoir Dialog Box 6-4
6.6 Configuration Notes - Reservoir 6-4
6.7 Levee Drawing 6-5
6.8 Levee Properties Editor 6-6
6.9 Warning Message when Renaming Levee 6-7
6.10 Confirm Removal of Levee Dialog Box 6-7
6.11 Configuration Notes - Levee 6-8
6.12 Example Diversions 6-9
6.13 Diversion Editor 6-10
6.14 Warning Message when Renaming Diversion 6-10
6.15 Disconnecting an Outflow - Diversion Shortcut Menu 6-11
6.16 Configuration Notes - Diversion 6-12
6.17 Channel Modification Editor 6-13
6.18 Warning Message when Renaming Channel Modification 6-13
6.19 Configuration Notes - Channel Modification 6-14
6.20 Off-Channel Storage Editor 6-15
6.21 Warning Message when Renaming Off-Channel Storage Area 6-16
6.22 Configuration Notes - Off-Channel Storage 6-17
6.23 "Other" Projects Editor 6-18
6.24 Warning Message when Renaming "Other" Project 6-19
6.25 Configuration Notes - "Other" Projects 6-20
6.26 Computation Point Editor 6-21
6.27 Rename Dialog Box - Computation Point 6-23
6.28 Confirm Deletion Dialog Box - Computation Point 6-23
6.29 Time-Series Icons 6-24

List of Figures (continued)

Figure Number **Page**

7.1 Configuration Editor ... 7-1
7.2 Create a New Configuration ... 7-2
7.3 Calendar Tool ... 7-2
7.4 Configuration Editor – Edit Project List Option from Projects Menu ... 7-3
7.5 Project Selector Dialog Box ... 7-4
7.6 Configuration Notes Dialog Box ... 7-5
7.7 Configuration Save As... Dialog Box ... 7-5
7.8 Confirm Delete of a Configuration ... 7-6
7.9 List of Configurations Report ... 7-7

8.1 Reservoir Network Module Main Window ... 8-2
8.2 File Menu ... 8-3
8.3 Edit Menu ... 8-3
8.4 View Menu ... 8-3
8.5 Network Menu ... 8-4
8.6 Alternative Menu ... 8-4
8.7 Reports Menu ... 8-4
8.8 Tools Menu ... 8-4
8.9 Help Menu ... 8-4
8.10 Network, Configuration, and Lock/Unlock ... 8-5
8.11 Create New Reservoir Network Dialog Box ... 8-7
8.12 Open Reservoir Network Dialog Box ... 8-8
8.13 Rename Reach Dialog Box ... 8-10
8.14 Confirm Delete Reach Dialog Box ... 8-10
8.15 Reservoir Network Reports: Reservoir List ... 8-11
8.16 Reservoir Network Reports: Reach List ... 8-11
8.17 Reservoir Network Reports: Junction List ... 8-12
8.18 Reservoir Network Reports: Diversion List ... 8-12
8.19 Reservoir Network Reports: Advanced -- Network Summary ... 8-13
8.20 Reservoir Network Reports: Advanced -- Node List ... 8-14
8.21 Watershed Setup Module, Watershed Menu, Save Configuration before Updating Network ... 8-14
8.22 Reservoir Network Module, Network Menu, Update Network from Configuration ... 8-15

9.1 Junction Editor: Info Tab ... 9-2
9.2 Junction Editor: Local Flow Tab ... 9-3
9.3 Junction Editor: Rating Curve Tab ... 9-4
9.4 Junction Editor: Observed Data Tab ... 9-5
9.5 Reach Editor ... 9-6
9.6 Reach Editor: Coefficient Routing Method ... 9-7
9.7 Reach Editor: Muskingum Routing Method ... 9-8
9.8 Reach Editor: Muskingum-Cunge 8-pt Channel Routing Method ... 9-9
9.9 Reach Editor: Muskingum-Cunge Prismatic Channel Routing Method ... 9-11
9.10 Reach Editor: Modified Puls Routing Method ... 9-13

List of Figures (continued)

Figure Number **Page**

9.11 Reach Editor: SSARR Routing Method 9-14
9.12 Reach Editor: Losses Tab 9-16
9.13 Reach Editor: Observed Data Tab 9-17
9.14 Diversion Editor 9-18
9.15 Diversion Editor: Constant Diversion Method 9-19
9.16 Diversion Editor: Monthly Varying Diversion Method 9-20
9.17 Diversion Editor: Seasonal Diversion Method 9-21
9.18 Diversion Editor: Function of Flow Diversion Method 9-22
9.19 Diversion Editor: Function of Pool Elevation Diversion Method 9-23
9.20 Diversion Editor: Time-Series Diversion Method 9-24
9.21 Diversion Editor: Losses Tab 9-25
9.22 Diversion Editor: Observed Data Tab 9-26

10.1 Reservoir Editor: Physical Tab 10-2
10.2 Reservoir Editor, Physical Tab: Default Reservoir Component Tree 10-3
10.3 Reservoir Editor, Physical Tab: Default Reservoir Component Tree with Diverted Outlet 10-3
10.4 Reservoir Editor, Physical Tab: with Pool Losses 10-4
10.5 Reservoir Editor: Pool Menu 10-4
10.6 Reservoir Tree Shortcut Menu: Pool 10-4
10.7 Reservoir Tree: Dam 10-4
10.8 Reservoir Editor, Physical Tab: Dam Menu 10-5
10.9 Reservoir Tree Shortcut Menu: Dam 10-5
10.10 Reservoir Tree: Outlet Groups 10-6
10.11 Diverted Outlet Shortcut Menu: Add Outlet Group 10-6
10.12 Reservoir Tree: Controlled Outlets 10-7
10.13 Dam Shortcut Menu: Add Controlled Outlet 10-7
10.14 Reservoir Editor, Physical Tab: Outlet Menu - Add Power Plant 10-8
10.15 Controlled Outlet Shortcut Menu: Add Power Plant 10-8
10.16 Reservoir Tree: Uncontrolled Outlets 10-9
10.17 Dam Shortcut Menu: Add Uncontrolled Outlet 10-9
10.18 Reservoir Tree: Tailwater Elevation 10-10
10.19 Dam Shortcut Menu: Add Tailwater Elevation 10-10
10.20 Reservoir Tree: Diverted Outlet 10-11
10.21 Reservoir Editor: Outlet Menu for Diverted Outlet 10-11
10.22 Reservoir Component Shortcut Menu: Rename Component 10-12
10.23 Rename Reservoir Component Dialog Box 10-12
10.24 Reservoir Component Shortcut Menu: Delete Component 10-13
10.25 Confirm Deletion of Reservoir Component 10-13
10.26 Reservoir Parameter Shortcut Menu: Remove Parameter 10-14
10.27 Confirm Removal of Reservoir Parameter 10-14
10.28 Reservoir Editor: Physical Data--Pool 10-15
10.29 Reservoir Editor: Physical Data--Pool Evaporation 10-16
10.30 Reservoir Editor: Physical Data--Pool Seepage 10-17
10.31 Reservoir Editor: Physical Data--Dam Leakage 10-18

List of Figures (continued)

Figure Number **Page**

10.32 Controlled Outlet (no Gate Settings) 10-19
10.33 Gate Settings Dialog Box 10-20
10.34 Controlled Outlet (with Gate Settings) 10-20
10.35 Power Plant Physical Data Editor: Capacity Tab 10-21
10.36 Power Plant Physical Data Editor: Efficiency Tab - Constant Efficiency Method 10-22
10.37 Power Plant Physical Data Editor: Efficiency Tab - Function of Reservoir Elevation 10-23
10.38 Power Plant Physical Data Editor: Efficiency Tab - Function of Reservoir Release 10-24
10.39 Power Plant Physical Data Editor: Efficiency Tab - Function of Operating Head 10-25
10.40 Power Plant Physical Data Editor: Station Use Tab - Constant Method 10-26
10.41 Power Plant Physical Data Editor: Station Use Tab - Function of Release Method 10-27
10.42 Power Plant Physical Data Editor: Hydraulic Losses Tab - Constant Method 10-28
10.43 Power Plant Physical Data Editor: Hydraulic Losses Tab - Function of Release Method 10-29
10.44 Reservoir Editor: Physical Data--Uncontrolled Outlet 10-30
10.45 Reservoir Editor: Physical Data--Tailwater 10-31
10.46 Composite Release Capacity Table 10-33
10.47 Reservoir Editor: Observed Data Tab 10-35

11.1 Reservoir Editor--Operations Tab 11-2
11.2 New Operation Set Dialog Box 11-4
11.3 Rename Operation Set Dialog Box 11-4
11.4 Duplicate Operation Set 11-5
11.5 Select Operation Set to Delete 11-5
11.6 Reservoir Editor Showing New Operation Set 11-6
11.7 New Zone Dialog Box 11-7
11.8 Reservoir Editor--Operations Tab: Zone Editor 11-8
11.9 New Operating Rule Dialog Box 11-13
11.10 Select Existing Rule Dialog Box 11-14
11.11 Reservoir Editor--Operations Tab: New Release Function Rule 11-15
11.12 Reservoir Editor--Operations Tab: Release Function Rule, Selecting a Function from the Independent Variable Definition Editor 11-16
11.13 Reservoir Editor--Operations Tab: Release Function Rule, Selecting an Independent Variable from the Model Variable List 11-16
11.14 Reservoir Editor--Operations Tab: Release Function Rule, Defining an External Variable as the Independent Variable 11-17
11.15 Time Series Options for Model and External Variables 11-17
11.16 Reservoir Editor--Operations Tab: Example of Completed Release Function Rule 11-18

List of Figures (continued)

Figure Number **Page**

11.17 Reservoir Editor--New Operating Rule: Downstream Control Function ..11-19
11.18 Reservoir Editor--Example of a Downstream Control Function Rule 11-20
11.19 Reservoir Editor--New Operating Rule: Tandem Operation 11-21
11.20 Reservoir Editor--Example of a Tandem Operation Rule 11-22
11.21 Reservoir Editor--Operations Tab: Create Induced Surcharge Rule 11-23
11.22 Reservoir Editor--Operations Tab: Induced Surcharge Rule 11-24
11.23 Plot of Computed Induced Surcharge Curves 11-25
11.24 Induced Surcharge--Falling Pool Options 11-25
11.25 Reservoir Editor--Operations Tab: Flow Rate of Change Limit Rule 11-27
11.26 Reservoir Editor--Operations Tab: Elevation Rate of Change Limit Rule (Pool) 11-28
11.27 Hydropower Rule Types 11-29
11.28 Hydropower – Schedule Rule Editor 11-30
11.29 Hydropower – Time Series Requirement Rule Editor 11-31
11.30 Hydropower – Power Guide Curve Rule Editor 11-32
11.31 Hour of Day Weighting with Default Values of 1.0 Specified for Entire Day 11-33
11.32 Hour of Day Weighting with Values of 1.0 Specified for Portion of Day 11-33
11.33 Hour of Day Weighting to "Double" the Power Requirement for Portion of Day 11-34
11.34 Hour of Day Weighting Modified from Default Values 11-34
11.35 Day of Week Weighting with Default Values of 1.0 for Each Day of the Week 11-34
11.36 Day of Week Weighting with Values of 0.0 for Saturday and Sunday 11-34
11.37 Day of Week Weighting to "Double" the Power Requirement on Wednesday 11-35
11.38 Day of Week Weighting Modified from Default Values 11-35
11.39 Interpolation Methods 11-35
11.40 Linear Interpolation Method 11-36
11.41 Step Interpolation Method 11-36
11.42 Cubic Interpolation Method 11-36
11.43 Hour of Day Multiplier with Default Values of 1.0 Specified for Entire Day 11-37
11.44 Hour of Day Multiplier with Values of 0.0 Specified for Portion of Day 11-37
11.45 Hour of Day Multiplier Modified from Default Values 11-37
11.46 Day of Week Multiplier with Default Factors of 1.0 Specified for Each Day of the Week 11-38
11.47 Day of Week Multiplier with Factors of 0.0 Specified for Saturday and Sunday 11-38
11.48 Day of Week Multiplier Modified from Default Values 11-38
11.49 Rising / Falling Condition Dialog Box 11-39
11.50 Rising / Falling Condition Modified from Default 11-39

List of Figures (continued)

Figure Number **Page**

11.51 Seasonal Variation Dialog Box 11-40
11.52 Reservoir Decision Interval Editor, Interval Options 11-41
11.53 Reservoir Decision Interval Editor, Regular Interval Option 11-41
11.54 Reservoir Decision Interval Editor, Weekly Schedule Option 11-41
11.55 Operations Menu, Guide Curve Option 11-42
11.56 Reservoir Guide Curve Editor 11-42
11.57 Reservoir Guide Curve Editor, Checkbox to Indicate Guide Curve is Modified by Available Flood Control Storage in Other Reservoirs 11-43
11.58 Reservoir Guide Curve Editor, Edit Reservoir Set to Select Reservoirs to Provide Flood Control Storage Credit 11-43
11.59 Reservoir Guide Curve Editor, Reservoirs to Provide Flood Control Storage Credit 11-44
11.60 Reservoir Guide Curve Editor, Definition of Function for Using Flood Control Storage Credit 11-44
11.61 Example of Reservoir Guide Curve Editor Showing Definition of Flood Control Storage Credit 11-45
11.62 Reservoir Guide Curve Editor, Available Credit Storage vs. Credit Storage 11-45
11.63 Reservoir Guide Curve Editor, Seasonal Guide Curves for Potential Credit Storage 11-45

12.1 Example of a Two-Reservoir Tandem System 12-2
12.2 Tandem Operation Rule Included for Reservoir 1 12-2
12.3 Implicit System Storage Balance 12-3
12.4 Example of Desired Storages using the Implicit System Storage Balance Method 12-4
12.5 Example of a Two-Reservoir Parallel System 12-5
12.6 Explicit System Storage Balance 12-6
12.7 Example of Desired Storages using the Explicit System Storage Balance Method 12-8
12.8 Reservoir System Editor (New Reservoir System) 12-9
12.9 Reservoir Network Module, Edit Menu, Reservoir Systems 12-10
12.10 Reservoir System Editor, ReservoirSystem Menu 12-10
12.11 Reservoir System Editor, Edit Menu 12-10
12.12 Reservoir System Editor, Operations Menu 12-11
12.13 Reservoir System Editor, Zones Menu 12-11
12.14 New Reservoir System Dialog Box 12-11
12.15 Reservoir System Editor (New Reservoir System) 12-12
12.16 Reservoir Selection Editor 12-13
12.17 New System Storage Balance Operation Set for Reservoir System 12-13
12.18 New Storage Zone Dialog Box 12-14
12.19 Configuring System Storage Balance 12-15
12.20 Percent Storage for each Reservoir in a Two-Reservoir System 12-16

List of Figures (continued)

Figure Number **Page**

13.1 Alternative Editor 13-1
13.2 New Alternative Dialog Box 13-2
13.3 Alternative Editor--Name and Description Fields 13-2
13.4 Alternative Editor--Operations Tab, Reservoir Operation Set 13-3
13.5 Alternative Editor--Operations Tab, Reservoir System Storage Balance Operation Set 13-4
13.6 Alternative Editor--Lookback Tab 13-5
13.7 Alternative Editor--Time-Series Tab 13-5
13.8 Select Time-Series Path Dialog Box 13-6
13.9 Alternative Editor--Observed Data Tab 13-7
13.10 Alternative Editor--Save Alternative 13-8
13.11 Reservoir Network Module--Network Menu, Save Network 13-8
13.12 File Menu--Save Watershed 13-8

14.1 Simulation Module Main Window 14-1
14.2 File Menu 14-2
14.3 Edit Menu 14-2
14.4 View Menu 14-3
14.5 Simulation Menu 14-3
14.6 Alternative Menu 14-3
14.7 Reports Menu 14-3
14.8 Tools Menu 14-4
14.9 Help Menu 14-4
14.10 Simulation Control Panel 14-5
14.11 Simulation Control Panel Shortcut Menu: New Simulation 14-6
14.12 Simulation Period Dialog Box 14-6
14.13 Creating Simulation Window 14-7
14.14 Simulation Control Panel Shortcut Menu: Open Simulation 14-8
14.15 Open Simulation Dialog Box 14-8
14.16 Simulation Tree 14-8
14.17 Simulation Control Panel Shortcut Menu: Set Alternative As Active 14-9
14.18 Simulation Control Panel Shortcut Menu: Compute 14-10
14.19 Compute Window 14-11
14.20 Compute Log 14-12
14.21 Select Font Dialog Box 14-12
14.22 Reservoir Shortcut Menu -- Plot Simulation Results 14-13
14.23 Sample Plot of Reservoir Results 14-13
14.24 Shortcut Menu for an Element 14-15
14.25 Select Plot Variables Dialog Box 14-15
14.26 Select Plot Variables: Region Shortcut Menu 14-16
14.27 Save Plot Type 14-16
14.28 Shortcut Menu: User Plots 14-17
14.29 Data in Tabular Form 14-17

List of Figures (continued)

Figure Number **Page**

14.30 Reservoir Summary Report 14-18
14.31 Flow Summary Report 14-19
14.32 Power Summary Report 14-20
14.33 Gate Summary Report 14-21
14.34 Stage Summary Report 14-22
14.35 Release Decision Report 14-23
14.36 ResSim Editor Interface 14-24
14.37 Release Overrides Editor 14-25
14.38 Release Overrides Editor Shortcut Menu: Fill Data Values 14-27
14.39 Table Fill Options Dialog Box 14-27
14.40 Release Overrides Editor Table: Revised Data Values using Repeat Fill Option 14-27
14.41 Import Time Series Dialog Box 14-28
14.42 ResSim Editor Interface: Compute Options 14-29
14.43 Alternative Shortcut Menu: Save to Base Directory 14-30
14.44 Save Simulation Run Model Parameters to Base Directory 14-30
14.45 Alternative Shortcut Menu: Replace from Base Directory 14-31
14.46 Replace Simulation Run Model Parameters from Base Directory 14-31
14.47 Accessing HEC-DssVue from the Tools Menu 14-32
14.48 HEC-DssVue Main Window Showing Pathname Listing 14-32
14.49 Screened Pathname Listing Showing Observed (OBS) Records 14-32
14.50 Example Plot Using HEC-DssVue 14-33
14.51 Example of Tabulated Data Using HEC-DssVue 14-33

List of Appendices

Appendix **Page**

A ResSim Application Settings A-1
B Setting Up the Coordinate System B-1
C Using Map Editors C-1
D Using the Color Chooser D-1
E Using HEC-DssVue E-1
F Copying and Printing ResSim Data F-1
G References G-1

History and Acknowledgments

The HEC-ResSim software was developed at the Hydrologic Engineering Center, U.S. Army Corps of Engineers. HEC-ResSim is a component of the HEC Next Generation (NexGen) Software Development Project. The NexGen project is under the guidance of Darryl Davis, Director, HEC. Joan Klipsch, as the Project Engineer, and Vernon Bonner (HEC, retired) and Daniel Barcellos, as the Program Managers, led an experienced team of HEC staff, Corps reservoir regulators, and private contractors, in the design and development of HEC-ResSim. John DeGeorge, Ph.D. and his staff at Resources Management Associates (RMA) were major participants in the development of the HEC-ResSim program.

Requirements definition began in fiscal year (FY) 1996, with the document, "Reservoir System Simulation (RSS) Software, Draft Program Requirement," written by Douglas Speers, a contract consultant who had recently retired from the Corps' North Pacific Division. A Corps User Group formally developed the final program requirements in FY1997, as part of the Corps Water Management System (CWMS) Modernization Project.

Throughout FYs 1998-2001, program design and development progressed, producing HEC-ResSim Version 1.0. This first release was within the Corps' Water Control Management community as part of the CWMS Version 1.0 deployment during FY 2002. With the Version 1.0 program, a draft User's Manual was provided. Vernon Bonner (HEC, retired) and Cassie Carter, Ph.D. (RMA) provided substantial contributions to the ResSim Version 1.0 User's Manual. Program development, review, documentation, and testing continued throughout FY 2002 and 2003 culminating in the general release of HEC-ResSim Version 2.0 program and User's Manual in September 2003.

Chapter 1

Introduction

Table of Contents

Section **Page**

1 Introduction
1.1 ResSim Modules 1-1
1.1.1 Watershed Setup Module 1-2
1.1.2 Reservoir Network Module 1-2
1.1.3 Simulation Module 1-3

1.2 About this Manual 1-3

List of Tables

Table Number

1.1 Summary of Contents of HEC-ResSim User's Manual 1-4

List of Figures

Figure Number

1.1 ResSim Module Concepts 1-1

Chapter 1

Introduction

Welcome to the Hydrologic Engineering Center's Next Generation Reservoir Simulation (HEC-ResSim) computer program. At some time in the future, ResSim will be the successor to the "HEC-5, Simulation of Flood Control and Conservation Systems" program. ResSim is comprised of a graphical user interface (GUI), a computational program to simulate reservoir operation, data storage and management capabilities, and graphics and reporting facilities. The Data Storage System, HEC-DSS (HEC, 1995 and HEC, 2003b) is used for storage and retrieval of input and output time-series data.

1.1 ResSim Modules

ResSim offers three separate sets of functions called Modules that provide access to specific types of data within a watershed. These modules are **Watershed Setup**, **Reservoir Network**, and **Simulation**. Each module has a unique purpose and an associated set of functions accessible through menus, toolbars, and schematic elements. Figure 1.1 illustrates the basic modeling features available in each module.



Figure 1.1 ResSim Module Concepts

1.1.1 Watershed Setup Module

The purpose of the Watershed Setup module is to provide a common framework for watershed creation and definition among different modeling applications. This module is currently common to HEC-ResSim, HEC-FIA, and the CWMS CAVI.

A watershed is associated with a geographic region for which multiple models and area coverages can be configured. A watershed may include all of the streams, projects (e.g., reservoirs, levees), gage locations, impact areas, time-series locations, and hydrologic and hydraulic data for a specific area. All of these details together, once configured, form a watershed framework.

When you create a new watershed, ResSim generates a directory structure (see figure at right) for all files associated with the watershed.



In the Watershed Setup module, you assemble items that describe a watershed's physical arrangement. Once you have created a new watershed, you are able to import maps from external sources, specify the units of measure for *viewing* the watershed, add layers containing additional information about the watershed, create a common stream alignment, and configure elements. You can also add projects and create time-series icons within the Watershed Setup module.

Chapters 3 through 7 describe the Watershed Setup module in more detail.

1.1.2 Reservoir Network Module

The purpose of the Reservoir Network module is to isolate the development of the reservoir model from the output analysis. In the Reservoir Network module, you will build your river schematic, describe the physical and operational elements of your reservoir model, and develop the alternatives that you want to analyze. Using configurations that are created in the Watershed Setup module as a template, you will create the basis of a reservoir network. You will then add routing reaches and possibly other network elements to complete the connectivity of your network schematic. Once the schematic is complete, physical and operational data for each network element are defined. Also, alternatives are created that

specify the reservoir network, operation set(s), initial conditions, and assignment of DSS pathnames (time-series mapping).

Chapters 8 through 13 describe the Reservoir Network module in more detail.

1.1.3 Simulation Module

The purpose of the Simulation module is to isolate output analysis from the model development process. Once the reservoir model is complete and the alternatives have been defined, the Simulation module is used to configure the simulation. The computations are performed and results are viewed within the Simulation module.

When you create a simulation you must specify a simulation time window, a computation interval, and the alternatives to be analyzed. Then, ResSim creates a directory structure within the rss folder of the watershed that represents the "simulation". Within this "simulation" tree will be a copy of the watershed, including only those files needed by the selected alternatives. Also created in the simulation is a DSS file called simulation.dss, which will ultimately contain all the DSS records that represent the input and output for the selected alternatives. Additionally, elements can be edited and saved for subsequent simulations.

Chapter 14 describes the Simulation module in more detail.

1.2 About this Manual

This User's Manual is the primary reference for providing ResSim users with detailed instructions for creating ResSim models and analyzing simulation results. With the exception of the first and second chapters, (which deal with introductory and core concepts), the chapters of this manual group tasks according to module. Each chapter provides an overview of key concepts and a detailed description of screen components and tools available in the module, and then shows you how to carry out specific tasks in the module. Appendices cover topics and tasks that require levels of detail beyond the scope of an individual chapter.

The organization of this manual is summarized in Table 1.1.

Table 1.1 Summary of Contents of HEC-ResSim User's Manual

HEC-ResSim Module	If you want to find out…	Refer to…
Watershed Setup	Concepts of HEC-ResSim	Chapter 2
	How to create and manage watersheds	Chapter 3
	How to work with map layers	Chapter 4
	How to establish a stream alignment	Chapter 5
	How to create and define watershed elements and projects (e.g., reservoirs, levees, etc.)	Chapter 6
	How to create computation points (hydrograph locations)	Chapter 6
	How to create watershed configurations	Chapter 7
Reservoir Network	How to develop reservoir networks	Chapter 8
	How to edit element data (junctions, routing reaches and diversions)	Chapter 9
	How to define physical reservoir data	Chapter 10
	How to edit physical reservoir data	Chapter 10
	How to develop reservoir operation data	Chapter 11
	How to define reservoir systems	Chapter 12
	How to define alternatives	Chapter 13
Simulation	How to develop and execute simulations	Chapter 14
	How to analyze results	Chapter 14
	How to calibrate model	Chapter 14
	How to manage simulations	Chapter 14
	Detailed application settings	Appendix A
	How to define the coordinate system	Appendix B
	How to edit maps	Appendix C
	How to change colors	Appendix D
	How to use HEC-DSSVue	Appendix E
	How to copy, export, and print tables	Appendix F
	References	Appendix G

Chapter 2
ResSim Concepts

Table of Contents

Section **Page**

2 ResSim Concepts
2.1 Starting ResSim 2-2
2.2 Recognizing Common Screen Components 2-3
2.2.1 Menu Bar 2-3
2.2.2 Module List 2-5
2.3 Watershed Setup Module 2-6
2.4 Reservoir Network Module 2-10
2.5 Simulation Module 2-13
2.6 Opening an Existing Watershed 2-15
2.7 Understanding Schematic Elements 2-16
2.7.1 Stream Alignment 2-17
2.7.2 Other Watershed Elements 2-17
2.7.3 Reservoir Network Schematic 2-18
2.7.4 Using Shortcut Menus 2-19
2.8 Printing and Exporting Reports 2-19
2.8.1 Printing Reports 2-19
2.8.2 Print Preview 2-22
2.8.3 Exporting Reports to a File 2-23

List of Figures

Figure Number

2.1 ResSim Information Screen 2-2
2.2 ResSim Main Window 2-2
2.3 File Menu 2-4
2.4 View Menu 2-4
2.5 Tools Menu 2-4
2.6 Help Menu 2-5
2.7 Watershed Setup Module 2-6
2.8 Reservoir Network Module 2-10
2.9 Simulation Module 2-13
2.10 Tools Menu, Options Dialog Box, General Tab:
Reload last Watershed at Startup 2-15

List of Figures (continued)

Figure Number **Page**

2.11 Open Watershed Dialog Box 2-16
2.12 Stream Alignment 2-17
2.13 Reservoir 2-17
2.14 Levee 2-17
2.15 Diversion 2-17
2.16 Channel Modification 2-17
2.17 Off-Channel Storage 2-17
2.18 Other Project 2-17
2.19 Computation Points 2-18
2.20 Impact Areas 2-18
2.21 Time-Series Icons 2-18
2.22 Reservoir Network Schematic 2-19
2.23 Selecting a Report 2-20
2.24 Select Print from Report's File Menu 2-20
2.25 Select Print from Report's Shortcut Menu 2-20
2.26 Printing Properties, Page Tab 2-21
2.27 Printing Properties, Header/Footer Tab 2-21
2.28 Printing Properties, Table Title Tab 2-21
2.29 System Print Dialog Box 2-22
2.30 Select Print Preview from Report's Shortcut Menu 2-22
2.31 Print Preview Dialog Box 2-23
2.32 Select Export from the Report's File Menu 2-23
2.33 Select Export from Report's Shortcut Menu 2-24
2.34 Table Export Options Dialog Box 2-24
2.35 System Save Browser (for Saving a File) 2-25

Chapter 2

ResSim Concepts

Before you begin working with the individual modules available in ResSim, you will need to understand the concepts that will allow you to develop, access and interact with watersheds in ResSim.

This chapter begins with the following basics: explaining how to start ResSim; describing screen components that are common across modules, including menu items and map/mouse tools; and showing you how to create a new watershed or open an existing watershed.

Next, you will learn about the following four kinds of schematic elements in ResSim: Time-Series Icons, the Stream Alignment, Watershed (Study) Components, and the Model Schematic. This chapter also explains how to interact with schematic elements using right-click shortcut menus, which allow you to plot and tabulate data, edit model data, and edit common components of the watershed.

Layers are another concept in ResSim. This chapter will help you to understand how layers work in ResSim and describe the six kinds of layers: Time Series, Study, Stream Alignment, Gridded Data, Model Schematic, and Maps.

To work with Layers, you will use the Layer Selector. This chapter describes the components of the Layer Selector, including its menu items and layout, and shows you how to control layer display using the Layer Selector. You will learn how to view layer legends, organize layers, configure toolbar icons to control layer display, and add and remove map layers.

Each layer has a unique set of properties that you can configure to make your watershed display look the way you prefer. This chapter shows you how to use Properties Editors and other tools to configure the properties of Time Series, Study, Stream Alignment, Gridded Data, Model Schematic, and Map layers.

2.1 Starting ResSim

To begin working with the Watershed Data Sets, you must first start ResSim. Either double-click the HEC-ResSim icon on your PC's desktop, or from the **Start** menu, select **Programs → HEC → ResSim**. Once you start ResSim, an information screen (as shown in Figure 2.1) will appear briefly; then, ResSim's Main Window will open (Figure 2.2).



Figure 2.1 ResSim Information Screen



Figure 2.2 ResSim Main Window

2.2 Recognizing Common Screen Components

ResSim offers three modules, each with its own functions and module-specific tools, menus, and output. However, the modules share common screen components, as previously illustrated in Figure 2.2.

The **Title Bar** displays the ResSim title. After a watershed is opened, the name of the watershed will appear.

The **Menu Bar** contains menus for the modules. The items on the menus change as you switch between the modules, offering module-specific commands. You can select a menu item by clicking on the name of the menu (such as **File**), then pointing and clicking on the item you wish to select. Section 2.2.1 describes the **Menu Bar** in more detail.

The **Module List** contains all the available modules of ResSim. Use this list to move between the Watershed Setup module, the Reservoir Network module, and the Simulation module. Section 2.2.2 describes the **Module List** in more detail.

The **Display Area** is the geographic-referenced (geo-referenced) map space where all model schematic objects (reservoirs, junctions, diversions, etc.), watershed objects (stream alignments, reservoirs, stream reaches, etc.), and map layers are shown. You can manipulate elements and view results in the modules through the use of the tools in the **Toolbar**. Tools that affect the **Display Area** can have different functions depending on which module is selected.

The **Status Bar** displays map coordinates of the pointer in the display area when you are interacting with the watershed. When the pointer is outside of the display area, the **Status Bar** reflects the status of the program.

The **General Message Bar** displays a scrolling list of messages. System output log information appears in this window from the time you start ResSim until you exit the program. The scroll buttons on the right end of the Message Bar control the display and allow you to review all messages received during your ResSim session.

2.2.1 Menu Bar

In the Menu Bar, the **File**, **View**, **Tools**, and **Help** menus contain commands you can access from all three ResSim modules. Some of these menus also contain module-specific commands that appear only within individual modules. Commands and options that are *common* to *all three modules* are described as follows:

The **File** menu (Figure 2.3) allows you to create a **New Watershed**, **Open** an existing watershed, **Save** a watershed, **Save Map** (the Display Area) and **Exit** ResSim. Your most-recently-used watersheds are located at the bottom of the File menu. When a watershed is opened, the remaining menu items become active.



Figure 2.3 File Menu

In the **View** menu (Figure 2.4), select **Zoom to All** to restore your watershed view to full size after zooming in on one portion. **Layers** opens the Layers Selector dialog box which is used to select the spatially referenced layers (map/coverage). **Unit System** allows you to see the current screen view settings. *You can view data using whichever Unit System you prefer (English or SI); however, the Watershed (native) Unit System is established when a watershed is created and cannot be changed afterward (see* ***Tools*** *menu for Watershed information).* Lastly, if a dialog or editor window is open but inactive, **Restore Windows** brings the dialog or editor window to the front as the active window.

Figure 2.4 View Menu

The **Tools** menu (Figure 2.5) provides access to **Hec-DssVue,** which you will use to view (and possibly edit) dssfiles that are used for storing primarily time-series data. The **Scripts** command allows you to create, open and edit scripts (the scheduling of scripts is accomplished in the Simulation Module, from the Edit Menu). **Options** lets you specify watershed locations for storing your watersheds; specify a directory for caching map files; set the colors for compute messages and the format of log files; set the level of debug messages; choose whether or not you want a confirmation message to appear when you exit ResSim; and choose whether you want the last watershed reloaded at startup of the program. **Information** provides details about client, user, and watershed settings as well as server and system properties.

Figure 2.5 Tools Menu

In the **Help** menu (Figure 2.6), the **About** command displays information about the version of ResSim.



Figure 2.6 Help Menu

In addition to the four common menus described above, the following two menus appear in all three modules but contain module specific commands:

Edit – Typically, the edit options will be relevant to data element(s) for a specific module. The edit options available for each module are described in more detail in subsequent sections of this chapter.

Reports – Provides access to reports produced for a specific module. The reports available for each module are described in more detail in subsequent sections of this chapter.

2.2.2 Module List

From the ResSim main window (Figure 2.2) the graphical user interface (GUI) is organized to provide the necessary information to enter data, review data, edit data, run a simulation, and view results. The steps are divided into separate sets of functions called **modules**. A **module** has a specific set of commands that are accessed through menus and toolbars. Each module provides access to specific types of data or results. The modules of ResSim are as follows:

Watershed Setup – create a stream alignment, define projects (e.g., reservoirs, levees), define computation points, identify impact areas, create configurations for the watershed, and define time-series icons that represent specific locations or time-series identifiers. Section 2.3 provides more details of this module.

Reservoir Network – create networks, add routing reaches, edit elements, create and edit alternatives including assigning the DSS pathnames for time-series references. Section 2.4 provides more details of this module.

Simulation – define simulations for a watershed. A simulation consists of a time window and the ResSim alternatives you wish to execute for the simulation. Within this module, you can also edit element data. Once a simulation is defined, a compute is performed and the results are analyzed using graphical and tabular output. Section 2.5 provides more details of this module.

Each module has a menu bar and toolbar that are very similar for all of the modules. Example windows for each of the modules are presented in subsequent sections of this chapter.

2.3 Watershed Setup Module

The **Watershed Setup** module is used to create and setup your watershed. From the **Module** list, select **Watershed Setup**. The main window and the different components for the **Watershed Setup** module are illustrated in Figure 2.7.



Figure 2.7 Watershed Setup Module

The **Menu Bar** (in Figure 2.7) contains the menus for the **Watershed Setup** module. In addition to the four common menus described in Section 2.2.1, the following list is a description of the available menus in the **Watershed Setup** module.

Edit – From this menu, you can edit study information and view watershed information, edit global information for impact areas and projects, and adjust the colors and fonts used by the individual projects. Also, you can set the lock for editing the stream

alignment and/or configurations. Available commands are: **Watershed Data, All Impact Areas, Projects, Drawing Properties,** and **Allow Editing**.

WaterShed – From this menu, you will establish the program sequence, create and edit configurations. You can also import and/or export the Stream Alignment. Available commands are: **Program Sequence, Configuration Editor, Update Computation Points, Import**, **Export**, and **Save Configuration**.

Reports – From this menu, you can review reports. These reports contain information about the streams, watershed elements, and configurations for the watershed. The available reports are: **List of Streams, List of Impact Areas, List of All Configurations, List of Computation Points**, and **Projects**.

The **Configuration List** (in Figure 2.7) shows the current configuration. Configurations are created, edited, and deleted in the **Watershed Setup** module. See Chapter 7 for discussion on Watershed Configurations.

The **Setup Lock** (in Figure 2.7) allows you to edit the stream alignment and the current configuration. This lock prevents others from editing the stream alignment and configuration elements while you are editing.

The **Display Area** (in Figure 2.7) is where you create and view the stream alignment, projects, impact areas, and computation points through the use of the available tools in the **Watershed Setup** module. The following are descriptions of the available tools:

Pointer/Selector Tool –this tool can be used to edit, rename, and delete elements. To access, select the **Pointer/Selector Tool**, click the right mouse button (right-click) on an element, and the commands are available from a shortcut menu.

Zoom Tool - this tool allows zooming in and out of the display area. To zoom in, hold the left mouse button down and outline the area you want to zoom in on. To zoom out, right-click in the display area.

Pan Tool – this tool can be used to move the display area while you are zoomed in. To do this, hold down the left mouse button and drag the mouse in the direction you would like to pull the display area.

Time-Series Icon Tool - this tool is used to create, delete, and rename time-series icons used for plotting and tabulating time-series data. To create, select the **Time-Series Icon Tool**, hold down the **CTRL** key and click. To access the available commands, select the **Time-Series Icon Tool**, right-click on a time-series icon, and the commands are available from the shortcut menu.

Stream Alignment Tool - this tool is used to create, delete, and edit stream elements that make up the stream alignment.

Stream Node Tool - this tool is used to create, delete, and edit stream nodes on the stream alignment.

Impact Area Tool - this tool is used to create, delete, rename, and edit impact areas. To create, select the **Impact Area Tool**; hold down the **CTRL** key while clicking the mouse button. Each click creates a vertex point, which is the boundary of the polygon. When reaching the end point, release the **CTRL** key and double-click. An impact area element is now visible. To access the available commands, select the **Impact Area Tool**, right-click on the impact area, and the commands are available from the shortcut menu.

Computation Point Tool - this tool is used to create, edit, rename, and delete computation points. Computation points are locations where time-series information is to be exchanged between models. For ResSim, this might be a control location for reservoir operations, a location where flows will be input, a location where a hydrograph is needed for FIA, etc. To create a computation point, select the **Computation Point Tool**, hold down the **CTRL** key and click on the stream alignment at the appropriate location. To access the available commands, select the **Computation Point Tool**, right-click on the computation point, and the commands are available from the shortcut menu.

Project Tools:

Reservoir Tool - this tool is used to create, delete, rename, and edit reservoirs. To create a reservoir, select the **Reservoir Tool**. A reservoir has to be created on the stream alignment. Hold down the **CTRL** key and click on the *upstream* end of the reservoir pool, release the **CTRL** key, drag along the stream alignment to the *downstream* end of the reservoir pool and click, and then name the reservoir. To access available commands, select the **Reservoir Tool**, right-click on the reservoir, and the commands are available from the shortcut menu.

Levee Tool - this tool is used to create, delete, rename, and edit levees. To create a levee, select the **Levee Tool**. A levee has to be created on the stream alignment. Hold down the **CTRL** key and click on the *upstream* end of the levee, release the **CTRL** key, drag along the stream alignment to the *downstream* end of the levee and click. To access available commands, select the **Levee Tool**, right-click on the levee, and the commands are available from the shortcut menu.

Diversion Tool - this tool is used to create, delete, rename, and edit diversions. To create a diversion, select the **Diversion Tool**. A diversion has to begin on the stream alignment. Hold down the **CTRL** key and click on the stream alignment. Each click creates a vertex point, along the diversion. When reaching the end point of the diversion release the **CTRL** key, and click. To access available commands, select the **Diversion Tool**, right-click on the diversion, and the commands are available from the shortcut menu.

Channel Modification Tool - this tool is used to create, delete, rename, and edit channel modifications. To create a channel modification, select the **Channel Modification Tool**. A channel modification has to be created on the stream alignment. Hold down the **CTRL** key and click on the *upstream* end of the channel modification, release the **CTRL** key, drag along the stream alignment to the *downstream* end of the channel modification and click. To access available commands, select the **Channel Modification Tool**, right-click on the channel modification, and the commands are available from the shortcut menu.

Off-Channel Storage Area Tool - this tool is used to create, delete, rename, and edit off-channel storage areas. To create an off-channel storage area, select the **Off-Channel Storage Area Tool** and hold down the **CTRL** key while clicking the mouse button. Each click creates a vertex point, which is the boundary of the polygon. When reaching the end point, release the **CTRL** key and double-click. An off-channel storage area element is now visible. To access available commands, select the **Off-Channel Storage Area Tool**, right-click on the off-channel storage area, and the commands are available from the shortcut menu.

Other Project Tool - this tool is used to create, delete, rename, and edit other projects. This tool enables the placement of elements that represent "other" projects, such as pump stations and gages. To create an "other" project, select the **Other Project Tool** and hold down the **CTRL** key and click. To access available commands, select the **Other Project Tool**, right-click on the other project, and the commands are available from the shortcut menu.

2.4 Reservoir Network Module

The **Reservoir Network** module is used for editing element data and placing additional elements onto the stream alignment. From the **Module** list, select **Reservoir Network**. The main window and the different components for the **Reservoir Network** module are illustrated in Figure 2.8.



Figure 2.8 Reservoir Network Module

Your network elements will not be shown in the Display Area until you create or open a network from the Network Menu.

The **Menu Bar** (in Figure 2.8) contains the menus for the **Reservoir Network** module. After a reservoir network has been created or opened and is shown in the Display Area, the menus and their commands will become active. In addition to the four common menus described in Section 2.2.1, the following list is a description of the available menus in the **Reservoir Network** module.

Edit – From this menu, you can edit Reservoirs, Routing Reaches, Junctions, Diversions, and Reservoir Systems. Also, you can set the lock for editing the reservoir network. Available commands are: **Reservoirs, Reaches, Junctions, Diversions, Reservoir Systems,** and **Allow Network Editing**.

Network – From this menu, you will create, open, save, rename and delete reservoir networks. You can also update a network to recognize revisions made to its configuration within the Watershed Setup module. Available commands are: **New, Open, Save, Save As, Rename, Update Network from Configuration,** and **Delete Networks**.

Alternative – From this menu, you will open the Alternative Editor that will enable you to create, edit, save and delete alternatives. The only command available from this menu is **Edit**.

Reports – From this menu, you can review reports that list the elements for the currently opened network. These reports contain information about the reservoirs, routing reaches, junctions and diversions. Also, an advanced network summary listing is available. The available reports are: **Reservoir List, Reach List, Junction List, Diversion List,** and **Advanced**.

The **Network** box (in Figure 2.8) shows the "currently opened" Reservoir Network. *You will not see a watershed schematic in the Display Area until you create or open a network.*

The **Configuration** box (in Figure 2.8) shows the configuration the currently opened Reservoir Network is based upon. *If you make changes to the network's Configuration (within the Watershed Setup module), then you can update the network(s) that use that configuration to recognize those revisions by selecting the **Update Network from Configuration** command from the **Network** menu.*

The **Network Lock** (in Figure 2.8) allows you to edit the elements within the Reservoir Network. This lock prevents others from editing the elements while you are editing.

The **Display Area** (in Figure 2.8) is where you create the routing reaches for your Reservoir Network. Also, you can edit the elements through the use of the available tools in the **Reservoir Network** module. The following are descriptions of the available tools:

Pointer/Selector Tool –this tool can be used to edit, rename, and delete elements. To access, select the **Pointer/Selector Tool**, right-click on an element, and the commands are available from a shortcut menu.

Zoom Tool - this tool allows zooming in and out of the display area. To zoom in, hold the left mouse button down and outline the

area you want to zoom in on. To zoom out, right-click in the display area.

Pan Tool –this tool can be used to move the display area while you are zoomed in. To do this, hold down the left mouse button and drag the mouse in the direction you would like to pull the display area.

Reservoir Tool - this tool is used to create, edit, and delete reservoirs. Typically, you will only be "editing" reservoirs within the Reservoir Network module. The other options would normally be done within the Watershed Setup module. To access available commands, select the **Reservoir Tool**, right-click on the reservoir, and the commands are available from the shortcut menu.

Diverted Outlet Tool - this tool is used to create, edit, rename, and delete diverted outlets from a reservoir. To create a diverted outlet, select the **Diverted Outlet Tool**. A diverted outlet must originate from a reservoir. Hold down the **CTRL** key and click on the appropriate reservoir, release the **CTRL** key, move the mouse pointer to a location in the watershed that will receive the diversion from the outlet and click. It is possible to create a diverted outlet that re-enters the network system. To do this, continue holding down the **CTRL** key and click to create vertex points and release the key when you are ready to place the final point back into the system. To access available commands, select the **Diverted Outlet Tool**, right-click on the diverted outlet, and the commands are available from the shortcut menu.

Routing Reach Tool - this tool is used to create, edit, rename, and delete routing reaches. A routing reach must be created between junctions and will follow the stream alignment. Attempting to create a reach where junctions don't exist will automatically generate junctions at the upstream and downstream ends of the reach. To create a routing reach, select the **Reach Tool**, hold down the **CTRL** key and click on the junction at the *upstream* end of the reach, release the **CTRL** key, drag along the stream alignment to the junction at the *downstream* end of the reach and click. To access available commands, select the **Reach Tool**, right-click on the routing reach, and the commands are available from the shortcut menu.

Junction Tool - this tool is used to create, edit and delete junctions. To add junctions (before creating routing reaches), select the **Junction Tool**, hold down the **CTRL** key and click on the stream alignment where you want to create the junction. To access available commands, select the **Junction Tool**, right-click on the junction, and the commands are available from the shortcut menu.

Diversion Tool - this tool is used to create, edit, rename, and delete diversions. To create a diversion, select the **Diversion Tool**. A diversion must begin from a junction. Hold down the **CTRL** key and click on the junction from which the diversion will occur. If you continue to hold down the **CTRL** key, each click creates a vertex point along the diversion. When reaching the end point of the diversion release the **CTRL** key, and click. Diversions can re-enter the network or leave the network system entirely. To access available commands, select the **Diversion Tool**, right-click on the diversion, and the commands are available from the shortcut menu.

2.5 Simulation Module

The **Simulation** module is used to perform a simulation (compute), edit element data and view results. From the **Module** list, select **Simulation**. The main window and the different components for the **Simulation** module are illustrated in Figure 2.9.



Figure 2.9 Simulation Module

The **Menu Bar** (in Figure 2.9) contains the menus for the **Simulation Module**. After a simulation has been created or opened and is shown in the Display Area, the menus and their commands will become active. In addition to the four common menus described in Section 2.2.1, the following list describes the available menus in the **Simulation Module**.

Edit – From this menu, you can edit the list of scheduled Scripts, make an Alternative Active, and edit Reservoirs, Routing Reaches, Junctions, Diversions, and Reservoir Systems. Available commands are: **Script List, Set Active Alternative, Reservoirs, Reaches, Junctions, Diversions,** and **Reservoir Systems**.

Simulation – From this menu, you can create, open, re-open, close, edit, save, and delete simulations. You can also get information about the currently opened simulation and define release and target elevation overrides. Available commands are: **New, Open, Re-Open, Close, Edit, Save, Delete, Info,** and **Release Overrides**.

Alternative – From this menu, you can edit alternatives. This menu only becomes active when a simulation is open. The only available command is **Edit**.

Reports – The available reports summarize results and provide network input summaries for the currently opened simulation. Available commands are: **Reservoir Summary, Flow Summary, Power Summary, Gates Summary, Stage Summary, Release Decision, Compute,** and **Network.**

The **Display Area** (Figure 2.9) is where your stream alignment and watershed elements are displayed. You can view simulation results and edit projects and computation points through the use of the available tools in the **Simulation Module**. The following are descriptions of the available tools:

Pointer/Selector Tool –this tool can be used to edit projects and computation points, plot hydrographs, and view results. To access this tool, select the **Pointer/Selector Tool**, right-click on a location and select commands from the shortcut menu.

Zoom Tool - this tool allows zooming in and out of the display area. To zoom in, hold the left mouse button down and outline the area to which you want to zoom. To zoom out, right-click in the display area.

Pan Tool – this tool can be used to move the display area while you are zoomed in. To do this, hold down the left mouse button and drag the mouse in the direction you would like to pull the display area.

The **Control Panel** (Figure 2.9) shows the time window for the currently selected simulation in the **Simulation Module**. Also from the **Control Panel** you can manipulate simulations and alternatives.

2.6 Opening an Existing Watershed

With the ResSim main window open, you will need to open a watershed. In ResSim, a **watershed** is a data set associated with a geographic region for which you may configure multiple models and area coverages. A **watershed** may include all of the streams, projects (reservoir, levees), gage locations, impact areas, time-series locations, and hydrologic and hydraulic data for a specific area. All of these details together, once configured, form a watershed data set.

You may open an existing watershed from any of the modules (if you need to create a new watershed, refer to Chapter 3). Three methods of opening an existing watershed are available:

First, you can specify that your previously opened watershed be automatically opened by selecting **Reload last Watershed at Startup** from the **General** tab of the **Options** dialog box (Figure 2.10) from the **Tools** menu.



Figure 2.10 Tools Menu, Options Dialog Box, General Tab: Reload last Watershed at Startup

Second, if you have opened the watershed before, you can select it from the list of most-recently-used watersheds, located at the bottom of the **File** menu.

Third, you may use the **Open Watershed** dialog to open the watershed, as follows:

1. On the **File** menu, click **Open Watershed**. The **Open Watershed** dialog box (Figure 2.11) will open.
2. Select a watershed from **Available Watersheds** (see Chapter 3, Section 3.3.1 for information on defining Watershed Locations). The **Current Watershed** box displays the watershed that is currently open, if any.
3. Click **OK**. The Open Watershed dialog box will close and the watershed you have selected will load and appear in the main window with the watershed name shown in the title bar.



Figure 2.11 Open Watershed Dialog Box

You can have only one watershed open at a time. Therefore, if a watershed is open and you attempt to open another, the program prompts you to save the current watershed. If you do not save, any changes you have made to the current watershed will be lost.

2.7 Understanding Schematic Elements

Schematic elements in ResSim allow you to represent watershed, reservoir network, and simulation data visually in a geo-referenced context that interacts with associated data. You create schematic elements and edit their properties in the Watershed Setup Module (see Chapters 3 through 7) and the Reservoir Network Module (see Chapters 8 through 13). In the Simulation Module (see Chapter 14), you can plot and tabulate data by using the shortcut menus associated with the schematic elements.

2.7.1 Stream Alignment

The **Stream Alignment** (Figure 2.12) is a common component of the watershed. To create it, use the map (mouse) tools in the Watershed Setup Module to draw multi-segmented lines into the map display and to mark nodes and stream junctions.



Figure 2.12 Stream Alignment

Stream elements (segments), stream nodes, and stream junctions are the components of a Stream Alignment. See Chapter 5 for more detailed information on creating and editing a Stream Alignment.

2.7.2 Other Watershed Elements

Other watershed elements include Projects, Computation Points, Impact Areas and Time-Series Icons. Create watershed elements in the Watershed Setup Module (see Chapter 6).

These watershed elements are common components of a watershed that multiple models can reference (e.g., ResSim and FIA). To represent the elements, you use the Watershed Setup Module's map (mouse) tools to insert icons and draw polygons and multi-segmented lines into the map display.

Projects include Reservoirs (Figure 2.13), Levees (Figure 2.14), Diversions (Figure 2.15), Channel Modifications (Figure 2.16), Off-Channel Storage (Figure 2.17), and Other Projects like pump stations and agricultural diversions (Figure 2.18).



Figure 2.13 Reservoir



Figure 2.14 Levee



Figure 2.15 Diversion



Figure 2.16 Channel Modification

Figure 2.17 Off-Channel Storage



Figure 2.18 Other Project

Computation Points (Figure 2.19) are common points where data is exchanged between models. To represent them, you use the map (mouse) tools to insert icons into the map display.



Figure 2.19 Computation Points

Impact Areas (Figure 2.20) are common elements representing distinct portions of a watershed affected by rising stage in a stream, river, lake, or reservoir where flood damages will be evaluated.



Figure 2.20 Impact Areas

For more information about Impact Areas, refer to the *HEC-FIA User's Manual* (HEC, 2003c).

Time-Series Icons (Figure 2.21) indicate sites where time-series data is available. You can use Time-Series Icons to represent the locations of gages or Time-Series locations.

For more information about Time-Series Icons, refer to the *CWMS User's Manual* (HEC, 2003a).

Figure 2.21 Time-Series Icons

2.7.3 Reservoir Network Schematic

The **Reservoir Network Schematic**, which you develop in the Reservoir Network Module (based on a Configuration created in the Watershed Setup module), is a template for simulation computations. The graphical elements allow you to access data editors and specify properties of reservoir network components.

The **Reservoir Network Schematic** (Figure 2.22) displays geo-referenced, graphical representations of Reaches, Diversions, Junctions, and Reservoirs. When you interact with these representations in the Simulation Module, you are able to view results from the ResSim model's observed and computed hydrographs.



Figure 2.22 Reservoir Network Schematic

The Schematic is visible in the **Reservoir Network** module *only when a Network has been opened* and is visible in the **Simulation** module *only when a Simulation Alternative is "set as active"*.

2.7.4 Using Shortcut Menus

Shortcut menus display when you right-click on schematic elements in the map display and other ResSim components such as plots, tables, and "tree structures". In ResSim, shortcut menus offer a variety of commands and options that allow you to access data editors, plot and tabulate data, view reports, compute Simulations, and more. Specific shortcut menu commands and options are described throughout this manual.

2.8 Printing and Exporting Reports

From each individual report there is a shortcut menu that allows you to print the report, preview the report before you print, and export the report to an ASCII delimited file. Right-clicking on the active report accesses the shortcut menu. Another way to print or export the reports is by clicking on **Export** or **Print** from the report's **Report** menu (in the Reservoir Network or Simulation module) or from the report's **File** menu (in the Watershed Setup module). Either method accesses the same dialog boxes.

2.8.1 Printing Reports

The output will be a print of the screen image of the active report. If items in the columns of the report are not printing, you can use the mouse to resize the column widths and the width of the entire report dialog box if you need to see more detail. To do so, roll the mouse

pointer over one of the lines that delimit the columns or over the dialog box border. You can click on that line with the left mouse button and drag the mouse from side to side to indicate how wide you want the columns or dialog box. If you end up highlighting some cells in the table, then you probably moved the mouse slightly just before you pressed the button.

To print a report from the Watershed Setup module:

1. You must have a report selected (opened). For example, from the **Reports** menu in the **Watershed Setup** module, select **List of Computation Points** (Figure 2.23).



Figure 2.23 Selecting a Report

2. From the **File** menu of the opened report, select **Print** (Figure 2.24). Or, you can right-click anywhere within the tabulated data of the report and from the shortcut menu select **Print** (Figure 2.25).



Figure 2.24 Select Print from Report's File Menu



Figure 2.25 Select Print from Report's Shortcut Menu

3. The Print **Properties** dialog box will open (Figure 2.26).



Figure 2.26 Printing Properties, Page Tab

4. From the **Page** tab (Figure 2.26), you can set the orientation (default is Portrait), make the report columns fit on one page, print the entire table (default) or print selected cells, repeat headers on subsequent pages, and display gridlines. By default the report prints in an ASCII format, if you want a screen image of the report, unclick ASCII and the report will print with any shading that you see on the report.
5. The **Header/Footer** tab (Figure 2.27) allows you enter a header and/or footer for the report.
6. The **Table Title** tab (Figure 2.28) allows you to change the default title of the report, and to determine whether you want the report title repeated on subsequent pages.



Figure 2.27 Printing Properties, Header/Footer Tab



Figure 2.28 Printing Properties, Table Title Tab

7. After you have everything set, click **Print** and the default system **Print** dialog box will open (Figure 2.29). Select the printer, and any other options you wish to set, click **OK**. The report will then be printed on the selected printer.



Figure 2.29 System Print Dialog Box

2.8.2 Print Preview

You can also preview the report before printing. To do so, do the following:

1. You must have a report selected (opened).
2. Right-click anywhere within the tabulated data of the report and from the shortcut menu, select **Print Preview** (Figure 2.30).



Figure 2.30 Select Print Preview from Report's Shortcut Menu

3. The **Properties** dialog box (see Figure 2.26) will appear.
4. Make the same adjustments for printing as described in Section 2.8.1. When you are satisfied, select **Print** from the **Properties** dialog box, and the **Print Preview** dialog box (Figure 2.31) will open.



Figure 2.31 Print Preview Dialog Box

5. If you like what you see in the **Print Preview** dialog box, you can print by clicking **Print**, which opens the system **Print** dialog box (see Figure 2.29), or you can close the **Print Preview** dialog box by clicking **Close**.

2.8.3 Exporting Reports to a File

You can also export reports to an ASCII delimited file. To export a report from the Watershed Setup module, do the following:

1. You must have a report selected (opened).
2. From the **File** menu of the opened report, select **Export** (Figure 2.32). Or, you can right-click anywhere within the tabulated data of the report and from the shortcut menu select **Export** (Figure 2.33).



Figure 2.32 Select Export from the Report's File Menu



Figure 2.33 Select Export from Report's Shortcut Menu

3. The **Table Export Options** dialog box (Figure 2.34) will open.
4. You can select the **Field Delimiter** from the list to be **TAB, SPACE, COMMA**, or **COLON**.
5. By default, the export does not use fixed width columns; however, if you want to do this you can click in the **Fixed Width Columns** checkbox.



Figure 2.34 Table Export Options Dialog Box

6. You can also include the **Column Headers** of the report (default), include **Gridlines**, and include the **Title** of the report.
7. Once you have chosen your desired options, click **OK** and the **System Save Browser** (Figure 2.35) will open.



Figure 2.35 System Save Browser (for Saving a File)

8. You will need to select where you want the file to be saved and a filename. If you want the file to have an extension, you must enter your own; *there is no default file extension*.
9. Click **Save** and the **System Save Browser** will close. The filename that you entered will now be saved on your computer.

Chapter 3

Creating and Managing Watersheds

Table of Contents

Section **Page**

3 Creating and Managing Watersheds
3.1 Recognizing Watershed Setup Screen Components 3-1
3.1.1 Menu Bar 3-2
3.1.2 Configuration Selector and Lock/Unlock 3-3
3.1.3 Map (Mouse) Tools 3-4
3.2 Using Shortcut Menus 3-6
3.3 Watershed Creation 3-6
3.3.1 Defining a Watershed Location 3-6
3.3.2 Creating a New Watershed 3-8
3.3.3 Specifying Units of Measure 3-9
3.3.4 Specifying Time Zone 3-9
3.4 Setting Up New Map Layers 3-9
3.4.1 Importing Maps into ResSim 3-9
3.4.2 Adding a New Map Layer 3-12
3.4.3 Specifying the Geographic Referencing and Coordinate System 3-13

List of Tables

Table Number

3.1 Map Layer Formats Supported by ResSim 3-10

List of Figures

Figure Number

3.1 Watershed Setup Module Main Window 3-2
3.2 File Menu 3-2
3.3 Edit Menu 3-3
3.4 Watershed Menu 3-3
3.5 Reports Menu 3-3
3.6 Reservoir Shortcut Menu 3-6
3.7 HEC-ResSim Options Dialog Box 3-7

List of Figures (continued)

Figure Number **Page**

3.8 Add Watershed Location Dialog Box....3-7
3.9 Create New Watershed Dialog Box....3-8
3.10 Layer Selector Dialog Box....3-12
3.11 Open File Dialog Box to Add Map Layer....3-12
3.12 Geographic Region Dialog Box....3-13

Chapter 3

Creating and Managing Watersheds

A watershed is a data set associated with a geographic region for which you may have configured multiple models and area coverages. A watershed may include all of the streams, projects (reservoir, levees, etc.), gage locations, impact areas, time-series locations, and hydrologic and hydraulic data for a specific area. All of these details together, once configured, form a watershed data set.

In the **Watershed Setup Module**, you will set up your watershed's *physical* arrangement including: background maps, the Stream Alignment, geo-extents, projects, and other geo-referenced data.

You define **Configurations** when you initially create a watershed. This should enable modelers to develop data explicitly for a specific configuration and reduce the possibility that incompatible model data sets will be used for multiple program applications (e.g., HEC-ResSim and HEC-FIA).

You can also use the Watershed Setup Module to define Projects and Computation Points associated with specific configurations in your watershed. Projects can include Reservoirs, Levees, Diversions, Channel Modifications, Off-Channel Storage Areas, and "Other" Projects. Computation Points are locations where time-series information is exchanged between models (e.g. ResSim and FIA).

3.1 Recognizing Watershed Setup Screen Components

The Watershed Setup Module provides tools for setting up your watershed's *physical* arrangement, including maps, the Stream Alignment, geo-extents, projects, and other geo-referenced data. Figure 3.1 shows the components of the Watershed Setup Module main window. Tools unique to this module are described in the following sections.



Figure 3.1 Watershed Setup Module Main Window

3.1.1 Menu Bar

The following is an overview of menus unique to the **Watershed Setup** Module. These tools will be described in more detail in the context of specific tasks later in this chapter.

Refer to Chapter 2 for information about the **View**, **Tools,** and **Help** menus, which are common to all three modules.

The **File** menu (Figure 3.2) allows you to create a **New** watershed, **Open** an existing watershed, **Save** a watershed, **Save Map** (saves the display area) and **Exit** ResSim. Your most-recently-used watersheds are located at the bottom of the File menu.



Figure 3.2 File Menu

Use the **Edit** menu (Figure 3.3) to access the following editors in the Watershed Setup Module: the **Watershed Data Editor**, **All Impact Areas Editor**, **Projects Editor**, and **Drawing Properties Editor**. You must select **Allow Editing** if you wish to make changes to your watershed (or toggle the Lock above the display area).



Figure 3.3 Edit Menu

Using the **Watershed** menu (Figure 3.4), you can create and edit **Configurations**, **Update Computation Points**, **Import** and **Export** Stream Alignments, and Impact Areas, and **Save Configurations**.



Figure 3.4 Watershed Menu

The **Reports** menu (Figure 3.5) gives you access to reports for your watershed. Reports include the **List of Streams**, **List of Impact Areas**, **List of All Configurations**, **List of Computation Points**, and **Projects** listings by project type.



Figure 3.5 Reports Menu

3.1.2 Configuration Selector and Lock/Unlock

When you add a schematic element to the map display, you must choose its Configuration using the Configuration Selector. The default Configuration, Study, contains the entire set of all projects and Computation Points defined in the watershed. You can also associate projects with custom configurations.

Before you can add, remove, or edit schematic elements in your watershed, you must lock the Configuration by clicking on the symbol to the right of the Configuration Selector. When the

Configuration is locked, the symbol appears. If the Configuration is unlocked, the symbol appears.

3.1.3 Map (Mouse) Tools

In the Watershed Setup Module, Map (Mouse) Tools allow you to access and configure objects within your watershed. Project Tools help you to create and edit the various project types. After you have created a project, ResSim adds it to the active Configuration. The following are descriptions of the available tools:

Pointer Tool
Right-click with the Pointer Tool to select and access a shortcut menu for any schematic element in the watershed map display.

Zoom Tool
Use the Zoom Tool to zoom in and out of the display area. To zoom in, hold the left mouse button down and outline the area you want to zoom in on. To zoom out, right-click in the display area.

Pan Tool
Use the Pan Tool to move the display area while you are zoomed in.

Time-Series Icon Tool
Use the Time-Series Icon tools to create, delete, and rename time-series icons that are used for plotting and tabulating time-series data. To create, select the **Time-Series Icon Tool**, hold down the **CTRL** key and click. To access the available commands, select the **Time-Series Icon Tool**, right-click on a time-series icon, and the commands are available from the shortcut menu.

Stream Alignment Tool
Use the Stream Alignment Tool to draw the multi-segmented lines that comprise a Stream Alignment representing river systems in the map display.

Stream Node Tool
The Stream Node Tool allows you to create and edit stream nodes and junctions, two of the primary components of a Stream Alignment.

Reservoir Tool
Use the Reservoir Tool to select and add reservoir projects to the map display and access editors for reservoirs.

Levee Tool
Use the Levee Tool to select and add levee projects to the map display panel and access editors for levees. In the Watershed Setup Module, only the name and description can be edited.

Diversion Tool
Use the Diversion Tool to select and add diversions to the map display and access editors for Diversions.

Channel Modification Tool
Use the Channel Modification Tool to select and add channel modifications (such as channel straightening, concrete walls, dredging, and widening) to the map display and access editors for Diversions.

Off Channel Storage Tool
Use the Off-Channel Storage Areas Tool to select and create Off-Channel Storage Area polygons in the map display and edit their properties.

"Other" Project Tool
Use the "Other" Projects Tool to place icons representing "other" projects, such as pump stations and gages, etc., and edit their properties.

Impact Area Tool
Use the Impact Area Tool to create and edit impact areas representing regions in the watershed where flood damages will be evaluated.

Computation Point Tool
Use the Computation Point Tool to create and edit Computation Points. Computation Points are locations in the watershed where individual models will share information. Typically one model will produce results at a Computation Point that another model will use as input.

3.2 Using Shortcut Menus

Shortcut menu commands vary according to the schematic elements with which they are associated. Figure 3.6 shows the shortcut menu for a reservoir named "Sayers".

If your watershed is locked, the shortcut menu will allow you to edit, rename, and delete the object (depending on the object type), as well as view its properties. If your watershed is unlocked, some of the options will be unavailable.



Figure 3.6 Reservoir Shortcut Menu

3.3 Watershed Creation

The first thing you must do to create a new watershed is to specify its directory location, give it a name and description, and establish the Units of Measure and Time Zone. Once you have created your new watershed, ResSim generates a new directory hierarchy in the "base" working directory. Your new watershed becomes active in the main window and the tools needed to create the watershed data become available. At this point you may continue to configure the new watershed by adding layers and schematic elements, setting preferences for the map display, etc., as described later in this chapter.

3.3.1 Defining a Watershed Location

A **Watershed Location** is your working directory--the place on disk where you create and edit your watershed data. You can have multiple watershed locations, although an individual watershed cannot span multiple locations. Each watershed location should have a logical name, such as *CWMS* or *General Projects*.

Before you can create or open a watershed, you must define at least one watershed location. To define a Watershed Location:

1. From the **Tools** menu, select **Options**. The **HEC-ResSim Options** dialog box (Figure 3.7) will open.



Figure 3.7 HEC-ResSim Options Dialog Box

2. Select the **Model Directories** tab. The **Name** and **Location** of any watershed locations you have previously defined will display in the list.
3. To add a new location to the list, click the **Add Location**…button. The **Add Watershed Location** dialog box will open (Figure 3.8).



Figure 3.8 Add Watershed Location Dialog Box

4. Enter a logical **Name** for the new location, then click the **Browse…** button to select the area on disk where you want to build your watershed. This directory is the "holder" of the "base" directory and the "base" directory is the "holder" of your watershed. In other words, the Watershed Location contains a directory named **base**, which contains the directory(s) for your watershed(s).
5. Click **OK** to close the Add Watershed Location dialog box.

The new location will now appear in the list of watershed locations on the **Model Directories** tab.

Refer to Appendix A for information about other options available in the **Options** dialog box.

3.3.2 Creating a New Watershed

Once you have established the working directory, you can create a new watershed.

To create a new watershed:

1. Select **New Watershed** from the **File** menu. The **Create New Watershed** dialog box (Figure 3.9) opens.



Figure 3.9 Create New Watershed Dialog Box

2. Type a **Name** for the new watershed. The watershed name must be less than 32 characters and cannot contain any of the following characters: | / : * ? " < > - \ .
3. Type a **Description** for the new watershed that clearly explains what it is.
4. Select a **Location** (working directory) for the new watershed's directory from your list of available locations.
5. Specify either **English** (U.S. customary units) or **SI** (System International) as the **Units of Measure**. You will not be able to change this after you click **OK** (see Specifying Units of Measure, below, for more information).
6. Specify the **Time Zone** of the new watershed by selecting from the list of standard time zones. Note that the *watershed* Time Zone does not recognize Daylight Savings Time (see Section 3.3.4, Specifying Time Zone, for more information).
7. Click **OK** to close the Create New Watershed dialog box.

3.3.3 Specifying Units of Measure

All modeling data, time-series data, geometric and reservoir information, model parameters, and flow-, elevation- and stage-time-series data must use the same unit system when saved. Therefore, it is crucial that you specify either **English** or **SI** as the Units of Measure for your watershed when you set it up. NOTE: You *cannot change the watershed units of measure* once the watershed setup is complete, but you can at any time customize the *display of data* using the **View** menu.

3.3.4 Specifying Time Zone

When a new watershed is created, the user must select the appropriate time zone for the watershed. This typically would be the time zone for the outlet or major portion of the watershed. Internally, ResSim will store all time-series data using the fixed "standard time offset from GMT" for the selected watershed time zone. Thus, internally, the data will be held in standard time only.

*You **cannot change the Watershed Units of Measure or the Time Zone** once the watershed setup is complete.*

3.4 Setting Up New Map Layers

Layers in ResSim are like transparencies laid one on top of the other, with static physical images such as roads, county and state boundaries, rivers, subbasins, etc., layered in the display as color pictures. Each of these images, along with its associated data, is a map layer. Access to the Layers Selector is available from the **View** menu. Refer to Chapter 4 for a more detailed description of Map Layers.

3.4.1 Importing Maps into ResSim

The background maps you will use in your watershed will come from sources outside of ResSim. To import a map file for use in your watershed, copy the appropriate map files to the "maps" directory of your watershed (see Appendix A for information about the ResSim directory structure). ResSim does not perform coordinate transformation for background maps. Therefore, all of the map layers you use in a watershed should be referenced to the same coordinate system (see Appendix B for more information on coordinate systems). Table 3.1 shows the file formats ResSim supports and each format is described in the paragraphs that follow. Appendix C describes how to access the map editors for configuring each type of map format.

Table 3.1 Map Layer Formats Supported by ResSim

Description	Common **File** Name **Extension**
ArcView® Shapefile	.shp
AutoCAD® DXF	.dxf
Raster image	.img, .gif, .jpg
USGS* Digital Line Graph	.dlg
USGS* Digital Elevation Model	.dem
ASCII NET TIN	.net
ArcInfo® DEM	.asc
*US Geological Survey	

Arc Shapefiles (.shp)
This layer type is the native data structure for the ArcView® GIS program. Shapefiles store non-topological geometry and attribute information for the spatial features of a data set. Usually there are three files: *.dbf, *.shp, and *.shx. The .shp file contains the shapes (point, polylines, or polygons) that display in the layer. Each shape has a record in the .dbf file containing descriptive data called "attributes." The .shx file contains an index that links each shape to its record in the .dbf file.

AutoCAD® DXF (.dxf)
A Drawing Interchange file (.dxf) is created by a Computer-Aided Design (CAD) package, AutoCAD®. This format is a tagged data representation of an AutoCad® drawing file. In tagged data, a group code precedes each data element. A group code is an integer number indicating the type of data element. The file created is a vector-based graphic. The DXF format is commonly used for data exported from other CAD and GIS programs.

Raster Image
ResSim supports JPEG (.jpg) and Graphics Interchange (.gif) raster image formats. Before ResSim can access these file types, you must first create an .img (ASCII text) file containing the following lines:

```
Image West=2051443.
Image North=355443.
Image East=2054925.6
Image South=351947.4
```

These are image boundaries that are determined by the user and usually calculated using a program such as ArcInfo®.

```
Image URL  = path and filename of raster image
             (i.e., maps/lh_2m.gif)
```

The raster image boundaries must match the easting and northing parameters stated in the Geographic Region Dialog (see Section 3.4.3, "Specifying the Geographic Referencing and Coordinate System").

USGS Digital Line Graph (.dlg)
USGS Digital Line Graph (DLG) files are created from two sources using manual and automated digitizing methods. The two sources are aerial photographs and cartographic sources. DLG files are vector representations of the data. When ResSim interacts with a .dlg file, it automatically creates a .dlgbin file, which is a binary representation of the ASCII .dlg file.

USGS Digital Elevation Model (.dem)
The USGS Geological Survey publishes the raster file format USGS Digital Elevation Model (DEM). DEM files usually contain terrain elevations, but the file format can be used for representing any surface. The format, published by the USGS, allows internal documentation of coordinate system, date of publication, etc.

ASCII NetTin (.net)
This is an ASCII file format used to represent a Triangulated Irregular Network (TIN). The TIN data is stored in a simple format that defines the nodes, edges, and triangles contained in the TIN. This format is common for transferring TIN data between software packages.

ArcInfo® DEM (.asc)
This is an ASCII file format representation of a grid generated by ArcInfo®. The file consists of keywords followed by values defining the number of columns, number of rows, lower left corner, cell size, no data value, and each cell value.

3.4.2 Adding a New Map Layer

To make map files accessible in the watershed, first make sure that the map files are in the "maps" directory of the watershed, as previously described in Section 3.4.1. Also, ensure all maps you add to a watershed share the same coordinate system before you add them to the watershed.

To add a map layer to your watershed:

1. Select **Layers** from the View menu. The **Layer Selector** dialog box will appear (Figure 3.10).
2. From the **Edit** menu, select **Allow Layer Editing**.
3. Next, from the **Maps** menu, select **Add Map Layer**. The **Open File** dialog box (Figure 3.11) will open.



Figure 3.10 Layer Selector Dialog Box



Figure 3.11 Open File Dialog Box to Add Map Layer

4. Locate the map file you wish to use on your local computer (for example, "raingage.shp").
5. After you have selected the map you wish to use, click **OK**. The new map will now appear in the Layer Selector dialog box.

3.4.3 Specifying the Geographic Referencing and Coordinate System

To maintain a geographic reference, you must specify a coordinate system for each watershed. To establish the grid size and coordinate system:

1. Select **Layers** from the **View** menu to open the **Layer Selector** dialog box.
2. From the **Maps** menu, select **Map Display Coordinates** to open the **Geographic Region** dialog box (Figure 3.12).



Figure 3.12 Geographic Region Dialog Box

The **Geographic Region** dialog box includes the following information:

Coordinate System
This box identifies the coordinate system established for the watershed. The coordinate system can be edited, but remember that all maps and data must exist in one unified coordinate system. Therefore, some layers or data might require the use of a GIS program to transform coordinate system information. For additional information about editing the Coordinate System, see "Editing the Coordinate System" below.

Extents
The values of **Easting Min**, **Easting Max**, **Northing Min**, and **Northing Max** indicate the location of the left, right, bottom and top borders (respectively) of the grid in the display area. ResSim displays coordinates in the Status Bar as you move the cursor within the map display panel.

Grow to Map Extents
When you check this box, ResSim automatically sets the geographic region to define the smallest rectangle that encompasses all of the

objects (maps, icons, alignments, etc.) in the display area. If you add any objects to the watershed that lie outside the geographic region, ResSim automatically updates the extents to include the new objects.

You must select the geographic extents of your watershed carefully to ensure that all layers in your watershed setup are included. The extents you specify and the coordinate system you use must be consistent for all layers in the watershed. You should use GIS tools to transform layers from one coordinate system to another before you use them in ResSim.

Setting Map Coordinates to Display

You can automatically set the geographic extents to the coordinates in your current view. First, zoom in or out in the display area to determine a preferred geographic region, then open the **Geographic Region** dialog box and click **Set Map Coordinates to Display**. ResSim will set the extents to the current view in your map display. Objects beyond the geographic extents remain in the watershed, but they are not included in the grid of the display area.

Editing the Coordinate System

You can edit the Coordinate System of the Watershed by selecting **Edit** in the **Geographic Region** dialog box. This opens the **Map Coordinate Information** dialog box, where you can configure the System, Units, Spheroid, and other system-specific data. See Appendix B for more information on configuring map coordinate information.

Chapter 4

Working with Layers

Table of Contents

Section **Page**

4 Working with Layers
4.1 Understanding Layers 4-1
4.1.1 Time-Series Icon Layer 4-1
4.1.2 Study Layer 4-1
4.1.3 Stream Alignment Layer 4-2
4.1.4 Map Layers 4-2
4.2 Exploring the Layer Selector 4-2
4.2.1 The Layer Selector Menus 4-3
4.2.2 The Layer Selector "Tree" 4-4
4.2.3 Controlling Layer Display 4-5
4.2.4 Viewing Layer Legend 4-6
4.3 Controlling Layer Organization 4-6
4.3.1 Configuring Toolbar Icons to Control Layers 4-7
4.3.2 Adding Map Layers 4-8
4.3.3 Removing Map Layers 4-8
4.3.4 Using Layer Selector Shortcut Menus 4-9
4.4 Viewing and Configuring Layer Properties 4-10
4.4.1 Study Layer Properties 4-11
4.4.2 Stream Alignment Layer Properties 4-14
4.4.3 Map Layers Properties 4-15

List of Figures

Figure Number

4.1 Layer Selector 4-2
4.2 Layers Menu - Layer Selector 4-3
4.3 Edit Menu - Layer Selector 4-3
4.4 Edit Menu - Allow Layer Editing Turned Off and No Layer Selected 4-3
4.5 Maps Menu - Layer Selector 4-4
4.6 View Menu - Layer Selector 4-4
4.7 Layer Selector - Layers Expanded 4-5
4.8 Layer Selector - Map Legend for Reservoirs 4-6
4.9 Toolbar Button Editor 4-7
4.10 Layer Selector Shortcut Menu for the Stream Alignment Layer 4-9
4.11 Layer Selector Shortcut Menu for a Map Layer 4-10

List of Figures (continued)

Figure Number **Page**

4.12 Drawing Properties Editor - Reservoir Tab....4-11
4.13 Drawing Properties Editor - Levees Tab 4-12
4.14 Drawing Properties Editor - Diversions Tab 4-12
4.15 Drawing Properties Editor - Channel Modification Tab 4-13
4.16 Drawing Properties Editor - Computation Point Tab 4-13
4.17 Drawing Properties Editor - Impact Area Tab....4-14
4.18 Stream Alignment Properties Editor....4-14
4.19 USGS Digital Line Graph Editor for Digital Line Graph (DLG) Map Layer 4-15

Chapter 4

Working with Layers

Layers in ResSim are like transparencies laid one on top of the other, with static physical images such as roads, county and state boundaries, rivers, subbasins, etc., layered in the display as color pictures. Each of these images, along with its associated data, is a layer.

4.1 Understanding Layers

Layers are hierarchical. Primary (top level) layers include the **Time-Series Icon Layer** and the **Study Layer** (available only in the Watershed Setup Module), the **Stream Alignment Layer**, and **Map Layers**. These primary layers can contain component layers. For example, the Stream Alignment Layer contains the Stream Nodes, Stream Segments, and Stream Junctions. The Study Layer contains layers for all Reservoirs and other Projects, Computation Points, and Impact Areas contained within the Study.

4.1.1 Time-Series Icon Layer

The Time-Series Icon Layer includes all of the time-series icons for your watershed, and it allows you to separate different types of data in your map display. For example, a gage may report stage and precipitation (and compute flow from stage). If you create time-series layers named "Stage," "Flow," and "Precipitation," you can then place each data set in the appropriate layer.

ResSim does not use Time-Series Icons for any program needs. Refer to the *CWMS User's Manual* (HEC, 2003a) for additional details about Time-Series Icons.

4.1.2 Study Layer

The Study Layer appears in the Watershed Setup Module only. The Study layer is comprised of all of the projects, impact areas, and computation points contained in the watershed.

The Layer Selector displays Study as a primary layer in the Layer tree. When you click on the root handle for the Study branch, there is a layer for Computation Points, Diversions, Names (labels for the projects, computation points, and impact areas), Reservoirs, Channel Modifications, Levees, Off Channel Storage, Other Projects, and Impact Areas. ResSim creates a layer for each of these items even before you have defined any projects, computation points, or impact areas.

4.1.3 Stream Alignment Layer

The Stream Alignment Layer contains the Stream Alignment representing the river system in the watershed. The Stream Alignment layer includes three component layers: Stream Nodes, Streams Segments (also referred to as stream elements), and Stream Junctions. This layer is available in all ResSim Modules but is only available for editing within the Watershed Setup Module.

4.1.4 Map Layers

ResSim can display various types of maps and elements in the geo-referenced map display area. These maps, displayed as map layers, are static physical images. Examples of map layers include roads, county and state boundaries, rivers, subbasins, etc. Some maps are static images, which display as color pictures in the display area. Map Layers are not interactive. Instead, you interact with data associated with schematic elements you place in your map display.

For a description of the map layer formats supported by ResSim, see "Importing Maps into ResSim" in Chapter 3, Section 3.4.1.

4.2 Exploring the Layer Selector

The **Layer Selector** is the main controller for the organization of the various layer types described above, including the Study Layer, Stream Alignment Layer, and Map Layers.

To access the Layer Selector from any module, from the **View** menu, select **Layers….**

The **Layer Selector** window, shown in Figure 4.1, opens as a separate frame that you can minimize to the Windows taskbar.



Figure 4.1 Layer Selector

4.2.1 The Layer Selector Menus

Menus in the Layer Selector offer a variety of tools to assist you in managing layers.

The **Layers** menu (Figure 4.2) offers a **Close** command to close the Layer Selector.

Figure 4.2 Layers Menu - Layer Selector

The **Edit** menu (Figure 4.3) provides tools for rearranging layers, viewing and editing layer properties, and adding and reloading default toolbar buttons for access to individual layers.

To see all of the available commands in the Edit menu, you must first select a layer and activate **Allow Layer Editing**. When editing is enabled, a checkbox appears next to the menu item as shown in Figure 4.3.



Figure 4.3 Edit Menu - Layer Selector

Figure 4.4 shows the **Edit** menu as it appears with **Allow Layer Editing** turned off and with no layer selected.

Also note that the current position of an individual layer will determine which commands are available in the **Edit** menu. When a layer is already at the top, the **Move to Top** and **Move Up** options will be unavailable. Likewise, if a layer is at the bottom, the **Move Down** and **Move to Bottom** options will not be available.



Figure 4.4 Edit Menu - Allow Layer Editing Turned Off and No Layer Selected

The **Maps** menu (Figure 4.5) allows you to add and remove map layers. The **Map Display Coordinates** option opens the Geographic Region dialog box. These processes are described in "Adding a New Map Layer" in Chapter 3, Section 3.4.2. You must select a map layer to access the **Remove Map Layer** command.



Figure 4.5 Maps Menu - Layer Selector

The **View** menu (Figure 4.6) gives you control over display of the Layer Selector. The **Expand** option expands the "tree" of a layer to display its sub-layers (same functionality as clicking on the layer's plus- sign box in the tree). Once you have expanded a layer, Expand changes to **Collapse** to close the layer to show only the primary layer (same functionality as clicking on the minus-sign box in the tree). **Always on Top** keeps the Layer Selector on top of your desktop so you can leave it open while you work, if desired.



Figure 4.6 View Menu - Layer Selector

4.2.2 The Layer Selector "Tree"

The Layer Selector uses a tree metaphor for controlling the display and organization of layers in the watershed. The tree metaphor represents the hierarchical arrangement of layers in ResSim.

The top level of the tree is the Layers folder, which contains all of the layers in the watershed. Beneath the Layers folder is a tree branch for each primary layer, beginning with a plus/minus box, followed by a checkbox, then the layer name.

When you expand a layer (see "Controlling Layer Display" , Section 4.2.3), its sub-layers display. If no sub-layers exist, you will see a legend for the layer.

In following sections you will learn how to interact with layers in the Layer Selector by using the Menu items, shortcut menus, plus/minus boxes, checkboxes, and properties editors.

4.2.3 Controlling Layer Display

Beside each Layer branch is a plus/minus box, or root handle, that serves the same function as the **Expand/Collapse** options in the **View** menu. A plus means the layer can be expanded. You can click on a plus to expand a tree branch to display component layers; if no component layers exist, you will see a legend for the layer. When the root handle is a minus, you can click on it to collapse the tree branch. You can also expand and collapse layers by double-clicking them with your mouse. Figure 4.7 shows the Layer Selector with some of the layers expanded.



Figure 4.7 Layer Selector - Layers Expanded

The checkbox turns the display of the layer on or off (checked indicates the layer is active in the display area). When not checked, neither the primary layer nor the components beneath it will display. When checked, the primary layer and all checked component layers will display; however, any unchecked component layers beneath it will not display.

4.2.4 Viewing Layer Legend

When you click on the root handle of a layer with no components, the legend for the map displays.

The type of legend displayed is determined by the various file formats. Figure 4.8 shows the legend for Reservoirs.



Figure 4.8 Layer Selector - Map Legend for Reservoirs

4.3 Controlling Layer Organization

The Layer Selector also controls how layers are arranged in the display area. When you add map layers to the watershed (see "Adding a New Map Layer" in Chapter 3, Section 3.4.2), the map layer is added to the bottom of the list of maps in the Layer Selector. You can use the Layer Selector to rearrange the order of the primary layers:

1. Select the layer you would like to move.
2. From the **Edit** menu, select **Allow Layer Editing**.
3. From the **Edit** menu, select **Move Up** to move the layer towards the front of the map display, or click **Move Down** to move the layer to the back.
4. To see your changes, click **Apply** (to keep the Layer Selector open) or click **OK** to close the Layer Selector.

Continue to change the position of each layer until the necessary map features are visible in the display area.

4.3.1 Configuring Toolbar Icons to Control Layers

In the Layer Selector you can also add controls to the Toolbar of the main window. Toolbar buttons provide a shortcut for turning layers on and off without having to open the Layer Selector. Toggling on and off the toolbar button functions the same as the checkbox in the Layer Selector. When the button is depressed, the layer is selected for display in the map panel. When the button is up, the layer is turned off in the display. This shortcut is useful when you might want to have frequent control over layers that are being displayed.

Additionally, right-clicking on the toolbar button gives you access to various properties editors and allows you to select and deselect layers being displayed. The options available from the shortcut menu depend upon the layer type.

If you hover your mouse over a Toolbar Button, a Tool Tip appears with a description of the button.

Adding toolbar buttons is an optional configuration step, and if you want to use toolbar buttons, you must configure them separately in each module. Toolbar buttons are saved when you exit the watershed, so you will only have to set them up once.

To add a toolbar button,

1. In the **Layer Selector**, select a layer in the tree.
2. From the **Edit** menu, select **Add Toolbar Button**. The **Toolbar Button Editor** opens, as shown in Figure 4.9.
3. The name of the layer appears by default in the **Tool Tip** field, but you can specify a more descriptive **Tool Tip** if desired.

Figure 4.9 Toolbar Button Editor

4. From the **Icon** list, select an icon to represent the selected layer.
5. Select **OK** when you are done.

The toolbar button then appears in the toolbar above the Display Area.

To remove a toolbar icon, select the layer in the Layer Selector, and then from the **Edit** menu, select **Remove Toolbar Button**. To quickly remove all toolbar buttons that you have defined, select **Reload Default Button** from the **Edit** menu in the Layer Selector.

4.3.2 Adding Map Layers

You will find it helpful to add maps to the watershed and the display area to provide a geographical reference for time-series icons, the stream alignment, and projects in your watershed.

To add map layers:

1. From the **Edit** menu of the **Layer Selector**, select **Allow Layer Editing**.
2. From the **Maps** menu, select **Add Map Layer…** This command opens a file browser to the default "maps" directory in the watershed directory hierarchy. You must first copy any maps you wish to use in the watershed to the "maps" directory for your watershed.
3. From the file browser, choose the map you wish to add.
4. Click **OK**.

The map name now appears in the Layer Selector as a new tree branch. See "Adding a New Map Layer" in Chapter 3, Section 3.4.2 for more information.

4.3.3 Removing Map Layers

To remove a layer from the map display, select the layer in the layer selector, and then select **Remove Map Layer** from the **Maps** menu.

4.3.4 Using Layer Selector Shortcut Menus

Shortcut menus in the Layer Selector offer commonly used commands that are also available in the Layer Selector's **Edit** and **View** menus. Figure 4.10 shows the shortcut menu for the Stream Alignment layer in the Layer Selector.

The **Expand** option expands the tree of a layer to display its component layers. **Collapse** closes the layer to show only the primary layer.

Move to Top, **Move Up**, **Move Down**, and **Move to Bottom** allow you to rearrange layers. The current position of an individual layer will determine which **Move** buttons are available.



Figure 4.10 Layer Selector Shortcut Menu for the Stream Alignment Layer

Properties opens a **Properties** dialog box for the layer.

For map layers that you add (Figure 4.11), the **Change Label** command is also available. The command allows you to change the name of the layer in the tree. Also, the **Show Legend** command expands the map layer tree to display the map legend. The option changes to **Hide Legend** when the layer is expanded, allowing you to close the branch view of legends.

Reminder: you must first activate **Allow Layer Editing** (in the **Edit** menu) before you can access many of the shortcut menu commands.



Figure 4.11 Layer Selector Shortcut Menu for a Map Layer

4.4 Viewing and Configuring Layer Properties

The **Layer Selector** provides three ways to view and configure layer properties. You can:

- Select a layer in the Layer Selector and then choose **Properties** from the **Edit** menu.
- Right-click on a layer in the Layer Selector and then select **Properties** from the shortcut menu.
- Double click on a layer in the Layer Selector.

Each of these techniques opens a **Properties** dialog box specific to the layer type; map layers also have additional dialog boxes for configuring properties. For information about configuring the Time-Series Icon Layer, refer to the *CWMS User's Manual* (HEC, 2003a).

4.4.1 Study Layer Properties

The Study Layer is available only in the Watershed Setup module. When you select **Properties** for the **Study** layer, the **Drawing Properties Editor** appears (Figure 4.12).

The Drawing Properties Editor has six tabs that allow you to view and edit properties of Reservoirs, Levees, Diversions, Channel Modifications, Computation Points, and Impact Areas in your watershed.



Figure 4.12 Drawing Properties Editor - Reservoir Tab

With the **Reservoir** tab selected (Figure 4.12), you can choose the **Fill** and **Outline Color** for the **Triangle** (which is the "visual" representation of the Reservoir) and the **Fill** and **Outline Color** and the **Width** of the **Storage Reach** (which represents the Reservoir reach along the stream alignment) of reservoirs in your watershed display. Also, you can choose the **Fill Color** and **Width** of the **Dam** element. When you select **Draw Reservoir Triangle** with a checkmark, the reservoir shape drawn in the Watershed Setup Module displays on the map; when it is not checked, the reservoir shape does not display. Likewise, **Draw Reservoir Name**, when checked, displays the reservoir name on the map and hides the name when unchecked. The **Font…** button for the **Reservoir Name** allows you to choose the text font for the name of the reservoir in the map display.

The **Levees** tab (Figure 4.13) allows you to edit the properties of levees in your watershed. You can specify the **Line Color** and **Levee Width**. **Draw Levee Name**, when checked, displays Levee names on the map and hides the names when unchecked. The **Font…** button for the **Levee Name** allows you to choose the text font for the name of the levee in the map display.



Figure 4.13 Drawing Properties Editor - Levees Tab

With the **Diversions** tab (Figure 4.14), you can select the **Line Color** and **Width** for the diversion. You can also select the **Fill Color** for the Diversion Arrowhead. The arrowhead colors can be different to indicate whether or not the diversion is **Connected** or **Disconnected** (e.g., Connected indicates that the diverted water remains in the system and Disconnected indicates that the diverted water is lost to the system). **Draw Diversion Name**, when checked, displays the Diversion names in the display area and does not display when the name is unchecked. The **Name Font…** button allows you to choose the text font for the name of the diversion in the watershed display area.



Figure 4.14 Drawing Properties Editor - Diversions Tab

The **Channel Modification** tab (Figure 4.15) allows you to select the **Line Color** and **Width** of the Channel Modifications. **Draw Channel Modification Name**, when checked, displays the Channel Modification names in the display area and does not display when the name is unchecked. The **Name Font…** button allows you to choose the text font for the names of Channel Modification points in the watershed display area.



Figure 4.15 Drawing Properties Editor - Channel Modification Tab

The **Computation Point** tab (Figure 4.16) allows you to select the **Fill Color** and **Width** of the Computation Points. **Draw Computation Point Name**, when checked, displays the Computation Point names in the display area and does not display when the name is unchecked. The **Name Font…** button allows you to choose the text font for the names of Computation Points in the watershed display area.



Figure 4.16 Drawing Properties Editor - Computation Point Tab

The **Impact Area** tab (Figure 4.17) allows you to display or hide the Impact Area name for your watershed. **Draw Impact Area Name**, when checked, displays Impact Area names on the map and hides the names when unchecked. The **Name Font…** button allows you to choose the text font for the names of Impact Areas in the watershed display.



Figure 4.17 Drawing Properties Editor - Impact Area Tab

4.4.2 Stream Alignment Layer Properties

When you select **Properties** for the Stream Alignment layer, the **Stream Alignment Properties Editor** (Figure 4.18) appears.



Figure 4.18 Stream Alignment Properties Editor

The **Stream Alignment Properties Editor** allows you to specify **Stream Width** and **Stream Color** in your watershed display. **Show Stream Name**, when checked, displays stream names on the map and hides the names when unchecked. The first **Choose Font** button allows you to choose the text font for the names of streams in the map display. When **Draw Station Tics** is checked, station tics display on the map, and you are able to specify the **Tic Length** and **Major Tic Length**. **Draw Tic Labels**, when checked, displays Tic labels on the map and hides the labels when unchecked. The second **Choose Font** button allows you to specify the text font for the Tic Labels. When **Draw Station Tics** is unchecked, Station Tics do not display on the map and the Tic Length, Major Tic Length, Draw Tic Labels, and Choose Font options are not available.

The Stream Alignment Properties Editor's preview pane allows you to view your changes before applying them.

4.4.3 Map Layers Properties

Map layers can be any of a number of formats supported by ResSim, including ArcView® Shapefiles, AutoCAD® DXF files, raster images, U.S Geological Survey (USGS) Digital Line Graphs (DLG) files, USGS Digital Elevation Model (DEM) files, ASCII NET TIN files, and ArcInfo® DEM files. Hence, when you select Properties for a map layer, the editor that opens is specific to the type of map.

For example, if the map layer you wish to configure is a USGS Digital Line Graph map layer, the **Properties** command opens the **USGS Digital Line Graph Editor** (Figure 4.19).



Figure 4.19 USGS Digital Line Graph Editor for Digital Line Graph (DLG) Map Layer

With this Map Layers Properties Editor, you can specify the default **Color** of the map and choose whether or not **Nodes**, **Lines**, and **Areas** display in the watershed. You can also set the **Saturation** and **Brightness** of the display. The directory location of the map file in your ResSim watershed is shown at the top of the dialog box.

Appendix C describes additional map layer editors available in ResSim.

Chapter 5

Working with the Stream Alignment

Table of Contents

Section **Page**

5 Working with the Stream Alignment
5.1 Creating a New Stream Alignment 5-2
5.2 Editing an Existing Stream Alignment 5-5
5.2.1 Moving Vertices of a Stream Element 5-5
5.2.2 Adding Vertices to a Stream Element 5-6
5.2.3 Deleting Vertices from a Stream Element 5-6
5.2.4 Editing a Stream Element 5-6
5.2.5 Renaming a Stream Element 5-8
5.2.6 Deleting a Stream Element 5-8
5.2.7 Inserting a Stream Node 5-9
5.2.8 Editing a Stream Node 5-9
5.2.9 Deleting a Stream Node 5-10
5.2.10 Moving a Stream Junction 5-10
5.2.11 Editing a Stream Junction 5-11
5.2.12 Reversing the Direction of a Stream 5-11
5.2.13 Disconnecting a Stream Element 5-12
5.3 Importing a Stream Alignment 5-12
5.4 Exporting a Stream Alignment 5-14
5.5 Configuring Stream Alignment Display Properties 5-15
5.6 Saving the Stream Alignment 5-16
5.7 Listing of Streams 5-16

List of Figures

Figure Number

5.1 Stream Alignment 5-1
5.2 Stream Elements 5-1
5.3 Stream Nodes 5-1
5.4 Stream Junctions 5-1
5.5 Relationship of Line Segments, Stream Elements, and Stream Alignment 5-2
5.6 Drawing a Stream Element 5-3
5.7 Create New Stream Dialog Box 5-4
5.8 Connect Stream Reaches Dialog Box 5-4
5.9 Stream Junction 5-4

List of Figures (continued)

Figure Number **Page**

5.10 Moving Stream Element Vertices 5-5
5.11 Stream Alignment Shortcut Menu 5-6
5.12 Stream Editor 5-7
5.13 Enter Description Dialog Box - Stream Element 5-7
5.14 Name Stream Dialog Box 5-8
5.15 Confirmation Message when Deleting a Stream Element 5-8
5.16 Stream Node Shortcut Menu 5-9
5.17 Stream Node Editor 5-9
5.18 Confirm Delete of Stream Node 5-10
5.19 Moving a Stream Junction 5-10
5.20 Stream Junction Shortcut Menu 5-11
5.21 Stream Junction Editor 5-11
5.22 Confirm Reverse Direction of Stream Element 5-12
5.23 Import Stream Alignment Dialog Box 5-13
5.24 Choose Shapefile Dialog Box 5-13
5.25 Save File Browser 5-15
5.26 Stream Alignment Properties Dialog Box 5-15
5.27 List of Streams in Stream Alignment 5-16

Chapter 5

Working with the Stream Alignment

The **Stream Alignment**, illustrated in Figure 5.1, represents the river system in the watershed. It indicates where confluences and bifurcations occur and provides a sense of distance and scale.



Figure 5.1 Stream Alignment

In the **Watershed Setup Module**, Stream Elements (Figure 5.2), Stream Nodes (Figure 5.3), and Stream Junctions (Figure 5.4) are the components of a Stream Alignment.



Figure 5.2 Stream Elements



Figure 5.3 Stream Nodes



Figure 5.4 Stream Junctions

When you create a Stream Alignment, you draw it as a set of connected, multi-segmented lines. The Stream Alignment must have at least two nodes, defining the beginning and end of a stream element. Figure 5.5 illustrates the relationship of line segments, stream elements, and the Stream Alignment.



Figure 5.5 Relationship of Line Segments, Stream Elements, and Stream Alignment

ResSim creates and labels stream stations (or river stations) automatically along each stream element. By default, the station at the downstream end of an element is Station 0 (zero), and the stationing increases upstream along the element according to the linear distance between nodes on the stream element in the watershed coordinate system. You can override the default stationing by editing the station values of the stream nodes at the upstream and downstream ends of the stream element, as well as by adding additional nodes along the stream element.

Stream stationing is based on the geographic extents you define when you draw a stream element. If you have set the geographic extents to represent feet, either manually or by importing a layer projected in feet, the station labels will represent feet.

After you have drawn a Stream Alignment in the display area, you can edit, rename, delete, and move its component stream elements, stream nodes, and stream junctions using the Stream Alignment shortcut menus.

5.1 Creating a New Stream Alignment

You must be in the **Watershed Setup Module** to create a Stream Alignment in ResSim. Although it is not necessary, you will find it useful to display a background map of the river system as a guideline for creating your stream alignment. If your stream alignment is going to be based on a map layer, the map layer should already have been included in the watershed by copying the map files into the "maps" directory. The map layer should contain water features, such as stream channels and reservoirs or lakes. Use this map layer as a guide while creating the stream alignment. By doing this, the units of the labels on the stream alignment will be the same as the units of the water feature layer (i.e., if your water feature layer is projected in state plane coordinates (feet), then the labels on the stream alignment will be in feet). Refer to Chapters 3 and 4 for more information about adding and displaying maps.

You can either digitize a stream alignment by hand or import a stream alignment from an ArcView® shapefile. The following are the steps for digitizing a stream alignment (see Section 5.3 for details on importing a stream alignment).

To create a stream alignment:

1. You must be in the **Watershed Setup Module**. On the **Module** list, select **Watershed Setup**.
2. On the map toolbar, press the **Stream Alignment Tool** .
3. Determine an *upstream* location where you want to start a stream element (typically, you will begin at the upstream end of the mainstem and end at the most downstream location of the primary river in your watershed).
4. Hold down the **CTRL** key. Starting at the *upstream* end, draw the stream element by clicking the left mouse button at each vertex point as illustrated in Figure 5.6.



Figure 5.6 Drawing a Stream Element

5. Continue *downstream* (while *continuing to hold down* the **CTRL** key) and before placing the last point of the stream element, release the **CTRL** key, and then click the left mouse button at the last downstream location. This creates the ending stream node of the stream element.
6. The **Create New Stream** dialog box (Figure 5.7) opens. You can either accept the default name or enter a new name. Also, you can enter a description for the stream element. Click **OK** to close the **Create New Stream** dialog box.



Figure 5.7 Create New Stream Dialog Box

7. Repeat steps 4 through 6 to add more stream elements to your stream alignment.
8. To create a confluence or bifurcation, end the stream element by clicking directly on an existing stream element. After naming the new stream element, the **Connect Stream Reaches** dialog box (Figure 5.8) will appear. You need to determine whether you want to connect the new stream element to the existing stream element. Click **Yes** if you want the two stream elements connected; otherwise click **No**. If you selected **No**, and if there are additional existing streams that are possible candidates for connecting your new stream element to, then a subsequent **Connect Stream Reaches** dialog will appear to give you the opportunity to connect to the existing stream.



Figure 5.8 Connect Stream Reaches Dialog Box

When multiple stream elements are connected (e.g., at a confluence), a stream junction is automatically created and appears as a highlighted green circle (a "light green halo") as shown in Figure 5.9.



Figure 5.9 Stream Junction

9. Once you have completed the creation of your stream alignment, save your work. From the **File** menu, select **Save Watershed** and the stream alignment for your watershed will be saved.

5.2 Editing an Existing Stream Alignment

After drawing a stream alignment in the display area, there are many options available for revising your stream alignment. To edit your stream alignment, you must be in the **Watershed Setup Module**. The **Zoom Tool** can be used to help magnify the stream network, thus providing more detail to make editing the stream alignment easier.

This section describes the following capabilities for editing your Stream Alignment:

- how to refine and re-shape your stream alignment (by moving/adding/deleting vertex points of the stream elements)
- how to review stream stationing and provide a stream element description (by using the stream element editor)
- how to rename and delete stream elements
- how to add and edit stream nodes (for defining stream stationing)
- how to move and edit stream junctions
- how to reverse the flow direction of a stream element
- how to disconnect a stream element

Since the Stream Alignment may be referenced by other models, care should be used when making any changes to it.

5.2.1 Moving Vertices of a Stream Element

To move a vertex of an existing Stream Element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, double-click anywhere on the stream element. The stream element you select will turn red and all the vertices of that stream element will turn blue.
3. Click on the vertex you want to move, and drag it to a new location, as illustrated in Figure 5.10.



Figure 5.10 Moving Stream Element Vertices

5.2.2 Adding Vertices to a Stream Element

To add vertex points to an existing stream element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, double-click anywhere on the stream element. The stream element you select will turn red and all the vertices of that stream element will turn blue.
3. Place the pointer on the selected stream element where you want to add a vertex point. Hold down the **CTRL** key and click. A blue point will appear on the selected stream where you have added a vertex point.

5.2.3 Deleting Vertices from a Stream Element

To delete vertex points from an existing stream element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, double-click anywhere on the stream element. The stream element you select will turn red and all the vertices of that stream element will turn blue.
3. Hold down the **SHIFT+CTRL** keys and click on the vertex point to be deleted. The blue vertex point will disappear from the stream element, and the stream will straighten between the two adjacent vertices.

5.2.4 Editing a Stream Element

To edit a Stream Element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, right-click on the stream you want to edit.
3. From the shortcut menu (Figure 5.11), select **Edit Stream Element** to open the **Stream Editor** (Figure 5.12).



Figure 5.11 Stream Alignment Shortcut Menu



Figure 5.12 Stream Editor

The **Stream Editor** displays a summary of the stream name, description, stationing, and coordinates for a stream element. *You can edit only the description*.

Stream name:
The Stream Editor displays the name of the Stream Element you have selected in the list along with all available Stream Elements in the watershed. Also, left and right arrows (navigator buttons) allow you to click through the Stream Elements in the watershed.

Description:
To edit the Description of the Stream Element, you can type into the text area or click the ... button to access the **Enter Description** dialog box (Figure 5.13)



Figure 5.13 Enter Description Dialog Box - Stream Element

Stationing:
The Stream Editor provides you with a report of the stream stationing and coordinates of the Upstream and Downstream nodes, plus any stream nodes in between them. Use the **Stream Node Editor** (described in Section 5.2.8) to edit the stream stationing of the nodes.

5.2.5 Renaming a Stream Element

To rename a stream element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, right-click on the stream element and select **Rename Stream Element**.
3. Enter a new **Name** and **Description** for the stream element in the **Name Stream** dialog box illustrated in Figure 5.14.



Figure 5.14 Name Stream Dialog Box

5.2.6 Deleting a Stream Element

To delete a stream element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, right-click on the stream element and select **Delete Stream Element**.
3. When the confirmation message (shown below in Figure 5.15) appears, select either **Yes** or **No**.



Figure 5.15 Confirmation Message when Deleting a Stream Element

It is important to remember that other models may use the same stream alignment, so be sure to confirm with other modelers before deleting any stream elements.

5.2.7 Inserting a Stream Node

By default, ResSim generates beginning and ending stream nodes for each stream element. Also, stream nodes are automatically created where stream elements connect (stream junctions). Since stream nodes are used for establishing the stream stationing, you may want to include additional stream nodes along your stream element for locations where you want to define specific stream stationing.

It is important to keep in mind when defining the stream stations that the locations you specify for stationing are common to all models that use stationing in their computations.

To insert a stream node on an existing Stream Alignment:

1. Lock the configuration.

4. Using the **Stream Node Tool** , hold down the **CTRL** key and right-click on the Stream Alignment in the place where the stream node is to be inserted.
5. When you right-click on the stream station node, a shortcut menu appears (Figure 5.16).
6. From the shortcut menu on the stream node, you can choose **Edit Node**, which will bring up the **Stream Node Editor** illustrated in Figure 5.17.



Figure 5.16 Stream Node Shortcut Menu

5.2.8 Editing a Stream Node

The **Stream Node Editor** (Figure 5.17) displays the location information for the node.

1. The **Use Default Stationing** check box is selected by default. When you select this option, the current location of the selected node displays in the Stream Node Editor.
2. If you want to specify the exact location for the node on the stream element, "deselect" the **Use Default Stationing** to make the Station box editable.
3. Enter the location for the station directly into the Station box, and then click **OK**.



Figure 5.17 Stream Node Editor

5.2.9 Deleting a Stream Node

Since stream nodes define the stream stationing that may be referenced by other models, care should be used when deleting stream nodes.

To delete a stream node from an existing Stream Alignment:

1. Lock the configuration.
2. Find the stream node you wish to delete.
3. Using the **Stream Node Tool**, right-click on the stream node.
4. Select **Delete Node** from the shortcut menu.
5. A **Confirm Delete** message will display (Figure 5.18) asking you whether you really want to delete the selected stream node.
6. Click **Yes** and the message will close and the stream node will be deleted from the stream element.



Figure 5.18 Confirm Delete of Stream Node

5.2.10 Moving a Stream Junction

When two stream elements intersect (e.g., at a confluence), a Stream Junction is automatically created. A stream junction is multiple stream nodes at one location and is represented by a dark green circle with a light green halo around the circle. Although ResSim generates default stream junctions when you create the Stream Alignment, you can move them as needed.

To move a Stream Junction along an existing Stream Alignment:

1. Lock the configuration.
2. With the **Stream Node Tool** selected, double-click on the stream junction. The stream junction you select will turn dark green and will have small squares (handles) at each corner (Figure 5.19).
3. To move the stream junction, click and drag it along the stream element to its new position.



Figure 5.19 Moving a Stream Junction

5.2.11 Editing a Stream Junction

To edit a Stream Junction:

1. Lock the configuration.
2. Using the **Stream Node Tool**, right-click on the Stream Junction to access the shortcut menu (Figure 5.20).

Figure 5.20 Stream Junction Shortcut Menu

3. Select **Edit Junction** to open the **Stream Junction Editor** (Figure 5.21).



Figure 5.21 Stream Junction Editor

The Stream Junction Editor displays the list of stream nodes associated with a junction and allows you to edit the stationing of each of the nodes by deselecting the "Use Default Stationing" box and entering the desired station.

5.2.12 Reversing the Direction of a Stream

If you find that you have inadvertently drawn your stream element in the wrong direction (e.g., downstream to upstream when it should be upstream to downstream), then instead of having to delete the stream element and redraw it, you can choose to reverse the direction of the stream element.

To reverse the direction of a stream element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, right-click on the stream element and select **Reverse Direction** from the shortcut menu.

3. A warning message (Figure 5.22) will open asking you whether you really want to reverse the direction of the stream element.



Figure 5.22 Confirm Reverse Direction of Stream Element

4. Click **Yes** and the warning message will close and the stream element's direction will be reversed.

5.2.13 Disconnecting a Stream Element

A stream element can be connected to another stream element (e.g., at the confluence of two streams). If, for some reason, you need to disconnect the stream element from another stream element, you can do so.

To disconnect a stream element from another stream element:

1. Lock the configuration.
2. With the **Stream Alignment Tool** selected, right-click on the stream element you want to disconnect and select either **Disconnect Upstream** or **Disconnect Downstream**, as appropriate, from the shortcut menu.
3. The stream element will now be disconnected from the other stream element. On the display area, the upstream (or downstream) point will physically move away from the connecting stream element and a stream node will remain where the stream element was originally connected.

5.3 Importing a Stream Alignment

To import a stream alignment you must first have as an *active map layer* (see "Adding a New Map Layer" in Chapter 3, Section 3.4.2) an ArcView® shapefile which represents the stream system of your watershed. This shapefile must have an attribute that is the name of each stream, and each stream must form a contiguous line with one upstream point and one downstream point.

To import a stream alignment:

1. You must be in the **Watershed Setup Module**. From the **Module** list, select **Watershed Setup**.
2. Add the map layer that will be imported to the display area (see "Adding a New Map Layer" in Chapter 3, Section 3.4.2 to add a map layer).
3. From the **Watershed** menu, point to **Import**, and then select **Stream Alignment**.
4. The **Import Stream Alignment** dialog box (Figure 5.23) will open.



Figure 5.23 Import Stream Alignment Dialog Box

5. In the **Shapefile Name** box is displayed one of the ArcView® shapefiles defined as *active map layers* in your watershed. ResSim automatically selects the first shapefile that contains polylines. Therefore, if this is not the desired shapefile, then from the **File** menu, select **Choose Shapefile**.
6. The **Choose Shapefile** dialog box (Figure 5.24) will open. In the **Available** box, is a list of the available polyline shapefiles that you have added as map layers. In the **Selected** box, is the polyline shapefile that has been chosen. To choose a different polyline shapefile, use the **Add** and **Remove** buttons to get the correct shapefile. In Figure 5.24, the polyline shapefile to be used for importing the stream alignment is *stream.shp*.



Figure 5.24 Choose Shapefile Dialog Box

7. Once the correct shapefile has been chosen, the required attribute is the name of each stream. The program automatically searches for a database field name of **Stream_ID**. If there is not a database field name of **Stream_ID**, then in the **Database Field Name** list, you must select the database field name that contains the names of each stream. In the example shown in Figure 5.23, for the shapefile *stream.shp*, the database field name is *Stream_ID*.
8. When you have selected the correct database field name, the table will list the stream names. If each stream is a contiguous line with one upstream point and one downstream point, then the checkbox in the **Import** column of the table will be set. If there is something wrong with the line that represents a stream, the checkbox will not be set, and ResSim will not import that stream element.
9. **Gap Tolerance** (see Figure 5.23) is used to connect stream elements that have a gap between the end point and the junction with another stream. By default, the **Gap Tolerance** is set to zero (0.0), so ResSim can connect streams to other streams. If you click **Gap Tolerance**, then you need to enter a value larger than zero in the **Gap Tolerance** box, which will allow ResSim to connect streams that might have a larger gap between them.
10. The **Replace Existing Stream Alignment** box, allows you to replace the existing stream alignment with the one being imported from the selected ArcView® shapefile.
11. Once everything is set, click **Import**. The stream alignment will be automatically drawn in the display area. From the **File** menu, choose **Close** and the **Import Stream Alignment** dialog box (Figure 5.23) will close.

5.4 Exporting a Stream Alignment

If you have digitized a stream alignment by hand, you might want to save that stream alignment as an ArcView® shapefile. To export a stream alignment you must have a stream alignment in the display area.

To export a stream alignment:

1. You must be in the **Watershed Setup Module**. On the **Module** list, click **Watershed Setup**.
2. From the **Watershed** menu, point to **Export**, and then select **Stream Alignment**.

3. A **Save File** browser (Figure 5.25) will open. Enter a name in the **File Name** box. Click **OK**, the **Save File** browser will close, and you will have an ArcView® shapefile of the displayed stream alignment.



Figure 5.25 Save File Browser

5.5 Configuring Stream Alignment Display Properties

You can change the color, line width, font, and tic mark properties of a Stream Alignment using the **Stream Alignment Properties Editor**. The section on "Viewing and Configuring Layer Properties" in Chapter 4, Section 4.4 describes in detail how to change Stream Alignment display properties.

To change stream alignment properties:

1. From the **View** menu, select **Layers**.
2. The **Layer Selector** dialog box will open.
3. Right-click on the **StreamAlignment** layer in the tree. From the shortcut menu, click **Properties**.
4. The **Stream Alignment Properties** dialog box (Figure 5.26) will open.



Figure 5.26 Stream Alignment Properties Dialog Box

5. To change the color of the stream alignment layer, select a color from the **Stream Color** list. The preview pane to the right of the **Edit Properties** box will display the selected color.
6. Click **OK** and the **Stream Alignment Properties** dialog box will close and the color change will appear in the display area.
7. Repeat steps 5 and 6 for any other changes you wish to make to the stream alignment properties.
8. Once you have finished, from the **Layer Selector** dialog box, click **OK** to close.

5.6 Saving the Stream Alignment

Since creating a stream alignment can be a very detailed activity, you should save it frequently during its creation. From the **File** menu, click **Save Watershed**. This command will save all of the stream alignment properties and the appropriate files created and used by ResSim for the stream alignment.

5.7 Listing of Streams

Once you have your stream alignment completed, it's a good idea to review the streams in your stream alignment. From the **Watershed Setup Module**, there is a report that contains this information.

1. From the **Reports** menu, select **List of Streams** and a report similar to Figure 5.27 will appear.



Figure 5.27 List of Streams in Stream Alignment

2. This report provides a list of streams and their descriptions that have been input for the stream alignment.
3. From the **File** menu of the report, you can print the report, or you can export the report as an ASCII tab-delimited file.
4. Click **Close** and the **List of Streams** report will close.

Chapter 6

Creating Watershed Elements

Table of Contents

Section **Page**

6 Creating Watershed Elements
6.1 Creating a Reservoir 6-1
6.1.1 Editing Reservoir Data (Watershed Setup) 6-2
6.1.2 Renaming a Reservoir 6-3
6.1.3 Removing a Reservoir from a Configuration 6-4
6.1.4 Deleting a Reservoir 6-4
6.1.5 Adding Configuration Notes for a Reservoir 6-4
6.2 Creating a Levee 6-5
6.2.1 Editing Levee Data 6-5
6.2.2 Renaming a Levee 6-7
6.2.3 Removing a Levee from a Configuration 6-7
6.2.4 Deleting a Levee 6-8
6.2.5 Adding Configuration Notes for a Levee 6-8
6.3 Creating a Diversion 6-9
6.3.1 Editing Diversion Data 6-10
6.3.2 Renaming a Diversion 6-10
6.3.3 Disconnecting a Diversion 6-11
6.3.4 Removing a Diversion from a Configuration 6-11
6.3.5 Deleting a Diversion 6-11
6.3.6 Adding Configuration Notes for a Diversion 6-12
6.4 Creating Channel Modifications 6-12
6.4.1 Editing Channel Modification Data 6-13
6.4.2 Renaming a Channel Modification 6-13
6.4.3 Removing a Channel Modification from a Configuration 6-14
6.4.4 Deleting a Channel Modification 6-14
6.4.5 Adding Configuration Notes for Channel Modifications 6-14
6.5 Creating Off-Channel Storage Areas 6-15
6.5.1 Editing Off-Channel Storage Data 6-15
6.5.2 Renaming an Off-Channel Storage Area 6-16
6.5.3 Removing an Off-Channel Storage Area from a Configuration 6-16
6.5.4 Deleting an Off-Channel Storage Area 6-17
6.5.5 Adding Configuration Notes for an Off-Channel Storage Area 6-17

Section (continued) **Page**

6.6 Creating "Other" Projects 6-18
6.6.1 Editing "Other" Project Data 6-18
6.6.2 Renaming "Other" Projects 6-19
6.6.3 Removing "Other" Projects from a Configuration 6-19
6.6.4 Deleting "Other" Projects 6-20
6.6.5 Adding Configuration Notes for "Other" Projects 6-20
6.7 Configuring Project Display Properties 6-20
6.8 Defining Computation Points 6-21
6.8.1 Editing Computation Point Data 6-21
6.8.2 Renaming a Computation Point and Editing the Description 6-23
6.8.3 Deleting a Computation Point 6-23
6.9 Working with Time-Series Icons 6-24

List of Figures

Figure Number

6.1 Reservoir Elements in Watershed Setup Module 6-1
6.2 Name New Reservoir Dialog Box 6-2
6.3 Reservoir Editor 6-3
6.4 Warning Message when Renaming Reservoir 6-3
6.5 Confirm Removal of Reservoir Dialog Box 6-4
6.6 Configuration Notes - Reservoir 6-4
6.7 Levee Drawing 6-5
6.8 Levee Properties Editor 6-6
6.9 Warning Message when Renaming Levee 6-7
6.10 Confirm Removal of Levee Dialog Box 6-7
6.11 Configuration Notes - Levee 6-8
6.12 Example Diversions 6-9
6.13 Diversion Editor 6-10
6.14 Warning Message when Renaming Diversion 6-10
6.15 Disconnecting an Outflow - Diversion Shortcut Menu 6-11
6.16 Configuration Notes - Diversion 6-12
6.17 Channel Modification Editor 6-13
6.18 Warning Message when Renaming Channel Modification 6-13
6.19 Configuration Notes - Channel Modification 6-14
6.20 Off-Channel Storage Editor 6-15
6.21 Warning Message when Renaming Off-Channel Storage Area 6-16
6.22 Configuration Notes - Off-Channel Storage 6-17
6.23 "Other" Projects Editor 6-18
6.24 Warning Message when Renaming "Other" Project 6-19
6.25 Configuration Notes - "Other" Projects 6-20
6.26 Computation Point Editor 6-21
6.27 Rename Dialog Box - Computation Point 6-23
6.28 Confirm Deletion Dialog Box - Computation Point 6-23
6.29 Time-Series Icons 6-24

Chapter 6

Creating Watershed Elements

In the **Watershed Setup Module** you can define the Projects and Computation Points used in ResSim.

ResSim provides the tools for drawing geographically referenced Projects including Reservoirs, Levees, Diversions, Channel Modifications, Off-Channel Storage Areas, and "Other" Projects. The tools provide the ability to edit the graphical representation of the Project within the map display panel, and they also provide access to menu items for editing the Project data directly from the map display. ResSim computations include only reservoir and diversion projects.

When you add a Project to the map display panel, it becomes part of the Configuration you currently have selected. A "superset" of all configurations is named "Study" and includes all of the Projects for the watershed. For more information on associating projects with Configurations, refer to Chapter 7.

The Computation Point set contains all locations where time-series information is to be computed for possible exchange between application models (e.g., ResSim and FIA). ResSim automatically generates Computation Points when Projects are placed on the Stream Alignment.

6.1 Creating a Reservoir

You will create a reservoir by starting at the *upstream* end of the reservoir. After the reservoir has been created, several visual elements will appear (as shown in Figure 6.1) that represent a reservoir: a storage reach (dark cyan), a "pool" (light cyan triangle), a "dam" (small gray rectangle), and computation points (black dots) at the upstream and downstream locations of the reservoir on the stream alignment.



Figure 6.1 Reservoir Elements in Watershed Setup Module

To add a reservoir to the watershed:

1. Select the **Reservoir Tool** .
2. While holding down the **CTRL** key, click on the stream alignment at the *upstream* location of the reservoir. If more than one stream flows into the reservoir pool, continue holding down the **CTRL** key and click at each location of inflow into the reservoir on these streams.
3. Release the **CTRL** key and click on the stream alignment at the *downstream* location of the reservoir (where the dam is located). Reservoirs should not overlap previously placed computation points.
4. When you release the mouse button after creating the downstream end of the reservoir, the **Name New Reservoir** dialog box appears (Figure 6.2).



Figure 6.2 Name New Reservoir Dialog Box

5. You name the Reservoir by typing a name in the **Name** field. Optionally, you can enter a **Description** for the Reservoir.
6. Click **OK** when you are done.

The new Reservoir will now appear in your map display.

6.1.1 Editing Reservoir Data (Watershed Setup)

To edit data for the Reservoir in the Watershed Setup Module, select the **Reservoir Tool** and right-click on the Reservoir. From the shortcut menu, select **Edit Reservoir** to access the **Reservoir Editor** (Figure 6.3).



Figure 6.3 Reservoir Editor

In the Watershed Setup Module, the only data that you need to specify for the Reservoir is its **Name** and **Label Position** (additional data is entered in the Reservoir Network Module). The **Label Position** selects where to place the reservoir name in the display area, relative to the reservoir.

Check **Existing Project** if the reservoir currently exists so that the reservoir will be added automatically to any new configurations. You can remove it at any time by selecting **Remove from Configuration** in the shortcut menu or by using the **Configuration Editor**. This is a useful option if you are creating multiple configurations that use the same set of reservoirs.

Certain models compute project benefits (e.g., HEC-FIA); therefore, use the **Corps Projects** checkbox to indicate if the reservoir is a Corps Project.

The **Year in Service** field is optional and is used in planning studies. You do not need to specify a year in service when defining projects for real-time studies.

6.1.2 Renaming a Reservoir

To rename a Reservoir, select the **Reservoir Tool** and right-click on the Reservoir. From the shortcut menu, select **Rename Reservoir**. This command opens a dialog box that allows you to rename the reservoir. A warning message (Figure 6.4) appears when you save the new name, asking you to confirm that you want to rename the reservoir. If you choose to rename the reservoir, remember that changing a reservoir name may affect one or more of the configurations that recognize the reservoir.



Figure 6.4 Warning Message when Renaming Reservoir

6.1.3 Removing a Reservoir from a Configuration

To remove a Reservoir from the current Configuration, select the **Reservoir Tool** and right-click on the Reservoir. From the shortcut menu, select **Remove from Configuration**. This command removes the reservoir from the Configuration that is currently displayed in the **Configuration** box on the toolbar. The **Confirm Removal** dialog box appears (Figure 6.5).

Figure 6.5 Confirm Removal of Reservoir Dialog Box

You can also remove a Reservoir from a Configuration by accessing the **Configuration Editor** and manually removing the reservoir from the Projects tab using the **Project Selector**.

6.1.4 Deleting a Reservoir

To delete a Reservoir from the watershed, select the **Reservoir Tool** and right-click on the Reservoir. From the shortcut menu, select **Delete Reservoir**. This command removes the reservoir and all data associated with the reservoir from the watershed. You are asked to confirm a deletion before the reservoir is removed, and asked if you would like to delete the reservoir's computation points. If you choose to delete the reservoir, remember that deleting the reservoir may affect one or more of the configurations that recognize the reservoir.

6.1.5 Adding Configuration Notes for a Reservoir

To add Configuration Notes for a Reservoir, select the **Reservoir Tool** and right-click on the Reservoir. From the shortcut menu, select **Configuration Notes**. This command opens a dialog box (Figure 6.6) for entering text information about a project specific to the configuration.



Figure 6.6 Configuration Notes - Reservoir

6.2 Creating a Levee

A levee is an earthen barrier built along a stream to provide protection from flooding. A levee can reduce flood damage by preventing flood stages from reaching a potential damage area.

To add a levee to the watershed:

1. Select the **Levee Tool** .
2. While holding down the **CTRL** key, click on the stream alignment to select the *upstream* end of the levee, then release the **CTRL** key and click to select the *downstream* end.

When you release the mouse button after clicking at the downstream end of the levee, a dialog box appears for you to provide a name and description. After entering a Levee name, the levee will be drawn as a black line following the stream alignment. However, using the Levee Editor (see Follows Stream option in Section 6.2.1), you can allow for positioning the levee along the side of the stream alignment in the display area (Figure 6.7).



Figure 6.7 Levee Drawing

6.2.1 Editing Levee Data

To edit Levee data, right-click on the levee and select **Edit Levee**. The **Levee Properties Editor** opens, as shown in Figure 6.8.

In addition to the **Levee Name** and **Description**, the Levee Editor displays the **Stream Name** and the **Start** and **End Stations** for the levee. You can edit the stationing manually by directly entering values in the **Start Station** and **End Station** fields.

The **Follows Stream** checkbox is selected by default. With this option selected, the levee is drawn in parallel to the stream alignment. By deselecting the **Follows Stream** checkbox, you can allow for

moving the levee and editing its shape using the **Levee Tool** in the map display. To do this, first double-click the levee to select it. The levee will turn yellow and the beginning and end points will appear as black dots. To add additional vertex points, **CTRL**-click along the levee. You can then drag any of the vertex points to the desired location. This process is very similar to editing the stream alignment, with the exception of the mouse tool used.

Certain models compute project benefits (e.g., HEC-FIA); therefore, use the **Corps Projects** checkbox to indicate if the levee is a Corps Project.

ResSim does not actually use levees in its computations. However, those models that do use levee data in their computations contain the tools for configuring the levee data. Therefore, refer to the appropriate model's User's Manual (e.g., HEC-FIA) for further information.



Figure 6.8 Levee Properties Editor

6.2.2 Renaming a Levee

To rename a Levee:

1. Select the **Levee Tool** and right-click on the Levee.
2. From the shortcut menu, select **Rename Levee**. This command opens a dialog box that allows you to rename the levee.
3. If you choose to rename the levee, remember that changing the levee name may affect one or more of the configurations that recognize the levee.
4. A warning message appears (Figure 6.9) when you save the new name, asking you to confirm that you want to rename the levee.

Figure 6.9 Warning Message when Renaming Levee

6.2.3 Removing a Levee from a Configuration

To remove a Levee from the current Configuration:

1. Select the **Levee Tool**
2. Right-click on the Levee.
3. From the shortcut menu, select **Remove from Configuration**. This command removes the levee from the Configuration that is currently displayed in the **Configuration** box on the toolbar. The **Confirm Removal** dialog box appears (Figure 6.10).



Figure 6.10 Confirm Removal of Levee Dialog Box

You can also remove a Levee from a Configuration by accessing the **Configuration Editor** and manually removing the levee from the **Projects** tab using the **Project Selector**.

6.2.4 Deleting a Levee

To delete a Levee from the watershed:

1. Select the **Levee Tool** .
2. Right-click on the Levee.
3. From the shortcut menu, select **Delete Levee**. This command removes the levee and all data associated with the levee from the watershed. You are asked to confirm a deletion before the levee is removed. Again, if you choose to delete the levee, remember that deleting the levee may affect one or more of the configurations that recognize the levee.

6.2.5 Adding Configuration Notes for a Levee

To add Configuration Notes for a Levee:

1. Select the **Levee Tool** and right-click on the Levee.
2. From the shortcut menu, select **Configuration Notes**. This command opens a dialog box (Figure 6.11) for entering text information about a project that is specific to the configuration.



Figure 6.11 Configuration Notes - Levee

6.3 Creating a Diversion

To add a Diversion to the watershed:

1. Select the **Diversion Tool** .
2. While holding down the **CTRL** key, click to select the location on the stream alignment where the diversion will occur (the "from" location). Then, release the **CTRL** key and click to select the location where the diverted water will go (the "to" location). The "to" location (location that will receive the diverted water) can be on the stream alignment (which indicates that the diverted water will remain within the channel system) or it can be a point in the display area that is not connected to the stream alignment (which will indicate a loss of the diverted water to the channel system).
3. When you release the mouse button after creating the diversion, a dialog box appears for you to provide a name and description. After entering a name, the Diversion is drawn in the display area. If both ends of the diversion are connected to the stream alignment, then Computation Points are automatically generated at each end of the diversion (the color of the arrow head will be blue). If the diversion is only connected to the stream alignment at the location where the water is diverted from, then a Computation Point will be generated at that location only (and the color of the arrow head will be black).
4. It's a good idea to rename the Computation Points that are automatically generated for a diversion. To do this, select the **Computation Point Tool** and right-click on the computation points at the ends of the diversion. Then, from the shortcut menu, select **Rename Computation Point**. Figure 6.12 shows example diversions where the Computation Points for the diversions were renamed ("PutDiv", "GetDiv", and "DivOut").

After the diversion is defined, it will show up as a black line with an arrow head at the divert-to end. If the diversion leaves one location and returns to another location (see "MyDiv" diversion in Figure 6.12), the arrow head is blue. If the diversion leaves the system (see "YourDiv" diversion in Figure 6.12), then the arrow head is displayed in black instead of blue.



Figure 6.12 Example Diversions

6.3.1 Editing Diversion Data

To edit Diversion Data:

1. Select the **Diversion Tool** .
2. Right-click on the Diversion and select **Edit Diversion**. The **Diversion Editor** opens, as shown in Figure 6.13.



Figure 6.13 Diversion Editor

The Diversion Editor is similar to the Reservoir Editor described in Section 6.1.1. You can specify whether the diversion is an **Existing Project**, a **Corps Project**, the **Label Position**, and the **Year In Service** (as previously described in Section 6.1.1). The **Stream** the diversion connects to is shown.

6.3.2 Renaming a Diversion

To rename a Diversion

1. Select the **Diversion Tool** .
2. Right-click on the Diversion and from the shortcut menu select **Rename Diversion**. This command opens a dialog box that allows you to rename the diversion. If you choose to rename the diversion, remember that changing the diversion name may affect one or more of the configurations that recognize the diversion.
3. A warning message (Figure 6.14) appears when you save the new name, asking you to confirm that you want to rename the diversion.

Figure 6.14 Warning Message when Renaming Diversion

6.3.3 Disconnecting a Diversion

If you decide to disconnect the outflow of a diversion:

1. Select the **Diversion Tool** .
2. Right-click on a Diversion that is connected to another location and select **Disconnect Outflow** from the shortcut menu (Figure 6.15).



Figure 6.15 Disconnecting an Outflow - Diversion Shortcut Menu

6.3.4 Removing a Diversion from a Configuration

To remove a Diversion from the current Configuration:

1. Select the **Diversion Tool** .
2. Right-click on the Diversion and from the shortcut menu select **Remove from Configuration**. This command removes the diversion from the Configuration that is currently displayed in the **Configuration** box on the toolbar. The **Confirm Removal** dialog box will appear.

You can also remove a Diversion from a Configuration by accessing the **Configuration Editor** and manually removing the diversion from the **Projects** tab using the **Project Selector**.

6.3.5 Deleting a Diversion

To delete a Diversion from the watershed:

1. Select the **Diversion Tool** and right-click on a Diversion.
2. From the shortcut menu, select **Delete Diversion**. This command removes the diversion and all data associated with the diversion from the watershed. You are asked to confirm a deletion before the diversion is removed. Again, if you choose to delete the diversion, remember that deleting the diversion may affect one or more of the configurations that recognize the diversion.

6.3.6 Adding Configuration Notes for a Diversion

To add Configuration Notes for a Diversion:

1. Select the **Diversion Tool** and right-click on the Diversion.
2. From the shortcut menu, select **Configuration Notes**. This command opens a dialog box (Figure 6.16) for entering text information about a diversion that is specific to the configuration.



Figure 6.16 Configuration Notes - Diversion

6.4 Creating Channel Modifications

To add a Channel Modification to the watershed:

1. Select the **Channel Modification Tool** .
2. Hold down the **CTRL** key and click at the upstream end of the channel modification along the stream alignment.
3. Release the **CTRL** key and click on the downstream end of the channel modification.

When you release the mouse button after creating the downstream end, the channel modification is drawn along the stream alignment and a dialog box appears for you to provide a name and description. After entering a name, the channel modification is drawn along the stream alignment in the display area. Note that Channel Modifications are not yet implemented in ResSim's computations.

6.4.1 Editing Channel Modification Data

To edit Channel Modification Data:

1. Select the **Channel Modification Tool** .
2. Right-click on the Channel Modification and select **Edit Channel Modification**. The **Channel Modification Editor** opens, as shown in Figure 6.17.



Figure 6.17 Channel Modification Editor

The Channel Modification Editor contains the basic configuration data for the Channel Modification Project, such as whether it is an **Existing Project**, a **Corps Project**, the **Label Position**, the **Stream Name**, and the **Year in Service** (as previously described in Section 6.1.1).

6.4.2 Renaming a Channel Modification

To rename a Channel Modification:

1. Select the **Channel Modification Tool** and right-click on the Channel Modification.
2. From the shortcut menu, select **Rename Channel Modification**. This command opens a dialog box that allows you to rename the channel modification. If you choose to rename the channel modification, remember that changing the name may affect one or more of the configurations that recognize the channel modification.
3. A warning message (Figure 6.18) appears when you save the new name, asking you to confirm that you want to rename the channel modification.



Figure 6.18 Warning Message when Renaming Channel Modification

6.4.3 Removing a Channel Modification from a Configuration

To remove a Channel Modification from the current Configuration:

1. Select the **Channel Modification Tool** and right-click on the Channel Modification.
2. From the shortcut menu, select **Remove from Configuration**. This command removes the Channel Modification from the Configuration that is currently displayed in the Configuration box on the toolbar. The Confirm Removal dialog box appears.

You can also remove a Channel Modification from a Configuration by accessing the **Configuration Editor** and manually removing the Channel Modification from the **Projects** tab using the **Project Selector**.

6.4.4 Deleting a Channel Modification

To delete a Channel Modification from the watershed:

1. Select the **Channel Modification Tool** and right-click on the Channel Modification.
2. From the shortcut menu, select **Delete Channel Modification**. This command removes the Channel Modification and all data associated with it from the watershed. You will be asked to confirm a deletion before the Channel Modification is removed. Again, if you choose to delete the Channel Modification, remember that deleting it may affect one or more of the configurations that recognize the project.

6.4.5 Adding Configuration Notes for Channel Modifications

To add Configuration Notes for a Channel Modification:

1. Select the **Channel Modification Tool** and right-click on the Channel Modification.
2. From the shortcut menu, select **Configuration Notes**. This command opens a dialog box (Figure 6.19) for entering text information about a project that is specific to the configuration.



Figure 6.19 Configuration Notes - Channel Modification

6.5 Creating Off-Channel Storage Areas

To add an Off-Channel Storage Area to the watershed:

1. Select the **Off-Channel Storage Tool** .
2. Hold down the **CTRL** key and click the location in the map where you want to add the Storage Area. Continue to hold the **CTRL** key while you click to add additional vertex points for the bounding polygon that represents the Off-Channel Storage Area.
3. When you reach the end point, release the **CTRL** key and click to place the last point.
4. When you release the mouse button, a dialog box appears for you to provide a name and description. After entering a name, the polygon appears in the map display area. Note that Off-Channel Storage Areas are not yet implemented in ResSim's computations.

6.5.1 Editing Off-Channel Storage Data

To edit Off-Channel Storage data:

1. Select the **Off-Channel Storage Tool** and right-click on the Off-Channel Storage Area.
2. Select **Edit Off-Channel Storage**. The **Off-Channel Storage Editor** opens, as shown in Figure 6.20.



Figure 6.20 Off-Channel Storage Editor

The Off-Channel Storage Editor contains the basic configuration data for the Off-Channel Storage project, such as whether the project is an **Existing Project**, a **Corps Project**, the **Label Position**, the **Stream Name**, and the **Year in Service** (as previously described in Section 6.1.1).

6.5.2 Renaming an Off-Channel Storage Area

To rename an Off-Channel Storage Area:

1. Select the **Off-Channel Storage Tool** and right-click on the Off-Channel Storage Area.
2. From the shortcut menu, select **Rename Off-Channel Storage**. This command opens a dialog box that allows you to rename the Off-Channel Storage Area project. If you choose to rename the Off-Channel Storage Area project, remember that changing the name may affect one or more of the configurations that recognize the project.
3. A warning message (Figure 6.21) appears when you save the new name, asking you to confirm that you want to rename the Off-Channel Storage Area project.

Figure 6.21 Warning Message when Renaming Off-Channel Storage Area

6.5.3 Removing an Off-Channel Storage Area from a Configuration

To remove an Off-Channel Storage Area from the current Configuration:

1. Select the **Off-Channel Storage Tool** and right-click on the Off-Channel Storage Area.
2. From the shortcut menu, select **Remove from Configuration**. This command removes the Off-Channel Storage project from the Configuration that is currently displayed in the Configuration box on the toolbar. The Confirm Removal dialog box will appear.

You can also remove an Off-Channel Storage Area from a Configuration by accessing the **Configuration Editor** and manually removing the project from the **Projects** tab using the **Project Selector**.

6.5.4 Deleting an Off-Channel Storage Area

To delete an Off-Channel Storage Area from the watershed:

1. Select the **Off-Channel Storage Tool** and right-click on the Off-Channel Storage Area.
2. From the shortcut menu, select **Delete Off-Channel Storage**. This command removes the Off-Channel Storage Area project and all data associated with it from the watershed. You will be asked to confirm a deletion before the Off-Channel Storage Area project is removed. Again, if you choose to delete the project, remember that deleting it may affect one or more of the configurations that recognize the Off-Channel Storage Area project.

6.5.5 Adding Configuration Notes for an Off-Channel Storage Area

To add Configuration Notes for an Off-Channel Storage Area:

1. Select the **Off-Channel Storage Tool** and right-click on the Off-Channel Storage Area.
2. From the shortcut menu, select **Configuration Notes**. This command opens a dialog box for entering text information about an Off-Channel Storage Area project that is specific to the configuration (Figure 6.22).



Figure 6.22 Configuration Notes - Off-Channel Storage

6.6 Creating "Other" Projects

To add "Other" Projects to the watershed:

1. Select the **Other Project Tool** .
2. Hold down the **CTRL** key and single click in the location where you want the other project to appear.

The Other Projects symbol will appear in the map display. Note that Other Projects are not yet implemented in ResSim's computations.

6.6.1 Editing "Other" Project Data

To edit "Other" Projects Data:

1. Select the **Other Project Tool** and right-click on the "Other" Project.
2. Select **Edit Other Project**. The **Other Project Properties** editor opens, as shown in Figure 6.23.



Figure 6.23 Other Project Properties Editor

The **Other Projects Properties** editor allows you to define the spatial location (Coordinates), and contains basic configuration data, such as whether the project is an **Existing Project**, a **Corps Project**, the **Label Position**, the **Stream Name**, and the **Year in Service** (as previously described in Section 6.1.1).

Two options are unique to the Other Project Editor:

1. **Connect to Stream** checkbox allows you to associate the project with a particular stream in case it might be used with a supplemental model.
2. **Do Not Generate Computation Point** checkbox determines whether or not ResSim will automatically generate a Computation Point at the location specified in the Coordinates box.

6.6.2 Renaming "Other" Projects

To rename an "Other" Project:

1. Select the **Other Project Tool** and right-click on the Other Project.
2. From the shortcut menu, select **Rename Other Project**. This command opens a dialog box that allows you to rename the Other Project. If you choose to rename the project, remember that changing the project name may affect one or more of the configurations that recognize the Other Project.
3. A warning message (Figure 6.24) appears when you save the new name, asking you to confirm that you want to rename the project.



Figure 6.24 Warning Message when Renaming "Other" Project

6.6.3 Removing "Other" Projects from a Configuration

To remove an "Other" Project from the current Configuration:

1. Select the **Other Project Tool** and right-click on the Other Project.
2. From the shortcut menu, select **Remove from Configuration**. This command removes the Other Project from the Configuration that is currently displayed in the Configuration box on the toolbar. The **Confirm Removal** dialog box appears.

You can also remove an Other Project from a Configuration by accessing the **Configuration Editor** and manually removing it from the **Projects** tab using the **Project Selector**.

6.6.4 Deleting "Other" Projects

To delete an "Other" Project from the watershed:

1. Select the **Other Project Tool** and right-click on the Other Project.
2. From the shortcut menu, select **Delete Other Project**. This command removes the Other Project and all data associated with it from the watershed. You will be asked to confirm a deletion before the Other Project is removed. Again, if you choose to delete the Other Project, remember that deleting it may affect one or more of the configurations that recognize the Other Project.

6.6.5 Adding Configuration Notes for "Other" Projects

To add Configuration Notes for an "Other" Project:

1. Select the **Other Project Tool** and right-click on the Other Project.
2. From the shortcut menu, select **Configuration Notes**. This command opens a dialog box (Figure 6.25) for entering text information about an Other Project that is specific to the configuration.



Figure 6.25 Configuration Notes - "Other" Projects

6.7 Configuring Project Display Properties

You can configure the appearance of Reservoirs, Levees, Diversions, and Computation Points in the **Study Layer** of your watershed using the **Study Properties Editor**. See Chapter 4, Section 4.4.1, "Study Layer Properties" for information on how to change Project display properties.

6.8 Defining Computation Points

The Computation Point set contains all locations where time-series information is to be computed. ResSim automatically generates Computation Points for the watershed based on Project, Stream Alignment, and Impact Area placement.

To add a Computation Point:

1. Lock the configuration.
2. Select the **Computation Point Tool**.
3. Hold down the **CTRL** key and click in the desired location.

The new Computation Point will appear in the map display. By default, Computation Points snap to the stream alignment. If you prefer that the Computation Point not snap to the stream alignment, de-select the **Snap to Stream Alignment** check box in the Computation Point Editor, described below.

6.8.1 Editing Computation Point Data

Use the **Computation Point Editor** to edit a Computation Point:

1. Lock the configuration.
2. Select the **Computation Point Tool**.
3. Right-click on the Computation Point to access the shortcut menu.
4. Select **Edit Computation Point**. The **Computation Point Editor** (Figure 6.26) will appear.



Figure 6.26 Computation Point Editor

The **Computation Point Editor** displays the information associated with a Computation Point and allows you to edit its location information.

Computation Point Name:
The Computation Point Editor displays the name of the Computation Point you have selected (in the list along with all available Computation Points in the watershed). Also, left and right arrows (navigator buttons) allow you to click through the Computation Points in the watershed.

Description:
To edit the Description of the Computation Point, you can type into the text area or click the button to access the **Enter Description** dialog box.

Location ID:
Optionally, you can enter a Location ID to reference the Computation Point to a ResSim ID.

Stream Name:
The stream name automatically appears in the Stream Name box. In the case of a Computation Point situated at a confluence of two streams, you need to verify that the Computation Point resides on the appropriate stream.

Stream Station:
The Stream Station field displays the location of the computation point along the stream element.

Label Position: ResSim automatically positions the text label for a Computation Point where it is least likely to overlap other labels. However, you can move the position of the layer by selecting a position from the Label Position list.

Location:
ResSim automatically fills in the coordinate information for Northing/Easting. You may type in new coordinates to relocate the Computation Point on the map display.

Snap to Stream Alignment:
By selecting the Snap to Stream Alignment check box, you can place a Computation Point at any location and it will snap to the alignment. After a Computation Point is snapped on the stream alignment, only the Stream Station can be edited. ResSim automatically displays the Stream Name and Stream Stationing and Coordinates.

System Generated:
ResSim automatically generates Computation Points for the watershed based on Project, Stream Alignment, and Impact Area placement. The System Generated checkbox is selected if the Computation Point has been system generated.

6.8.2 Renaming a Computation Point and Editing the Description

To rename a Computation Point or edit its description:

1. Lock the configuration.
2. Select the **Computation Point Tool** and right-click on the Computation Point.
3. Select **Rename Computation Point**.
4. Use the **Rename** dialog box (Figure 6.27) to edit the name and description. Click the ... button to access the **Enter Description** dialog box for longer descriptions.



Figure 6.27 Rename Dialog Box - Computation Point

6.8.3 Deleting a Computation Point

To delete a Computation Point:

1. Lock the configuration.
2. Select the **Computation Point Tool** and right-click on the Computation Point.
3. Select **Delete Computation Point** from the shortcut menu. The **Confirm Deletion** dialog box will appear (Figure 6.28).
4. Click **Yes** to confirm the deletion.



Figure 6.28 Confirm Deletion Dialog Box - Computation Point

6.9 Working with Time-Series Icons

Time-Series Icons are not necessary for ResSim simulations. However, as part of watershed setup, you may need to configure them for other applications in the modeling software suite.

You can use **Time-Series Icons** to represent the locations of gages or Time-Series locations. Typically used in CWMS, they can be linked to data from either the Oracle Database or from a DSS file. The complete inventory of Time-Series Icons is viewable in the Watershed Setup Module. Figure 6.29 shows examples of the icons you can configure in the **Watershed Setup Module**.

Figure 6.29 Time-Series Icons

Refer to the *CWMS User's Manual* (HEC, 2003a) for additional information about Time-Series Icons.

Chapter 7

Creating Watershed Configurations

Table of Contents

Section **Page**

7 Creating Watershed Configurations
7.1 Adding Watershed Configurations....7-1
7.2 Adding and Removing Projects from Configurations....7-3
7.2.1 Adding Projects to a Configuration....7-4
7.2.2 Removing Projects from a Configuration....7-4
7.3 Adding Configuration Notes....7-5
7.4 Making a Copy of a Configuration....7-5
7.5 Deleting a Configuration....7-6
7.6 Saving Configuration Data....7-6
7.7 Listing Configurations....7-6

List of Figures

Figure Number **Page**

7.1 Configuration Editor....7-1
7.2 Create a New Configuration....7-2
7.3 Calendar Tool....7-2
7.4 Configuration Editor – Edit Project List Option from Projects Menu....7-3
7.5 Project Selector Dialog Box....7-4
7.6 Configuration Notes Dialog Box....7-5
7.7 Configuration Save As... Dialog Box....7-5
7.8 Confirm Delete of a Configuration....7-6
7.9 List of Configurations Report....7-7

Chapter 7

Creating Watershed Configurations

Once you have added all of the Projects and Computation Points needed for the watershed, you will need to create one or more Configurations. A Configuration is a specific physical arrangement of projects and computation points that will be modeled for the study of the watershed. **Watershed Configurations** are defined within the **Watershed Setup Module**.

ResSim provides enough flexibility to create Configurations for use in both real-time and planning contexts. ResSim creates a "superset" of all configurations (named **Study**) that contains all of the projects and computation points defined for the watershed. Additional Configurations you create reflect particular watershed conditions. For example, you might create Configurations for *Existing Condition* and *Future Condition – 2030*.

When you create additional Configurations, you can associate projects with specific Configurations, or add and remove them from the list of projects associated with a particular Configuration. You make Configuration associations with Alternatives, as described in Chapter 13.

7.1 Adding Watershed Configurations

Watershed Configurations are added and edited within the **Watershed Setup Module**. To add a Configuration:

1. Lock the configuration.
2. From the **Watershed** menu, click **Configuration Editor**. The **Configuration Editor** (Figure 7.1) will open.



Figure 7.1 Configuration Editor

3. In the **Configuration** menu, click **New**. The **Create a New Configuration** dialog box (Figure 7.2) will open.



Figure 7.2 Create a New Configuration

4. Enter the **Name** (required) and **Description** (optional).
5. The Configuration **Time Step** is only used when ResSim is operated as part of the Corps Water Management System (CWMS) software package, but it is required even when using ResSim as standalone software. From the **Time Step** list, select a computation time step interval for the configuration.
6. Click **OK** to close the Create a New Configuration dialog box.
7. The name of the new configuration will appear in the **Name** list of the **Configuration Editor**, along with its defined **Time Step**.
8. Any project flagged as an Existing project (see Chapter 6, Section 6.1.1), before you defined the new Configuration, will automatically be included in the table. To add projects (that are not flagged as Existing) to the configuration refer to Sections 7.2 and 7.2.1.
9. Once you have created the new Configuration, you can also *optionally* associate a **Date** with the Configuration. The **Base Date** field is used by some HEC applications (e.g., HEC-FIA), particularly in a planning context. You can either directly type the date into the field in the appropriate format (e.g., 01Feb2002), or use the **Calendar Tool** (Figure 7.3).

   To use the Calendar tool:

   - In the **Configuration Editor**, click on the … button to the right of the **Base Date** field. The **Calendar Tool** will appear.
   - Select the month and year by clicking the left and right arrow buttons to navigate backwards and forwards. Select the day by clicking on the appropriate day button.
   - Click **OK** to close the Calendar tool.

Figure 7.3 Calendar Tool

10. When you are done creating the new Configuration, Click **OK** to close the Configuration Editor.

7.2 Adding and Removing Projects from Configurations

As you set up your watershed and manage it over time, you may need to add new Projects to, or remove Projects from, Configurations you have created. To do this:

1. Select the **Configuration** you want to edit from the **Configurations** list on the toolbar.
2. Lock the configuration.
3. Open the **Configuration Editor** from the **Watershed** menu.
4. From the **Projects** menu, select **Edit Project List**, as shown in Figure 7.4.



Figure 7.4 Configuration Editor – Edit Project List Option from Projects Menu

5. The **Project Selector** dialog box (Figure 7.5) will open. The Project Selector displays the Configuration name and description for reference. The left pane contains all **Available Projects** not already associated with the Configuration (in this example, two projects, Channel and ChannelMod). The **Projects in Configuration** pane on the right lists all Projects currently

associated with the Configuration. Between the two panes are four buttons that enable you to add and remove projects of the Configuration by moving Projects from one pane to the other.



Figure 7.5 Project Selector Dialog Box

7.2.1 Adding Projects to a Configuration

To add Projects to an existing Configuration:

1. To add *individual* Projects, click on the Project's name in the **Available Projects** list (Figure 7.5) to select it, and then click the **Add** button to move it to the **Projects in Configuration** list.
2. To add *all* of the **Available Projects** to a Configuration, click the **Add All** button.
3. Click **OK** to save your changes and close the Project Selector dialog box.

7.2.2 Removing Projects from a Configuration

To remove Projects from an existing Configuration:

1. To remove *individual* Projects, click on the Project's name in the **Projects in Configuration** list (Figure 7.5) to select it, and then click the **Remove** button to move it to the **Available Projects** list.
2. To remove *all* of the **Projects in Configuration** from a Configuration, click the **Remove All** button.
3. Click **OK** to save your changes and close the Project Selector dialog box.

7.3 Adding Configuration Notes

Project notes within a Configuration are any comments that pertain specifically to a project in a particular Configuration. To **Add** or **Edit** project notes within a Configuration:

1. Select a project row in the **Configuration Editor**. If you do not select a project in the Configuration Editor before selecting the Project Notes menu item, you are alerted to select a project from the list.
2. Choose **Project Notes** from the **Edit** menu. The **Configuration Notes** dialog opens (Figure 7.6).



Figure 7.6 Configuration Notes Dialog Box

3. When the **Configuration Notes** dialog opens, enter any Configuration-specific notes as needed.
4. Click **OK** to close the Configuration Notes dialog box.

7.4 Making a Copy of a Configuration

Sometimes you might want to make an exact copy of an existing configuration and then make some changes to it so you have a different configuration. To make a copy of a configuration:

1. On the **Configuration Editor** (see Figure 7.1), from the **Name** list, select a configuration that you wish to copy.
2. From the **Configuration** menu, click **Save As...**, and the **Save As** dialog box (Figure 7.7) opens.



Figure 7.7 Configuration Save As... Dialog Box

3. The **Name** box contains the name of the selected configuration. Enter a new name in the **Name** box, and replace the description in the **Description** box.
4. Click **OK** to close the **Save As** dialog box. In the **Name** list on the **Configuration Editor** the new configuration is included.

7.5 Deleting a Configuration

To delete a configuration:

1. On the **Configuration Editor** (see Figure 7.1), from the **Name** list, select the Configuration that you want to delete.
2. From the **Configuration** menu, select **Delete.**
3. A warning message (Figure 7.8) will open asking you whether you really want to delete the selected configuration. Click **Yes**, the warning message will close and the configuration name will no longer appear in the **Name** list on the **Configuration Editor**.



Figure 7.8 Confirm Delete of a Configuration

7.6 Saving Configuration Data

To save the data you have entered for a Configuration, from the **Watershed** menu, click **Save Configuration**. This command will cause the program to save all configuration specific data.

7.7 Listing Configurations

Once you have all of your configurations entered, you might like to review the configurations in your watershed. From the **Watershed Setup Module** there is a report that contains this information.

To view the List of All Configurations:

1. You must be in the **Watershed Setup Module**. On the **Module** list, click **Watershed Setup**.
2. From the **Reports** menu, choose **List of All Configurations**, and the **List of Configurations** dialog box (Figure 7.9) will open.



Figure 7.9 List of Configurations Report

3. This report provides a list of configurations that have been input for the watershed. The list includes the **Name** and **Description,** along with the **Time Step** and **Base Date** (if entered) for each Configuration.
4. From the **File** menu, you can send the report to a printer, or you can export the report to an ASCII file. See Appendix F, Section F.4 for more details about printing and exporting tabulated data.
5. Click **Close** to close the **List of Configurations** report.

Chapter 8

Developing a Reservoir Network

Table of Contents

Section **Page**

8 Developing a Reservoir Network
8.1 Recognizing Reservoir Network Screen Components 8-2
8.1.1 Menu Bar 8-3
8.1.2 Network, Configuration, and Lock/Unlock 8-5
8.1.3 Map (Mouse) Tools 8-5
8.1.4 Display Area 8-6
8.2 Defining a Reservoir Network 8-7
8.2.1 Creating a New Reservoir Network 8-7
8.2.2 Opening an Existing Reservoir Network 8-8
8.3 Making the Network Editable 8-8
8.4 Adding Routing Reaches 8-9
8.4.1 Drawing Routing Reaches 8-9
8.4.2 Renaming Routing Reaches 8-10
8.4.3 Deleting Routing Reaches 8-10
8.5 Viewing Network Reports 8-11
8.5.1 Viewing the Reservoir List 8-11
8.5.2 Viewing the Reach List 8-11
8.5.3 Viewing the Junction List 8-12
8.5.4 Viewing the Diversion List 8-12
8.5.5 Viewing Advanced Reports 8-13
8.6 Updating a Reservoir Network 8-14

List of Figures

Figure Number **Page**

8.1 Reservoir Network Module Main Window 8-2
8.2 File Menu 8-3
8.3 Edit Menu 8-3
8.4 View Menu 8-3
8.5 Network Menu 8-4
8.6 Alternative Menu 8-4
8.7 Reports Menu 8-4
8.8 Tools Menu 8-4
8.9 Help Menu 8-4

List of Figures (continued)

Figure Number **Page**

8.10 Network, Configuration, and Lock/Unlock 8-5
8.11 Create New Reservoir Network Dialog Box 8-7
8.12 Open Reservoir Network Dialog Box..... 8-8
8.13 Rename Reach Dialog Box 8-10
8.14 Confirm Delete Reach Dialog Box..... 8-10
8.15 Reservoir Network Reports: Reservoir List 8-11
8.16 Reservoir Network Reports: Reach List 8-11
8.17 Reservoir Network Reports: Junction List 8-12
8.18 Reservoir Network Reports: Diversion List..... 8-12
8.19 Reservoir Network Reports: Advanced -- Network Summary 8-13
8.20 Reservoir Network Reports: Advanced -- Node List..... 8-14
8.21 Watershed Setup Module, Watershed Menu, Save Configuration before Updating Network 8-14
8.22 Reservoir Network Module, Network Menu, Update Network from Configuration 8-15

Chapter 8

Developing a Reservoir Network

A reservoir network represents a collection of watershed elements connected by routing reaches. Elements created in the Watershed Setup Module belong to specific watershed configurations, and when you create a reservoir network, it references one of those configurations.

The computation points defined for a configuration in the Watershed Setup Module automatically become junctions in the Reservoir Network Module. Your primary task in developing a reservoir network is to connect the junctions with routing reaches between junctions.

This chapter provides an overview of the Reservoir Network Module's screen components and describes the processes for creating a new reservoir network, opening an existing reservoir network, making a network editable, and adding routing reaches. ResSim also allows you to add additional elements to a reservoir network.

After you have established your reservoir network connectivity, you will need to edit Junction, Reach, and Diversion data (see Chapter 9), define and edit the Physical components of Reservoirs in your network (see Chapter 10), define Reservoir Operations data (see Chapter 11), define Reservoir Systems (see Chapter 12), and define Alternatives (see Chapter 13). These steps will prepare your reservoir network to run Simulations (see Chapter 14).

8.1 Recognizing Reservoir Network Screen Components

The **Reservoir Network Module** (Figure 8.1) provides the tools you will need to develop the connectivity of your reservoir network as well as enter and edit physical and operations data. What follows is a discussion of the components and features of the Reservoir Network Module.



Figure 8.1 Reservoir Network Module Main Window

8.1.1 Menu Bar

The following is an overview of the Reservoir Network Module's Menu Bar tools, which allow you to create and edit the connectivity of your reservoir network. The tools specific to this module will be described in more detail in the context of particular tasks later in this chapter.

The **File** menu (Figure 8.2) allows you to **Open** an existing watershed, **Save** a watershed, **Save** the Display Area (Map), and **Exit** ResSim. Your most-recently-used watersheds are listed at the bottom of the File menu.



Figure 8.2 File Menu

The **Edit** menu (Figure 8.3) provides access to the ResSim editors for **Reservoirs**, **Reaches**, **Junctions**, **Diversions**, and **Reservoir Systems**. You must select the **Allow Network Editing** command to access the editors.



Figure 8.3 Edit Menu

In the **View** menu (Figure 8.4) select **Zoom to All** to restore your watershed map view to full size. **Layers** opens the Layer Selector dialog box. **Unit System** allows you to customize the display (view) settings for your watershed. If a dialog or editor window is open but inactive, **Restore Windows** brings the dialog or editor window to the front as the active window.



Figure 8.4 View Menu

The **Network** menu (Figure 8.5) is unique to the Reservoir Network Module. It allows you to create a **New** network, **Open** an existing network, **Save** a network or **Save As** a new network, or **Rename** a network. You can also **Update Network from Configuration** and **Delete Networks**.



Figure 8.5 Network Menu

The **Alternative** menu (Figure 8.6), also available in the Simulation Module, provides access to the **Alternative Editor**.

Figure 8.6 Alternative Menu

The **Reports** menu (Figure 8.7) provides access to the **Reservoir List**, **Reach List**, **Junction List**, and **Diversion List**. Also, two **Advanced** reports are available: the **Network Summary** and the **Node List** reports.



Figure 8.7 Reports Menu

As in the other modules, the **Tools** menu (Figure 8.8) provides access to **Hec-DssVue** and to **Scripts**. **Options** allows you specify Model Directories, Cache Directory, Compute Display, Debug Levels, General information (including whether to show a confirmation when exiting the program and whether to reload last watershed at startup of program), and Fonts. **Information** provides details about client, user, and watershed settings as well as server and system properties.

Figure 8.8 Tools Menu

The **Help** menu (Figure 8.9) displays information about the current version of ResSim. **About** indicates the version, revision and build numbers.



Figure 8.9 Help Menu

8.1.2 Network, Configuration, and Lock/Unlock

In the Reservoir Network Module, your current **Reservoir Network** and **Configuration**, along with the **Lock/Unlock** icon, are displayed below the Menu Bar and to the right of the Module List, as shown in Figure 8.10.

Figure 8.10 Network, Configuration, and Lock/Unlock

The **Configuration** indicates which configuration the current **Network** is based on. As will be described in Section 8.2, you select the Configuration when you setup the Network (using the **Network** menu).

The **Lock/Unlock** icon indicates whether or not the Network is locked and available for editing. You can lock and unlock the Network by clicking on the icon or by selecting or deselecting **Allow Editing** in the **Edit** menu.

8.1.3 Map (Mouse) Tools

The **Map (Mouse) Tools**, which appear in the toolbar on the left side of the ResSim screen, allow you to interact with objects in the map display. The Reservoir Network Module has three standard Map Tools and five network connectivity tools that allow you to establish the connectivity of your reservoir network.

Pointer Tool
Right-click with the Pointer Tool to select and access a shortcut menu for any schematic element within your map display. The Pointer Tool is available in all ResSim modules.

Zoom Tool
The Zoom Tool allows you to zoom in and out of the display area in all modules. To zoom in, hold the left mouse button down and outline the area you want to enlarge. To zoom out, click the right mouse button. Zooming out using the right click button zooms out by a factor of two, positioning the clicked location at the center of the screen. The Zoom Tool is available in all ResSim modules.

Pan Tool
After you have zoomed in with the Zoom Tool, you can use the Pan Tool to view watershed areas that fall outside of the ResSim window borders. The Pan Tool is available in all ResSim modules.

Reservoir Tool
With the Reservoir Tool, you can add reservoirs to your reservoir network. You can also edit reservoir properties, rename, and delete reservoirs using commands in the shortcut menu.

Diverted Outlet Tool
The Diverted Outlet Tool allows you to create a diverted outlet from a reservoir in your network. The shortcut menu for this tool provides access to the Reservoir Editor and also allows you to rename and delete a diverted outlet.

Reach Tool
Use the Reach Tool to draw routing reaches (from *upstream* to *downstream*) to connect the junctions on the stream alignment. You can also edit reach properties, rename, break, and delete reaches using commands in the shortcut menu.

Junction Tool
The Junction Tool allows you to manually insert junctions in your reservoir network. The shortcut menu for this tool allows you to edit junction properties, rename and delete junctions.

Diversion Tool
With the Diversion Tool you can add diversions to your reservoir network. You can also edit diversion properties, rename, delete, and disconnect outflow of diversion reaches using commands in the shortcut menu.

8.1.4 Display Area

In the Reservoir Network Module, the display area contains the reservoir network connectivity you construct, along with the map layers, stream alignment, reservoirs and computation points you have established in the Watershed Setup Module for the current network's configuration. Any other time-series icons, projects, and impact areas you established in the Watershed Setup Module will not appear.

Using the Map (Mouse) Tools to access shortcut menus, you can open data editors as well as rename and delete elements in your reservoir network directly from the display area.

8.2 Defining a Reservoir Network

With a stream alignment in place and one or more configurations defined, you can create a network of reservoirs and routing reaches. This process involves defining a new network and then adding routing reaches.

8.2.1 Creating a New Reservoir Network

When you create a new reservoir network, you are defining which elements will be included in your network by selecting the appropriate watershed configuration. Once you have created your network, you can add additional elements. Remember, however, that any additional elements you add will not be available for use in other networks. If you want the additional elements to be available for other networks, you will need to go back to the Watershed Setup Module and add the new elements to the appropriate configuration, then return to the Reservoir Network Module to create your reservoir network using the updated configuration (see Section 8.6, "Updating a Reservoir Network").

To create a new reservoir network:

1. From the **Network** menu, select **New**. The **Create New Reservoir Network** dialog box will appear (Figure 8.11).



Figure 8.11 Create New Reservoir Network Dialog Box

2. Specify a **Name** for the network and enter a **Description**. You can click the ... button to access a larger text field for your description.
3. From the **Configuration** list, choose the configuration on which this network will be based.
4. Click **New**.

The **Create New Reservoir Network** dialog box will close, and you will see the name of your new network and its configuration displayed below the Menu Bar, to the right of the Module List (see Section 8.1.2 above).

In the display area, ResSim will automatically create the reservoirs and computation points that were part of the selected configuration as elements in the new Reservoir Network. Reservoirs transfer directly, whereas computation points appear as Junctions.

8.2.2 Opening an Existing Reservoir Network

To open an existing Reservoir Network for editing:

1. From the **Network** menu, select **Open**. The **Open Reservoir Network** dialog box will appear (Figure 8.12).



Figure 8.12 Open Reservoir Network Dialog Box

2. Select the **Reservoir Network** you want by clicking on it.
3. Click **Open**.

The Open Reservoir Network dialog box will close, and you will see the name of your network and its configuration displayed below the Menu Bar, to the right of the Module List (see Section 8.1.2 above).

8.3 Making the Network Editable

Before you can begin editing your reservoir network, you must ensure that the network is editable ("locked"). To do so, select **Allow Network Editing** from the **Edit** menu or click the **Lock/Unlock** button .

8.4 Adding Routing Reaches

Routing reaches are elements that establish the connectivity of the reservoir network schematic. By adding a routing reach between two junctions, you can connect the reservoir network so that water will transverse through the routing reach from *upstream* to *downstream*.

8.4.1 Drawing Routing Reaches

Routing Reaches are drawn from *upstream* to *downstream*. You connect two adjacent junctions (typically, computation points added to the network's Configuration in the Watershed Setup Module) by drawing a routing reach.

To draw routing reaches:

1. Select the **Reach Tool** .
2. Point to the *upstream* junction at the upstream end of the reach.
3. Hold down the **CTRL** key and click on the junction to start the *upstream* end of the reach.
4. Release the **CTRL** key and move the mouse pointer along the stream alignment and click on the *downstream* junction.

Routing reaches automatically conform to the stream alignment. You can connect routing reaches to existing junctions; otherwise, if you begin and/or end a reach elsewhere on the stream alignment, ResSim will create new junctions at both/either end of the reach.

ResSim will automatically constrain a new reach between existing junctions (e.g., will not allow a reach to be drawn past an existing junction). If the reach appears to draw past a junction, then the junction is not on the stream you think it's on. This can occur if the computation point (that the junction is based on) is not initially placed on the appropriate stream. To solve this situation, go back to the Watershed Setup Module and revise the location of the computation point (you may need to delete and recreate the computation point to be on the appropriate stream). After saving your watershed configuration, change to the Reservoir Network Module and select **Update Network from Configuration** from the **Network** menu. See Section 8.6, "Updating a Reservoir Network", for additional information for updating networks.

Additionally, you may not connect tributaries to the middle of a reach; tributaries must connect to a junction.

8.4.2 Renaming Routing Reaches

ResSim automatically names routing reaches according to the names of the upstream and downstream junctions. To rename a reach component:

1. Select the **Reach Tool** .
2. Right-click on the routing reach to be renamed.
3. Select **Rename** from the shortcut menu. The **Rename Reach** dialog box will appear (Figure 8.13), allowing you to type in a new name.
4. Type in the new name and optional description.
5. Click **OK** to close the Rename Reach dialog box.

Figure 8.13 Rename Reach Dialog Box

The new name will now appear as a label in the map display.

8.4.3 Deleting Routing Reaches

To delete routing reaches:

1. Select the **Reach Tool** .
2. Right-click on the routing reach to be deleted.
3. Select **Delete** from the shortcut menu. A **Confirm Delete** dialog box will appear (Figure 8.14).
4. Click **Yes** if you are sure about the deletion.

Figure 8.14 Confirm Delete Reach Dialog Box

The routing reach will no longer appear in the map display.

8.5 Viewing Network Reports

In the Reservoir Network Module, the **Reports** menu allows you to access summary reports pertinent to the elements in your network. These reports summarize your reservoirs, routing reaches, junctions, and diversions. In addition, advanced reports of your network connectivity are also available.

8.5.1 Viewing the Reservoir List

The **Reservoir List** (Figure 8.15) displays the names and descriptions of all reservoirs in your network. For information about printing and exporting options available from the report's **Report** menu, see Appendix F.



Figure 8.15 Reservoir Network Reports: Reservoir List

8.5.2 Viewing the Reach List

The **Reach List** (Figure 8.16) displays the names and descriptions of all reaches in your network. For information about printing and exporting options available from the report's **Report** menu, see Appendix F.



Figure 8.16 Reservoir Network Reports: Reach List

8.5.3 Viewing the Junction List

The **Junction List** (Figure 8.17) displays the names and descriptions of all junctions in your network. For information about printing and exporting options available from the report's **Report** menu, see Appendix F.



Figure 8.17 Reservoir Network Reports: Junction List

8.5.4 Viewing the Diversion List

The **Diversion List** (Figure 8.18) displays the names and descriptions of all diversions in your network. For information about printing and exporting options available from the report's **Report** menu, see Appendix F.



Figure 8.18 Reservoir Network Reports: Diversion List

8.5.5 Viewing Advanced Reports

Two advanced reports are available from the **Reports** menu. The first report is the **Network Summary** (Figure 8.19). This report provides a connectivity summary of all of the elements/nodes in your reservoir network. Details include the Element ID, Name, Function/Upstream Element, and Parent/Downstream Element.

For information about printing and exporting options available from the report's **Report** menu, see Appendix F.



Figure 8.19 Reservoir Network Reports: Advanced -- Network Summary

The second advanced report is the **Node List** (Figure 8.20). This report provides a summary of all nodes in your reservoir network. Details include the Node ID, Name, Key String, Upstream Element and Downstream Element.



Node ID	Name	KeyStr	Upstrm Elem	Dnstrm Elem
0	Beech Ck Station	~E0	Beech Ck Station	RR_Beech-MillH
1	Milesburg Jct	~E1	Milesburg Jct	RR_Miles-Sayer
2	Mill Hall	~E2	Mill Hall	RR_MillH-Fishi
3	Marsh Ck Jct	~E3	Marsh Ck Jct	RR_Marsh-Beech
4	Bald Eagle Total	~E4	Bald Eagle Total	
7	Fishing Ck Jct	~E7	Fishing Ck Jct	RR_Fishi-beTot
8	Sayers Inflow Jct	~E6	Sayers Inflow Jct	Sayers-Pool
9	Sayers-Dam Tailwater	~E11	Sayers-Dam Tailw...	Blanchard
10	Sayers-Dam IN	~E12~IN	Sayers-Pool	Sayers-Dam
11	Sayers-Dam	~E12	Sayers-Dam	Sayers-Dam Tailw...
12	RR_Miles-Sayer	~E13	RR_Miles-Sayer	Sayers Inflow Jct
13	Blanchard	~E5	Blanchard	RR_Blanc-Marsh
14	RR_Blanc-Marsh	~E14	RR_Blanc-Marsh	Marsh Ck Jct
15	RR_Marsh-Beech	~E15	RR_Marsh-Beech	Beech Ck Station
16	RR_Beech-MillH	~E16	RR_Beech-MillH	Mill Hall
17	RR_MillH-Fishi	~E17	RR_MillH-Fishi	Fishing Ck Jct
18	RR_Fishi-beTot	~E18	RR_Fishi-beTot	Bald Eagle Total
19	Sayers-SayersSpillway Tailwater	~E21	Sayers-SayersSpil...	Sayers-SayersSpil...
20	Sayers-SayersSpillway Reach	~E20	Sayers-SayersSpil...	Marsh Ck Jct
21	Milesburg Jct MILESBURG HW	~E1~MILESBURG ...		Milesburg Jct
23	Marsh Ck Jct MARSH CREEK HW	~E3~MARSH CRE...		Marsh Ck Jct

Figure 8.20 Reservoir Network Reports: Advanced -- Node List

For information about printing and exporting options available from the report's **Report** menu, see Appendix F.

8.6 Updating a Reservoir Network

In the Watershed Setup Module, if you make changes (e.g., add, delete, or move elements) to the watershed configuration your network is based on, you need to update your Reservoir Network to include those changes. First, in the **Watershed Setup** module, from the **Watershed** menu, select **Save Configuration** (see Figure 8.21).



Figure 8.21 Watershed Setup Module, Watershed Menu, Save Configuration before Updating Network

Next, in the **Reservoir Network** module, with the network to be updated shown in the display area, select **Update Network from Configuration** from the **Network** menu (see Figure 8.22).



Figure 8.22 Reservoir Network Module, Network Menu, Update Network from Configuration

After the network has been updated, you should see the revisions in the display area.

You will need to update each Reservoir Network that is based on the revised watershed Configuration.

Chapter 9

Editing Junction, Reach, and Diversion Data

Table of Contents

Section **Page**

9 Editing Junction, Reach, and Diversion Data
9.1 Editing Junction Properties....9-1
9.1.1 Junction Editor: Info Tab....9-2
9.1.2 Junction Editor: Local Flow Tab....9-3
9.1.3 Junction Editor: Rating Curve Tab....9-4
9.1.4 Junction Editor: Observed Data Tab....9-5
9.2 Editing Reach Properties....9-6
9.2.1 Reach Editor: Routing Tab....9-7
9.2.1.1 Coefficient Routing Method....9-7
9.2.1.2 Muskingum Routing Method....9-8
9.2.1.3 Muskingum-Cunge 8-pt Channel Routing Method....9-9
9.2.1.4 Muskingum-Cunge Prismatic Channel Routing Method....9-11
9.2.1.5 Modified Puls Routing Method....9-13
9.2.1.6 SSARR Routing Method....9-14
9.2.2 Reach Editor: Losses Tab....9-16
9.2.3 Reach Editor: Observed Data Tab....9-17
9.3 Editing Diversion Properties....9-18
9.3.1 Diversion Editor: Diversion Tab....9-19
9.3.1.1 Constant Diversion Method....9-19
9.3.1.2 Monthly Varying Diversion Method....9-20
9.3.1.3 Seasonal Diversion Method....9-21
9.3.1.4 Function of Flow Diversion Method....9-22
9.3.1.5 Function of Pool Elevation Diversion Method....9-23
9.3.1.6 Time-Series Diversion Method....9-24
9.3.2 Diversion Editor: Routing Tab....9-25
9.3.3 Diversion Editor: Losses Tab....9-25
9.3.4 Diversion Editor: Observed Data Tab....9-26

List of Figures

Figure Number **Page**

9.1 Junction Editor: Info Tab 9-2
9.2 Junction Editor: Local Flow Tab 9-3
9.3 Junction Editor: Rating Curve Tab 9-4
9.4 Junction Editor: Observed Data Tab 9-5
9.5 Reach Editor 9-6
9.6 Reach Editor: Coefficient Routing Method 9-7
9.7 Reach Editor: Muskingum Routing Method 9-8
9.8 Reach Editor: Muskingum-Cunge 8-pt Channel Routing Method 9-9
9.9 Reach Editor: Muskingum-Cunge Prismatic Channel Routing Method 9-11
9.10 Reach Editor: Modified Puls Routing Method 9-13
9.11 Reach Editor: SSARR Routing Method 9-14
9.12 Reach Editor: Losses Tab 9-16
9.13 Reach Editor: Observed Data Tab 9-17
9.14 Diversion Editor 9-18
9.15 Diversion Editor: Constant Diversion Method 9-19
9.16 Diversion Editor: Monthly Varying Diversion Method 9-20
9.17 Diversion Editor: Seasonal Diversion Method 9-21
9.18 Diversion Editor: Function of Flow Diversion Method 9-22
9.19 Diversion Editor: Function of Pool Elevation Diversion Method 9-23
9.20 Diversion Editor: Time-Series Diversion Method 9-24
9.21 Diversion Editor: Losses Tab 9-25
9.22 Diversion Editor: Observed Data Tab 9-26

Chapter 9

Editing Junction, Reach, and Diversion Data

Once you have established the connectivity of your Reservoir Network (see Chapter 8), you can define and edit the properties of elements in the network. You will need to specify parameters for all junctions, reaches, diversions, and reservoirs using ResSim's specialized editors. You will also need to edit the physical and operations data for reservoirs, as described in Chapters 10-11.

This chapter explains how to enter and edit data for junctions, reaches, and diversions. Refer to Chapter 8 for developing a Reservoir Network within the **Reservoir Network Module**.

9.1 Editing Junction Properties

To edit junction data, select the **Junction Tool** and right-click on a junction. From the shortcut menu, select **Edit Junction Properties**. The **Junction Editor** will open.

The **Name** field at the top of the editor contains a list of all of the junctions in your reservoir network, with the name of the selected junction displayed. You can access all of the junctions both from this list and by using the VCR-style buttons to navigate through the available junctions.

The Junction Editor has four tabs that allow you to edit junction information (**Info**), **Local Flow**, **Rating Curve**, and **Observed Data**, as described in the following sections.

9.1.1 Junction Editor: Info Tab

The **Info** tab (Figure 9.1) displays the description, stream station, stream, and tributaries you have defined within the Watershed Setup Module and during the process of creating your reservoir network within the Reservoir Network Module.



Figure 9.1 Junction Editor: Info Tab

The **Stream** and **Tributaries** fields are not editable, but you may revise the junction **Description** and **Stream Station**. If the historic flow for a junction is available for the hindcast (lookback) period, then click on the **Outflow known during hindcast** box. An entry will appear in the time-series table that you will complete during the creation of an Alternative (see Chapter 13).

You may also choose the position of the name label in your map display from the options in the **Label Position** field.

To edit properties for other junctions without exiting the Junction Editor, click the **Apply** button and then select another junction from the **Name** list or use the navigator buttons.

9.1.2 Junction Editor: Local Flow Tab

On the **Local Flow** tab (Figure 9.2) of the Junction Editor, you can input a **Name** and **Factor** in the table for each external flow entering the junction.



Figure 9.2 Junction Editor: Local Flow Tab

- **Name:** The name you enter will appear during the Alternative definition to identify the local flow for time-series mapping (see Chapter 13).
- **Factor:** The factor value is available to increase or decrease the local flow hydrographs. If you enter a value of 1.0, then the local flow will be equal to the hydrograph reference.

You must define flows for headwater junctions. Flows are optional at other junctions.

To edit properties for other junctions without exiting the Junction Editor, click the **Apply** button and then select another junction from the **Name** list or use the navigator buttons.

9.1.3 Junction Editor: Rating Curve Tab

The **Rating Curve** tab (Figure 9.3) is optional. However, if you need stages calculated at a junction, you can enter **Stage** and **Discharge** values for the junction here. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 9.3 Junction Editor: Rating Curve Tab

- **Stage:** Enter Stage values (in meters or feet) that correspond to the Discharge values.
- **Discharge:** Enter Discharge (flow) values (in cms or cfs) that correspond to the Stage values.

To edit properties for other junctions without exiting the Junction Editor, click the **Apply** button and then select another junction from the **Name** list or use the navigator buttons.

9.1.4 Junction Editor: Observed Data Tab

Use the **Observed Data** tab (Figure 9.4) to indicate that observed data is available for comparison purposes. If the **Observed** box in the table is checked (as shown in Figure 9.4), then there will be a corresponding entry in the Observed Time-Series mapping table when you create an Alternative (see Chapter 13).



Figure 9.4 Junction Editor: Observed Data Tab

To edit properties for other junctions without exiting the Junction Editor, click the **Apply** button and then select another junction from the **Name** list or use the navigator buttons.

9.2 Editing Reach Properties

To edit routing reach data, select the **Reach Tool** and right-click on a routing reach. From the shortcut menu, select **Edit Reach Properties**. The **Reach Editor** will open (Figure 9.5).



Figure 9.5 Reach Editor

The **Reach Name** field at the top of the editor contains a list of all of the routing reaches in your reservoir network, with the name of the selected reach displayed. You can access all of the reaches from this list or by using the VCR-style buttons to navigate through the available reaches.

Below the Reach Name list is the **Description** of the current reach; this field is editable.

The Reach Editor has three tabs that allow you to edit **Routing** methods, **Losses**, and **Observed Data**, as described in the following sections.

9.2.1 Reach Editor: Routing Tab

The Reach Editor's **Routing** tab allows you to choose from six routing methods: Coefficient Routing, Muskingum, Muskingum-Cunge 8-pt Channel, Muskingum-Cunge Prismatic Channel, Modified Puls, and SSARR Routing, each method with its own set of parameters. If there is no lag or translation of the hydrograph through the reach, you can select **Null Routing**. Select the routing method for the reach from the **Method** list. The appropriate fields for data entry will appear according to the method you have selected.

9.2.1.1 Coefficient Routing Method

For the **Coefficient Routing** method (Figure 9.6), you will need to enter coefficients for each time step. Each coefficient equates to the fraction of the flow entering the reach that will reach the downstream end at the end of each time step in the table. The values in the table must sum up to 1.



Figure 9.6 Reach Editor: Coefficient Routing Method

If you enter a 1 in the first row and leave the rest of the table blank, you have effectively described null or no-route routing. This means that 100% of the flow entering the reach instantaneously leaves the reach in that time step.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.1.2 Muskingum Routing Method

The **Muskingum** routing method (Figure 9.7) requires you to enter values for **Muskingum K** (in hours) and **Muskingum X**. You will also need to specify the **Number of Subreaches**.



Figure 9.7 Reach Editor: Muskingum Routing Method

- **Muskingum K**: Enter the number of hours (travel time) for the reach, *i.e.*, how long it takes for a drop of water that enters the reach to exit the reach.
- **Muskingum X:** Enter the attenuation coefficient (from 0.0 to 0.5). A value of 0.0 indicates maximum attenuation of the hydrograph through the routing reach. A value of 0.5 indicates a "direct translation" of the hydrograph through the reach.
- **Number of Subreaches:** Number of steps (subreaches) applicable for the routing reach. This parameter should be approximately equal to travel time divided by the computation interval.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.1.3 Muskingum-Cunge 8-pt Channel Routing Method

The **Muskingum-Cunge 8-pt Channel** routing method (Figure 9.8) uses a representative eight-point channel cross section to perform the Muskingum-Cunge hydrologic routing method. This method requires that you enter the **Channel Length** and **Channel Slope**, as well as eight **Station** and **Elevation** values to describe the cross section. The cross section displays in both a generalized illustration of a cross section and a mini-plot of the data you enter and can be viewed in full size when you double-click on it. Other parameters you will need to enter are **Manning's n Values** for the **Left Overbank**, **Main Channel**, and **Right Overbank**. The **Default Reference Flow** value is used to compute the celerity for the reach.



Figure 9.8 Reach Editor: Muskingum-Cunge 8-pt Channel Routing Method

- **Channel Length:** Enter the length of the routing reach.
- **Channel Slope:** Enter the slope of the routing reach, $\Delta y/\Delta x$.
- **Station:** Enter the horizontal position of a point used to describe a stream cross section.
- **Elevation:** Enter the vertical position of a point used to describe a stream cross section.
- **Manning's n Values:** Enter the unitless loss coefficients for **Left Overbank**, **Main Channel**, and **Right Overbank** to be used in the normal depth calculations of the cross section.
- **Default Reference Flow:** The flow value is used to compute the celerity (and thus the travel time) for the reach. If the travel time is less than the time-step size, the reach is divided into subreaches for the computation. Travel time (and thus the number of subreaches) is greater for low flow; therefore, the reference flow value should approximate the base flow for the reach.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.1.4 Muskingum-Cunge Prismatic Channel Routing Method

The **Muskingum-Cunge Prismatic Channel** method (Figure 9.9) provides two more options for describing the cross section to be used by the Muskingum-Cunge hydrologic routing method. In this method, you can describe the cross section as either a trapezoid or a circle.



Figure 9.9 Reach Editor: Muskingum-Cunge Prismatic Channel Routing Method

For the Muskingum-Cunge Prismatic Channel method, enter the appropriate parameters, described below:

- **Channel Length:** Enter the length of the routing reach.
- **Channel Slope:** Enter the slope of the routing reach, $\Delta y/\Delta x$.
- **Manning's n:** Enter the unitless loss coefficient to be used in the normal depth calculations of the cross section.

- **Channel Shape:** Select either Prismatic (trapezoid) or Circular (pipe).
  - **Prismatic:** This shape is a basic trapezoid with the bottom of the trapezoid less than or equal to the width of the top. When you choose Prismatic as the Channel Shape, you also need to specify the Bottom Width and Side Slope.
    - **Bottom Width:** the width of the bottom of the trapezoidal section.
    - **Side Slope:** the slope of the sides of the trapezoid entered as $\Delta x/\Delta y$.
  - **Circular:** This shape is a simple circle used to represent a pipe or culvert. This method is valid for flow depth up to 0.77*diameter. For depths greater than this, the depth used by the method is held to 0.77*diameter and a warning message is generated. If you choose Circular as the Channel Shape, you also need to specify the Channel Diameter.
    - **Channel Diameter:** Define the size of the circle.

- **Default Reference Flow:** The flow value is used to compute the celerity (and thus the travel time) for the reach. If the travel time is less than the time step size, the reach is divided into subreaches for the computation. Travel time (and thus the number of subreaches) is greater for low flow; therefore, the reference flow value should approximate the base flow for the reach.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.1.5 Modified Puls Routing Method

The **Modified Puls** channel routing method (Figure 9.10) describes the reach as a set of cascading reservoirs, the number of which is specified by the number of subreaches. The outflow from the reach is defined as a function of the storage. An option is available within this method to account for seepage losses within the routing computation. To use this option, check the **With Channel Losses** box and enter the average **Invert Elevation** of the reach, the **Percolation Rate** to describe the seepage, and extend the outflow-storage table by adding associated elevation data.

*If you use the **Channel Losses** option in this method, do not define seepage losses on the losses tab for this reach – you will be double accounting for the seepage losses.*



Figure 9.10 Reach Editor: Modified Puls Routing Method

- **Storage:** Enter monotonically increasing values of storage to describe the storage-outflow relationship needed for this routing method.
- **Outflow:** Enter the outflow values associated with each storage value in the storage-outflow relationship.

- **Elevation:** Enter associated elevation values; ResSim uses these values as extensions to the storage-outflow relationship when you select the **With Channel Losses** option. This column is only available when this option is active.
- **Number of Subreaches:** This parameter is similar to that used in the Muskingum routing method. Enter the reach travel time divided by the computation interval.
- **Invert Elevation:** Enter the average minimum elevation of the channel in this reach.
- **Percolation Rate:** Enter the flow rate identifying the loss of water to the soil/groundwater.
- In the **Select Plot** area, you can choose whether the plot shows **Storage vs. Outflow** or **Storage vs. Elevation**. The plot will reflect the values you enter.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.1.6 SSARR Routing Method

The SSARR routing method (Figure 9.10) describes the channel routing based on the computer program *Streamflow Synthesis & Reservoir Regulation (SSARR)*, from the Corps' Northwestern Division (USACE, 1991).



Figure 9.11 Reach Editor: SSARR Routing Method

The storage in the routing reach is defined by Time of Storage values (T_s), in units of hours. Therefore, the storage is defined like Muskingum K values (described in Section 9.2.1.2). Instead of using Modified Puls storage-outflow, this method uses T_s versus outflow.

An alternative method for defining T_s is by the following equation, which defines T_s as a power function of flow.

$$T_s = \frac{KTS}{Q^n}$$

where:

T_s	=	Time of storage per increment in hours
KTS	=	Constant determined by trial and error or estimated from physical measurements of flow and corresponding routing times.
Q	=	Discharge in cubic meters (or feet) per hour
n	=	Coefficient usually between -1 and 1

As evident from the above equation, T_s is a nonlinear function of discharge except when n = 1. It is possible to use a negative value of n if time of storage increases as discharge increases. According to the SSARR User's Manual, a value of n = 0.2 is reasonable for most streams in the Columbia River Basin.

For the SSARR routing method, enter the appropriate parameters, described below:

- **Time of Storage Method:** Select either the **Use Interpolation Table** or the **TS = KTS/Q**n** method.
- **Outflow** and **Time of Storage:** If the Use Interpolation Table method is selected, enter the outflow and corresponding T_s values.
- **Time of Storage Equation:** If the TS = KTS/Q**n method is selected, enter values for KTS and n.
- **Number of Subreaches:** Number of steps applicable for the routing reach.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.2 Reach Editor: Losses Tab

The **Losses** tab of the Reach Editor (Figure 9.12) provides two options for computing losses in the routing reach: **Constant Seepage** or **Seepage as a function of Flow**. The default is no losses in the reach.



Figure 9.12 Reach Editor: Losses Tab

- **Constant Seepage:** Enter the flow (in cms or cfs) lost to the reach through the soil, non-varying throughout the simulation.
- **Seepage as a function of Flow:** With this option, you can define the loss as a function of the routed flow of the reach. Reach losses are computed after the flow is routed through the reach; therefore, the final outflow from the reach is the routed flow minus the loss.
- **Flow:** Enter a monotonically increasing set of flow values to define the relationship of seepage with respect to flow.
- **Seepage:** Enter the associated seepage values for each flow value in the table, expressed in flow units.

The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.2.3 Reach Editor: Observed Data Tab

Use the **Observed Data** tab (Figure 9.13) to indicate that observed data is available for comparison purposes. If the **Observed** box in the table is checked (as shown in Figure 9.13), then there will be a corresponding entry in the Observed Time-Series mapping table when you create an Alternative (see Chapter 13).



Figure 9.13 Reach Editor: Observed Data Tab

To edit another reach without exiting the Reach Editor, click the **Apply** button and then select another reach from the **Name** list or use the navigator buttons.

9.3 Editing Diversion Properties

To edit diversion data, select the **Diversion Tool** and right-click on a diversion. From the shortcut menu, select **Edit Diversion Properties**. The **Diversion Editor** will open (Figure 9.14).



Figure 9.14 Diversion Editor

The **Name** field at the top of the Editor contains a list of all of the diversions in your reservoir network, with the name of the current diversion displayed. You can access all of the diversions both from this list and by using the VCR-style buttons to navigate through the available diversions.

If the **Computed during UnReg** box is checked, then the diversion will operate during the unregulated flow calculation. If the box is left unchecked, then the unregulated flow will reflect flow conditions without the diversion.

The Diversion Editor has four tabs that allow you to edit diversion information (**Diversion** tab), **Losses**, **Routing**, and **Observed Data**, as described in the following sections.

Note that the **Losses** and **Routing** tabs are available only for diversions that connect to downstream nodes.

9.3.1 Diversion Editor: Diversion Tab

The Diversion Editor's **Diversion** tab allows you to choose from six methods: Constant, Monthly Varying, Seasonal, Function of Flow, Function of Pool Elevation, and Time Series, each with its own parameters. The default method is **Constant**.

Select the diversion method from the **Method** list. The appropriate editing fields will appear according to the method you have selected.

9.3.1.1 Constant Diversion Method

For the **Constant** method (Figure 9.15), you will need to enter a diversion flow value (in the appropriate units of your watershed). This constant value will apply to each period of your simulation.



Figure 9.15 Diversion Editor: Constant Diversion Method

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.1.2 Monthly Varying Diversion Method

For the **Monthly Varying** diversion method (Figure 9.16), you will need to enter the diversion flow value (in the appropriate units of your watershed) corresponding to each month of a year. These monthly values will apply to each year in your simulation.



Figure 9.16 Diversion Editor: Monthly Varying Diversion Method

- **Diversion:** Enter a flow value (in cms or cfs) for each month.

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.1.3 Seasonal Diversion Method

For the **Seasonal** method (Figure 9.17), you will need to enter a **Date** and **Time** along with a corresponding **Diversion** flow value (in the appropriate units of your watershed). The seasonal diversion is applicable for each year of your simulation.



Figure 9.17 Diversion Editor: Seasonal Diversion Method

- **Date:** Enter the Day and Month in the format ddMMM (e.g., 01Jan).
- **Time:** Enter the Hour in the range of 0000–2400.
- **Diversion:** Enter a Flow value in cms or cfs.

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.1.4 Function of Flow Diversion Method

For the **Function of Flow** diversion method (Figure 9.18), you will need to enter a relationship between a junction's net flow and the resulting diverted flow (in the appropriate units of your watershed). The **Flow Location** junction can be selected from the list and need not be the same location as where the diversion occurs. This allows for a diversion to limit or augment flow based on any junction's flow. For a given net **Flow** value entering the diversion element, the **Diversion** flow will be removed from the junction. This relationship applies to your entire Simulation period.



Figure 9.18 Diversion Editor: Function of Flow Diversion Method

- **Flow:** Enter the net flow (in cms or cfs) entering the junction.
- **Diversion:** Enter the flow (in cms or cfs) that is diverted from the junction.

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.1.5 Function of Pool Elevation Diversion Method

For the **Function of Pool Elevation** diversion method (Figure 9.19), you will need to enter a relationship between reservoir elevation and diversion flow (in the appropriate units of your watershed). Also, you will need to select the appropriate reservoir from the **Reservoir** list. When a given **Elevation** at the selected reservoir occurs, then the corresponding **Diversion** flow will be diverted from the junction. Linear interpolation will be made between the elevations (and corresponding diversions) that you enter. This relationship applies to your entire simulation.



Figure 9.19 Diversion Editor: Function of Pool Elevation Diversion Method

- **Elevation:** Enter the reservoir elevation (in meters or feet) on which the diversion is based.
- **Diversion:** Enter the flow (in cms or cfs) that is diverted from the diversion element.

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.1.6 Time-Series Diversion Method

For the **Time-Series** diversion method (Figure 9.20), you only need to select **Time Series** from the **Method** list. An entry for this diversion will appear in the Time-Series mapping table when you create an Alternative (see Chapter 13). The time series of diversion flow values must be in the appropriate units (cms or cfs) of your watershed.



Figure 9.20 Diversion Editor: Time-Series Diversion Method

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.2 Diversion Editor: Routing Tab

For diversions connected to downstream junctions, the Diversion Editor's **Routing** tab allows you to choose from six routing methods: Coefficient Routing, Muskingum, Muskingum-Cunge 8-pt Channel, Muskingum-Cunge Prismatic Channel, Modified Puls, and SSARR routing, each with its own set of parameters. If there is no lag or translation of the hydrograph through the diversion reach, you can select Null Routing (which is the default routing method).

The Routing tab of the Diversion Editor is identical to the Routing tab of the Reach Editor. For details about using the Routing tab, refer to Section 9.2.1.

9.3.3 Diversion Editor: Losses Tab

Available for diversions connected to a downstream junction, the **Losses** tab of the Diversion Editor (Figure 9.21) provides three options for computing losses in the diversion's routing reach: **Return Ratio**, **Constant Seepage**, or **Seepage as a function of Flow**.



Figure 9.21 Diversion Editor: Losses Tab

- **Return Ratio:** Enter a value between 0.0 and 1.0 (the default is 1.0) to indicate how much diversion continues through the diversion to the downstream junction.

- **Constant Seepage:** Enter a seepage value (in cms or cfs) to indicate how much diversion flow will "seep into" the ground and therefore be lost from the system.
- **Seepage as a function of Flow:** Enter a Flow vs. Seepage relationship (in cms or cfs) to indicate how much of the diversion flow is lost from the diversion to the ground.

The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

9.3.4 Diversion Editor: Observed Data Tab

Use the **Observed Data** tab (Figure 9.22) to indicate that observed data is available for comparison purposes. If the **Observed** box in the table is checked, then there will be a corresponding entry in the Observed Time-Series mapping table when you create an Alternative (see Chapter 13).



Figure 9.22 Diversion Editor: Observed Data Tab

To edit another diversion without exiting the Diversion Editor, click the **Apply** button and then select another diversion from the **Diversion Name** list or use the navigator buttons.

Chapter 10

Defining Physical Components of Reservoirs

Table of Contents

Section **Page**

10 Defining Physical Components of Reservoirs
10.1 Accessing the Reservoir Editor 10-2
10.2 Using the Reservoir Editor to Define Physical Components 10-2
10.3 Specifying Physical Components of a Reservoir 10-3
10.4 Specifying Reservoir Pool Losses 10-4
10.5 Defining Physical Features of a Dam 10-4
10.6 Adding Leakage to a Dam 10-5
10.7 Adding Outlet Groups 10-6
10.8 Defining Controlled Outlets 10-7
10.8.1 Adding Controlled Outlets 10-7
10.8.2 Adding a Power Plant to a Controlled Outlet 10-8
10.9 Adding Uncontrolled Outlets 10-9
10.10 Adding Tailwater Elevation 10-10
10.11 Defining Physical Components of a Diverted Outlet 10-11
10.12 Renaming, Deleting, and Removing Reservoir Components 10-12
10.12.1 Renaming Reservoir Components 10-12
10.12.2 Deleting Reservoir Components 10-13
10.12.3 Removing Reservoir Parameters 10-14
10.13 Editing Reservoir Physical Data 10-14
10.14 Editing Pool Physical Data 10-15
10.14.1 Editing Pool Evaporation Data 10-16
10.14.2 Editing Pool Seepage 10-17
10.15 Editing Dam Leakage 10-18
10.16 Editing Controlled Outlet Physical Data 10-19
10.17 Editing Power Plant Physical Data 10-21
10.17.1 Editing Capacity Data for a Power Plant 10-21
10.17.2 Editing Efficiency Data for a Power Plant 10-22
10.17.2.1 Constant Efficiency Method 10-22
10.17.2.2 Function of Reservoir Elevation Efficiency Method 10-23
10.17.2.3 Function of Release Efficiency Method 10-24
10.17.2.4 Function of Operating Head Efficiency Method 10-25
10.17.3 Editing Station Use Data for a Power Plant 10-26
10.17.3.1 Constant Station Use Method 10-26
10.17.3.2 Function of Release Station Use Method .. 10-27

Section (continued) **Page**

10.17.4 Editing Hydraulic Losses Data for a Power Plant..... 10-28
10.17.4.1 Constant Hydraulic Losses Method 10-28
10.17.4.2 Function of Release Hydraulic Losses Method 10-29
10.18 Editing Uncontrolled Outlet Physical Data 10-30
10.19 Editing Tailwater Elevation Physical Data..... 10-31
10.20 Viewing Composite Release Capacity Tables 10-33
10.20.1 Reservoir Composite Release Capacity Table 10-33
10.20.2 Dam Composite Release Capacity Table 10-34
10.20.3 Diverted Outlet Composite Release Capacity Table.... 10-34
10.20.4 Outlet Group Composite Release Capacity Table 10-34
10.21 Reservoir Editor: Observed Data Tab..... 10-35

List of Figures

Figure Number **Page**

10.1 Reservoir Editor: Physical Tab 10-2
10.2 Reservoir Editor, Physical Tab: Default Reservoir Component Tree 10-3
10.3 Reservoir Editor, Physical Tab: Default Reservoir Component Tree with Diverted Outlet 10-3
10.4 Reservoir Editor, Physical Tab: with Pool Losses 10-4
10.5 Reservoir Editor: Pool Menu 10-4
10.6 Reservoir Tree Shortcut Menu: Pool 10-4
10.7 Reservoir Tree: Dam 10-4
10.8 Reservoir Editor, Physical Tab: Dam Menu 10-5
10.9 Reservoir Tree Shortcut Menu: Dam..... 10-5
10.10 Reservoir Tree: Outlet Groups 10-6
10.11 Diverted Outlet Shortcut Menu: Add Outlet Group 10-6
10.12 Reservoir Tree: Controlled Outlets..... 10-7
10.13 Dam Shortcut Menu: Add Controlled Outlet 10-7
10.14 Reservoir Editor, Physical Tab: Outlet Menu - Add Power Plant 10-8
10.15 Controlled Outlet Shortcut Menu: Add Power Plant 10-8
10.16 Reservoir Tree: Uncontrolled Outlets 10-9
10.17 Dam Shortcut Menu: Add Uncontrolled Outlet 10-9
10.18 Reservoir Tree: Tailwater Elevation 10-10
10.19 Dam Shortcut Menu: Add Tailwater Elevation..... 10-10
10.20 Reservoir Tree: Diverted Outlet..... 10-11
10.21 Reservoir Editor: Outlet Menu for Diverted Outlet..... 10-11
10.22 Reservoir Component Shortcut Menu: Rename Component..... 10-12
10.23 Rename Reservoir Component Dialog Box 10-12
10.24 Reservoir Component Shortcut Menu: Delete Component..... 10-13
10.25 Confirm Deletion of Reservoir Component..... 10-13
10.26 Reservoir Parameter Shortcut Menu: Remove Parameter..... 10-14
10.27 Confirm Removal of Reservoir Parameter 10-14

List of Figures (continued)

Figure Number **Page**

10.28 Reservoir Editor: Physical Data--Pool 10-15
10.29 Reservoir Editor: Physical Data--Pool Evaporation 10-16
10.30 Reservoir Editor: Physical Data--Pool Seepage 10-17
10.31 Reservoir Editor: Physical Data--Dam Leakage 10-18
10.32 Controlled Outlet (no Gate Settings) 10-19
10.33 Gate Settings Dialog Box 10-20
10.34 Controlled Outlet (with Gate Settings) 10-20
10.35 Power Plant Physical Data Editor: Capacity Tab 10-21
10.36 Power Plant Physical Data Editor: Efficiency Tab - Constant Efficiency Method 10-22
10.37 Power Plant Physical Data Editor: Efficiency Tab - Function of Reservoir Elevation 10-23
10.38 Power Plant Physical Data Editor: Efficiency Tab - Function of Reservoir Release 10-24
10.39 Power Plant Physical Data Editor: Efficiency Tab - Function of Operating Head 10-25
10.40 Power Plant Physical Data Editor: Station Use Tab - Constant Method 10-26
10.41 Power Plant Physical Data Editor: Station Use Tab - Function of Release Method 10-27
10.42 Power Plant Physical Data Editor: Hydraulic Losses Tab - Constant Method 10-28
10.43 Power Plant Physical Data Editor: Hydraulic Losses Tab - Function of Release Method 10-29
10.44 Reservoir Editor: Physical Data--Uncontrolled Outlet 10-30
10.45 Reservoir Editor: Physical Data--Tailwater 10-31
10.46 Composite Release Capacity Table 10-33
10.47 Reservoir Editor: Observed Data Tab 10-35

CHAPTER 10

Defining Physical Components of Reservoirs

The data that defines an individual reservoir element within the reservoir network consists of two conceptual types: **Physical** and **Operational**. This chapter describes the physical components of a reservoir that include the Pool, the Dam (and its Outlets), and any Diverted Outlets (commonly called diversions from the pool). ResSim represents these components using a "tree structure". As you add optional physical components to the reservoir, they will appear in the reservoir tree. This reservoir tree is more than just an illustration. It is the mechanism you will use to access the editors for the separate reservoir components. As you select a component in the reservoir tree, the edit panel to the right of the reservoir tree will display the editor you need to define the properties of that component.

An elevation-storage-area relationship describes the properties of the pool, while a crest elevation and length describes the dam, represented internally in the ResSim program as an uncontrolled spillway. You will need to add one or more outlets to the dam to enable water to pass through it into the downstream system. You can also add a power plant to an individual outlet in order to describe the hydropower generating capacity of the flow through that outlet. Within the Reservoir Editor, Diverted Outlets (or reservoir diversions) are separate outlet "groups". As with the dam, you will need to add one or more outlets to a diverted outlet group to enable the reservoir to allocate flow through the diversion.

The order in which you add physical components and edit their properties is flexible. You can add all the physical components to the reservoir then go back and define each component's properties, or you can define the properties of each component as you add it, before going on to add and edit the next component. Choose the style that works best for you. However, you should finish defining the physical representation of your reservoir before going on to define its operational data (see Chapter 11), as the definition of the operational zones depends on the physical definition of the pool, and the rules depend on the description of the outlet works.

10.1 Accessing the Reservoir Editor

In the Reservoir Network Module, you can access the Reservoir Editor from either the **Edit** menu in the menu bar or from the right-click shortcut menu of a reservoir in the map display.

- From the **Edit** menu, select **Reservoirs...**.
- From the map display, right-click on a reservoir with the **Reservoir Tool** , then select **Edit Reservoir Properties**.

10.2 Using the Reservoir Editor to Define Physical Components

The **Physical** tab of the **Reservoir Editor** allows you to define the physical properties of reservoirs in your reservoir network. Figure 10.1 shows the **Reservoir Editor** with the **Physical** tab selected.



Figure 10.1 Reservoir Editor: Physical Tab

On the **Physical** tab, a reservoir tree appears in the left panel of the window. By default, the reservoir tree displays the reservoir and its primary components: the **Pool** and the **Dam**. Additionally, if you add a diversion to remove water from this reservoir's pool in the reservoir network, a **Diverted Outlet** appears in the reservoir tree. As you add components to the reservoir, such as outlets and losses, the reservoir tree will expand to show these components.

The area to the right of the reservoir tree is the Edit Panel. The content of this panel changes according to the component you select in the reservoir tree. Figure 10.1 shows the **Composite Release Capacity** summary for the reservoir because the reservoir is the selected component in the reservoir tree.

The menu bar of the Reservoir Editor also changes according to the component you select in the reservoir tree. For example, when you select the **Dam** in the reservoir tree, a **Dam** menu becomes available in the menu bar.

The **Reservoir** field at the top of the Editor contains a list of all of the reservoirs in your network, with the name of the current reservoir displayed. You can access all of the reservoirs both from this list and by using the VCR-style buttons to navigate through the available reservoirs. Below the Reservoir name list is the **Description** of the current reservoir; this field is editable.

The following sections describe how to use the **Physical** tab of the Reservoir Editor to define the physical components of the reservoir that appear in the reservoir tree.

10.3 Specifying Physical Components of a Reservoir

On the Physical tab of the Reservoir Editor, a reservoir tree appears in the left panel of the window. By default, the primary components for all reservoirs are a **Pool** and a **Dam**, as Figure 10.2 illustrates.

Figure 10.2 Reservoir Editor, Physical Tab: Default Reservoir Component Tree

A **Pool** reflects characteristics of reservoir storage, while a **Dam** reflects the reservoir dam and its outlets.

Additionally, if the individual reservoir has a diverted outlet, a **Diverted Outlet** will appear as a primary component of the reservoir, as illustrated in Figure 10.3.

Figure 10.3 Reservoir Editor, Physical Tab: Default Reservoir Component Tree with Diverted Outlet

The Reservoir and primary components that appear in the default reservoir tree are features of the reservoir network that you have setup previously using the map (mouse) tools. The following sections explain how to add details to the primary components of a reservoir and how to define secondary components such as outlets and losses.

10.4 Specifying Reservoir Pool Losses

You can specify both **Pool Evaporation** and **Pool Seepage**, as shown in Figure 10.4.

On the **Physical** tab, you may use either the **Pool** menu in the Reservoir Editor's menu bar (Figure 10.5) or the right-click shortcut menu (Figure 10.6) to specify **Losses** for a reservoir pool.

Figure 10.4 Reservoir Editor, Physical Tab: with Pool Losses

To add Pool Evaporation and/or Pool Seepage:

1. Select **Pool** in the reservoir tree.
2. Either click on **Pool** in the menu bar or right-click on **Pool** in the reservoir tree to access the shortcut menu.
3. Select **Add Pool Evaporation** or **Add Pool Seepage**.



Figure 10.5 Reservoir Editor: Pool Menu



Figure 10.6 Reservoir Tree Shortcut Menu: Pool

You can also remove Pool Seepage and Pool Evaporation, as described in Section 10.12.3.

10.5 Defining Physical Features of a Dam

As Figure 10.7 shows, you can add **Leakage** (Section 10.6) and **Tailwater Elevation** (Section 10.10) to a dam, along with **Controlled Outlets** (Section 10.8), **Uncontrolled Outlets** (Section 10.9), and **Outlet Groups** (Section 10.7).

You can also rename Dams in the reservoir tree, as described in Section 10.12.1.



Figure 10.7 Reservoir Tree: Dam

On the Physical tab, you may use either the **Dam** menu in the Reservoir Editor's menu bar (Figure 10.8) or the right-click shortcut menu (Figure 10.9) to specify features of a dam.

10.6 Adding Leakage to a Dam

To add **Leakage** to a dam:

1. Select the dam by clicking on it in the reservoir tree.
2. Select **Add Leakage** from either the **Dam** menu in the Reservoir Editor's menu bar (Figure 10.8) or the right-click shortcut menu of the Dam (Figure 10.9).



Figure 10.8 Reservoir Editor, Physical Tab: Dam Menu

Leakage will now appear as a "branch" of the reservoir tree, beneath the dam.

You can also remove Leakage from a dam (see Section 10.12.3).



Figure 10.9 Reservoir Tree Shortcut Menu: Dam

10.7 Adding Outlet Groups

You can add **Outlet Groups** as components of Dams, Diverted Outlets, and other Outlet Groups, as shown in Figure 10.10.

An Outlet Group allows you to define subsets of a reservoir component. An Outlet Group can include **Tailwater Elevation** (Section 10.10), **Controlled Outlets** (Section 10.8), **Uncontrolled Outlets** (Section 10.9), and other **Outlet Groups** as components.

On the Physical tab, you may use either the component-specific menus in the Reservoir Editor's menu bar or the right-click shortcut menus (Figure 10.11) to add an Outlet Group as a component of a Dam, Diverted Outlet, or other Outlet Group.



Figure 10.10 Reservoir Tree: Outlet Groups

To add an Outlet Group:

1. Select the Dam, Diverted Outlet, or Outlet Group to which you want to add the new Outlet Group.
2. Choose **Add Outlet Group** from the shortcut menu (Figure 10.11) or from the component's menu in the Reservoir Editor's menu bar.



Figure 10.11 Diverted Outlet Shortcut Menu: Add Outlet Group

The new Outlet Group will appear in the reservoir tree as a branch beneath the component you selected.

You can also rename and delete Outlet Groups in the reservoir tree, as described in Section 10.12.

10.8 Defining Controlled Outlets

You can add **Controlled Outlets** to Dams, Diverted Outlets, and Outlet Groups, as shown in Figure 10.12.

Additionally, as shown in Figure 10.15 you can add **Tailwater Elevation** (Section 10.10) and **Power Plants** (Section 10.8.2) as components of Controlled Outlets.

You can also rename and delete Controlled Outlets in the reservoir tree (see Section 10.12).



Figure 10.12 Reservoir Tree: Controlled Outlets

10.8.1 Adding Controlled Outlets

On the Physical tab, you may use either the component-specific menus in the Reservoir Editor's menu bar or the right-click shortcut menus (Figure 10.13) to add a **Controlled Outlet** as a component of a **Dam**, **Diverted Outlet**, or **Outlet Group**.

To add a Controlled Outlet:

1. Select the Dam or Outlet Group to which you want to add the new Controlled Outlet.
2. Choose **Add Controlled Outlet** from the shortcut menu (Figure 10.13) or from the component's menu in the Reservoir Editor's menu bar.



Figure 10.13 Dam Shortcut Menu: Add Controlled Outlet

The new Controlled Outlet will appear in the reservoir tree as a branch beneath the dam or outlet group you selected.

10.8.2 Adding a Power Plant to a Controlled Outlet

To add a **Power Plant** to a Controlled Outlet:

1. Select the Controlled Outlet by clicking on it in the reservoir tree.
2. Select **Add Power Plant** from either the **Outlet** menu in the Reservoir Editor's menu bar (Figure 10.14) or the right-click shortcut menu (Figure 10.15).



Figure 10.14 Reservoir Editor, Physical Tab: Outlet Menu - Add Power Plant

The Power Plant will now appear as a branch of the reservoir tree, beneath the Controlled Outlet.

You can also remove a Power Plant from the reservoir tree, as described in Section 10.12.3.



Figure 10.15 Controlled Outlet Shortcut Menu: Add Power Plant

10.9 Adding Uncontrolled Outlets

You can add **Uncontrolled Outlets** to Dams, Diverted Outlets, and Outlet Groups, as shown in Figure 10.16.

On the Physical tab, you may use either the component-specific menus in the Reservoir Editor's menu bar or the right-click shortcut menus (Figure 10.17) to add an Uncontrolled Outlet as a component of a Dam, Diverted Outlet, or Outlet Group.



Figure 10.16 Reservoir Tree: Uncontrolled Outlets

To add an Uncontrolled Outlet:

1. Select the Dam, Diverted Outlet, or Outlet Group to which you want to add the new Uncontrolled Outlet.
2. Choose **Add Uncontrolled Outlet** from the shortcut menu (Figure 10.17) or from the component's menu in the Reservoir Editor's menu bar.



Figure 10.17 Dam Shortcut Menu: Add Uncontrolled Outlet

The new Uncontrolled Outlet will appear in the reservoir tree as a branch beneath the component you selected.

You can also rename and delete Uncontrolled Outlets in the reservoir tree, as described in Section 10.12.

10.10 Adding Tailwater Elevation

You can add **Tailwater Elevation** to Dams, Diverted Outlets, and Outlet Groups, as shown in Figure 10.18.

On the Physical tab, you may use either the component-specific menus in the Reservoir Editor's menu bar or the right-click shortcut menus (Figure 10.19) to add Tailwater Elevation to a Dam, or Diverted Outlet.



Figure 10.18 Reservoir Tree: Tailwater Elevation

To add Tailwater Elevation:

1. Select the Dam, Diverted Outlet, or Outlet Group to which you want to add Tailwater Elevation.
2. Choose **Add Tailwater Elevation** from the shortcut menu (Figure 10.19) or from the component's menu in the Reservoir Editor's menu bar.



Figure 10.19 Dam Shortcut Menu: Add Tailwater Elevation

The Tailwater Elevation you have added will appear in the reservoir tree as a branch beneath the component you selected.

You can also remove Tailwater Elevation from the reservoir tree, as described in Section 10.12.3.

10.11 Defining Physical Components of a Diverted Outlet

As Figure 10.20 shows, you can add **Tailwater Elevation** (Section 10.10), **Uncontrolled Outlets** (Section 10.9), **Controlled Outlets** (Section 10.8), and **Outlet Groups** (Section 10.7) to a Diverted Outlet.



Figure 10.20 Reservoir Tree: Diverted Outlet

On the Physical tab, you may use either the **Outlet** menu in the Reservoir Editor's menu bar (Figure 10.21) or the right-click shortcut menu to specify features of a Diverted Outlet.

You can also rename and delete Diverted Outlets in the reservoir tree, as described in Section 10.12.



Figure 10.21 Reservoir Editor: Outlet Menu for Diverted Outlet

10.12 Renaming, Deleting, and Removing Reservoir Components

The following sections explain how to rename and delete or remove reservoir components.

10.12.1 Renaming Reservoir Components

ResSim assigns default names to reservoir components you have created in the Reservoir Network Module. You can rename Dams, Diverted Outlets, Outlet Groups, and Uncontrolled Outlets.

To rename a reservoir component:

1. Select the component by clicking on it in the reservoir tree.
2. Using either the right-click shortcut menu (Figure 10.22) or the component menu in the Reservoir Editor's menu bar, choose **Rename**. The **Rename Reservoir Component** dialog box will open (Figure 10.23).



Figure 10.22 Reservoir Component Shortcut Menu: Rename Component

Figure 10.23 Rename Reservoir Component Dialog Box

3. Type the new name for the component in the **Name** field. You may also enter a new description in the **Description** field.
4. Click **OK** to close the dialog box. The new name will appear in the reservoir tree.

10.12.2 Deleting Reservoir Components

When you delete components from the reservoir tree, you *permanently remove them from the reservoir network*. You can delete Outlet Groups, Diverted Outlets, Controlled Outlets, and Uncontrolled Outlets.

To delete a reservoir component:

1. Select the component by clicking on it in the reservoir tree.
2. Using either the right-click shortcut menu (Figure 10.24) or the component menu in the Reservoir Editor's menu bar, choose **Delete**.
3. A confirmation window will appear (Figure 10.25). Click **Yes** to verify the deletion.



Figure 10.24 Reservoir Component Shortcut Menu: Delete Component



Figure 10.25 Confirm Deletion of Reservoir Component

When you delete a reservoir component, it will no longer appear in the reservoir tree.

Additionally, when you delete a Diverted Outlet, it will no longer appear in the map display of the Reservoir Network Module. To replace a Diverted Outlet, you will need to re-draw it in the map display area.

10.12.3 Removing Reservoir Parameters

You may remove Dam Leakage, Pool Evaporation and Seepage, Tailwater Elevation, and Power Plants from the reservoir tree without losing the associated data.

To remove these parameters:

1. Select the parameter by clicking on it in the reservoir tree.
2. Using either the right-click shortcut menu (Figure 10.26) or the primary component's menu in the Reservoir Editor's menu bar, choose **Remove**.
3. A confirmation window will appear (Figure 10.27). Click **Yes** to verify the removal.



Figure 10.26 Reservoir Parameter Shortcut Menu: Remove Parameter



Figure 10.27 Confirm Removal of Reservoir Parameter

The parameter you have removed will no longer appear in the reservoir tree. However, if you re-add this parameter, the previously entered values will be restored.

10.13 Editing Reservoir Physical Data

To edit the physical data associated with a reservoir component, select the component in the reservoir tree in the Reservoir Editor. The appropriate data editor will appear in the area to the right of the reservoir tree.

In most cases, you will want to copy and paste tabular data from a spreadsheet application into the data editors, rather than typing the data manually.

10.14 Editing Pool Physical Data

To edit physical data for a reservoir Pool, select the **Pool** in the reservoir tree.

Figure 10.28 shows the Reservoir Editor's Pool data editor. The table in this Editor allows you to choose either **Linear** or **Conic** Interpolation and enter the **Elevation** vs. **Storage** vs. **Area** data. Two plots visually represent Storage and Area values in relation to Elevation.



Figure 10.28 Reservoir Editor: Physical Data--Pool

To enter data into the table, either copy and paste it from a spreadsheet application or type in the data manually.

- **Linear Interpolation**: By default, the interpolation method ResSim uses to compute values for elevations and storages between those specified in the table is linear.
- **Conic Interpolation**: The pool definition detailed in the regulation manual for most reservoirs was originally developed using the assumption that the volume of water between two elevations can be described by the same equation as that used to compute the volume of a section of a cone. The area of the pool surface at each elevation can be computed based on the topography of the land and the change in elevation. Using this information, ResSim can compute the storage between the two elevations. This method of computing storage is available with the conic interpolation option. This option requires you to input an elevation vs. area relationship and a starting storage value at the lowest elevation in the table. ResSim will then compute the storage values using the conic assumption. Conic interpolation will also

be used to obtain intermediate storage values for elevations between those explicitly entered in the table.

The following are requirements for **Elevation, Storage**, and **Area** data:

- You must enter at least two rows, with values increasing down the columns.
- You may not enter duplicate values.
- The maximum elevation should not exceed the Elevation at top of Dam.

Be sure to click the **Apply** button before moving on to edit the next component.

10.14.1 Editing Pool Evaporation Data

To edit Evaporation data, select **Evaporation** in the reservoir tree. Figure 10.29 shows the Reservoir Editor's Evaporation data editor and its corresponding mini-plot. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.

You may choose either Monthly Average Evaporation or Evaporation Time-Series data.



Figure 10.29 Reservoir Editor: Physical Data--Pool Evaporation

- **Monthly Average Evaporation:** Enter Evaporation values by month. To enter data into the table, either copy and paste it from a spreadsheet application or type in the values manually.
- **Evaporation Time Series:** If you select this option, you will need to specify the time-series data source when you create an Alternative (see Chapter 13).

Be sure to click the **Apply** button before moving on to edit the next component.

10.14.2 Editing Pool Seepage

To edit Seepage data, select **Seepage** in the reservoir tree. Figure 10.30 shows the Reservoir Editor's Seepage data editor and its corresponding mini-plot. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.

You may choose either **Constant Seepage** or **Seepage as a function of Reservoir Elevation**.



Figure 10.30 Reservoir Editor: Physical Data--Pool Seepage

- **Constant Seepage:** Enter the constant value in the field provided.
- **Seepage as a Function of Reservoir Elevation:** Enter **Elevation** and **Seepage** values into the table. To enter data into the table, either copy and paste it from a spreadsheet application or type in the values manually.

Be sure to click the **Apply** button before moving on to edit the next component.

10.15 Editing Dam Leakage

To edit Leakage data for a dam, select **Leakage** in the reservoir tree. Figure 10.31 shows the Reservoir Editor's Leakage data editor and its corresponding mini-plot. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.

The Leakage data editor allows you to define **Leakage** as a function of pool **Elevation**. Leakage, although referred to as a "loss," is not a true loss of flow to the system. In fact, leakage effectively passes through the dam into the downstream system at the downstream (or tailwater) junction.



Figure 10.31 Reservoir Editor: Physical Data--Dam Leakage

To enter data into the table, either copy and paste it from a spreadsheet application or type in the data manually.

Be sure to click the **Apply** button before moving on to edit the next component.

10.16 Editing Controlled Outlet Physical Data

A **Controlled Outlet** can be a component of a Dam, Diverted Outlet, or Outlet Group. Additionally, a Controlled Outlet may have its own components Tailwater Elevation and Power Plants.

To edit data for the primary Controlled Outlet, select the name of the Controlled Outlet in the reservoir tree.

Figure 10.32 shows the Reservoir Editor's Controlled Outlet data editor and its corresponding mini-plot. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.32 Controlled Outlet (no Gate Settings)

To enter Controlled Outlet data:

1. Specify the **Number of Gates** of this type.
2. Enter **Elevation** and **Flow** values into the table. You can either copy and paste data from a spreadsheet application or type in the values manually.
3. Specify **Max Rate of Increase** and **Max Rate of Decrease** limitations.

4. Click the **Edit Gate Settings** button to access the **Gate Settings** dialog box (Figure 10.33). Gate settings are sometimes known as "cranks."
5. Choose either **Specify Maximum Capacity Only** or **Specify Capacity at Specific Gate Openings**.
   To **Specify Capacity at Specific Gate Openings:**
   - Select the **Number of Gate Settings** (or "cranks") and the **Gate Setting Units** (Length or Percent).
   - Enter the **Setting** for each gate.
6. Click **OK** to close the Gate Settings dialog box.



Figure 10.33 Gate Settings Dialog Box

Figure 10.34 shows the Reservoir Editor's Controlled Outlet data editor with Gate Settings specified.



Figure 10.34 Controlled Outlet (with Gate Settings)

When you are done entering Controlled Outlet data, be sure to click the **Apply** button before moving on to edit the next component.

10.17 Editing Power Plant Physical Data

A Power Plant is a component of a Controlled Outlet. To edit data for a Power Plant, select the **Power Plant** in the reservoir tree.

The Reservoir Editor's Power Plant data editor has four tabs that allow you to edit data for **Capacity**, **Efficiency**, **Station Use**, and **Hydraulic Losses**, as described in the following sections.

10.17.1 Editing Capacity Data for a Power Plant

On the **Capacity** tab, you can enter **Installed Capacity** and **Overload Factor** (Figure 10.35). The Installed Capacity is entered in megawatts (MW) and represents the nameplate capacity. The Overload Factor is used in conjunction with the Installed Capacity to determine the maximum energy the power plant can produce in a time interval.



Figure 10.35 Power Plant Physical Data Editor: Capacity Tab

10.17.2 Editing Efficiency Data for a Power Plant

Power efficiency is the total efficiency (generator efficiency x turbine efficiency) of the power plant. On the **Efficiency** tab, you can specify an **Efficiency Method** from a list of four options: Constant, Function of Reservoir Elevation, Function of Release, or Function of Operating Head. Each Efficiency Method has its own data editor, as described in the following sections.

10.17.2.1 Constant Efficiency Method

For the **Constant** efficiency method (Figure 10.36), enter a percentage value for **Constant Efficiency**. A constant turbine-generator efficiency of 86% is often used. In actual operation, however, the turbine-generator efficiency varies throughout its range of operation (subsequent sections describe efficiency as a function of elevation, release or operating head).



Figure 10.36 Power Plant Physical Data Editor: Efficiency Tab - Constant Efficiency Method

When you have finished entering Efficiency data, be sure to click the **Apply** button before moving on to the next tab.

10.17.2.2 Function of Reservoir Elevation Efficiency Method

For the **Function of Reservoir Elevation** efficiency method (Figure 10.37), enter values for **Elevation** and **Efficiency**. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.37 Power Plant Physical Data Editor: Efficiency Tab - Function of Reservoir Elevation

When you have finished entering Efficiency data, be sure to click the **Apply** button before moving on to the next tab.

10.17.2.3 Function of Release Efficiency Method

For the **Function of Release** efficiency method (Figure 10.38), enter values for **Release** and **Efficiency**. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.38 Power Plant Physical Data Editor: Efficiency Tab - Function of Reservoir Release

When you have finished entering Efficiency data, be sure to click the **Apply** button before moving on to the next tab.

10.17.2.4 Function of Operating Head Efficiency Method

For the **Function of Operating Head** efficiency method (Figure 10.39), enter values for **Head** and **Efficiency**. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.39 Power Plant Physical Data Editor: Efficiency Tab - Function of Operating Head

When you have finished entering Efficiency data, be sure to click the **Apply** button before moving on to the next tab.

10.17.3 Editing Station Use Data for a Power Plant

Station Use is a portion of the flow that passes through the outlet but is not used to generate power for the "grid." On the **Station Use** tab, you can define the **Station Use Method** as Constant or as a Function of Release. Each method has its own data editor, as described in the following sections.

10.17.3.1 Constant Station Use Method

The **Constant** station use method (Figure 10.40) simply means that the flow "loss" is not affected by any parameter.

Enter a value for **Constant Station Use**.



Figure 10.40 Power Plant Physical Data Editor: Station Use Tab - Constant Method

When you have finished entering Station Use data, be sure to click the **Apply** button before moving on to the next tab.

10.17.3.2 Function of Release Station Use Method

The loss of flow for generating hydropower through station use can also be defined as a function of flow entering the outlet. For the **Function of Release** station use method (Figure 10.41), enter values for **Release** (flow) and **Use** (the loss in flow units). The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.41 Power Plant Physical Data Editor: Station Use Tab - Function of Release Method

When you have finished entering Station Use data, be sure to click the **Apply** button before moving on to the next tab.

10.17.4 Editing Hydraulic Losses Data for a Power Plant

Hydraulic loss can also be referred to as head loss. ResSim uses the value of head (the difference between the pool elevation and the tailwater elevation) within the power equations to compute capacity. When you enter a hydraulic loss, you are describing a loss to the head, thereby reducing the plant's generating capacity.

You can choose one of two methods to describe hydraulic losses. On the **Hydraulic Losses** tab, you can specify the head loss as a Constant or as a Function of Release (flow through the outlet). Each method has its own data editor, as described in the following sections.

10.17.4.1 Constant Hydraulic Losses Method

For the **Constant** hydraulic losses method (Figure 10.42), enter a value for **Constant Hydraulic Loss**.



Figure 10.42 Power Plant Physical Data Editor: Hydraulic Losses Tab - Constant Method

When you have finished entering Hydraulic Losses data, be sure to click the **Apply** button before moving on.

10.17.4.2 Function of Release Hydraulic Losses Method

For the **Function of Release** hydraulic losses method (Figure 10.43), enter values for **Release** and **Loss** to describe the head loss as a function of flow through the outlet. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.43 Power Plant Physical Data Editor: Hydraulic Losses Tab - Function of Release Method

- **Release:** Flow through the outlet.
- **Loss:** Head Loss, a unit of length to be removed from the head value used to compute generating capacity.

When you have finished entering Hydraulic Losses data, be sure to click the **Apply** button before moving on.

10.18 Editing Uncontrolled Outlet Physical Data

An **Uncontrolled Outlet** can be a component of a Dam, Diverted Outlet, or Outlet Group. The uncontrolled outlet is an uncontrolled spillway and you can use a weir equation to compute the flow over the spillway. Otherwise, the outlet can be defined by a simple rating curve that describes flow through the outlet.

Figure 10.44 shows the Reservoir Editor's Uncontrolled Outlet data editor and its corresponding mini-plot. The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.



Figure 10.44 Reservoir Editor: Physical Data--Uncontrolled Outlet

In the Uncontrolled Spillway data editor you will specify **Outlet Elevation.** This elevation will serve as a trigger to determine when this outlet starts "flowing." Next, choose how you want to represent your uncontrolled outlet: as a spillway using the weir equation (**Weir Coefficient**) or as a rating curve (**Elevation vs. Outflow**). If you choose to define your uncontrolled outlet as a spillway, enter the spillway length and weir coefficient; otherwise, enter the rating curve's elevation and outflow values.

- **Length:** Spillway length.
- **Outlet Elevation:** Minimum elevation at which the outlet will begin to release water.

- **Weir Coefficient:** Typically in the range 2.6-4.0 depending on the shape of the spillway crest. This value determines flow over the spillway in the weir equation.
- **Elevation vs. Outflow:** To enter data into the table, either copy and paste it from a spreadsheet application or type in the data manually.

Be sure to click the **Apply** button before moving on to edit the next component.

10.19 Editing Tailwater Elevation Physical Data

Tailwater Elevation can be a component of a Dam, Diverted Outlet, Outlet Group, and Controlled Outlet. You must add a Tailwater component to the dam or outlet if you have defined one or more power plants for this reservoir, so the head can be computed for the power computations. Three different methods for defining tailwater are available. If you define more than one, ResSim will compute all defined but will use only the highest to determine the head.

To edit Tailwater Elevation data, select the **Tailwater** component in the reservoir tree. Figure 10.45 shows the Reservoir Editor's Tailwater Elevation data editor. The mini-plot will reflect the rating curve values you enter and can be viewed in full size when you double-click on it.



Figure 10.45 Reservoir Editor: Physical Data--Tailwater

- **Constant Elevation:** Enter a value for the tailwater elevation. If the reservoir has a stilling basin at the tailwater, a constant elevation may be an appropriate definition.
- **Downstream Control:** Select a junction from the list. The junction should represent the point of outflow of the power plant and contain a rating curve from which the elevation of the junction can be determined.
- **Rating Curve:** You can also apply a rating curve to represent the tailwater of the dam or outlet of the reservoir. You may either copy and paste the data from a spreadsheet application or type in the values manually.
  - ❖ **Stage:** The height from some datum, representing the water surface elevation.
  - ❖ **Discharge:** The flow passing that location that would produce the associated water surface elevation.

Stage Datum: The "zero" elevation against which stage is measured. This elevation must be in the same vertical reference as the elevations describing the reservoir.

Be sure to click the **Apply** button before moving on to edit the next component.

10.20 Viewing Composite Release Capacity Tables

Composite Release Capacity tables and their corresponding mini-plots provide a summary of outlet capacity data for Controlled and Uncontrolled Outlets of a reservoir. Figure 10.46 shows a Composite Release Capacity table for a reservoir. The mini-plot reflects the composite values and can be viewed in full size when you double-click on it.



Figure 10.46 Composite Release Capacity Table

Composite Release Capacity tables are informational and are not editable. Instead, they fill in automatically as you add data for the individual components.

10.20.1 Reservoir Composite Release Capacity Table

To view the **Reservoir Composite Release Capacity** table, select the Reservoir's name at the top of the reservoir tree (corresponding to the symbol) as shown in Figure 10.46.

In ResSim, a reservoir consists of, minimally, a Pool and a Dam; it may also include Diverted Outlets. The dam (and diverted outlet) can then, in turn, include outlets and outlet groups. The dam, diverted outlet, and any outlet group will display Composite Release Capacity tables similar to that of the reservoir to represent the total outlet capacity of the components contained within each group.

10.20.2 Dam Composite Release Capacity Table

To access the **Dam Release Capacity** table, select the Dam in the reservoir tree (corresponding to the symbol).

The components of a dam that influence the Composite Release Capacity table include controlled outlets, uncontrolled outlets, and outlet groups.

10.20.3 Diverted Outlet Composite Release Capacity Table

To access the **Diverted Outlet Composite Release Capacity** table, select the Diverted Outlet in the reservoir tree (corresponding to the symbol).

The components of a diverted outlet that influence the composite release capacity table include controlled outlets, uncontrolled outlets, and outlet groups.

10.20.4 Outlet Group Composite Release Capacity Table

To access the **Outlet Group Composite Release Capacity** table, select the Outlet Group in the reservoir tree (corresponding to the symbol).

An outlet group can be a component of a dam, diverted outlet, or another outlet group. The components that can influence the Outlet Group Composite Release Capacity table include controlled outlets, uncontrolled outlets, and outlet groups.

10.21 Reservoir Editor: Observed Data Tab

Use the **Observed Data** tab (Figure 10.47) to indicate that observed data is available for comparison purposes. If the **Observed** box in the table is checked, then there will be a corresponding entry in the Observed Time-Series mapping table when you create an Alternative (see Chapter 13).



Figure 10.47 Reservoir Editor: Observed Data Tab

To edit another reservoir without exiting the Reservoir Editor, click the **Apply** button and then select another reservoir from the **Reservoir** name list or use the navigator buttons.

Chapter 11

Defining Reservoir Operations Data

Table of Contents

Section **Page**

11 Defining Reservoir Operations Data
11.1 Reservoir Editor's Operations Tab 11-2
11.2 Reservoir Operation Sets 11-3
11.2.1 Creating a New Operation Set 11-3
11.2.2 Renaming an Operation Set 11-4
11.2.3 Copying an Operation Set 11-5
11.2.4 Deleting an Operation Set 11-5
11.2.5 Editing an Operation Set 11-6
11.3 Reservoir Operation Zones 11-6
11.3.1 Renaming and Describing Operation Zones 11-7
11.3.2 Adding a New Reservoir Storage Zone 11-7
11.3.3 Defining Operation Zones 11-8
11.3.4 Deleting Operation Zones 11-9
11.4 Understanding Reservoir Operation Rules 11-10
11.4.1 Release Decision Process 11-10
11.4.2 Using Existing Rules 11-11
11.4.3 Removing Rules 11-11
11.4.4 Deleting Rules 11-11
11.4.5 Prioritizing Rules 11-11
11.4.6 Renaming Rules 11-11
11.5 Defining Reservoir Operation Rules 11-12
11.5.1 Adding a New Operation Rule to a Zone 11-13
11.5.2 Adding an Existing Rule to a Zone 11-14
11.5.3 Defining a Release Function Rule 11-14
11.5.4 Defining a Downstream Control Function Rule 11-19
11.5.5 Defining a Tandem Operation Rule 11-21
11.5.6 Defining an Induced Surcharge Rule 11-22
11.5.7 Defining a Flow Rate of Change Limit Rule 11-26
11.5.8 Defining an Elevation Rate of Change Limit Rule 11-27
11.5.9 Defining Hydropower Rules 11-29
11.5.9.1 Hydropower – Schedule 11-29
11.5.9.2 Hydropower – Time Series Requirement 11-30
11.5.9.3 Hydropower – Power Guide Curve 11-31
11.5.9.4 Hour of Day Weighting Factors 11-33
11.5.9.5 Day of Week Weighting Factors 11-34

Section (continued) **Page**

11.6 Common Options for Rule Definition 11-35
11.6.1 Interpolation Method 11-35
11.6.2 Hour of Day Multiplier 11-37
11.6.3 Day of Week Multiplier 11-38
11.6.4 Rising / Falling Condition 11-39
11.6.5 Seasonal Variation 11-40
11.7 Editing the Reservoir Decision Interval 11-41
11.8 Selecting the Reservoir Guide Curve 11-42
11.9 Adjusting the Guide Curve for Flood Control Credit Storage 11-43

List of Figures

Figure Number **Page**

11.1 Reservoir Editor--Operations Tab 11-2
11.2 New Operation Set Dialog Box 11-4
11.3 Rename Operation Set Dialog Box 11-4
11.4 Duplicate Operation Set 11-5
11.5 Select Operation Set to Delete 11-5
11.6 Reservoir Editor Showing New Operation Set 11-6
11.7 New Zone Dialog Box 11-7
11.8 Reservoir Editor--Operations Tab: Zone Editor 11-8
11.9 New Operating Rule Dialog Box 11-13
11.10 Select Existing Rule Dialog Box 11-14
11.11 Reservoir Editor--Operations Tab: New Release Function Rule 11-15
11.12 Reservoir Editor--Operations Tab: Release Function Rule, Selecting a Function from the Independent Variable Definition Editor 11-16
11.13 Reservoir Editor--Operations Tab: Release Function Rule, Selecting an Independent Variable from the Model Variable List 11-16
11.14 Reservoir Editor--Operations Tab: Release Function Rule, Defining an External Variable as the Independent Variable 11-17
11.15 Time Series Options for Model and External Variables 11-17
11.16 Reservoir Editor--Operations Tab: Example of Completed Release Function Rule 11-18
11.17 Reservoir Editor--New Operating Rule: Downstream Control Function 11-19
11.18 Reservoir Editor--Example of a Downstream Control Function Rule 11-20
11.19 Reservoir Editor--New Operating Rule: Tandem Operation 11-21
11.20 Reservoir Editor--Example of a Tandem Operation Rule 11-22
11.21 Reservoir Editor--Operations Tab: Create Induced Surcharge Rule 11-23
11.22 Reservoir Editor--Operations Tab: Induced Surcharge Rule 11-24
11.23 Plot of Computed Induced Surcharge Curves 11-25
11.24 Induced Surcharge--Falling Pool Options 11-25
11.25 Reservoir Editor--Operations Tab: Flow Rate of Change Limit Rule 11-27
11.26 Reservoir Editor--Operations Tab: Elevation Rate of Change Limit Rule (Pool) 11-28

List of Figures (continued)

Figure Number **Page**

11.27 Hydropower Rule Types 11-29
11.28 Hydropower – Schedule Rule Editor 11-30
11.29 Hydropower – Time Series Requirement Rule Editor 11-31
11.30 Hydropower – Power Guide Curve Rule Editor 11-32
11.31 Hour of Day Weighting with Default Values of 1.0 Specified for Entire Day 11-33
11.32 Hour of Day Weighting with Values of 1.0 Specified for Portion of Day 11-33
11.33 Hour of Day Weighting to "Double" the Power Requirement for Portion of Day 11-34
11.34 Hour of Day Weighting Modified from Default Values 11-34
11.35 Day of Week Weighting with Default Values of 1.0 for Each Day of the Week 11-34
11.36 Day of Week Weighting with Values of 0.0 for Saturday and Sunday 11-34
11.37 Day of Week Weighting to "Double" the Power Requirement on Wednesday 11-35
11.38 Day of Week Weighting Modified from Default Values 11-35
11.39 Interpolation Methods 11-35
11.40 Linear Interpolation Method 11-36
11.41 Step Interpolation Method 11-36
11.42 Cubic Interpolation Method 11-36
11.43 Hour of Day Multiplier with Default Values of 1.0 Specified for Entire Day 11-37
11.44 Hour of Day Multiplier with Values of 0.0 Specified for Portion of Day 11-37
11.45 Hour of Day Multiplier Modified from Default Values 11-37
11.46 Day of Week Multiplier with Default Factors of 1.0 Specified for Each Day of the Week 11-38
11.47 Day of Week Multiplier with Factors of 0.0 Specified for Saturday and Sunday 11-38
11.48 Day of Week Multiplier Modified from Default Values 11-38
11.49 Rising / Falling Condition Dialog Box 11-39
11.50 Rising / Falling Condition Modified from Default 11-39
11.51 Seasonal Variation Dialog Box 11-40
11.52 Reservoir Decision Interval Editor, Interval Options 11-41
11.53 Reservoir Decision Interval Editor, Regular Interval Option 11-41
11.54 Reservoir Decision Interval Editor, Weekly Schedule Option 11-41
11.55 Operations Menu, Guide Curve Option 11-42
11.56 Reservoir Guide Curve Editor 11-42
11.57 Reservoir Guide Curve Editor, Checkbox to Indicate Guide Curve is Modified by Available Flood Control Storage in Other Reservoirs 11-43

List of Figures (continued)

Figure Number **Page**

11.58 Reservoir Guide Curve Editor, Edit Reservoir Set to Select Reservoirs to Provide Flood Control Storage Credit 11-43
11.59 Reservoir Guide Curve Editor, Reservoirs to Provide Flood Control Storage Credit 11-44
11.60 Reservoir Guide Curve Editor, Definition of Function for Using Flood Control Storage Credit 11-44
11.61 Example of Reservoir Guide Curve Editor Showing Definition of Flood Control Storage Credit 11-45
11.62 Reservoir Guide Curve Editor, Available Credit Storage vs. Credit Storage 11-45
11.63 Reservoir Guide Curve Editor, Seasonal Guide Curves for Potential Credit Storage 11-45

CHAPTER 11

Defining Reservoir Operations Data

The regulation plan for most Corps reservoirs centers on a seasonally varying target pool elevation commonly called the **Guide Curve**. The storage of the reservoir above this target elevation is referred to as the **Flood Control** pool. The storage below the guide curve is called the **Conservation** pool. The guidelines for determining the release from the reservoir are then based on where the current pool elevation is in relation to the guide curve. Under basic operation, if the pool is below the guide curve, then the basic objective of the regulator is to reduce releases in order to refill the pool; if the pool is above the guide curve, then the regulator will want to increase releases to draw down the pool. Additional goals and constraints are then applied to temper such a rigid operation plan.

In a manner similar to the methods a regulator may use, each reservoir in your ResSim network must determine how much water to release at each time step of a simulation run. To make this possible, you must describe an operation plan or scheme upon which it can base its decisions. This plan is called an **Operation Set**. You can define multiple operation sets for each reservoir, but an individual alternative can follow only one operation set per reservoir.

An operation set consists of three basic features: **Zones**, **Rules,** and the identification of the **Guide Curve**.

Zones are operational subdivisions of the Reservoir Pool. Each zone is defined by a curve describing the top of the zone. When you create an operation set, ResSim establishes a default set of zones within the operation set. These zones are **Flood Control**, **Conservation**, and **Inactive**. The ***Inactive*** zone is a special zone in the operation set. It represents the "dead" storage of the reservoir. The reservoir cannot release water from the Inactive pool, and rules cannot be added to this zone.

Rules represent the goals and constraints upon the release(s). Rules can be applied to selected zones of the reservoir to describe the different factors influencing the release decision when the reservoir elevation is within each zone.

The guide curve concept is used as the basis for the release decision process in ResSim. Basic Guide Curve operation means "get the reservoir pool elevation to the current guide curve elevation as fast as possible, within the physical and operational constraints of the outlets".

The **Guide Curve** is identified by selecting the top of one of your operational zones to represent the target elevation of the reservoir. By default, ResSim assigns the Guide Curve to the top of the **Conservation** zone.

> **Tip** *An operation set that has the zones defined but no rules will cause ResSim to follow the Basic Guide Curve operation. For testing purposes, every reservoir should have an operation set of this type. It is the easiest way to verify that your physical data, your operational zones, and your guide curve have been properly defined.*

This chapter will guide you through the process of defining operations data for your reservoir network. The first section describes key features of the **Operations** tab you will need to recognize. The remainder of the chapter explains how to create an Operation Set, define Zones, define Rules, and select your Guide Curve.

11.1 Reservoir Editor's Operations Tab

Using the **Operations Tree**, the **Edit Panel**, and the **Operations**, **Zone**, and **Rule** menus, the Operations tab of the Reservoir Editor (Figure 11.1) allows you to define operation sets and their zones and rules for the reservoirs in your network.



Figure 11.1 Reservoir Editor--Operations Tab

When the Operations tab is selected for display in the Reservoir Editor, the **Menu Bar** at the top of the editor changes to include three menus unique to the Operations tab. They are **Operations**, **Zone**, and **Rule**. These menus provide the options for creating and deleting operation sets, zones, and rules, respectively. These options, as well as others, will be covered in detail later in this chapter.

The **Operations Tree** displays the zones you have defined for the current operation set. With each new operation set, ResSim creates a default set of zones that includes **Flood Control**, **Conservation**, and **Inactive**. Beneath each zone in the tree is a prioritized list of the rules that apply to that zone. As you add zones and rules to the reservoir, the tree will expand to show them.

The **Edit Panel** changes depending upon the element you have selected in the operations tree. If you select a zone, the zone editor will appear. If you select a rule, the specialized rule editor for that rule type will be displayed. A **mini-plot** on the right side of the Edit Panel reflects the data you enter in the table of the current editor. The mini-plot can be viewed in full size when you double-click on it.

At the top of the Reservoir Editor, the **Reservoir** field contains a list of all of the reservoirs in your network, with the name of the current reservoir displayed. You can access all of the reservoirs in your network either from this list or by using the VCR-style buttons to navigate through the available reservoirs. Beside the Reservoir name list is the **Description** of the current reservoir; this field is editable. Use the description field to keep notes on decisions you made while developing the data for the reservoir, your plans, intentions, references, etc. You can enter a longer description by using the ... button to access the full text editor for the description.

11.2 Reservoir Operation Sets

An **Operation Set** is the operation plan or scheme upon which a reservoir bases its decisions regarding how much water to release at each time step of a simulation run. You can define multiple operation sets for each reservoir, but an individual alternative can follow only one operation set per reservoir.

This section describes how to create and edit an operation set. The next section (Section 11.3) describes how to configure the zones within your operation set.

11.2.1 Creating a New Operation Set

To create a new Operation Set:

1. Select **New** from the **Operations** menu of the Reservoir Editor. The **New Operation Set** dialog box will open (Figure 11.2).
2. Give the new operation set a **Name** and a **Description**.

3. Click **OK** to complete the process and to close the dialog box.



Figure 11.2 New Operation Set Dialog Box

The name you entered will now appear in the **Operation Set** list, and the description will appear in the **Description** field. The Description field is editable. Use the description to describe the purpose of the operation set, the expected behavior the operation set should provide, and any changes you had to make to accomplish your goal.

ResSim establishes a default set of zones within the new operation set. These zones are **Flood Control**, **Conservation**, and **Inactive**. These zones can be renamed or removed. However, the **Inactive** zone is a special zone in the operation set. It represents the "dead" storage of the reservoir. The reservoir cannot release water from the Inactive pool and rules cannot be added to this zone. *If you remove the **Inactive** zone from the operation set, it cannot be reestablished.*

11.2.2 Renaming an Operation Set

To rename an operation set:

1. Select **Rename** from the **Operations** menu of the Reservoir Editor. The **Rename Operation Set** dialog box will open (Figure 11.3).
2. Give the operation set a new **Name**.
3. Click **OK** to complete the rename process and to close the dialog box. A confirmation dialog box will appear asking if you really want to rename the selected operation set.

Figure 11.3 Rename Operation Set Dialog Box

11.2.3 Copying an Operation Set

To copy (or duplicate) an operation set:

1. Select the Operation set you want to make a copy from the **Operation Set** list on the Operations tab.
2. Select **Duplicate** from the **Operations** menu of the Reservoir Editor. The **Duplicate Operation Set** dialog box will open (Figure 11.4).
3. Give the operation set a new **Name** and a **Description**.
4. Click **OK** to complete the copy process and to close the dialog box.

The new operation set will have a copy of all the zones that were in the original operation set. Each zone in the new operation set will also list the same rules that were used by the original operation set.



Figure 11.4 Duplicate Operation Set

11.2.4 Deleting an Operation Set

To delete an operation set:

1. Select **Delete** from the **Operations** menu of the Reservoir Editor. The **Select Operation Set to Delete** dialog box will open (Figure 11.5).
2. Highlight the operation set you wish to delete. Its name should appear in the grey box at the bottom.
3. Click **OK** to complete the delete process and to close the dialog box. A confirmation dialog box will appear asking if you really want to delete the selected operation set.



Figure 11.5 Select Operation Set to Delete

11.2.5 Editing an Operation Set

At the top of the Operations tab, the **Operation Set** field contains a list of all of the operation sets for your reservoir, with the name of the current operation set displayed. Use this list to select the operation set you wish to edit. The Operations tab will fill with the data for the selected operation set.

Beside the **Operation Set** name list is the **Description** of the current operation set; this field is editable. Use the description to describe the purpose of the operation set, the expected behavior the operation set should provide, and any changes you had to make to accomplish your goal. You can enter a much longer description by using the … button to access the full text editor for the description.

The remainder of this chapter will detail all the options available for editing your operation set. Each section assumes that you have already created an operation set. If you have not, go back and do so (see Section 11.2.1).

11.3 Reservoir Operation Zones

As illustrated in Figure 11.6, when you create a new Operation Set, ResSim automatically creates three default reservoir operation zones: **Flood Control**, **Conservation**, and **Inactive**. You may wish to rename these default zones and add descriptions. You may need to define additional zones as well. This section will detail how to edit the zone definitions of your operation set.



Figure 11.6 Reservoir Editor Showing New Operation Set

11.3.1 Renaming and Describing Operation Zones

To change the name of a Zone as it appears in the operations tree and/or edit its description:

1. Select the Zone in the operations tree.
2. Enter the new name and/or description in the editable **Storage Zone** name field and/or **Description** field of the editor.

Any changes you make to the **Storage Zone** name field will be reflected in the operations tree.

*Renaming the **Inactive** zone does not change its nature. The inactive zone is still a special zone from which the reservoir cannot release water and no rules can be applied to this zone.*

11.3.2 Adding a New Reservoir Storage Zone

To add a new Reservoir Storage Zone:

1. Select **New** from the **Zone** menu of the Reservoir Editor. The **New Zone** dialog box will open (Figure 11.7).
2. Enter a **Name** and **Description** for the new zone.
3. Click **OK** to complete the new process and close the **New Zone** dialog box.



Figure 11.7 New Zone Dialog Box

The new zone you created now appears in the operations tree. Complete the creation of the zone by defining the curve that represents the top of the zone, as explained in the next section.

11.3.3 Defining Operation Zones

You will need to define the curves representing the top of each zone you have created. A table of dates and elevations defines each curve. The first date in the table is always 01Jan. The curve is defined by straight lines connecting the points defined in the table. By default, the table represents one year, so the last point connects back to the first as the year repeats. If your curve represents more than one year, follow the instructions in Step 3 below for creating a multi-year curve, or follow the instructions in Step 4 below for reading the top of zone from HEC-DSS.

When the selected feature in the operations tree is a Zone, the **Zone Editor** is displayed in the Edit Panel and the mini-plot at the right will illustrate the curves representing the top of each zone. The color of the selected zone's curve will be red. All other zones will be black.

Figure 11.8 shows the curve definition for a zone named **Conservation.**



Figure 11.8 Reservoir Editor--Operations Tab: Zone Editor

To define the top of zone curves, do the following for each zone:

1. Select the Zone in the operations tree to access the **Zone Editor** containing the data for that zone.
2. Enter the **Date** and **Top Elevation** values in the table to define the curve for the zone. You can either copy and paste data from a spreadsheet application or type in the values manually. Note that dates often do not copy and paste correctly and must be entered manually.

Be careful when copying "Date" data from a spreadsheet. Most spreadsheet applications use their own specialized numeric format for dates. Only 'text' can be pasted into a date cell in ResSim.

Dates are entered in a ddmmm format with the month as a three-letter abbreviation. Dates can also be entered with the calendar tool (which can be accessed by double-clicking in a date cell and then clicking the small ellipse button that appears on the right side of the cell).

3. If you wish to **Allow Multi-year Seasonal Data** for the top of zone definition, select this checkbox and enter a four-digit year as a reference for the start of the table. The multi-year table will repeat if the simulation time window overlaps the span of the table. Type in the starting year of the table in the Starting Year field.
4. If you wish to define the zone with a HEC-DSS time-series record, select the **Define Zone with Time Series** check box. You will still need to define a default zone in the table, but that zone definition will be overridden by the time series that you will later select for the zone on the time-series tab of the Alternative Editor (see Chapter 13, Section 13.7).
5. When you have finished entering top of zone curves for a zone, be sure to click the **Apply** button before moving on to the next zone. Be careful when defining each zone curve – zones should NOT cross each other.

11.3.4 Deleting Operation Zones

To delete a zone from an operation set:

1. Select the Zone you wish to delete from the operations tree.
2. Select **Delete** from the **Zone** menu or select **Delete** from the shortcut menu by right-clicking on the zone you wish to delete in the operations tree.
3. Click **OK** in the **Delete Storage Zone** dialog box to complete the delete process.

The Inactive Zone is a special zone in the operation set. If you delete the Inactive Zone from the operation set, it cannot be reestablished.

11.4 Understanding Reservoir Operation Rules

Operation Rules represent the flow goals and constraints upon the releases for each zone of the operation set. Each zone can contain a different set of rules depending on the flow limits and requirements of that zone within the regulation plan. As previously described in Section 11.3.3 and illustrated in Figure 11.8, the rules and zones appear in the **Operations Tree** on the left side of the Reservoir Editor's Operations tab window.

11.4.1 Release Decision Process

When a set of rules exist within a reservoir zone, the decision logic first determines what the release would be for *Guide Curve* operation (see Section 11.8). Then, working from the "lowest to the highest" priority rule, the program adjusts the release to meet each rule. If two rules contradict each other, the higher priority rule applies (see Section 11.4.5 for a description of prioritizing rules).

The release decision process has 3 basic steps:

1. Identify the maximum and minimum *physical limits* on the release. This is the allowable release range.
2. Narrow the allowable *release range* by applying the rules in the current zone, starting with the highest priority rule (see Section 11.4.5 for a description of prioritizing rules). For example, if a higher priority rule defines a more restrictive limit on the range that is currently defined by a lower priority rule, then the more restrictive limit is applied. However, if a rule defines a limit outside the current range, then the rule is ignored.
3. Evaluate the desired release for the basic *Guide Curve* operation (see Section 11.8). This is the release needed to get the reservoir to the guide curve in the current time step (computation interval) based on the starting pool elevation, the prior release, and the current inflow.

If the desired release falls within the allowable release range, then the release decision will be the desired release determined in Step 3 above. However, if the desired release is outside the allowable release range determined in the first two steps above, the release will be set to the limit closest to the desired value.

11.4.2 Using Existing Rules

Once you have defined a rule, you can include it in more than one zone by selecting **Use Existing** from the **Rule** menu of the Reservoir Editor.

Rules belong to the Reservoir in the current Network, not to a zone or to an operation set. Therefore, any given rule can be used in more than one zone and in more than one operation set. So, be careful – a change to a reservoir's rule in one operation set carries through all operation sets in the current Network that use that rule.

11.4.3 Removing Rules

You can remove a rule from a zone by highlighting the rule in the operations tree and then selecting **Remove** from the shortcut menu (or select **Remove from Zone** from the **Rule** menu of the Reservoir Editor). Removing a rule from a zone does not delete the rule. The rule still exists in the reservoir for inclusion in other zones and operation sets.

11.4.4 Deleting Rules

To delete a rule from the reservoir, you can use the **Delete** option from the **Rule** menu. ***Use caution when deleting rules.*** When you delete a rule, it will no longer be available in any of the zones in this, or any other, operation set for this reservoir in the current reservoir network.

11.4.5 Prioritizing Rules

You must prioritize the rules within a zone, with the highest priority rule being at the top of the list. To raise or lower the priority of a rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu. In Section 11.5, pay special attention to the discussion for each rule type. Some rules, such as the Induced Surcharge rule (see Section 11.5.6), may need to be the highest priority rule in a zone.

11.4.6 Renaming Rules

To rename a rule, highlight the rule in the operations tree and select **Rename** from the shortcut menu (or select **Rename** from the **Rule** menu of the Reservoir Editor). ***Use caution when renaming rules.*** If you rename a rule, all instances of the rule will be renamed (i.e., the rule's existence within all reservoir zones and operations sets for the reservoir in the current reservoir network).

11.5 Defining Reservoir Operation Rules

This section explains how to define a variety of rules using the different rule types available in ResSim for reservoir Pools, Outlets, and Outlet Groups. Rule types differ depending on whether you apply the rule to the reservoir **Pool**, to a **Dam** (or an **Outlet Group** or **Diverted Outlet**), or to a **Controlled Outlet**. The Operations tab of the Reservoir Editor provides a separate editor for each rule type, as listed below and described in subsequent sub-sections.

Rules for the **Reservoir Pool** include:

- Release Function
- Downstream Control Function
- Tandem Operation
- Induced Surcharge
- Flow Rate of Change Limit
- Elevation Rate of Change Limit

Rules for the **Dam** and **Outlet Groups** and **Diverted Outlets** are as follows:

- Release Function
- Flow Rate of Change Limit

Rules for the **Controlled Outlets** are as follows:

- Release Function
- Flow Rate of Change Limit
- Hydropower Requirements:
    - Hydropower Schedule – Regular
    - Hydropower Schedule – Time Series
    - Power Guide Curve

11.5.1 Adding a New Operation Rule to a Zone

When you create a rule, you must name it, assign the rule to a specific sub-element of the reservoir, and select the rule type. The list of available sub-elements includes: the reservoir **Pool** (identified by the name of the reservoir); the **Dam** (identified by the reservoir name hyphenated with the dam name), **Outlet Groups**, and **Diverted Outlets**; and, all user-defined **Controlled Outlets**.

To add a new operation rule to a zone:

1. Highlight the appropriate Zone in the operations tree.
2. Select **New** from the **Rule** menu of the Reservoir Editor. The **New Operating Rule** dialog box will open.
3. Select the control element of the reservoir to which you will assign this rule (reservoir pool, dam, outlet group, outlet) from the **Operates Release from** list (Figure 11.9).



Figure 11.9 New Operating Rule Dialog Box

4. Select the **Rule Type** from the list. The available rule types will depend upon whether you have selected a pool, dam, outlet, or outlet group, as listed in Section 11.5
5. Enter a **Name** for the new rule.
6. Click **OK** to close the **New Operating Rule** dialog box.

The new rule will appear, highlighted, in the operations tree and the edit panel will display the rule editor based on the rule type. The first two fields for each rule editor contain the name of the rule and its description. These fields are editable, however, use care when editing a rule name – all instances of the rule (in all operation sets) will be updated. See the appropriate section below to determine how to define the data for your new rule.

11.5.2 Adding an Existing Rule to a Zone

Once you have created a rule in a zone, you may want to use that same rule in another zone so you do not have to create a new rule in the other zone.

To add an existing operation rule to a zone:

1. Highlight the appropriate Zone in the operations tree.
2. Select **Use Existing** from the **Rule** menu of the Reservoir Editor or **Use Existing Rule** from the zone's shortcut menu. The **Select Existing Rule** dialog box will open (similar to Figure 11.10 which shows an example list of existing rules).



Figure 11.10 Select Existing Rule Dialog Box

3. Select the rule you want to add from the list. Only those rules defined for the current reservoir *but not yet used in the current zone* will be listed.
4. Click **OK** to complete the Use Existing process and close the dialog box.

11.5.3 Defining a Release Function Rule

The **Release Function** rule type is one of the two most powerful rule types available (the other being the **Downstream Control Function** rule). With this rule type, you can define a wide array of rules, any of which can be described as a "function of" rule. This rule can be assigned to any of the release elements (pool, dam, or outlet) and it allows you to specify the maximum, minimum, or *specified* flow to be released through the release element.

Use **specified** *with caution. Most operation rules describe either a minimum or maximum limit. Specified rules describe the precise amount of flow to be released, neither more or less, making them effectively both a minimum and a maximum limit at the same time. A specified release rule, therefore, sets the allowable range of the release to a single value.*

The simplest rules to define with this rule type are those where the release limit is a "function of date". Rules of this type are seasonally-varying release limits. For example: "the maximum release from the reservoir during the growing season is 6500 cfs and 8500 cfs during the non-growing season".

The more complex rules that you can create with the Release Function rule type are those where the release limit is a function of an internal (model) variable or an external variable, such as a rule where the minimum release is a function of the inflow to the reservoir. Inflow to the reservoir is just one of many internal or "model" variables that can be used to create a "function of model variable" rule. The "function of external variable" rule is also very powerful, limited only by your imagination and the time-series data available. An example of an "external variable" rule might be one where the minimum release is a function of dissolved oxygen at a specific gage. Since ResSim cannot compute dissolved oxygen, a time-series record that describes the predicted or observed values for that variable would be used to influence the release based on the function you define.

To define a Release Function rule:

1. To create a new Release Function rule, follow the instructions in Section 11.5.1. Be sure to select **Release Function** for the **Rule Type** in the **New Operating Rule** editor.
2. Highlight the appropriate rule in the operations tree to access the **Release Function** rule editor (Figure 11.11). The name and description of the rule will appear in the **Rule Name** and **Description** fields.



Figure 11.11 Reservoir Editor--Operations Tab: New Release Function Rule

3. Define the Release Function:
   - Click the "Function of:" **Define** button. The **Independent Variable Definition** editor will open (Figure 11.12).



Figure 11.12 Reservoir Editor--Operations Tab: Release Function Rule, Selecting a Function from the Independent Variable Definition Editor

   - Select the function type from the "**Release is a Function of**" list: **Date**, **Date and Time**, **Model Variable** or **External Variable**.
   - If the function type is **Model Variable**, select the independent variable using the **Filter** chooser (Figure 11.13).



Figure 11.13 Reservoir Editor--Operations Tab: Release Function Rule, Selecting an Independent Variable from the Model Variable List

- If the function type is **External Variable**, identify the independent variable in the name field (Figure 11.14). This name will appear on the time-series tab of the Alternative Editor (see Chapter 13, Section 13.7).



Figure 11.14 Reservoir Editor--Operations Tab: Release Function Rule, Defining an External Variable as the Independent Variable

- If desired, for either the Model or External variables, select the **Time Series Options** for the independent variable. From the **Function** list (Figure 11.15), you can select **Current Value**, **Previous Value**, **Lagged Value**, **Period Average**, **Period Maximum**, and **Period Minimum**. The **Lag** (in hours) can be specified (for all but Current and Previous value) along with the appropriate **Period** (in hours).



Figure 11.15 Time Series Options for Model and External Variables

- Click **OK** to complete the definition of the independent variable of your function.

4. Set the **Limit Type** as Minimum, Maximum or *Specified*.

> *Use* **specified** *with caution. Most operation rules describe either a minimum or maximum limit. Specified rules describe the precise amount of flow to be released, neither more or less, making them effectively both a minimum and a maximum limit at the same time. A specified release rule, therefore, sets the allowable range of the release to a single value.*

5. Select the **Interpolation Type** as Linear, Cubic, or Step (see Section 11.6.1 for a description of how the interpolation types work).

6. Define the function using the table in the release function rule editor (see Figure 11.16). You can either copy and paste data from a spreadsheet application or type in the values manually.

> *Be careful when copying date data from a spreadsheet. Most spreadsheet applications use their own specialized numeric format for dates. Only 'text' can be pasted into a date cell in ResSim.*

   The mini-plot will reflect the values you enter and can be viewed in full size when you double-click on it.

   - If using a function of date, you can enter a single value for 01 Jan to describe a constant release limit throughout the year or enter multiple dates to define a seasonally varying release limit rule. Dates can also be entered with the calendar tool, which can be accessed by double-clicking in a date cell then clicking the ellipse button that appears.
   - If your rule is a function of variable rule, you can make your rule *seasonally varying* by using the **Seasonal Variation** option. Refer to Section 11.6.5 for more details.

7. If you wish to use **Hour of Day** or **Day of the Week Multipliers**, refer to Sections 11.6.2 and 11.6.3 for more details.
8. To make your rule applicable only under rising (or falling) conditions, use the **Rising/Falling Condition** option. Refer to Section 11.6.4 for details.
9. Check the position of your new rule with respect to the other rules in this zone. To raise or lower the priority of a rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.

An example of a completed **Release Function** rule is shown in Figure 11.16. When you have finished entering data for the Release Function rule, be sure to click the **Apply** button before moving on to the next rule.



Figure 11.16 Reservoir Editor--Operations Tab: Example of Completed Release Function Rule

11.5.4 Defining a Downstream Control Function Rule

This rule type (and its editor) is an extension of the Release Function rule described in Section 11.5.3. Downstream control rules describe the minimum or maximum flow (e.g., flow requirement or channel capacity) or stage at a control point rather than an explicit limit on the release. The final release limit will be determined based on the influence of routing and cumulative local flows at the downstream control point.

In addition, the Downstream Control rules can be used to create system operation (where two or more parallel reservoirs are operated to have balanced storages while controlling for common downstream requirements). Once created for one reservoir, the Downstream Control rule will also be available in the List of Existing Rules (refer to Section 11.5.2) for other reservoirs in the network. *To establish a system operation, the same downstream control rule must be used in each applicable reservoir's operation set.* Chapter 12 discusses ResSim's methodology for system operation and storage balancing.

When creating the Downstream Control rule, it can be assigned only to the *reservoir* (pool), not to a specific outlet or outlet group, because only the reservoir can account for all releases from the reservoir's outlets that could influence the flow at the downstream control point.

To enter operations data for a Downstream Control Function rule:

1. To create a downstream control rule, follow the instructions for creating a new rule as described in Section 11.5.1. After selecting the **Operate Release from** to be the *reservoir* and the **Rule Type** to be **Downstream Control Function**, be sure to select the downstream control point from the **Downstream Location** list that appears when you select the Downstream Control Function rule type. Figure 11.17 illustrates the creation of a Downstream Control Function rule.



Figure 11.17 Reservoir Editor--New Operating Rule: Downstream Control Function

2. To define your downstream control rule, refer to Section 11.5.3 detailing how to define a Release Function rule. The Downstream Control Function rule editor is essentially the same as the Release Function rule editor. The only significant difference is that you have the option of defining the rule as a minimum or maximum **Flow** or **Stage** parameter limit at the downstream control point (see example in Figure 11.18).



Figure 11.18 Reservoir Editor--Example of a Downstream Control Function Rule

3. Check the position of your new rule with respect to other rules in the zone it is placed. To raise or lower the priority of a rule within the rule list for a particular zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.
4. When you have finished entering data for the Downstream Control Function rule, be sure to click the **Apply** button before moving on to the next rule.

After a downstream control rule has been defined, the downstream location in the display area will have a box drawn around the junction symbol.

11.5.5 Defining a Tandem Operation Rule

A **Tandem Operation** rule establishes a tandem system operation where an upstream reservoir operates for a downstream reservoir to achieve a storage balance. Unlike the Downstream Control rule, which is the only other rule type used for system operation and must be included in the operation sets of all reservoirs in the system, the Tandem Operation rule is created and included in the operation set at the upstream reservoir only. The Tandem Operation rule simply identifies the downstream reservoir that is being operated for. An implicit (default) storage balance scheme is invoked by the Tandem Operation rule, and an optional explicit (user-defined) storage balance scheme can be defined and used instead of the default (refer to Chapter 12 for more discussion on system operation).

When creating the Tandem Operation rule, it can be assigned only to the reservoir (pool), not to a specific outlet or outlet group, because only the reservoir can account for all releases from the reservoir's outlets that could influence the flow into the downstream reservoir.

To enter operations data for a Tandem Operation rule:

1. To create a Tandem Operation rule, follow the instructions for creating a new rule as described in Section 11.5.1. Be sure to select the *reservoir* for the release component (**Operates Release from**) and **Tandem Operation** for the **Rule Type** in the **New Operating Rule** editor. Figure 11.19 illustrates the creation of a Tandem Operation rule.



Figure 11.19 Reservoir Editor--New Operating Rule: Tandem Operation

2. To define your Tandem Operation rule, highlight the rule in the operations tree of the reservoir editor (Figure 11.20). In the Edit Panel, you can change the name of the rule, enter a description, and most importantly select the downstream reservoir for which the current (upstream) reservoir is operating.



Figure 11.20 Reservoir Editor--Example of a Tandem Operation Rule

3. Check the position of your new rule with respect to other rules in the zone it is placed. To raise or lower the priority of a rule within the rule list for a particular zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.
4. When you have finished setting up the Tandem Operation rule, be sure to click the **Apply** button before moving on to the next rule.

11.5.6 Defining an Induced Surcharge Rule

Induced Surcharge is a flood control operation that specifies emergency releases when the current pool elevation and rate of increase in inflow (or change in pool elevation) threaten to overtop the dam. This operation may necessitate releases that exceed channel capacity constraints. A reservoir must have a gated outlet to employ induced surcharge operations.

Induced Surcharge operation is achieved by physically regulating the position of spillway gates. When the gate opening is reduced to limit release to less than free overflow (the fully-open position), water is intentionally surcharged—or stored—behind the gates. For this reason, induced surcharge is also referred to as a gate regulation operation. Induced Surcharge operation allows operators to better manage a flood event by using additional reservoir storage volume above the spillway crest.

In HEC-ResSim, the Induced Surcharge rule must be defined and entered as the *highest priority rule* in every zone spanning elevations between the top of the dam and the lowest elevation from which the gate can be regulated, generally, the controlled spillway crest. Additionally, a Release Function rule (see Section 11.5.3) with **Limit Type** set to **Maximum** must be defined and entered as a lower priority rule in each of the applicable zones (below the induced surcharge rule). This maximum flow corresponds to the maximum discharge when surcharge operations are not in effect. It is essential to enter this maximum flow limit to guide releases back towards flood control operations after surcharge operations finish. Note that when creating a new rule, the Induced Surcharge option is only available if the "reservoir itself" is selected for **Operates Release from:** ("Sayers" in Figure 11.21, not "Sayers-Dam" or "Sayers-Gate").



Figure 11.21 Reservoir Editor--Operations Tab: Create Induced Surcharge Rule

Within the **Induced Surcharge** rule editor (Figure 11.22), the **Induced Surcharge Curve**, **Time of Recession**, and **Falling Pool Options** determine the magnitude and duration of gate-regulated releases, and how emergency release should transition back to normal flood control releases. The mini-plot will reflect the **Elevation** vs. **Release** values you enter for the Induced Surcharge Envelope and can be viewed in full size when you double-click on it.



Figure 11.22 Reservoir Editor--Operations Tab: Induced Surcharge Rule

To enter operational data for an Induced Surcharge rule:

1. Highlight the appropriate rule in the operations tree to access the **Induced Surcharge** rule editor (Figure 11.22). The name and description of the rule will appear in the **Induced Surcharge Rule** and **Description** fields.
2. Select the **Interpolation Type** as Linear or Cubic (see Section 11.6.1).
3. Enter **Elevation** and **Release** data into the table to describe the Induced Surcharge Envelope. This envelope defines the lower limit of allowable regulated release when the pool is at a certain elevation. The rule will compute a higher release as described in EM 1110-2-3600 (USACE, 1987). You can either copy and paste data from a spreadsheet application or type in the values manually.
4. Enter the **Time of Recession** in hours. This constant describes the length of time an incoming flood is expected to take to recede. The program uses this time to compute the volume of water that must be evacuated to prevent overtopping the dam. See discussion in EM 1110-2-3600 (USACE, 1987) for further documentation regarding the Recession Time constant parameter (Ts).

5. Select **Plot Surcharge Curves** to see plots of the computed Induced Surcharge Curves (Figure 11.23) based on the data you have entered.



Figure 11.23 Plot of Computed Induced Surcharge Curves

6. Next, select **Falling Pool Options** by clicking the **Edit** button beside the **Falling Pool Options** label. The **Falling Pool Options** dialog box will open (Figure 11.24).



Figure 11.24 Induced Surcharge--Falling Pool Options

7. In the Induced Surcharge - Falling Pool Options dialog box (Figure 11.24), enter the **Time for Pool Decrease** in hours. This parameter describes the required number of successive hours the reservoir pool level must be falling before transitioning from rising pool emergency spillway releases to falling pool releases.

8. Enter the **Falling Pool Transition Elevation** in feet (meters). This parameter represents the pool elevation above which Falling Pool releases will be made. Once the pool elevation falls below this elevation, the Induced Surcharge rule will no longer operate, and ResSim will resume releases based on other rules in the active zone.
9. For **Release Options**, choose Ratio of Inflow, Average of Inflow and Previous Release, or Maintain Peak Release to designate the method for computing falling pool releases. Falling Pool Releases will be made after the pool begins to fall and until the pool level returns to the Falling Pool Transition Elevation.
   - For **Ratio of Inflow**, enter the **Release** ratio **times inflow averaged over** number of **hours**.
   - For **Average of Inflow and Previous Release**, enter the number of **hours** for the **Inflow** to be **averaged over**.
10. Click **OK** to close the Falling Pool Options dialog and a checkmark will display in the box beside **Falling Pool Options** in the Reservoir Editor.
11. Check the position of your new rule with respect to the other rules in this zone. To raise or lower the priority of a rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.
12. When you have finished entering data for the Induced Surcharge rule, be sure to click the **Apply** button before moving on to the next rule.

11.5.7 Defining a Flow Rate of Change Limit Rule

A **Flow Rate of Change Limit** rule specifies the allowable change when increasing or decreasing release values (i.e., "ramping rates"). A single rule of this type will only limit a rising release or a falling release, but not both. To describe both increasing and decreasing limits, you must define two rules and set the type of one to increasing and the other to decreasing. A rule of this type can be assigned to any release element to influence the behavior of that element.

To enter operations data for a Flow Rate of Change Limit rule:

1. To create a new rule, follow the instructions in Section 11.5.1. Be sure to select **Flow Rate of Change Limit** for the **Rule Type** in the **New Operating Rule** editor.
2. Highlight the appropriate rule in the operations tree to access the **Flow Rate of Change Limit** rule editor (Figure 11.25). The name and description of the rule will appear in the **Release Rate of Change Limit** rule and **Description** fields.



Figure 11.25 Reservoir Editor--Operations Tab: Flow Rate of Change Limit Rule

3. For **Function Of:**, select either **Constant**, **Reservoir Inflow**, **Release**, or **Pool Elevation**.
4. For **Type**, select either **Increasing** or **Decreasing**.
5. Enter the **Max Rate of Change** value. The limit is described in units of flow (cms or cfs) per hour, regardless of the compute interval. For example, if you enter 500 cfs/hr with a compute interval of 12 hours, then this rule describes the maximum flow change per time step as 6000 cfs.
   - If your **Function Of:** selection is **Constant**, enter a single value for the limit.
   - If your **Function Of:** selection is **Reservoir Inflow**, **Release**, or **Pool Elevation**, then a table will appear to allow you to describe how the rate of change is influenced by the selected independent variable. Additionally, select the type of **Interpolation** to apply to the curve as either **Linear**, **Cubic**, or **Step** (see Section 11.6.1).
6. Check the position of your new rule with respect to the other rules in this zone. To raise or lower the priority of a rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.
7. When you have finished entering data for the Flow Rate of Change rule, be sure to click the **Apply** button before moving on to the next rule.

11.5.8 Defining an Elevation Rate of Change Limit Rule

An **Elevation Rate of Change Limit** rule describes the allowable change when increasing or decreasing pool elevation values. A single rule of this type will only limit a rising pool or a falling pool, but not both. To describe both increasing and decreasing limits, you must define two rules and set the type of one to increasing and the other to decreasing. Since this rule watches the pool elevation, you can assign

this rule only to the pool (reservoir), not to the dam or to a discrete outlet.

To enter operations data for an Elevation Rate of Change Limit rule:

1. To create a new rule, follow the instructions in Section 11.5.1. Be sure to select the *reservoir* for the Release Element and **Elev Rate of Change Limit** for the **Rule Type** in the **New Operating Rule** editor.
2. Highlight the appropriate rule in the operations tree to access the **Elevation Rate of Change Limit** rule editor (Figure 11.26). The name and description of the rule will appear in the **Elevation Rate of Change Limit** Rule and **Description** fields.



Figure 11.26 Reservoir Editor--Operations Tab: Elevation Rate of Change Limit Rule (Pool)

3. For **Function Of:**, select either **Constant**, **Reservoir Inflow**, or **Release**.
4. For **Type**, select either **Increasing** or **Decreasing**.
5. Choose either **Instantaneous** or **Period Average**.
   - For **Instantaneous**, enter the **Max Rate of Change** value in units of meters (feet) per hour.
   - For **Period Average**, specify the **Max Change** and the number of **Hours** over which the change is allowed.
6. Check the position of your new rule with respect to the other rules in this zone. To raise or lower the priority of a rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.
7. When you have finished entering data for the Elevation Rate of Change Limit rule, be sure to click the **Apply** button before moving on to the next rule.

11.5.9 Defining Hydropower Rules

There are three different Hydropower rule types (see Figure 11.27) available for you to create a rule that describes a hydropower requirement: **Hydropower – Schedule**, **Hydropower – Time Series Requirement**, and **Hydropower – Power Guide Curve**. Data entry for these rules will be described in the following sub-sections.



Figure 11.27 Hydropower Rule Types

11.5.9.1 Hydropower – Schedule

The Hydropower – Schedule rule allows you to define a regular *monthly schedule* of hydropower requirements. The various options on this rule editor allow you to define each month's power generation requirement, the form of the specification of the requirement (megawatt-hours or plant factor), and the hours of the day and days of the week during which the plant/outlet can generate.

To define a Hydropower – Schedule Requirement rule:

1. To create a new rule, follow the instructions in Section 11.5.1. Be sure to select the specific outlet containing the power plant for the Release Element and then select **Hydropower – Schedule** for the **Rule Type** in the **New Operating Rule** editor.
2. Highlight the appropriate rule in the operations tree to access the **Hydropower – Schedule** rule editor (Figure 11.28). The name and description of the rule will appear in the **Hydropower – Schedule** rule and **Description** fields.
3. Select the units in which you will specify the requirement (MWH or % Plant Factor).
4. Complete the table by entering the total monthly requirement for each month of the year.



Figure 11.28 Hydropower – Schedule Rule Editor

5. If desired, use **Hour of Day Weighting** and **Day of Week Weighting** factors to define the daily and weekly schedule during which the outlet/plant should operate to meet the monthly requirement. Refer to Sections 11.5.9.4 and 11.5.9.5 for more details.
6. Check the position of your new rule with respect to the other rules in the zone. To raise or lower the priority of your rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.
7. When you have finished entering data for the Hydropower - Schedule rule, be sure to click the **Apply** button before moving on to the next rule.

11.5.9.2 Hydropower – Time Series Requirement

The Hydropower – Time Series Requirement rule allows you to define an *irregular schedule* of Hydropower requirements through the use of a DSS time-series record. There are no options in this rule editor. Instead, a message is placed there to remind you that you will need to specify a time series of required power in units of megawatts when you develop an alternative that uses this operation set for this reservoir.

To define a Hydropower – Time Series Requirement rule:

1. To create a new rule, follow the instructions in Section 11.5.1. Be sure to select the specific outlet containing the power plant for the Release Element and then select **Hydropower – Time Series**

Requirement for the **Rule Type** in the **New Operating Rule** editor.

2. Highlight the appropriate rule in the operations tree to access the **Hydropower – Time Series Requirement** rule editor (Figure 11.29). The name and description of the rule will appear in the **Hydropower – Time Series Requirement** rule and **Description** fields.



Figure 11.29 Hydropower – Time Series Requirement Rule Editor

3. Make note of the message and the name of the Rule you just created. When you develop an alternative for this network, reservoir, and operation set, you will need to provide a DSS time-series pathname specification for this rule. The entry in the Time Series table of the rule editor will be identified by the rule name with a parameter of power.

11.5.9.3 Hydropower – Power Guide Curve

The Hydropower – Power Guide Curve rule allows you to define a function that describes the hydropower generation requirement with respect to the available storage in the "power pool". The power requirement must be described in units of % plant factor.

To define a Hydropower – Power Guide Curve Requirement rule:

1. To create a new rule, follow the instructions in Section 11.5.1. Be sure to select the specific outlet containing the power plant for the Release Element and then select **Hydropower – Power Guide Curve** for the **Rule Type** in the **New Operating Rule** editor.

2. Highlight the appropriate rule in the operations tree to access the **Hydropower – Power Guide Curve** rule editor (Figure 11.30). The name and description of the rule will appear in the **Hydropower – Power Guide Curve** rule and **Description** fields.



Figure 11.30 Hydropower – Power Guide Curve Rule Editor

3. From the lists for **Zone at Top of Power Pool** and **Zone at Bottom of Power Pool**, select the top of zone curves that bound the top and bottom of the **Power Pool**.
4. Complete the table to define the **Power Guide Curve**. The first column is the *percent of power storage* available in the power pool. These values should increase as you move down in the table. The second column is the *percent plant factor*. This is the power requirement as a percentage of the plant's capacity to generate.
5. If desired, use **Hour of Day Multiplier** and **Day of Week Multiplier** factors to define the daily and weekly schedule during which the outlet/plant should operate to meet the monthly requirement. Refer to Sections 11.6.2 and 11.6.3 for more details.
6. If desired, use **Seasonal Multiplier** factors to raise or lower the requirements throughout the year.
7. Check the position of your new rule with respect to the other rules in the zone. To raise or lower the priority of your rule within the rule list for the current zone, use the **Increase/Decrease Priority** or **Move to Top/Bottom** options in the rule's shortcut menu or from the **Rule** menu.

8. When you have finished entering data for the Hydropower – Power Guide Curve rule, be sure to click the **Apply** button before moving on to the next rule.

11.5.9.4 Hour of Day Weighting Factors

The Hour of Day Weighting Factors allow you to specify an hourly distribution of daily energy requirements (see Section 11.5.9.5) based on the *time of the day*. For example, if you want the power plant to generate during a portion of the day, you can set the factor for those hours to 1.0 and set all other hours to 0.0. To do this, click on the Hour of Day Weighting **Edit** button. The **Hour of Day Weighting** editor will appear where you will see that the default value for all hours of the day is 1.0 (Figure 11.31). To specify that energy would only be generated from 8:00 a.m. to 5:00 p.m., change the value of 1.0 to 0.0 for hours 0000-0800 and 1700-2400 (Figure 11.32).



Figure 11.31 Hour of Day Weighting with Default Values of 1.0 Specified for Entire Day



Figure 11.32 Hour of Day Weighting with Values of 1.0 Specified for Portion of Day

Basically, the values of 1.0 and 0.0 turn the hourly requirement "on" and "off", respectively (as previously shown in Figure 11.32). However, to indicate that the energy requirement between 10:00 a.m. and 1:00 p.m. is *twice* the energy requirements of the other hours (when energy is being generated), you would change the value of 1.0 to 2.0 for hours 1000-1300 (Figure 11.33).

Click **OK** to close the **Hour of Day Weighting** editor. In the hydropower rule editor, the check box in front of the Hour of Day Weighting will display a check mark, as shown in Figure 11.34 (only when the default set of weighting factors is modified).



Figure 11.33 Hour of Day Weighting to "Double" the Power Requirement for Portion of Day

Figure 11.34 Hour of Day Weighting Modified from Default Values

11.5.9.5 Day of Week Weighting Factors

The Day of Week Weighting Factors allow you to specify a daily distribution of monthly energy requirements (see Section 11.5.9.1) based on the *day of the week*. For example, if you want the power plant to only generate during a portion of the week (e.g., during the work week), you can set the factor 1.0 for Monday-Friday and set it to 0.0 for Saturday and Sunday. To do this, click on the Day of Week Weighting **Edit** button. The **Day of Week Weighting** editor will appear where you will see that the default value for all days of the week is 1.0 (Figure 11.35). To specify that energy would only be generated Monday through Friday, change the value of 1.0 to 0.0 for Saturday and Sunday (Figure 11.36).



Figure 11.35 Day of Week Weighting with Default Values of 1.0 for Each Day of the Week



Figure 11.36 Day of Week Weighting with Values of 0.0 for Saturday and Sunday

Basically, the values of 1.0 and 0.0 turn the daily requirement "on" and "off", respectively (as previously shown in Figure 11.36). However, to indicate that the energy requirement on Wednesday is *twice* the energy requirements of the other days (when energy is being generated), you would change the value of 1.0 to 2.0 for Wednesday (Figure 11.37).



Figure 11.37 Day of Week Weighting to "Double" the Power Requirement on Wednesday

Click **OK** to close the **Day of Week Weighting** editor. In the hydropower rule editor, the check box in front of the Day of Week Weighting will display a check mark, as shown in Figure 11.38 (only when the default set of weighting factors is modified).

Figure 11.38 Day of Week Weighting Modified from Default Values

11.6 Common Options for Rule Definition

All of the function rules allow the specification of one or more options to modify the release requirement defined by the rule. These options can be used individually or in combination with one or more other options. The rule definition options are described below and include Interpolation Method, Hour of Day and Day of Week multipliers, Rising and Falling conditions, and Seasonal Variation.

11.6.1 Interpolation Method

Many of the rule types describe the release as a function of some variable (e.g., time, elevation, inflow, etc.). You will need to enter these functions in the form of a table where the values of the variable increase as you move down the table. You must indicate to the program how to determine values between those values explicitly entered in the table by selecting one of the following interpolation types (see Figure 11.39):



Figure 11.39 Interpolation Methods

- **Linear Interpolation** (Figure 11.40) means the table describes a curve drawn with straight lines. Values between those values entered in the table are linearly interpolated.



Figure 11.40 Linear Interpolation Method

- **Step Interpolation** (Figure 11.41) means that the table describes a step function, where the values in one row hold constant until changed by the next row.



Figure 11.41 Step Interpolation Method

- **Cubic Interpolation** (Figure 11.42) will cause the program to interpret the table as a 3-point Cubic Spline curve. The interpolation between entered values is determined by the cubic spline function defined with each three consecutive rows in the table.



Figure 11.42 Cubic Interpolation Method

11.6.2 Hour of Day Multiplier

The Hour of Day Multiplier allows you to specify a factor (based on the *time of day*) that will be applied to the release specified by a rule. To do this, click on the Hour of Day Multiplier **Edit** button. The **Hour of Day Multiplier** editor will appear where you will see that the default value for all hours of the day is 1.0 (Figure 11.43). If you have a minimum release rule that requires a minimum flow only during a portion of the day, you can set the multiplier for those hours to 1.0 and set all other hours to 0.0. For example, to specify that a rule would only apply from 8:00 a.m. to 5:00 p.m., change the value of 1.0 to 0.0 for hours 0000-0800 and 1700-2400 (Figure 11.44). If you want to increase the minimum release by 50% between 1:00 p.m. and 3:00 p.m., then enter a factor of 1.5 for hours 1300-1500.



Figure 11.43 Hour of Day Multiplier with Default Values of 1.0 Specified for Entire Day



Figure 11.44 Hour of Day Multiplier with Values of 0.0 Specified for Portion of Day

Click **OK** to close the **Hour of Day Multiplier** editor. In the rule editor, the check box in front of the Hour of Day Multiplier will display a check mark (only when the default set of multipliers is modified, as shown in Figure 11.45).

Figure 11.45 Hour of Day Multiplier Modified from Default Values

11.6.3 Day of Week Multiplier

The Day of Week Multiplier allows you to specify a factor (based on the *day of the week*) that will be applied to the release determined by a rule. To do this, click on the Day of Week Multiplier **Edit** button.

The **Day of Week Multiplier** editor will appear (Figure 11.46) where you will see that the default value is 1.0 for all days of the week (Sunday through Saturday).



Figure 11.46 Day of Week Multiplier with Default Factors of 1.0 Specified for Each Day of the Week

If you have a minimum release rule that requires a minimum flow only during Monday through Friday, you can set the multiplier for Saturday and Sunday to 0.0 and leave all other days set to 1.0 (Figure 11.47).



Figure 11.47 Day of Week Multiplier with Factors of 0.0 Specified for Saturday and Sunday

If you want to increase the minimum release by 50% on Wednesday, then enter a factor of 1.5 for Wednesday.

Click **OK** to close the **Day of Week Multiplier** editor. In the rule editor, the check box in front of Day of Week Multiplier will display a check mark (only when the default set of multipliers is modified, as shown in Figure 11.48).

Figure 11.48 Day of Week Multiplier Modified from Default Values

11.6.4 Rising / Falling Condition

The Rising/Falling Condition is a mechanism you can use to restrict the applicability of a rule. If, during a given decision interval, the specified condition is met, then ResSim evaluates the rule and applies it within the release determination logic. However, if the condition is not met, ResSim ignores the rule.

The Rising/Falling Condition option is available from many of the rule editors and allows you to select one of eight conditions with which you can restrict the applicability of a rule. These conditions include rising pool elevation, rising or constant pool elevation, falling pool elevation, falling or constant pool elevation, rising inflow, rising or constant inflow, falling inflow, or falling or constant inflow.

To apply a rising/falling condition to a rule:

1. Click the Rising/Falling Condition **Edit** button and the **Rising/Falling Condition** dialog box will open (Figure 11.49).
2. For the **Condition**, choose **Rising**, **Rising or Constant**, **Falling or Constant**, or **Falling** from the list.
3. For the **Parameter**, choose **Pool Elevation** or **Inflow** from the list.



Figure 11.49 Rising / Falling Condition Dialog Box

4. Enter values for **Average Period** and **Tolerance**. These attributes help determine if the trend of the data meets the condition, rather than allowing a small deviation in the data to cause unstable or unexpected behavior.
5. Click **OK** to close the **Rising/Falling Conditions** dialog box. A check mark will appear in the Rising/Falling Conditions checkbox (as shown in Figure 11.50).

Figure 11.50 Rising / Falling Condition Modified from Default

11.6.5 Seasonal Variation

If your rule is a function of an internal (model) variable or an external variable (see Section 11.5.3), you can make your rule *seasonally varying* by using the **Seasonal Variation** option. For example, if the maximum flow allowed at a downstream control is described as a function of pool elevation and growing season, you would create a downstream control rule, make it a function of pool elevation, then select the Seasonal Variation **Edit** button from the rule editor. The **Seasonal Variation** editor will be displayed (Figure 11.51).

Enter the dates when the seasons change in the table. Each additional entry in the table will create an additional column in the function table on the main rule editor. Before clicking **OK**, be sure to select the interpolation type (see Section 11.6.1 for details on **Interpolation** methods). This will define how values will be determined between the seasonal columns describing the release function.



Figure 11.51 Seasonal Variation Dialog Box

11.7 Editing the Reservoir Decision Interval

By default, the reservoir makes a new release decision at every computation interval. The Reservoir Decision Interval Editor (Figure 11.52) allows you to specify a different decision interval (or schedule). By changing the decision interval, you can require the reservoir to evaluate conditions over a varying time horizon to determine its releases.



Figure 11.52 Reservoir Decision Interval Editor, Interval Options

To edit the reservoir decision interval:

1. Select **Decision Interval** from the **Operations** menu of the Reservoir Editor. The **Reservoir Decision Interval Editor** will open (Figure 11.52).
2. The name of the **Reservoir** and its **Operating Set** appear at the top of the editor.
3. Select an **Interval Option** from the list.
   - **Every Time Step** is the default.
   - **Regular Interval**
     Figure 11.53 allows you to specify the decision interval as some multiplier of the compute interval.
   - **Weekly Schedule**
     Figure 11.54 allows you to specify the days of the week and the hours of the day at which the reservoir can change the releases.



Figure 11.53 Reservoir Decision Interval Editor, Regular Interval Option



Figure 11.54 Reservoir Decision Interval Editor, Weekly Schedule Option

4. Click **OK** to close the editor.

11.8 Selecting the Reservoir Guide Curve

The top of zone curve of any zone in your reservoir can be selected to represent the Guide Curve (i.e., target elevation) of your reservoir. The Guide Curve (or rule curve) represents the basic objective of the reservoir − get the pool elevation to, and hold it at, the Guide Curve. Without any other operational constraints, the decision logic will attempt to get to and keep the reservoir at the Guide Curve, within maximum outlet capacity and physical rate of change constraints. By *default*, the zone initially labeled *Conservation* is selected as the Guide Curve. To select a different zone to represent the Guide Curve for your reservoir operation set:

1. Select **Guide Curve** from the **Operations** menu of the Reservoir Editor (Figure 11.55). The **Reservoir Guide Curve Editor** will open (Figure 11.56). The top portion of the editor is used for selecting the Guide Curve Zone while the bottom portion of the editor is used for defining Credit Storage for Flood Control (described in Section 11.9).



Figure 11.55 Operations Menu, Guide Curve Option



Figure 11.56 Reservoir Guide Curve Editor

2. Select a zone from the **Guide Curve Zone** list. The guide curve zone list includes all of the reservoir's zones in the current operation set and an option named **None**. Selecting the None option is equivalent to selecting the Inactive zone -- it will cause the reservoir to remain empty unless the rules in the zones cause the reservoir to store water for a period of time.

11.9 Adjusting the Guide Curve for Flood Control Credit Storage

In the previous section (Section 11.8), we learned that the Reservoir Guide Curve editor allows you to pick the top of zone curve for any zone in your operation set to act as the guide curve. This editor also allows you to identify reservoirs available to provide **Flood Control Credit Storage** to the current reservoir. What this means is that if flood control space is available in other reservoirs, then the required flood control space in the current reservoir can be reduced. You can think of this as raising the Guide Curve at the current reservoir.

To define the reservoirs providing storage credit and the available flood control space in each reservoir that is used for credit:

1. Select **Guide Curve** from the **Operations** menu of the Reservoir Editor (as previously shown in Figure 11.55). The **Reservoir Guide Curve Editor** will open (as previously shown in Figure 11.56).
2. Click in the check box labeled **Guide Curve Modified by Available Flood Control Storage in Other Reservoirs** (Figure 11.57).

Figure 11.57 Reservoir Guide Curve Editor, Checkbox to Indicate Guide Curve is Modified by Available Flood Control Storage in Other Reservoirs

3. Select the **Edit Reservoir Set**

button to access a dialog box that allows you to choose from a list of available reservoirs.
4. In the **Available** list, click on the name of the reservoir(s) you want to use for flood control storage credit (Figure 11.58), then click **Add** to move it to the **Selected** list. Click **OK** to close the selection dialog box.



Figure 11.58 Reservoir Guide Curve Editor, Edit Reservoir Set to Select Reservoirs to Provide Flood Control Storage Credit

5. The reservoir(s) selected to provide flood control storage credit are shown in the upper table of the Reservoir Guide Curve editor (Figure 11.59). For each reservoir in the upper table, define the **Maximum Credit Pool Storage** (typically, near the storage at the top of the flood pool) and the **Maximum Credit** that the reservoir can provide. You will also need to determine if each reservoir can provide "negative" credit. Negative credit from a credit reservoir would have the effect of lowering the guide curve at the reservoir where you are defining the guide curve. This could occur if the computed storage in the credit reservoir's pool is greater than its maximum credit pool storage.



Figure 11.59 Reservoir Guide Curve Editor, Reservoirs to Provide Flood Control Storage Credit

6. Next, in the lower table of the Reservoir Guide Curve editor (Figure 11.60), define the credit storage that can be used at the current reservoir as a function of the total maximum credit storage provided by those reservoirs listed in the upper table. This can be defined by a single curve or by a seasonally varying family of curves. See Section 11.6.5 for details on the **Seasonal Variation** option.

Available Credit (ac-ft)	Storage Credit (ac-ft)			
	01Jan	15May	15Oct	01Dec
0.0	0.0	0.0	0.0	0.0
15500.0	10000.0	10000.0	5000.0	15000.0
20500.0	20500.0	20500.0	20500.0	20500.0

Figure 11.60 Reservoir Guide Curve Editor, Definition of Function for Using Flood Control Storage Credit

Figure 11.61 shows an example of the Reservoir Guide Curve Editor where Flood Control Storage Credit is defined for a reservoir (Sayers) using credit storage from three reservoirs (Beech Creek, Flat Rock, and Marsh Creek).



Figure 11.61 Example of Reservoir Guide Curve Editor Showing Definition of Flood Control Storage Credit

On the right side of the editor, there are two mini-plots that are associated with data in the lower table of the editor. The top mini-plot (Credit vs. Available Credit) shows the storage credit values as a function of available credit in the other reservoirs. Figure 11.62 illustrates the top mini-plot along with cross-reference numbers that refer to the four seasonal columns in the lower table of the editor. The bottom mini-plot displays the *regular* Guide Curve (in red) along with the adjusted Guide Curve(s) based on the potential credit storage to be used (seasonally, in this example). Figure 11.63 illustrates the bottom mini-plot along with cross-reference letters that refer to the rows in the lower table of the editor. These mini-plots can be viewed in full size when you double click on them.



Figure 11.62 Reservoir Guide Curve Editor, Available Credit Storage vs. Credit Storage



Figure 11.63 Reservoir Guide Curve Editor, Seasonal Guide Curves for Potential Credit Storage

Chapter 12

Defining Reservoir Systems

Table of Contents

Section **Page**

12 Defining Reservoir Systems
12.1 Concept of Reservoir Systems 12-1
12.1.1 Implicit System Storage Balance Method 12-2
12.1.2 Explicit System Storage Balance Method 12-5
12.2 Overview of the Reservoir System Editor 12-9
12.3 Accessing the Reservoir System Editor 12-10
12.4 Reservoir System Editor Menu Items 12-10
12.5 Defining a New Reservoir System 12-11
12.6 Selecting Reservoirs for the System 12-12
12.7 Defining a System Storage Balance Operation Set 12-13
12.8 Defining Reservoir System Zones 12-14
12.9 Configuring System Storage Balance 12-15
12.10 General System Operation Notes 12-17

List of Tables

Table Number **Page**

12.1 Explicit System Storage Balance 12-7

List of Figures

Figure Number **Page**

12.1 Example of a Two-Reservoir Tandem System 12-2
12.2 Tandem Operation Rule Included for Reservoir 1 12-2
12.3 Implicit System Storage Balance 12-3
12.4 Example of Desired Storages using the Implicit System Storage Balance Method 12-4
12.5 Example of a Two-Reservoir Parallel System 12-5
12.6 Explicit System Storage Balance 12-6

List of Figures (continued)

Figure Number **Page**

12.7 Example of Desired Storages using the Explicit System Storage Balance Method 12-8
12.8 Reservoir System Editor (New Reservoir System) 12-9
12.9 Reservoir Network Module, Edit Menu, Reservoir Systems 12-10
12.10 Reservoir System Editor, ReservoirSystem Menu 12-10
12.11 Reservoir System Editor, Edit Menu 12-10
12.12 Reservoir System Editor, Operations Menu 12-11
12.13 Reservoir System Editor, Zones Menu 12-11
12.14 New Reservoir System Dialog Box 12-11
12.15 Reservoir System Editor (New Reservoir System) 12-12
12.16 Reservoir Selection Editor 12-13
12.17 New System Storage Balance Operation Set for Reservoir System 12-13
12.18 New Storage Zone Dialog Box 12-14
12.19 Configuring System Storage Balance 12-15
12.20 Percent Storage for each Reservoir in a Two-Reservoir System 12-16

Chapter 12

Defining Reservoir Systems

Reservoir systems are created by defining system operation rules for two or more reservoirs. ResSim provides for tandem operation to manage the storage distribution between upstream and downstream reservoirs on the same stream. Tandem operations are created by applying a tandem rule at an upstream reservoir operating for a downstream reservoir (e.g., reservoirs in series). In addition, ResSim supports parallel operation of reservoirs, where two or more reservoirs on different streams control for common downstream requirements, through the use of common downstream control (for flow or stage limit) rules. For each individual reservoir, system operation rules are prioritized among other rules in the operation set (refer to Chapter 11, Section 11.4.5 for a more detailed description of rule prioritization). This chapter will present the concept of system operation, specifically implicit and explicit methods for determining the system balance, and provide guidance for using the Reservoir System Editor to set up explicit system storage balances.

12.1 Concept of Reservoir Systems

When a tandem or parallel reservoir system is defined, the model determines the priority and the amount of release to make from each reservoir in order to operate towards a storage balance. For every decision interval, an end-of-period storage is first estimated for each reservoir based on the sum of beginning-of-period storage and period average inflow volume, minus all potential outflow volumes. The estimated end-of-period storage for each reservoir is compared to a desired storage that is determined by using a system storage balance scheme. The priority for release is then given to the reservoir that is *farthest above* the desired storage. When a final release decision is made, the end-of-period storages are recomputed. Depending on other constraints or higher priority rules (see Chapter 11), system operation strives for a storage balance such that the reservoirs have either reached their Guide Curves or they are operating at the **desired storage** (percent of the active storage zone).

There are two methods by which the desired storage balance is determined: implicit (default) and explicit (user-defined). The implicit method delineates the *default* storage balance scheme for the reservoir system. The explicit method is optional and allows a *user defined* storage balance scheme for the reservoir system. Detailed descriptions and examples are presented in Sections 12.1.1 and 12.1.2 for demonstrating the functionality of implicit and explicit storage balance methods.

12.1.1 Implicit System Storage Balance Method

The *default* method in ResSim for determining the desired storage balance in a reservoir system is referred to as the *implicit* method. This method applies to both tandem and parallel system operations. The implicit method is automatically used when a reservoir system is established − either by using a common **Downstream Control** rule in two or more parallel reservoirs, or adding a **Tandem Operation** rule to an upstream reservoir operating for a downstream reservoir.

For example, consider a two-reservoir tandem system, as shown in Figure 12.1. Reservoir 1 is the upstream reservoir where a **Tandem Operation** rule has been applied in its operation set, as shown in Figure 12.2 (see Section 11.5.5 for details about adding the Tandem Operation rule). This establishes an implicit system operation with the downstream reservoir, Reservoir 2. Assume that each reservoir has the same amount of storage capacity (100,000 ac-ft). For each of the reservoirs, the Guide Curve has been set to be the top of Conservation zone (see Section 11.8 for instructions on setting the Guide Curve). The conservation storage in Reservoir 1 is 75,000 ac-ft, whereas the conservation storage in Reservoir 2 is 30,000 ac-ft.



Figure 12.1 Example of a Two-Reservoir Tandem System



Figure 12.2 Tandem Operation Rule Included for Reservoir 1

The implicit system storage balance scheme (illustrated in Figure 12.3) takes into account the **System Storage** (the total storage from the reservoirs in the system). In this example, the system storage ranges from empty (0 ac-ft) to full (200,000 ac-ft). Additionally, this default scheme considers only one **System Zone**, the System Guide Curve (Sys G.C.) storage, which amounts to the sum of both reservoirs' conservation storages (105,000 ac-ft).

The **desired storage** for each reservoir is determined through an implicit "balance line". The balance line is simply a linear relationship between storage at each reservoir and the system storage. For each reservoir, the balance line hinges on the intersection of the reservoir's Guide Curve (G.C.) storage and the System Guide Curve (Sys G.C.) storage. For system storage *less than* the System Guide Curve storage, the balance line has a lower limit that corresponds to empty storage at the reservoir versus empty system storage, and the upper limit corresponds to Guide Curve storage at the reservoir (75,000 ac-ft at Res. 1 and 30,000 ac-ft at Res. 2) versus System Guide Curve storage (105,000 ac-ft). For system storage *greater than* the System Guide Curve storage, the lower limit of the balance line corresponds to Guide Curve storage at the reservoir (75,000 ac-ft at Res. 1 and 30,000 ac-ft at Res. 2) versus System Guide Curve storage (105,000 ac-ft), and the upper limit corresponds to full storage at the reservoir versus full system storage.



Figure 12.3 Implicit System Storage Balance

At the end of each decision interval (i.e., end-of-period), the **desired storage** for a reservoir corresponds to a point on the balance line that coincides with the sum of the estimated storages for both reservoirs. When the total estimated storage from both reservoirs is *less than* the System Guide Curve storage, the corresponding desired storages represent an equal percentage of the storage *below* the Guide Curve at each reservoir. When the total estimated storage from both reservoirs is *greater than* the System Guide Curve storage, the corresponding desired storages represent an equal percentage of the storage *above* the Guide Curve at each reservoir.

For instance, as shown in Figure 12.4, assume that preliminary end-of-period storage estimates are 25,000 ac-ft for Reservoir 1 and 45,000 ac-ft for Reservoir 2. The resultant total system storage of 70,000 ac-ft coincides with each reservoir's desired storage (50,000 ac-ft for Reservoir 1 and 20,000 ac-ft for Reservoir 2) found along the balance line from empty system storage to System Guide Curve storage. These desired storage values signify a desired balance because they amount to an equal 66.7 percent of the Guide Curve storage at each reservoir: 50,000 of 75,000 ac-ft at Reservoir 1, and 20,000 of 30,000 ac-ft at Reservoir 2.



Figure 12.4 Example of Desired Storages using the Implicit System Storage Balance Method

With 25,000 ac-ft estimated as its end-of-period storage, Reservoir 1 would be below its desired storage of 50,000 ac-ft. On the other hand, at an estimated storage of 45,000 ac-ft, Reservoir 2 would be above its desired storage of 20,000 ac-ft.

Since Reservoir 2 is above its desired storage, it receives the priority to release for this period in order to drop its storage down, as close as possible, to the desired storage. Unless other constraints (such as maximum physical outlet capacity, maximum flow limit rules, or flow rate of change limit rules) restrict releases and have higher priority than the system operation rule, Reservoir 2 would increase its releases in order to drop its pool to the desired storage of 20,000 ac-ft. As for Reservoir 1, it is forced to cut back its releases so that its storage can rise, as close as possible, to its desired storage of 50,000 ac-ft. If there are no restrictions (such as minimum flow limit rules or flow rate of change limit rules) that could require a different release due to having a higher priority than the system operation rule, Reservoir 1 would stop releasing from its outlet(s).

In the implicit system operation, a release decision made for a particular time period may not necessarily achieve the desired balance. The reservoirs in the system are considered "in balance" when both reservoirs have reached their Guide Curves, or they are operating at equivalent storage levels in terms of percentage of their counterpart system storage zones.

12.1.2 Explicit System Storage Balance Method

The *user-defined* method in ResSim for determining the desired storage balance in a reservoir system is referred to as the *explicit* method. This method can be used for an established reservoir system, whether tandem or parallel.

For example, consider two parallel reservoirs (Reservoir 1 and Reservoir 2) operating for a common downstream location (MyTown), as shown in Figure 12.5. In this case, both reservoirs are operating for a common downstream location, and each has the same downstream control rule applied in its operation set (establishing an implicit system operation). As described in Section 12.1.1, the implicit scheme by default develops balance lines, using a single system storage zone (System Guide Curve), to define linear relationships between storage at each reservoir and the total system storage. The



Figure 12.5 Example of a Two-Reservoir Parallel System

user can further modify these balance lines explicitly to characterize the desired storage distributions using one or more system zones and placing inflection points along the balance line.

For this example, both reservoirs have the same storage characteristics, maximum storage capacities and conservation storage as described in the tandem example in Section 12.1.1. Additionally, for Reservoir 1, the top of the Flood Control zone is at a storage of 85,000 ac-ft. For Reservoir 2, the top of Flood Control is at a storage of 65,000 ac-ft.

Figure 12.6 shows an explicit scheme defined such that Reservoir 1 fills up its conservation zone before Reservoir 2, and Reservoir 2 fills up its flood control zone sooner than Reservoir 1. This is accomplished by first identifying two system zones. For instance, System Conservation would represent one system zone that is the aggregate of the conservation storages from the two reservoirs. The other system zone would be the System Flood Control zone, the total of both reservoirs' flood control storages. As shown in Figure 12.6 and summarized in Table 12.1, a customized desired storage balance can be made by introducing inflection points to the balance lines within each system zone. Inflection points would transform the implicit balance line into an explicit curve. An unlimited number of balance line inflection points could be added within each system zone to further refine and shape the desired balance distribution.



Figure 12.6 Explicit System Storage Balance

Table 12.1 Explicit System Storage Balance

Storage	Reservoir 1	Reservoir 2	System Storage
Full	100,000 ac-ft	100,000 ac-ft	200,000 ac-ft
F.C.	85,000 ac-ft	65,000 ac-ft	150,000 ac-ft
%F.C.	*(25% F.C.)* *77,500* ac-ft	*(75% F.C.)* *56,250* ac-ft	*133,750 ac-ft*
Con	75,000 ac-ft	30,000 ac-ft	105,000 ac-ft
%Con	*(70% Con)* *52,500* ac-ft	*(33% Con)* *9,900* ac-ft	*62,400* ac-ft
Empty	0 ac-ft	0 ac-ft	0 ac-ft

In this example, within the System Conservation zone, balance line inflection points are set at 70 percent of the conservation storage (52,500 ac-ft) for Reservoir 1 and 33 percent of the conservation storage (9,900 ac-ft) for Reservoir 2. As a result, these inflection points coincide with system storage of 62,400 ac-ft, and reshape their respective balance line curves according to the general criterion that Reservoir 1 fills up its conservation zone before Reservoir 2. Similarly within the Flood Control System zone, balance line inflection points set at 25 percent of the flood control storage (77,500 ac-ft) for Reservoir 1 and at 75 percent of the flood control storage (56,250 ac-ft) for Reservoir 2 coincide with system storage of 133,750 ac-ft. This would satisfy the requirement that Reservoir 2 fills up its flood control zone sooner than Reservoir 1.

As demonstrated in Figure 12.7, for estimated end-of-period storages of 25,000 ac-ft at Reservoir 1 and 45,000 ac-ft at Reservoir 2, the resultant system storage of 70,000 ac-ft coincides with desired storages found along the explicitly defined balance line curves within the System Guide Curve storage zone. The desired storage levels are 56,500 ac-ft for Reservoir 1 and 13,500 ac-ft for Reservoir 2.



Figure 12.7 Example of Desired Storages using the Explicit System Storage Balance Method

At 45,000 ac-ft, Reservoir 2 would be above its desired storage of 13,500 ac-ft. As such, Reservoir 2 receives the priority to release for this period. Unless other constraints restrict releases and have higher priority than the system operation rule, Reservoir 2 would increase its releases in order to reduce its storage, as close as possible, to the desired storage. On the other hand, with only 25,000 ac-ft of estimated storage, Reservoir 1 would be below its desired storage of 56,500 ac-ft. Then Reservoir 1 is forced to cut back its releases for this particular time period so that its storage can rise, as close as possible, to the desired level. If there are no higher priority rules that require a release, Reservoir 1 would not make a release from its outlet(s).

Similar to the implicit system operation, the explicit system operation is carried out each time period when system rules are in effect. The process of determining desired storages is repeated every decision interval in order to assign the priority for release to the reservoir that is farthest above the desired storage. A release decision made for a particular time period may not necessarily achieve the desired balance. The reservoirs are considered "in balance" when both reservoirs have reached their Guide Curves or are operating at the desired storages levels along their balance line curves as prescribed in the explicit storage balance scheme.

The user interface process of creating an explicit system storage balance is described in subsequent sections.

12.2 Overview of the Reservoir System Editor

The **Reservoir System Editor** is used to create explicit system storage balances for selected reservoir systems. The editor is very similar to the **Operations** tab of the **Reservoir Editor** (see Chapter 11, Section 11.1). An example of the **Reservoir System Editor** is shown in Figure 12.8 and reflects the example data for the explicit storage balance method previously discussed in Section 12.1.2.



Figure 12.8 Reservoir System Editor (New Reservoir System)

As previously discussed, a reservoir system is implicitly created when two or more reservoirs are operating in tandem or when parallel reservoirs are operating together for a common downstream location. For system operations, you can either accept the implicit default system storage balance or you can create and define one or more explicit **System Storage Balance** schemes. For each system storage balance scheme you develop, you must define the **System Storage Zones** and the distribution of storage across the individual reservoirs (similar to the concept of **Reservoir Operation** sets discussed in Chapter 11, Section 11.2).

The remainder of this chapter will discuss the **Reservoir System Editor** in detail and will provide instructions for specifying explicit system storage balance data.

12.3 Accessing the Reservoir System Editor

To specify the explicit reservoir system balance scheme, you will use the **Reservoir System Editor** (previously shown in Figure 12.8). This editor is available in the **Reservoir Network Module** and is accessed from the **Edit** menu (in the menu bar), as shown in Figure 12.9.



Figure 12.9 Reservoir Network Module, Edit Menu, Reservoir Systems

12.4 Reservoir System Editor Menu Items

At the top of the **Reservoir System Editor**, the **Menu Bar** includes four menus unique to this editor. The menus are **ReservoirSystem**, **Edit**, **Operations**, and **Zones**. These menus provide the following options: creating, renaming and deleting reservoir systems; editing reservoir sets; creating, renaming and deleting system operation sets; and, creating and deleting system zones. These options are presented in the following paragraphs and described in subsequent sections of this chapter.

The **ReservoirSystem** menu (Figure 12.10) allows you to create a **New** system, **Rename** a system, **Delete** a system, and **Close** the editor. Refer to Section 12.5 for additional information.

Figure 12.10 Reservoir System Editor, ReservoirSystem Menu

From the **Edit** menu (Figure 12.11), select **Edit Reservoir Set** to specify which reservoirs are to be included in the reservoir system.

Figure 12.11 Reservoir System Editor, Edit Menu

The **Operations** menu (Figure 12.12) allows you to create a **New** system operation set, **Rename** a system operation set, or **Delete** a system operation set.

Figure 12.12 Reservoir System Editor, Operations Menu

The **Zones** menu (Figure 12.13) allows you to create **New** system zones or **Delete** system zones and is active only after a system operation set has been created.

Figure 12.13 Reservoir System Editor, Zones Menu

12.5 Defining a New Reservoir System

The **Reservoir System Editor** is used for creating a Reservoir System with explicit system storage balances. The process of setting up a new reservoir system includes defining a new reservoir system, creating a system operation set (see Section 12.7), defining system zone values (see Section 12.8), and specifying the storage balance (see Section 12.9) for each reservoir in your system.

The initial steps in creating a reservoir system that uses explicit system storage balancing are:

1. From the **ReservoirSystem** menu, select **New System**. The **New Reservoir System** dialog box will open (Figure 12.14).



Figure 12.14 New Reservoir System Dialog Box

2. Enter a **Name** and **Description** for the new reservoir system.
3. Click **OK**. The **New Reservoir System** dialog will close.

The name and description of the new **Reservoir System** will now appear in the **Reservoir System Editor**, with all other fields remaining blank (as shown in Figure 12.15).



Figure 12.15 Reservoir System Editor (New Reservoir System)

12.6 Selecting Reservoirs for the System

Once you have named your reservoir system, you will need to select all of the reservoirs to be included in the system storage balancing. *Only those reservoirs that have not been included in another reservoir system are available to be selected.*

To select the reservoirs to be included in the system storage balancing:

1. Choose **Edit Reservoir Set** from the **Edit** menu of the Reservoir System Editor. The **Reservoir Selection Editor** will open (Figure 12.16).
2. The available reservoirs in your network (that have not been included in another reservoir system) appear in the **Available** pane on the left side of the **Reservoir Selection Editor**. To add a reservoir to your new reservoir system, click on the reservoir's name and click the **Add** button. To select all of the available reservoirs, click the **Add All** button.
3. The reservoirs you select will move from the **Available** pane to the **Selected** pane on the right. To remove a reservoir from the selected list, click on its name and click the **Remove** button. To remove all reservoirs from the **Selected** list, click the **Remove All** button.



Figure 12.16 Reservoir Selection Editor

4. Click **OK** to approve your choices and close the **Reservoir Selection Editor**.

Although you have selected reservoirs for your reservoir system, they will not yet appear in the **Reservoir System Editor**. You must first specify the system storage balance and define reservoir system storage zones.

12.7 Defining a System Storage Balance Operation Set

To define the **System Storage Balance Operation Set** for the reservoirs in your reservoir system:

1. Select **New** from the **Operations** menu of the **Reservoir System Editor**. The **New Operation Set** dialog box will open (Figure 12.17).



Figure 12.17 New System Storage Balance Operation Set for Reservoir System

2. Enter **a Name** and **Description** for the **System Storage Balance Operation Set**.
3. Below the **Description** area, you will see the names of the reservoirs you have selected for your system. The white box below the name of each reservoir contains a list of the **Operation Sets** available for that reservoir. Double-click on the white box to access the list for each reservoir and then select an operation set that *contains the system operation rule(s)*.
4. Click **OK** to close the New Operation Set dialog box.

Note that your changes will not yet appear in the **Reservoir System Editor**. You must first define at least one **Reservoir System Zone**.

12.8 Defining Reservoir System Zones

To define the **Reservoir System Zone**(s):

1. Select **New** from the **Zones** menu of the **Reservoir System Editor**. The **New Storage Zone** dialog box will open (Figure 12.18)



Figure 12.18 New Storage Zone Dialog Box

2. Enter a **Name** and **Description** for the new storage zone.
3. Click **OK** to close the **New Storage Zone** dialog box.

When you have defined at least one system storage zone for your reservoir system, its name will appear in the white pane at the bottom left of the **Reservoir System Editor**, and a new set of fields will appear in the large gray area, as shown in Figure 12.19. These new fields allow you to configure the system storage balance for your reservoir system.

12.9 Configuring System Storage Balance

Once you have successfully created a new reservoir system (by following the steps presented in Sections 12.5 through 12.8), several new fields become available that allow you to configure the storage balance across reservoirs. We will use Figure 12.19 to illustrate how to do this.



Figure 12.19 Configuring System Storage Balance

1. Choose a **System Storage Balance** option from the drop-down list. Its description will appear in the editable **Description** field, and the available **System Storage Zones** will appear in the white pane on the left side of the editor window.

   In Figure 12.19, the **System Storage Balance** field indicates we are using a System Storage Balance called "Parallel SysOp_MyTown," and there are two **System Storage Zones**, "FC" and "Con."

2. Click on a **System Storage Zone** in the white pane on the left side of the editor window to select it. Its name and description will appear to the right in the editable **System Storage Zone** name (as shown below).

   In Figure 12.19, "FC" is selected, so its name and description appear in the **System Storage Zone** and **Description** fields.

3. For the selected zone ("FC" in this example), in the list beneath each reservoir name, select a reservoir zone for each reservoir in the system.

   In Figure 12.19, there are two reservoirs in the system and we have chosen the "Flood Control" zone for each reservoir, as shown below:

4. In the table below the reservoir operation sets, enter percentages of system storage zones for each reservoir, as shown in Figure 12.20. These storage percentages represent *inflection points* along the balance line curve, which delineates how the reservoirs will balance when system operations are performed.

% Storage	% Storage
100.0	100.0
75.0	25.0

Figure 12.20 Percent Storage for each Reservoir in a Two-Reservoir System

5. Click **Apply** to save your changes.
6. Repeat the process for each **System Storage Zone** you have created. For example, in Figure 12.19, once you have configured the "FC" System Storage Zone, you would want to configure the reservoir system balance for the "Con" System Storage Zone.
7. If you wish to configure additional storage balance options, click **Apply** to save your changes for the current storage balance option, then select another storage balance option from the **System Storage Balance** list.
8. When you have finished configuring your system storage balance, click **OK** to close the **Reservoir System Editor**.

12.10 General System Operation Notes

As previously discussed, you can allow ResSim to use its implicit storage balance, or you can create an explicit system storage balance. In addition, the following notes related to system operations are provided:

- Empty storage is always zero, while full storage for a reservoir is considered as the maximum storage level in the pool storage-elevation relationship that is defined in the physical tab of the Reservoir Editor.
- For tandem reservoirs, there can be an intermediate control point for which the upstream reservoir operates.
- For parallel reservoirs, the common downstream control rule must be created at only one of the reservoirs and it will automatically be available in the list of existing rules for the other reservoirs. Then, the downstream control rule can be added to the other reservoirs via the "Use Existing" option in the Reservoir Editor (see Chapter 11, Section 11.5.2) in order to establish system operation. If, on the other hand, the downstream control rules are created separately at each reservoir, even if the data entered into the rules are identical, system operation will not be invoked.
- System operation rules can be prioritized along with other rules in the operation set (i.e., depending on prioritization, they may be overridden)
- Guide Curve does not necessarily have to be the top of the conservation zone. The implicit balance scheme will recognize the user setting for a Guide Curve at each reservoir in delineating the default balance lines.
- Implicit and explicit storage balance schemes can be established among two or more reservoirs. When defining an explicit system balance, all reservoirs identified for parallel operation must be included in the reservoir system (refer to Section 12.6). For example, if you have three parallel reservoirs operating for a common downstream location(s), and only two of them are included in an explicit system storage balance, the explicit system storage balance will be ignored and the default implicit storage balance scheme will be used instead.
- The explicit system storage balance is defined using the Reservoir System Editor, as presented in the preceding sections of this chapter. In order to simulate the explicit system operation, the explicit system storage balance must be selected in the Alternative Editor's operations tab along with the reservoir operation sets that contain the system operation rules (refer to Chapter 13, Sections 13.4 and 13.5).

Chapter 13

Defining Alternatives

Table of Contents

Section **Page**

13 Defining Alternatives
13.1 Preparing to Develop Alternatives 13-1
13.2 Accessing the Alternative Editor 13-1
13.3 Creating a New Alternative 13-2
13.4 Selecting a Reservoir Operation Set 13-3
13.5 Selecting a Reservoir System Storage Balance Operation Set 13-4
13.6 Selecting Lookback Type 13-5
13.7 Associating Time-Series Data with a Location 13-5
13.8 Defining Observed Data 13-7
13.9 Saving an Alternative 13-8

List of Figures

Figure Number **Page**

13.1 Alternative Editor 13-1
13.2 New Alternative Dialog Box 13-2
13.3 Alternative Editor--Name and Description Fields 13-2
13.4 Alternative Editor--Operations Tab, Reservoir Operation Set 13-3
13.5 Alternative Editor--Operations Tab, Reservoir System Storage Balance Operation Set 13-4
13.6 Alternative Editor--Lookback Tab 13-5
13.7 Alternative Editor--Time-Series Tab 13-5
13.8 Select Time-Series Path Dialog Box 13-6
13.9 Alternative Editor--Observed Data Tab 13-7
13.10 Alternative Editor--Save Alternative 13-8
13.11 Reservoir Network Module--Network Menu, Save Network 13-8
13.12 File Menu--Save Watershed 13-8

Chapter 13

Defining Alternatives

An Alternative consists of a Configuration, a Reservoir Network, an Operation Set for each reservoir in the network, a Storage Balance Operation Set for each reservoir system in the network (if applicable), a definition of initial conditions, and a mapping of all time-series records to identified local inflows. To develop an Alternative, you use the **Alternative Editor** to name the Alternative and give it a description, select Reservoir Operation Sets, select System Operation Sets (if applicable), select a Lookback Type, associate time-series data with locations, define observed data, and save the Alternative you have created. This chapter will guide you through the steps.

13.1 Preparing to Develop Alternatives

Before you can develop an alternative, you need to define the operational reservoir data using the Reservoir Editor. Chapter 11 describes this procedure. Also, if your network contains reservoir systems, you need to define the storage balance operation set (as described in Chapter 12, Section 12.7).

13.2 Accessing the Alternative Editor

To access the **Alternative Editor** (Figure 13.1), choose **Edit** from the **Alternative** menu in the Reservoir Network Module.



Figure 13.1 Alternative Editor

13.3 Creating a New Alternative

The first step in creating an Alternative is to give it a name and description, associate it with a configuration, and then select the reservoir network you want to use.

To create a New Alternative:

1. From the **Alternative** menu of the Alternative Editor, select **New**. The **New Alternative** dialog box will open (Figure 13.2).



Figure 13.2 New Alternative Dialog Box

2. Enter a **Name** and **Description**. Use the ... button to open a larger editing window for the description.
3. Select a **Configuration** by choosing from the list of available configurations.
4. Click **OK** to close the New Alternative dialog box. The name and description you entered will now appear in the **Name** and **Description** fields of the Alternative Editor (Figure 13.3).



Figure 13.3 Alternative Editor--Name and Description Fields

5. Next, choose the **Reservoir Network** you want to use for this alternative. The selection list contains only those networks you have defined for the selected configuration.

13.4 Selecting a Reservoir Operation Set

Once you have given your alternative a name and description and have chosen the configuration and reservoir network, you will need to select the **Operation Set** you want each reservoir to follow for the alternative. You will have created the operation set(s) using the Reservoir Editor (see Chapter 11).

To select a reservoir operation set for an alternative:

1. In the **Alternative Editor**, select the **Operations** tab (Figure 13.4).



Figure 13.4 Alternative Editor--Operations Tab, Reservoir Operation Set

2. Select an Operation Set (for each reservoir in the network) by double-clicking on the white **Operation Set** field and choosing from the list.

13.5 Selecting a Reservoir System Storage Balance Operation Set

When you create a reservoir system and define an explicit storage balance scheme for a system operation (described in Chapter 12), an entry will appear in the Alternative Editor's Operations tab that identifies the Reservoir System along with a field in which you are required to select a system storage balance operation for the reservoirs to follow. Note that the individual operation sets for each reservoir containing the Downstream Control and/or Tandem Operation rules have to also be selected in the alternative in order to simulate system operation.

To select a system operation set for an alternative:

1. In the **Alternative Editor**, select the **Operations** tab (Figure 13.5).



Figure 13.5 Alternative Editor--Operations Tab, Reservoir System Storage Balance Operation Set

2. In addition to selecting the operation set for each reservoir (as previously described in Section 13.4), select a **Storage Balance** for each **Reservoir System** you have configured by double clicking on the white **Storage Balance** field and choosing from the list. The selection options will be either the operation set that contains the explicit storage balance scheme you want to apply, or "NONE" if you wish to have the alternative use the implicit (default) storage balance scheme instead of the explicit storage balance you previously set up.

13.6 Selecting Lookback Type

After specifying the operation set for each of your reservoirs, you will need to specify the initial (or starting) conditions for the alternative. This is referred to in ResSim as the **Lookback** (or warmup) period. You will need to specify whether constant or "mapped" time-series data will define each element and parameter during the lookback period.

To set the lookback **Type** for locations in your reservoir network:

1. In the **Alternative Editor**, select the **Lookback** tab.
2. For each location or parameter, double-click in the white **Type** cell and select either **Constant** or **Time-Series**, (as shown in Figure 13.6).



Figure 13.6 Alternative Editor--Lookback Tab

3. For locations or parameters where you have selected **Constant** as the lookback type, enter the value for the constant in the **Default Value** field.

13.7 Associating Time-Series Data with a Location

Next, you will need to associate (by "mapping") a time-series record to each location or parameter for which Time-Series Data are needed.

To associate Time-Series Data with a Location:

1. In the **Alternative Editor**, select the **Time-Series** tab (Figure 13.7).



Figure 13.7 Alternative Editor--Time-Series Tab

2. Each row in the Time-Series table is a local flow location (specified in the Local Flow tab within the Junction editor in the Reservoir Network module), an element/parameter you have defined on the Lookback tab as Time Series, or a Time Series that is referenced in the Operation rules. Select each row, one at a time, and click the **Select DSS Path** button to access the **Select Time-Series Path** dialog box (Figure 13.8).



Figure 13.8 Select Time-Series Path Dialog Box

The **Select Time-Series Path** dialog box allows you to select records from a list of pathnames (or *catalog*) in the database. From the **View** menu, you can choose to display a straight list of pathnames or a list of pathnames separated into parts, and you can refine the list by searching for either a string in the pathnames or for specific pathname parts. For detailed information about working with DSS files, refer to the discussion of **Hec-DssVue** in Appendix E.

3. To select time-series records for a location or element/parameter in your alternative, open the DSS file you wish to browse. If you know the name of the file, you can type the file name (including the path) directly into the **File Name** box to open the DSS file. Otherwise, choose **Open** from the **File** menu or click the button to select the DSS database file you want.
4. Once you have selected a file, the **Select Time-Series Path** dialog box displays the filename, the number of pathnames in the list, the number of pathnames selected, the total number of pathnames in

the database file, and the size of the database file. The individual pathnames display in a table beneath the search area.

5. Use the **Search** feature to "filter" and locate individual records in the DSS file or scroll through the list of pathnames with the vertical scrollbar.
6. Select a record by double clicking on its name in the list. The selected pathname will appear in the box on the bottom of the Select Time-Series Path dialog box (as previously shown in Figure 13.8). You can also highlight a pathname in the list and click the **Select** button. Until you select a pathname, the **Select** button remains inactive.

> Tip *Unlike in Hec-DssVue, you may select **only one record** at a time in the **Select Time-Series Path** dialog box.*

7. If you would like to view the DSS data, select **Plot** or **Tabulate** from the **Display** menu, or you can click on the **Plot** button or the **Tabulate** button.
8. When you are satisfied with the DSS record you have chosen for a location or element/parameter, click on the **Set Pathname** button and the selected pathname will appear in the Time-Series tab of the Alternative editor.

13.8 Defining Observed Data

While defining your reservoir network, if you have specified (by checking the appropriate box or boxes in the Observed tab within each element's editor in the Network module) that observed data is available for individual reservoirs, junctions, reaches, diversions, and diverted outlets, the **Observed Data** tab of the Alternative Editor will list these locations in a table along with the DSS path information associated with them, as shown in Figure 13.9.



Figure 13.9 Alternative Editor--Observed Data Tab

13.9 Saving an Alternative

When you have finished defining an alternative, save it by selecting **Save** from the **Alternative** menu of the **Alternative Editor**, as shown in Figure 13.10. You may then close the Alternative Editor.



Figure 13.10 Alternative Editor--Save Alternative

It is a good idea to save your **Network** and **Watershed** after creating a new Alternative. To do this, select **Save** from the **Network** menu (Figure 13.11), and then select **Save Watershed** from the **File** menu (Figure 13.12).



Figure 13.11 Reservoir Network Module--Network Menu, Save Network



Figure 13.12 File Menu--Save Watershed

Chapter 14

Running Simulations

Table of Contents

Section **Page**

14 Running Simulations
14.1 Recognizing Simulation Screen Components....14-1
14.1.1 Menu Bar....14-2
14.1.2 Map (Mouse) Tools....14-4
14.1.3 Simulation Control Panel....14-5
14.1.4 Display Area....14-5
14.2 Creating a Simulation....14-6
14.3 Working with Existing Simulations....14-7
14.3.1 Opening an Existing Simulation....14-8
14.3.2 Editing a Simulation....14-9
14.4 Computing a Simulation....14-9
14.4.1 Setting the Active Alternative....14-9
14.4.2 Computing the Simulation....14-10
14.5 Reviewing Simulation Results....14-11
14.5.1 Viewing Compute Logs....14-11
14.5.2 Using Plots and Tables....14-13
14.5.2.1 Features of Plots....14-13
14.5.2.2 Customizing Plots....14-14
14.5.2.3 Creating User-Defined Plots....14-15
14.5.2.4 Viewing Data in Tabular Form....14-17
14.5.2.5 Printing and Exporting Plots and Tables....14-18
14.5.3 Viewing Summary Reports....14-18
14.5.3.1 Reservoir Summary Reports....14-18
14.5.3.2 Flow Summary Reports....14-19
14.5.3.3 Power Summary Reports....14-20
14.5.3.4 Gate Summary Reports....14-21
14.5.3.5 Stage Summary Reports....14-22
14.5.3.6 Release Decision Reports....14-23
14.5.3.7 Network Reports....14-23
14.6 Calibrating the Model and Editing Data....14-24
14.6.1 Using the ResSim Editor Interface....14-24
14.6.2 Editing Alternative Lookback, Time Series, and Observed Data....14-25
14.6.3 Editing Release Override Values....14-25
14.6.4 Setting Compute Options....14-29

Section (continued) **Page**

14.7 Managing Simulation Data....14-30
14.7.1 Saving Data *to* the Base Directory....14-30
14.7.2 Replacing Data *from* the Base Directory....14-31
14.8 Using HEC-DssVue....14-32

List of Figures

Figure Number **Page**

14.1 Simulation Module Main Window....14-1
14.2 File Menu....14-2
14.3 Edit Menu....14-2
14.4 View Menu....14-3
14.5 Simulation Menu....14-3
14.6 Alternative Menu....14-3
14.7 Reports Menu....14-3
14.8 Tools Menu....14-4
14.9 Help Menu....14-4
14.10 Simulation Control Panel....14-5
14.11 Simulation Control Panel Shortcut Menu: New Simulation....14-6
14.12 Simulation Period Dialog Box....14-6
14.13 Creating Simulation Window....14-7
14.14 Simulation Control Panel Shortcut Menu: Open Simulation....14-8
14.15 Open Simulation Dialog Box....14-8
14.16 Simulation Tree....14-8
14.17 Simulation Control Panel Shortcut Menu: Set Alternative As Active....14-9
14.18 Simulation Control Panel Shortcut Menu: Compute....14-10
14.19 Compute Window....14-11
14.20 Compute Log....14-12
14.21 Select Font Dialog Box....14-12
14.22 Reservoir Shortcut Menu -- Plot Simulation Results....14-13
14.23 Sample Plot of Reservoir Results....14-13
14.24 Shortcut Menu for an Element....14-15
14.25 Select Plot Variables Dialog Box....14-15
14.26 Select Plot Variables: Region Shortcut Menu....14-16
14.27 Save Plot Type 14-16
14.28 Shortcut Menu: User Plots....14-17
14.29 Data in Tabular Form....14-17
14.30 Reservoir Summary Report....14-18
14.31 Flow Summary Report....14-19
14.32 Power Summary Report....14-20
14.33 Gate Summary Report....14-21
14.34 Stage Summary Report....14-22
14.35 Release Decision Report....14-23
14.36 ResSim Editor Interface....14-24
14.37 Release Overrides Editor....14-25

List of Figures (continued)

Figure Number		Page
14.38	Release Overrides Editor Shortcut Menu: Fill Data Values	14-27
14.39	Table Fill Options Dialog Box	14-27
14.40	Release Overrides Editor Table: Revised Data Values using Repeat Fill Option	14-27
14.41	Import Time Series Dialog Box	14-28
14.42	ResSim Editor Interface: Compute Options	14-29
14.43	Alternative Shortcut Menu: Save to Base Directory	14-30
14.44	Save Simulation Run Model Parameters to Base Directory	14-30
14.45	Alternative Shortcut Menu: Replace from Base Directory	14-31
14.46	Replace Simulation Run Model Parameters from Base Directory	14-31
14.47	Accessing HEC-DssVue from the Tools Menu	14-32
14.48	HEC-DssVue Main Window Showing Pathname Listing	14-32
14.49	Screened Pathname Listing Showing Observed (OBS) Records	14-32
14.50	Example Plot Using HEC-DssVue	14-33
14.51	Example of Tabulated Data Using HEC-DssVue	14-33

Chapter 14

Running Simulations

When you have entered all required data and have created Alternatives, you are ready to perform a Simulation. A Simulation is where you specify the time window and time interval parameters for either a single Alternative or a group of Alternatives. After a successful Simulation, you can analyze the results, make revisions, and perform additional Simulations to better evaluate the reservoir operations in your watershed.

14.1 Recognizing Simulation Screen Components

The **Simulation Module** (Figure 14.1) provides the tools you will need to create and run Simulations. The following is a discussion of the components and features of the Simulation Module.



Figure 14.1 Simulation Module Main Window

The **Title Bar** displays the name of the window or dialog box currently open in ResSim. The name of opened watershed displays next to **HEC-ResSim**.

The **Simulation Control Panel** provides Module-dependent controls that execute commands and/or display important dialog boxes. For more detail, see Section 14.1.3.

The **Menu Bar** contains menus of commands that you can use in ResSim. The items on the menus change as you switch between the various Modules, offering Module-specific commands. You can select a menu bar item by clicking on the name of the menu (such as **File**), then pointing and clicking on the item you wish to select. The Menu Bar is described in more detail below.

The **Module List** contains all the available Modules of ResSim. Use this list to move between the Watershed Setup, Reservoir Network, and Simulation Modules. By default, the Module List opens to the Module most recently used.

14.1.1 Menu Bar

The following is an overview of the **Simulation Module**'s Menu Bar tools, which allow you to create and edit Simulations. The tools specific to this module will be described in more detail in the context of particular tasks later in this chapter.

The **File** menu (Figure 14.2) allows you to **Open** an existing watershed, **Save** a watershed, **Save Map** (saves the display area) and **Exit** ResSim. Your most-recently-used watersheds are listed at the bottom of the File menu.



Figure 14.2 File Menu

The **Edit** menu (Figure 14.3) provides access to the **Script List**, allows you to **Set the Active Alternative,** and allows access to editors for **Reservoirs**, **Reaches**, **Junctions**, **Diversions**, and **Reservoir Systems**. Note that any revision you make to these elements applies only to the active Alternative. If you want the revisions to apply to subsequent Simulations, you must save the changes to your base directory (see Section 14.7.1).

Figure 14.3 Edit Menu

In the **View** menu (Figure 14.4) select **Zoom to All** to restore your watershed map view to full size. **Layers...** opens the Layers Selector dialog box. **Unit System** allows you to customize the display (view) settings for your watershed. If a dialog or editor window is open but inactive**, Restore Windows** brings the dialog or editor window to the front as the active window.

Figure 14.4
View Menu

The **Simulation** menu (Figure 14.5) is unique to the Simulation Module. It allows you to create a **New** Simulation, and **Open**, **Re-Open**, **Close**, **Save**, or **Delete** an existing Simulation. The **Edit** command opens the Simulation Period dialog box, while **Info** allows you to view the name, directory path, and user information for the current Simulation. You can also access **Release Overrides** for a Simulation.

Figure 14.5
Simulation Menu

The **Alternative** menu (Figure 14.6), also available in the Reservoir Network Module, provides access to the Alternative Editor.

Figure 14.6
Alternative Menu

The **Reports** menu (Figure 14.7) provides access to the **Reservoir Summary**, **Flow Summary**, **Power Summary**, **Gates Summary**, **Stage Summary**, and **Release Decision** reports, as well as **Compute** logs. You can also access **Network** reports, including the Reservoir List, Reach List, Junction List, Diversion List, and the Network Connectivity Summary report.



Figure 14.7
Reports Menu

As in the other Modules, the **Tools** menu (Figure 14.8) provides access to **Hec-DssVue** and **Scripts**. **Options** lets you specify watershed locations for storing your watersheds; specify a directory for caching map files; set the colors for compute messages and the format of log files; set the level of debug messages; choose whether or not you want a confirmation message to appear when you exit ResSim; and choose whether you want the last watershed reloaded at startup of the program. **Information** provides details about client, user, and watershed settings as well as server and system properties.



Figure 14.8
Tools Menu

The **Help** menu (Figure 14.9) displays information about the current version of ResSim. **About** specifies the version, revision and build numbers.



Figure 14.9
Help Menu

14.1.2 Map (Mouse) Tools

The **Map (Mouse) Tools**, which appear in a toolbar on the left side of the ResSim screen, allow you to interact with objects in the map display. The Simulation Module has three Map Tools and all are available in the other ResSim Modules:

Pointer Tool
In the Simulation Module, right-click model schematic elements in the map display with the Pointer Tool to access editors, default and user-defined plots, and release decision reports (for reservoirs).

Zoom Tool
The Zoom Tool allows you to zoom in and out of the display area in all Modules. To zoom in, hold the left mouse button down and outline the area you want to enlarge. To zoom out, click the right mouse button. Zooming out using the right-click button zooms out by a factor of two, positioning the clicked location at the center of the screen.

Pan Tool
After you have zoomed in with the Zoom Tool, you can use the Pan Tool to view watershed areas that fall outside of the ResSim window borders.

14.1.3 Simulation Control Panel

The **Simulation Control Panel** (Figure 14.10) displays details about the current Simulation and allows you to interact with Alternatives.

Displayed at the top of the panel are the **Simulation** time, **Lookback** time, and **End** time.

Below these details is the **Simulation Tree**, which displays the name of the current Simulation and its associated Alternatives. The currently active **Alternative** displays as bold, and a check mark in the box beside an Alternative indicates that it will be included in reports. Right-click on a Simulation or Alternative to access their shortcut menus.

When you select an Alternative, the **Compute** button becomes available, allowing you to execute a Simulation.

At the bottom of the Simulation Control Panel, the **Scripts** area displays buttons that launch user-created scripts.



Figure 14.10 Simulation Control Panel

14.1.4 Display Area

The **Display Area** displays model schematic objects and map layers representing the **Active Alternative**.

Model elements of a Reservoir Network will not appear in the display area until you have created or opened a Simulation and activated an Alternative (see Section 14.4.1).

14.2 Creating a Simulation

Once you have created a reservoir network, entered element data, and developed alternatives in the Reservoir Network Module, you can configure the model for a Simulation in the Simulation Model.

To create a new Simulation:

1. From the **Simulation** menu, select **New**. Or, in the **Simulation Control Panel**, right-click on the currently-active Simulation or *No Simulation* folder to access the shortcut menu (Figure 14.11). Select **New**.
2. The **Simulation Period** dialog box will open (Figure 14.12).

Figure 14.11 Simulation Control Panel Shortcut Menu: New Simulation



Figure 14.12 Simulation Period Dialog Box

3. The **Name** field contains a default name for the Simulation based on the current date and time. You may either accept the default or enter a name that is more meaningful to you.

4. Enter a **Start Date** and **Time** specifying when you want the Simulation to begin. It must occur after the Lookback Date.
5. Enter a **Lookback Date** and **Time**. The Lookback is the "warm-up" period before the Simulation begins.
6. Enter an **End Date** and **Time** specifying when you want the Simulation to conclude.
7. Choose a **Time Step** from the list. The Time Step is the computation interval and can be 15 Minutes, 30 Minutes, 1 Hour, 3 Hours, 6 Hours, 12 Hours, or 1 Day.
8. The **Alternatives** table includes all of the Alternatives you have defined in the Reservoir Network Module. Select one or more applicable Alternatives for the Simulation by checking the boxes beside them in the **Select** column. Ensure the Alternatives you select include time-series data for the entire Simulation period.
9. Click **OK** to close the Simulation Period dialog box. The **Creating Simulation** window (Figure 14.13) will inform you of the status as ResSim creates the Simulation you have defined.



Figure 14.13 Creating Simulation Window

The Simulation you have created will now appear in the Simulation Control Panel.

The Reservoir Network will not appear in the map region until you have set an Alternative to Active (see Section 14.4.1).

14.3 Working with Existing Simulations

If you have previously created a ResSim Simulation, you may want to make revisions to the Lookback date and time or End date and time (the Start date and time cannot be changed), or you may want to revise data in an Alternative (operation rules, reservoir operation zones, etc.). To accomplish this, you will open an existing Simulation.

14.3.1 Opening an Existing Simulation

To open an existing Simulation:

1. From the **Simulation** menu, select **Open**. Or, in the **Control Panel**, right-click on the currently-active Simulation or *No Simulation* folder to access the shortcut menu (Figure 14.14). Select **Open**.
2. The **Open Simulation** dialog box will open (Figure 14.15).



Figure 14.14 Simulation Control Panel Shortcut Menu: Open Simulation



Figure 14.15 Open Simulation Dialog Box

3. Click on the Simulation you want and select **Open**.

The time period details of your selected Simulation will now appear in the Simulation Tree (Figure 14.16), and the map display will now update to show the model schematic for the active Alternative (see Section 14.4.1 for information about setting the alternative to active).



Figure 14.16 Simulation Tree

14.3.2 Editing a Simulation

Once you have created a Simulation, you can use the **Simulation Period** dialog box (Figure 14.12) to edit the Lookback Date and Time, the End Date and Time, Time Step, and selected Alternatives. You cannot change the Start Date or Time.

You can access the **Simulation Period** dialog box two ways:

- Select **Edit** from the **Simulation** menu.
- Right-click on the Simulation folder at the top of the simulation tree in the Simulation Control Panel, then select **Edit** from the shortcut menu.

14.4 Computing a Simulation

After you have created a new simulation or have opened an existing simulation, you are ready to make one of the alternatives active (if not already active) and have ResSim perform the computations.

14.4.1 Setting the Active Alternative

Once you have opened a Simulation, the simulation tree will show all of the selected Alternatives for the Simulation you have chosen.

Model elements of a reservoir network will not appear in the display area until you set an Alternative to Active. During the Alternative activation process, ResSim makes a copy of the active alternative available for the simulation.

To set the **Active Alternative**:

1. Right-click on the Alternative you want in the simulation tree.
2. Select **Set as Active** from the shortcut menu (Figure 14.17).

The map display will now update to show the model schematic for the Alternative you have set as Active.



Figure 14.17 Simulation Control Panel Shortcut Menu: Set Alternative As Active

14.4.2 Computing the Simulation

After inputting all data and parameters as desired, you can compute a Simulation.

In the Simulation Control Panel of the main window of the Simulation Module, the simulation tree displays the current Simulation as a folder, beneath which is a list of the Alternatives associated with the Simulation. Also shown in the Simulation Control Panel is the time information associated with the Simulation.

To execute a Simulation, you must first set an Alternative as Active. Right-click on an Alternative in the Simulation Control Panel and, from the shortcut menu, select **Set as Active** (Figure 14.17).

The name of the active Alternative appears in bold in the simulation tree and the **Compute** button becomes available. Also, the model schematic for the active Alternative will appear in the display area.

To compute a Simulation, either click the **Compute** button in the Simulation Control Panel or, in the simulation tree, right-click on the Alternative and select **Compute** from the shortcut menu (Figure 14.18).



Figure 14.18 Simulation Control Panel Shortcut Menu: Compute

When you compute a Simulation, a **Compute** window opens, as shown in Figure 14.19. The **Compute** window provides **Message Output** that contains information regarding the status of each step of the computation process. The **Progress Bar** indicates the percentage of completion for each step. When the computation is finished, the **Progress Bar** is completely filled in and reads "100%" along with the message "Compute Complete" in the **Message Bar** of the **Compute** window.

If there are errors or any problems during the execution process, you can review the Message Output Text area of the compute window. Also the **Compute Log** can provide information regarding the type of problem that exists (see Section 14.5.1).

Click **Close** to close the Compute window.



Figure 14.19 Compute Window

14.5 Reviewing Simulation Results

After computing a Simulation, you can review results in many different forms. **Compute Messages** provide information about each step of the computation process. **Plots** and **Tables** in the Simulation Module offer detailed views of data and model results. **Reports** provide details about individual components of the Reservoir Network. These options for viewing your results are described in the following sections.

14.5.1 Viewing Compute Logs

If there are errors or any problems during the computation process, the **Compute Log** (Figure 14.20) can provide information regarding the type of problem that exists. To view **Compute Logs**, select **Compute** from the **Reports** menu, then select the appropriate Alternative.



Figure 14.20 Compute Log

You can use the **Find** and **Find Next** commands in the **Search** menu to locate specific issues in a log.

You can customize the appearance of the Compute Log with the **Colors** and **Font** commands in the **Format** menu.

The **Colors** command allows changes to the **Foreground** and **Background** colors. Selecting either one opens the **Select Color** dialog box. See Appendix D for instructions on how to use the **Color Chooser** tools.

The **Font** command opens the **Select Font** dialog box (Figure 14.21), which allows you to choose the font **Type** and **Size**. Also, you can choose whether or not to set the appearance to **Bold** and/or **Italic** characters.



Figure 14.21 Select Font Dialog Box

14.5.2 Using Plots and Tables

Plots and tables in the Simulation Module offer detailed views of data and model results.

You can access plots using shortcut menus in the Simulation Module's display area.

To access a **Plot** from the display area, right-click on a model element in the map display. The shortcut menu will provide a list of one or more plot options, as illustrated in Figure 14.22.

Once you have opened a plot, you can also tabulate values by selecting **Tabulate** from the plot's **File** menu.



Figure 14.22 Reservoir Shortcut Menu -- Plot Simulation Results

14.5.2.1 Features of Plots

ResSim plots offer a variety of information that will assist you with reviewing the results of a Simulation. Included in the information available from the default plots are reservoir elevation, storage, and release values as well as regulated and unregulated (without reservoirs and other projects) flow values. Figure 14.23 shows a sample plot illustrating reservoir results from a Simulation.



Figure 14.23 Sample Plot of Reservoir Results

The plot window displays the location name in the title bar. Axis labels and a color-coded legend identify the data contained in the plot.

When a plot depicts the results of an Alternative, as in Figure 14.23, a dashed vertical line represents the start time of the Simulation. The Lookback (historic/observed) period occurs prior to the start time.

The **Zoom Tool** allows you to view data closely at a specific time. To zoom in, hold the left mouse button down and outline the area you want to enlarge. To zoom out, click the right mouse button. To resize a plot, use the mouse to drag the edges of the window. It is possible to zoom in on one section of the entire plot (both the x and y variables simultaneously) or a range for either variable. To zoom in on a section of the plot, outline that area on the plot. To zoom in on a range (for either x or y variable), outline the desired range on the respective axis.

14.5.2.2 Customizing Plots

You can customize the appearance of plots by using several properties editors that you can access from shortcut menus:

Line Properties: Right-clicking on a plot line or point will allow you to open a Curve Properties Editor to edit line colors, styles, and weights, as well as labels and quality symbols.

Background Properties: Right-clicking on the background of a plot will allow you to open a View Port Editor where you can customize the border, background, and gridlines of the plot.

Axis Properties: Right-clicking on a plot axis will allow you to open an Axis Properties Editor where you can customize the axis scale and tic marks.

Label Properties: Right-clicking on an axis label or plot legend will allow you to open a Label Properties Editor where you can add backgrounds and borders to the labels.

14.5.2.3 Creating User-Defined Plots

Since everyone has their own preferences regarding which variables to include in the shortcut menu location plot selections, the **User Defined Plot** capability offers flexibility.



Figure 14.24 Shortcut Menu for an Element

To create a User Defined Plot:

1. Right-click on the element where you want the plot to appear, and select **Plot** from the shortcut menu (Figure 14.24). The default plot for that location will appear.
2. Select **Select Variables** from the **Plot** Menu. The **Select Plot Variables** dialog box will appear (Figure 14.25).



Figure 14.25 Select Plot Variables Dialog Box

The **Available Variables** list shows the variables you can choose for your User Defined Plot. The **Selected** list shows variables you have selected.

To add variables to your User Defined Plot:

1. Click on the variable in the **Available Variables** list, then click on the appropriate Plot Region or component in the **Selected** list. This allows you to specify where you want variables to appear in your plot.

2. Click the **Add** button to add the variable you have chosen to the Selected list. If the added variable reflects different units, a separate Y-axis will be automatically added.

To remove a variable, click on its name in the **Selected** list then click the **Remove** button.

You can also **Move** a Plot Region up or down or **Remove** it by right-clicking on the plot region name and choosing the action desired from the shortcut menu, as illustrated in Figure 14.26.



Figure 14.26 Select Plot Variables: Region Shortcut Menu

3. Click the **OK** button. The Select Plot Variables dialog box will close and your User Defined Plot will open.

To save your User Defined Plot:

1. From the **Plot** menu on the plot that appears, select **Save Plot Type...** The **Save Plot Type** dialog box will appear (Figure 14.27). You can specify whether you want this User Defined Plot to be available to **All Applications** or to just **This Watershed only**. Enter a **Name** for the plot.



Figure 14.27 Save Plot Type . . .

2. Click the **Save** button. The Save Plot Type... dialog box will close.

The new User Defined Plot will now be available when you select **User Plots** from the right-click shortcut menu in the Display Area (Figure 14.28).



Figure 14.28 Shortcut Menu: User Plots

14.5.2.4 Viewing Data in Tabular Form

You can view plotted data in tabular form by selecting **Tabulate** from the **File** menu of the plot. Figure 14.29 shows an example.

//SAYERS-FLOOD CONTROL POOL/ELEV-ZONE/20AUG2001/1HOUR/STDOPS----0/

File Edit View

Ordinate	Date / Time	SAYERS-FLOOD... ELEV-ZONE STDOPS----0	SAYERS-CONS... ELEV-ZONE STDOPS----0	SAYERS-INACTIV... ELEV-ZONE STDOPS----0	SAYERS-POOL ELEV STDOPS----0	SAYERS-POOL FLOW-IN STDOPS----0	SAYERS-POOL FLOW-OUT STDOPS----0
Units		ft	ft	ft	ft	cfs	cfs
Type		INST-VAL	INST-VAL	INST-VAL	INST-VAL	INST-VAL	INST-VAL
1	20 Aug 01 11:00	657.00	630.00	590.00	630.81	302.34	151.8
2	20 Aug 01 12:00	657.00	630.00	590.00	630.82	302.08	148.7
3	20 Aug 01 13:00	657.00	630.00	590.00	630.83	301.47	150.2
4	20 Aug 01 14:00	657.00	630.00	590.00	630.83	300.79	151.8
5	20 Aug 01 15:00	657.00	630.00	590.00	630.85	300.11	261.3
6	20 Aug 01 16:00	657.00	630.00	590.00	630.85	299.43	276.6
7	20 Aug 01 17:00	657.00	630.00	590.00	630.85	298.75	279.0
8	20 Aug 01 18:00	657.00	630.00	590.00	630.85	298.07	279.0
9	20 Aug 01 19:00	657.00	630.00	590.00	630.85	297.39	279.0
10	20 Aug 01 20:00	657.00	630.00	590.00	630.86	296.72	279.0
11	20 Aug 01 21:00	657.00	630.00	590.00	630.85	296.04	279.0
12	20 Aug 01 22:00	657.00	630.00	590.00	630.85	295.37	279.0
13	20 Aug 01 23:00	657.00	630.00	590.00	630.85	294.70	279.0
14	20 Aug 01 24:00	657.00	630.00	590.00	630.84	294.04	279.0
15	21 Aug 01 01:00	657.00	630.00	590.00	630.84	293.37	279.0
16	21 Aug 01 02:00	657.00	630.00	590.00	630.83	292.71	279.0

Figure 14.29 Data in Tabular Form

The **View** menu of the Tabular Data window offers four display options. The **View Commas** option displays commas in numbers greater than one thousand. The **Date and Time Separately** option splits the date and time into two separate columns. The **Date with 4 Digit Years** option displays the year with four digits instead of the default two. Lastly, you can set the decimal precision for data using the **Show Decimal Places** option.

You can also resize table columns by dragging their borders to the desired position with your mouse.

14.5.2.5 Printing and Exporting Plots and Tables

You can print ResSim plots and tables, copy and paste them into other applications, and specify export options for plots. See Appendix F for details.

14.5.3 Viewing Summary Reports

Summary Reports are available from the **Reports** menu. In all Summary Reports, the Simulation name and Alternative appear at the top of the window, along with the Lookback date and time, the Start date and time, and the End date and time.

Summary Reports also have two menus. The **File** menu allows you to **Print** and **Close** the report (see Appendix F for information about printing). The **Options** menu lets you **Specify the Time** to review the simulation results for a single time period.

14.5.3.1 Reservoir Summary Reports

The **Reservoir Summary Report** (Figure 14.30) displays Average, Maximum, and Minimum result values for pertinent reservoir parameters.

To view the Reservoir Summary Report, select **Reservoir Summary** from the **Reports** menu.



Location/Parameter	Average	Maximum	Minimum
Sayers			
Storage (ac-ft)	29931	30818	29215
Elevation (ft)	630	631	630
Controlled Release (cfs)	290	3040	149
Uncontrolled Spill (cfs)	0	0	0

Figure 14.30 Reservoir Summary Report

14.5.3.2 Flow Summary Reports

The **Flow Summary Report** (Figure 14.31) displays Average, Maximum, and Minimum values for individual location parameters.

To view the Flow Summary Report, select **Flow Summary** from the **Reports** menu.



Location/Parameter	Average	Maximum	Minimum
Bald Eagle Total			
Regulated Flow (cfs)	586	3083	390
Unregulated Flow (cfs)	542	715	390
Cumulative Local Flow (cfs)	296	412	196
Beech Ck Station			
Regulated Flow (cfs)	137	192	91
Unregulated Flow (cfs)	382	494	283
Cumulative Local Flow (cfs)	137	192	91
Blanchard			
Regulated Flow (cfs)	290	3040	149
Unregulated Flow (cfs)	244	302	192
Cumulative Local Flow (cfs)	0	0	0

Figure 14.31 Flow Summary Report

14.5.3.3 Power Summary Reports

The **Power Summary Report** (Figure 14.32) displays Average, Maximum, and Minimum values for individual location parameters.

To view the Power Summary Report, select **Power Summary** from the **Reports** menu.



Figure 14.32 Power Summary Report

14.5.3.4 Gate Summary Reports

The **Gate Summary Report** (Figure 14.33) displays Average, Maximum, and Minimum values for individual location parameters.

To view the Gate Summary Report, select **Gate Summary** from the **Reports** menu.



Figure 14.33 Gate Summary Report

14.5.3.5 Stage Summary Reports

The **Stage Summary Report** (Figure 14.34) displays Average, Maximum, and Minimum values for individual location parameters.

To view the Stage Summary Report, select **Stage Summary** from the **Reports** menu.



Figure 14.34 Stage Summary Report

14.5.3.6 Release Decision Reports

The **Release Decision Report** (Figure 14.35) displays the Active Zone and Active Rules for the reservoir pool, dam, and outlets at each time step for each reservoir.

To view the Release Decision Report, select **Release Decision** from the **Reports** menu or select **Release Decision Report** from the reservoir's shortcut menu (right-click on reservoir element).



Date-Time	Sayers			
	Active Zone Elev	Sayers Active Rule Flow	-Dam Active Rule Flow	-MainGates Active Rule Flow
24Aug2001 1100	630.82	173.50	173.50	173.50
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:ROC_Incr
24Aug2001 1200	630.81	673.50	673.50	673.50
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:ROC_Incr
24Aug2001 1300	630.78	1,173.50	1,173.50	1,173.50
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:ROC_Incr
24Aug2001 1400	630.73	1,673.50	1,673.50	1,673.50
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:ROC_Incr
24Aug2001 1500	630.66	2,173.50	2,173.50	2,173.50
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:ROC_Incr
24Aug2001 1600	630.56	2,673.50	2,673.50	2,673.50
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:MaxRel-Cau...
24Aug2001 1700	630.45	3,021.26	3,021.26	3,021.26
	Flood Control...	GC:MaxLim	GC:MaxLim	GC:MaxRel-Cau...
24Aug2001 1800	630.32	3,039.63	3,039.63	3,039.63

Figure 14.35 Release Decision Report

The **File** menu allows you to **Print** and **Close** the report (see Appendix F for information about printing).

14.5.3.7 Network Reports

The **Reservoir List**, **Reach List**, **Junction List**, **Diversion List**, and the **Network Connectivity Summary** report are also available from the **Reports** menu of the Simulation Module. Refer to Section 8.5 in Chapter 8 for more information about Network Reports.

14.6 Calibrating the Model and Editing Data

You may need to make adjustments as you test and calibrate your Simulation model. In the Simulation Module of ResSim, you can access editors that allow you to edit all components of your Reservoir Network, modify Alternatives, and fine-tune override controls.

14.6.1 Using the ResSim Editor Interface

In the Simulation Module, the **ResSim Editor Interface** (Figure 14.36) provides access to editors for Reservoirs, Junctions, Reaches, and Diversions, as well as the Alternative Editor, Systems Operations, and the Release Overrides Editor. You can also use the ResSim Editor Interface to quickly set Compute Options.

To access the ResSim Editor Interface, right-click on an Alternative in the simulation tree, then select **Edit > ResSim**.



Figure 14.36 ResSim Editor Interface

14.6.2 Editing Alternative Lookback, Time Series, and Observed Data

To edit *references* to Time Series and Observed data, you will need to access the individual editors for Reservoirs, Junctions, Reaches, and Diversions. To adjust Alternative Lookback data, you will need to use the Alternative Editor (see Chapter 13). You can access each of these editors either from the ResSim Editor Interface (Figure 14.36) or from the Edit menu of the Simulation Module or Reservoir Network Module. Refer to Chapters 9, 10 and 11 for detailed descriptions of the element editors available in ResSim.

14.6.3 Editing Release Override Values

Once you have computed a Simulation, the **Release Overrides Editor** (Figure 14.37) allows you to adjust the computed results for each time step of the Simulation. You can access the Release Overrides Editor using the **Overrides** button in the ResSim Editor Interface (described above in Section 14.6.1); or, you can select **Release Overrides** (and the appropriate Alternative) from the **Simulation** Menu.



Figure 14.37 Release Overrides Editor

ResSim will use the values you specify for Elevation Target and Release Overrides, within the physical limits of the reservoir. The physical rate-of-change and the amount of water available in the reservoir may preclude ResSim from using your override values.

For the Reservoir shown in the list at the top of the editor, there are two tabs available for overriding the simulation results: **Elevation Target** and **Release Overrides**. Each tab contains a **Date**, **Time** and either "Elevation Target" or "Release." You can use either one of these override capabilities to adjust the simulation results.

Specifying Elevation Target Overrides:
Initially, the Target Elevation is based on the elevation values you specified for the reservoir's "guide curve" (Reservoir Editor, Operations tab). This is typically the top of the Conservation pool and is commonly referred to as the "target" or "guide curve". In addition to meeting all of the other rules that you specify for a reservoir, ResSim will try to keep the reservoir pool at the guide curve elevation. Therefore, by specifying Elevation Target values within this editor, you are inherently overriding the reservoir's release decisions.

Specifying Release Overrides:
During a Simulation, ResSim determines the reservoir release values based on the rules you specified for the Alternative. However, there may be situations where you do not want the results to reflect the rules for specific time steps. Therefore, you can enter release values using the Release Overrides tab.

Editing Override Values
You can specify Elevation Target and Release Overrides by entering single cell values or by revising multiple adjacent values using a fill function.

To revise a *single* value, double-click in the cell you want to revise and enter the new value.

To revise *multiple* adjacent values:

1. Point and click on the first cell, then drag your mouse or shift-click (hold down the shift key while clicking in other cells) to highlight the cells to be revised.
2. Right-click on the highlighted cells, and select **Fill** from the shortcut menu (Figure 14.38). The **Table Fill Options** dialog box will open (Figure 14.39)
3. Select the appropriate fill option in the **Table Fill Options** dialog box (Figure 14.39), then click **OK**.



Figure 14.38 Release Overrides Editor Shortcut Menu: Fill Data Values



Figure 14.39 Table Fill Options Dialog Box

The revised values will reflect the fill option you selected. In the example shown in Figure 14.39, the **Repeat Fill** option is selected. Therefore, as the table in Figure 14.40 illustrates, all of the highlighted cells equal the value of the first cell selected; also, the color of the revised values changes from black to blue and the mini-plot shows the revised values as a red line. The mini-plot can be viewed in full size when you double-click on it.



Figure 14.40 Release Overrides Editor Table: Revised Data Values using Repeat Fill Option

For those time steps where you do not specify override values, ResSim uses the reservoir rules to determine the reservoir release values. After running a simulation using your override values, you may decide to no longer use some, or all, of your override values. Therefore, you can use the **Unspecify** and **Unspecify All** buttons to indicate that you want ResSim to determine the release values.

Use the **Unspecify** button when you want release values to be based on the reservoir rules for some of the override values you have specified (override values are in green text after a simulation is computed). Highlight the cells where you have specified override values, then press the **Unspecify** button.

Use the **Unspecify All** button when you want all of the release values to be based on the reservoir rules and not have any overrides specified.

Use the **Import** button when you want to use a time series of override values. The **Import Overrides Time Series** dialog box (Figure 14.41) will open, which functions exactly like the **Select Time Series Path** dialog box used to select time-series records for an Alternative. Refer to Section 13.6 in Chapter 13 for more information.



Figure 14.41 Import Time Series Dialog Box

14.6.4 Setting Compute Options

You can quickly set **Compute Options** for an Alternative using the ResSim Editor Interface.

To set Compute Options, access the ResSim Editor Interface by right-clicking on an Alternative in the simulation tree, then selecting **Edit>ResSim**.

The **ResSim Editor Interface** will open. **Compute Options** appear in the center of this interface (Figure 14.42.



Figure 14.42 ResSim Editor Interface: Compute Options

- Check **Compute Unregulated Flows** if you want ResSim to perform additional calculations to determine the unregulated conditions in the watershed (e.g., without the regulation of reservoirs and projects).
- Check **Compute Holdouts** when you want ResSim to calculate the amount of water the reservoir stores (as opposed to just releasing inflow). Holdouts indicate the effects of reservoir regulation and are most applicable when you will be performing a subsequent Flood Impact or Flood Damage analysis.
- Select the **Log Level** (1-10) to control the amount of detailed messages that will be output during the computations.

14.7 Managing Simulation Data

ResSim facilitates archiving and sharing of Simulation data. There are two operations involved in managing Simulation data. You can save your data to the base directory to make it available for other Simulations, and you can replace data in a Simulation for a specific Alternative with data from the base directory.

14.7.1 Saving Data *to* the Base Directory

When you edit model data from the Simulation Module, your changes apply only to an individual Alternative and are saved in your Simulation directory (see Appendix A for an overview of the ResSim directory structure).

> ***Important:*** *If you want your changes to be available for subsequent Simulations, you will need to* ***save*** *the data* ***back to*** *the Base directory.*

To *save* data *to* the Base directory:

1. In the Simulation Control Panel, right-click on the Alternative to access the shortcut menu, then choose **Save to Base Directory** (Figure 14.43). The **Save Simulation Run Model Parameters to Base Directory** dialog box will appear (Figure 14.44).



Figure 14.43 Alternative Shortcut Menu: Save to Base Directory



Figure 14.44 Save Simulation Run Model Parameters to Base Directory

2. Select the appropriate boxes in the **Copy Data** column beside the items you wish to copy from the Simulation directory to the Base directory.
3. Click the **OK** button to save the Simulation data to the Base directory.

14.7.2 Replacing Data *from* the Base Directory

If, while editing Simulation data, you need to revert to the original Alternative data, you can *replace* the changed data in your Simulation directory with data *from* the Base directory.

To *replace* Simulation data with data *from* the Base directory:

1. From the Simulation Control Panel, right-click on the Alternative to access the shortcut menu, then choose **Replace from Base Directory** (Figure 14.45). The **Replace Simulation Run Model Parameters from Base Directory** dialog box will appear (Figure 14.46).



Figure 14.45 Alternative Shortcut Menu: Replace from Base Directory



Figure 14.46 Replace Simulation Run Model Parameters from Base Directory

2. Select the appropriate boxes in the **Restore Data** column beside the items you wish to restore from the Base directory to the Simulation directory.
3. Click the **OK** button to replace the Simulation Alternative data you have selected with data from the Base directory.

14.8 Using HEC-DssVue

Included within the framework of ResSim is **HEC-DssVue**, a tool that allows you to access data stored in HEC-DSS database files.

When **HecDssVue** is selected from the **Tools** menu (Figure 14.47) within the Simulation Module, the current "simulation.dss" file is opened.

Figure 14.47 Accessing HEC-DssVue from the Tools Menu

In the Main Window of HEC-DssVue, a listing of pathnames that are contained in the simulation.dss file are provided, as shown in Figure 14.48.



Figure 14.48 HEC-DssVue Main Window Showing Pathname Listing

A screened listing of pathnames can be obtained by selecting a pathname part from the lists in the **Search by Parts** section of the window. For example, if you want a listing of "observed" records, you can select OBS from the F-part list, as shown in Figure 14.49. To obtain an unscreened listing of pathnames, select the "blank" area at the top of the list.



Figure 14.49 Screened Pathname Listing Showing Observed (OBS) Records

To select records to be plotted, tabulated, or edited, highlight the desired pathnames and click on the **Select** button. After one or more records are selected, the icons for the graph and table become active. Now, you can click on either icon to generate a plot (Figure 14.50) or table (Figure 14.51) of the selected records.



Figure 14.50 Example Plot Using HEC-DssVue



Ordinate	Date / Time	BALD EAGLE T... FLOW STDOPS----0	BALD EAGLE T... FLOW-CUMLOC STDOPS----0	BALD EAGLE T... FLOW-UNREG STDOPS----0
Units		cfs	cfs	cfs
Type		INST-VAL	INST-VAL	INST-VAL
1	20 Aug 01 11:00	564.2	412.44	714.78
2	20 Aug 01 12:00	564.0	412.18	714.52
3	20 Aug 01 13:00	563.3	411.48	713.81
4	20 Aug 01 14:00	561.9	410.47	712.78
5	20 Aug 01 15:00	559.7	409.28	711.43
6	20 Aug 01 16:00	558.6	407.97	709.77
7	20 Aug 01 17:00	569.6	406.61	707.91
8	20 Aug 01 18:00	607.9	405.22	705.93
9	20 Aug 01 19:00	640.5	403.83	703.90
10	20 Aug 01 20:00	659.9	402.44	701.85
11	20 Aug 01 21:00	669.5	401.04	699.78
12	20 Aug 01 22:00	673.6	399.65	697.72
13	20 Aug 01 23:00	674.8	398.27	695.66
14	20 Aug 01 24:00	674.7	396.89	693.61
15	21 Aug 01 01:00	673.9	395.51	691.56
16	21 Aug 01 02:00	672.8	394.14	689.51
17	21 Aug 01 03:00	671.6	392.77	687.48
18	21 Aug 01 04:00	670.3	391.41	685.45
19	21 Aug 01 05:00	669.0	390.05	683.43
20	21 Aug 01 06:00	667.6	388.70	681.41
21	21 Aug 01 07:00	666.3	387.35	679.40
22	21 Aug 01 08:00	665.0	386.01	677.40
23	21 Aug 01 09:00	663.6	384.67	675.41
24	21 Aug 01 10:00	662.3	383.34	673.42

Figure 14.51 Example of Tabulated Data Using HEC-DssVue

For a more detailed description of HEC-DssVue, see Appendix E.

HEC-ResSim

Reservoir System Simulation

User's Manual: APPENDICES

Version 2.0
September 2003

List of Appendices

Appendix Page

A ResSim Application Settings
A.1 Working with Watershed Directories and Files....A-1
A.2 Setting Application Options....A-2
A.2.1 Setting Model Directories for Watersheds....A-2
A.2.2 Setting the Cache Directory....A-3
A.2.3 Configuring the Compute Display....A-3
A.2.4 Specifying Debug Levels....A-4
A.2.5 Setting General Options....A-5
A.2.6 Specifying Fonts....A-5
A.3 Viewing Application Properties....A-6
A.3.1 Viewing Client Properties....A-6
A.3.2 Viewing User Properties....A-7
A.3.3 Viewing Watershed Properties....A-8
A.3.4 Viewing Server Properties....A-8
A.3.5 Viewing and Editing System Properties....A-9

B Setting Up the Coordinate System
B.1 Accessing Map Coordinate Information....B-1
B.2 Coordinate Systems Options....B-2
B.2.1 X-Y System....B-2
B.2.2 Geographic System....B-3
B.2.3 Universal Transverse Mercator System....B-3
B.2.4 State Plane Coordinates System....B-4
B.2.5 Albers Equal-Area Conic System....B-4
B.2.6 Lambert Conformal Conic System....B-5
B.2.7 Transverse Mercator System....B-6
B.2.8 Albers Equal-Area Conic (SHG) System....B-7
B.2.9 Polar Sterographic (HRAP) System....B-8

C Using Map Editors
C.1 USGS Digital Line Graph Maps (*.dlg)....C-2
C.2 ArcView® Shapefiles (*.shp)....C-3
C.2.1 Line and Polygon Shapefiles....C-3
C.2.2 Point Shapefiles....C-4
C.3 ArcInfo® DEM, ASCII DEM, and ASCII NetTIN Maps....C-4

D Using the Color Chooser
D.1 Swatches....D-1
D.2 HSB Colors....D-2
D.3 RGB Colors....D-2

List of Appendices (continued)

Appendix Page

E Using HEC-DssVue
E.1 The HEC-DssVue Data Selection List Window E-1
E.1.1 Menu Options E-3
E.1.2 Menu Buttons E-4
E.1.3 Data Selection Fields and Buttons E-4
E.2 Opening a DSS Database File for Browsing E-5
E.3 Sorting DSS Pathnames by Parts E-6
E.4 Selecting DSS Pathnames E-6
E.5 Using Plots and Tables to Visualize DSS Data E-6
E.6 Editing Tabular Data in HEC-DssVue E-8
E.7 Performing Math Functions in HEC-DssVue E-8
E.8 Entering Time-Series Data Manually in HEC-DssVue E-11
E.9 Entering Paired Data Manually in HEC-DssVue E-12
E.10 Renaming DSS Records in HEC-DssVue E-13
E.11 Copying Records into a DSS File in HEC-DssVue E-14
E.12 Duplicating Records in HEC-DssVue E-14
E.13 Merging Records into a DSS File in HEC-DssVue E-15
E.14 Squeezing DSS Files in HEC-DssVue E-15
E.15 Viewing DSS Status in HEC-DssVue E-16
E.16 Deleting Records from a DSS File E-16
E.17 Undoing Most Recent Revisions E-17
E.18 Printing Plots and Tables in HEC-DssVue E-17

F Copying and Printing ResSim Data
F.1 Saving Plots and Templates F-2
F.1.1 Save Plot to a File F-2
F.1.2 Saving and Applying Plot Templates F-2
F.2 Copying Plots to the Clipboard F-3
F.3 Printing Plots F-3
F.4 Copying, Exporting, and Printing Tabulated Data F-5
F.4.1 Copying Tabulated Data to the Clipboard F-5
F.4.2 Exporting Tabulated Data F-6
F.4.3 Printing Tabulated Data F-7
F.5 Printing Simulation Reports F-9

G References

List of Tables

Table Number **Page**

B.1 Available System, Unit and Spheroid Options for Defining Coordinate System B-2

List of Figures

Figure Number **Page**

A.1 ResSim Watershed Directory Structure A-1
A.2 HEC-ResSim Options Dialog Box A-2
A.3 Options Dialog Box, Model Directories Tab A-2
A.4 Options Dialog Box, Cache Directory Tab A-3
A.5 Options Dialog Box, Compute Display Tab A-4
A.6 Options Dialog Box, Debug Levels Tab A-4
A.7 Options Dialog Box, General Tab A-5
A.8 Options Dialog Box, Fonts Tab A-5
A.9 Application Properties Dialog Box, Client Tab A-6
A.10 Application Properties Dialog Box, User Tab A-7
A.11 Application Properties Dialog Box, Watershed Tab A-8
A.12 Application Properties Dialog Box, Server Tab A-8
A.13 Application Properties Dialog Box, System Properties Tab A-9
A.14 Edit System Property Dialog Box A-9
A.15 New System Property Dialog Box A-10

B.1 Steps for Accessing Map Coordinate Information B-1
B.2 Map Coordinate Information, X-Y System B-2
B.3 Map Coordinate Information, Geographic System B-3
B.4 Map Coordinate Information, Universal Transverse Mercator System B-3
B.5 Map Coordinate Information, State Plane Coordinates System B-4
B.6 Map Coordinate Information, Albers Equal-Area Conic System B-4
B.7 Map Coordinate Information, Lambert Conformal Conic System B-5
B.8 Map Coordinate Information, Transverse Mercator System B-6
B.9 Map Coordinate Information, Albers Equal-Area Conic (SHG) System B-7
B.10 Map Coordinate Information, Polar Sterographic (HRAP) System B-8

List of Figures (continued)

Figure Number **Page**

C.1 Layer Selector Dialog Box C-1
C.2 USGS Digital Line Graph Editor C-2
C.3 Shapefile Display Options Dialog Box C-3
C.4 Point Color Chooser Dialog Box C-4
C.5 Elevation Options Dialog Box C-5

D.1 Color Chooser: Swatches Tab D-1
D.2 Color Chooser: HSB Tab D-2
D.3 Color Chooser: RGB Tab D-2

E.1 HEC-DssVue - Data Selection List Window, Condensed Catalog Displayed E-2
E.2 HEC-DssVue - Data Selection List Window, Pathname Parts Displayed E-2
E.3 HEC-DssVue - Data Selection List Window, Pathname List Displayed E-3
E.4 Search Pathnames Option E-4
E.5 Search by Parts Option E-4
E.6 Data Selection List Buttons E-4
E.7 Open HEC-DSS File Browser E-5
E.8 Example Plot from HEC-DssVue E-7
E.9 Example Tabulation from HEC-DssVue E-7
E.10 Edit Menu -- Allow Editing Option E-8
E.11 HEC-DssVue Math Functions Dialog Box E-9
E.12 HEC-DssVue Math Functions, Statistics Tab E-9
E.13 HEC-DssVue Save As Dialog Box E-10
E.14 HEC-DssVue Manual Time Series Data Entry Dialog Box E-11
E.15 HEC-DssVue Manual Paired Data Entry Dialog Box E-12
E.16 HEC-DssVue Rename Records Dialog Box E-13
E.17 HEC-DssVue Copy Records into HEC-DSS File Dialog Box E-14
E.18 HEC-DssVue New Pathname Parts for Duplicate Records Dialog Box E-14
E.19 HEC-DssVue Merge (copy all records) into HEC-DSS File Dialog Box E-15
E.20 HEC-DssVue Squeeze Progress Window (Example) E-16
E.21 HEC-DssVue Squeeze Confirmation Message (Example) E-16
E.22 HEC-DSS File Manager Status Window E-16
E.23 Confirm List of Records to be Deleted E-17
E.24 Confirmation Message that Records have been Deleted E-17

List of Figures (continued)

Figure Number **Page**

F.1 Plot Window - File Menu F-1
F.2 Plot Window - File Menu: Save Plot F-2
F.3 Plot Window - File Menu: Save Plot Template F-2
F.4 Plot Window - File Menu: Print Dialog Box F-3
F.5 Page Setup Dialog Box F-3
F.6 Printer Margins Dialog Box F-3
F.7 Print Preview of a Plot (Example) F-4
F.8 Print Multiple Plots Dialog Box F-4
F.9 Print Multiple Preview Dialog Box (Example) F-5
F.10 Copy Command from Edit Menu of Tabulated Data Window F-6
F.11 Copy Command from Shortcut Menu of Tabulated Data F-6
F.12 Table Export Options Dialog Box F-6
F.13 Print Command from File Menu of Tabulated Data Window F-7
F.14 Print Command from Shortcut Menu of Tabulated Data F-7
F.15 Print Properties Dialog Box F-7
F.16 Print Preview of a Table (Example) F-8
F.17 Print Dialog Box F-8
F.18 Print Preview of Flow Summary Report F-9

Appendix A
ResSim Application Settings

Table of Contents

Section **Page**

A ResSim Application Settings
A.1 Working with Watershed Directories and Files....A-1
A.2 Setting Application Options....A-2
A.2.1 Setting Model Directories for Watersheds....A-2
A.2.2 Setting the Cache Directory....A-3
A.2.3 Configuring the Compute Display....A-3
A.2.4 Specifying Debug Levels....A-4
A.2.5 Setting General Options....A-5
A.2.6 Specifying Fonts....A-5
A.3 Viewing Application Properties....A-6
A.3.1 Viewing Client Properties....A-6
A.3.2 Viewing User Properties....A-7
A.3.3 Viewing Watershed Properties....A-8
A.3.4 Viewing Server Properties....A-8
A.3.5 Viewing and Editing System Properties....A-9

List of Figures

Figure Number **Page**

A.1 ResSim Watershed Directory Structure....A-1
A.2 HEC-ResSim Options Dialog Box....A-2
A.3 Options Dialog Box, Model Directories Tab....A-2
A.4 Options Dialog Box, Cache Directory Tab....A-3
A.5 Options Dialog Box, Compute Display Tab....A-4
A.6 Options Dialog Box, Debug Levels Tab....A-4
A.7 Options Dialog Box, General Tab....A-5
A.8 Options Dialog Box, Fonts Tab....A-5
A.9 Application Properties Dialog Box, Client Tab....A-6
A.10 Application Properties Dialog Box, User Tab....A-7
A.11 Application Properties Dialog Box, Watershed Tab....A-8
A.12 Application Properties Dialog Box, Server Tab....A-8

List of Figures (continued)

Figure Number **Page**

A.13 Application Properties Dialog Box, System Properties Tab A-9
A.14 Edit System Property Dialog Box A-9
A.15 New System Property Dialog Box A-10

Appendix A

ResSim Application Settings

A.1 Working with Watershed Directories and Files

When you create a new watershed, ResSim generates a directory structure and stores all files associated with the watershed inside that structure.

Figure A.1 illustrates a "tree structure" that shows how ResSim organizes the folders it creates in the root (modeling) directory identified for your watershed. The **root** directory (e.g., *HECResSim_V2.0*) contains a subdirectory named **base**.



Figure A.1 ResSim Watershed Directory Structure

When you create a new watershed, ResSim creates a new watershed directory in the base directory. The watershed directory is named according to the name you have given the watershed. For example, in Figure A.1, the **watershed** directory is *BaldEagle*. The watershed directory stores all of the base data for the watershed, including maps, schematic elements, base model data, and simulation data and results.

When you create a new simulation, ResSim generates a **simulation** directory named according to the date and time of the simulation. In Figure A.1, the directory name *1993.11.29-0700* corresponds to a simulation for November 29, 1993, at 07:00am. When a simulation is created, ResSim automatically copies all of the base data for your watershed (except for maps) into the simulation directory. This facilitates archiving of simulation information and ensures consistency in your model results.

If you **Save to Base Directory** in the Simulation Module, ResSim copies your model alternative data from the simulation directory back to the base directory. If you **Replace From Base Directory** in the Simulation Module, ResSim copies the original model alternative data from your base directory into your simulation directory. See Chapter 14, Section 14.7 for more information about these commands.

A.2 Setting Application Options

ResSim allows you to configure several options. You can specify the model directories for your watersheds, cache directory for maps, configure the display for the compute display, and specify debug levels.

To configure these options, select **Options** from the **Tools** menu of any module to access the **Options** dialog box (Figure A.2).



Figure A.2 HEC-ResSim Options Dialog Box

A.2.1 Setting Model Directories for Watersheds

The **Model Directories** tab lets you specify the working directory for watershed data on your local computer. An example of the **Model Directories** tab is shown in Figure A.3, and a detailed description is presented in Chapter 3, Section 3.3.1.



Figure A.3 Options Dialog Box, Model Directories Tab

A.2.2 Setting the Cache Directory

The **Cache Directory** is pertinent when running ResSim in a "client-server" mode (not applicable for standalone version of ResSim). The cache directory is the location on your computer where ResSim copies background maps for a watershed so they aren't downloaded from the server each time you access the watershed.

To specify the cache directory on your local computer, select the **Cache Directory** tab in the Options dialog box (Figure A.4). After clicking in the **Use Cache** box, you can either type in a directory path or click the **Browse** button to find the directory you want.



Figure A.4 Options Dialog Box, Cache Directory Tab

A.2.3 Configuring the Compute Display

When you compute a simulation in the Simulation Module, the **Compute Display** window reports on the progress of the model and presents warning and error messages generated by the model. The **Compute Display** tab of the Options dialog box (Figure A.5) allows you to configure the appearance of the Compute Display window. You can configure the Compute Display to present logs as HTML (web pages), specify a background color for HTML, and specify the text colors for compute messages, warnings, and errors.



Figure A.5 Options Dialog Box, Compute Display Tab

A.2.4 Specifying Debug Levels

You will use the **Debug Levels** tab of the Options dialog box (Figure A.6) primarily when you need technical support. With this tab, you can specify the level of detail for problem tracking. Higher numbers in the **Level** column specify more detail in debug reporting.



Figure A.6 Options Dialog Box, Debug Levels Tab

A.2.5 Setting General Options

Use the **General** tab of the Options dialog box (Figure A.7) to specify whether ResSim shows a confirmation message when you exit the program and/or whether to load the last Watershed when you start the program.



Figure A.7 Options Dialog Box, General Tab

A.2.6 Specifying Fonts

Use the **Fonts** tab of the Options dialog box (Figure A.8) to specify the font that will be used for a variety of components in the display. These components include: Tabs, Labels, Descriptions for Radio Buttons and Checkboxes, Buttons, Lists and Textfields.



Figure A.8 Options Dialog Box, Fonts Tab

A.3 Viewing Application Properties

The **Application Properties** dialog box will be of assistance if you need to seek technical support. Similar to a *File>Properties* dialog box in a Windows application, the Application Properties dialog box provides details about your ResSim setup. These details include information about your local computer (your ResSim root directory, whether you are working in local or networked mode, and the IP address of your computer); your unique user properties (your user ID, user name, login, user directory path, preference directory, and access levels); watershed properties for the watershed you are viewing; server properties (application server, **File** manager, and login server); and system properties.

To access the Application Properties dialog box, choose **Information** from the **Tools** menu of any ResSim module.

A.3.1 Viewing Client Properties

The **Client Properties** tab of the Application Properties dialog box (Figure A.9) displays information about your local computer's setup. The directory shown as **Base Directory** is your *root* directory for your watershed (as previously described in Sections A.1 and A.2.1). The **Mode** indicates whether you are working locally on your PC or are connected to a network in "client-server" mode. The **Port** and **Client URL** information are not applicable for the local mode of ResSim. The "client-server" mode is not described in the documentation for ResSim.



Figure A.9 Application Properties Dialog Box, Client Tab

A.3.2 Viewing User Properties

The **User** tab of the Application Properties dialog box (Figure A.10) is primarily used for displaying CWMS "client-server" information, such as your user ID, user name, login, user directory, user preference directory, and user types (access levels).



Figure A.10 Application Properties Dialog Box, User Tab

A.3.3 Viewing Watershed Properties

The **Watershed** tab of the Application Properties dialog box (Figure A.11) displays details about the currently opened watershed, and includes the Watershed Name, directory Path, Watershed Units, and Watershed Time Zone. Watershed Monetary Units is in development for later versions of ResSim. The Watershed Coordinate System being used is also displayed. The Current Watershed Users is pertinent for CWMS "client-server" mode and is not described in the ResSim documentation.



Figure A.11 Application Properties Dialog Box, Watershed Tab

A.3.4 Viewing Server Properties

The **Server** tab of the Application Properties dialog box (Figure A.12) is pertinent for CWMS "client-server" mode and is not described in the ResSim documentation.



Figure A.12 Application Properties Dialog Box, Server Tab

A.3.5 Viewing and Editing System Properties

You will only need to use the **System Properties** tab of the Application Properties dialog box (Figure A.13) for debugging purposes. Although you can view this tab, *editing properties is not recommended*.

> *You must be extremely careful when making changes to the System Properties, as they directly affect ResSim's functionality.*



Figure A.13 Application Properties Dialog Box, System Properties Tab

If you absolutely need to edit the properties, highlight the property to edit and click the **Edit** button. The **Edit System Property** dialog box will open (Figure A.14), allowing you to type in the **Property** name and **Property Value**. Note that only certain properties are editable.



Figure A.14 Edit System Property Dialog Box

You can also add system properties by clicking the **New...** button. The **New System Property** dialog box will open (Figure A.15), allowing you to enter a new **Property** name and **Property Value**.



Figure A.15 New System Property Dialog Box

You can also **Delete** System Properties but it is *not recommended* to do so.

Appendix B

Setting Up the Coordinate System

Table of Contents

Section **Page**

B Setting Up the Coordinate System
B.1 Accessing Map Coordinate Information B-1
B.2 Coordinate Systems Options..... B-2
B.2.1 X-Y System B-2
B.2.2 Geographic System B-3
B.2.3 Universal Transverse Mercator System B-3
B.2.4 State Plane Coordinates System B-4
B.2.5 Albers Equal-Area Conic System..... B-4
B.2.6 Lambert Conformal Conic System B-5
B.2.7 Transverse Mercator System B-6
B.2.8 Albers Equal-Area Conic (SHG) System B-7
B.2.9 Polar Sterographic (HRAP) System B-8

List of Tables

Table Number

B.1 Available System, Unit and Spheroid Options for Defining Coordinate System B-2

List of Figures

Figure Number

B.1 Steps for Accessing Map Coordinate Information B-1
B.2 Map Coordinate Information, X-Y System..... B-2
B.3 Map Coordinate Information, Geographic System B-3
B.4 Map Coordinate Information, Universal Transverse Mercator System..... B-3
B.5 Map Coordinate Information, State Plane Coordinates System..... B-4
B.6 Map Coordinate Information, Albers Equal-Area Conic System B-4
B.7 Map Coordinate Information, Lambert Conformal Conic System..... B-5
B.8 Map Coordinate Information, Transverse Mercator System..... B-6
B.9 Map Coordinate Information, Albers Equal-Area Conic (SHG) System..... B-7
B.10 Map Coordinate Information, Polar Sterographic (HRAP) System..... B-8

Appendix B

Setting up the Coordinate System

Chapter 3, Section 3.4.3 "Specifying the Geographic Referencing and Coordinate System" explains how to edit the coordinate system of your watershed by accessing the **Map Coordinate Information**. This Appendix provides more detailed information related to setting up the coordinate system for your watershed.

B.1 Accessing Map Coordinate Information

To access the Map Coordinate Information from any of the three ResSim modules:

1. From the **View** menu in the Main window, select **Layers**.
2. From the **Maps** menu in the Layer Selector dialog box, select **Map Display Coordinates**.
3. In the Display Coordinate Information dialog box, select **Edit**.
4. The **Map Coordinate Information** dialog box will appear where you can set the appropriate coordinate information.

These steps are illustrated in Figure B.1.



Figure B.1 Steps for Accessing Map Coordinate Information

Table B.1 shows the available options for **System**, **Units**, and **Spheroid**. When you choose specific coordinate systems, not all options are available from the **Spheroid** list. For example, choosing **X-Y** from the **System** list deactivates the **Spheroid** list. Additionally, when **State Plane Coordinates** is selected as the **System**, only **Clarke 1886** and **GRS 1980** are available choices from the **Spheroid** list.

Table B.1 Available System, Unit and Spheroid Options for Defining Coordinate System

System	Units	Spheroid
X-Y *	Radians	Clarke 1866
Geographic	U.S. Feet	WGS 72
Universal Transverse Mercator	Meters	GRS 1980
State Plane Coordinates **	Seconds of Arc	WGS 84
Albers Equal-Area Conic	Degrees of Arc	Sphere of Radius 6370997 Meters
Lambert Conformal Conic	International Feet	
Transverse Mercator	State Zone	
Albers Equal-Area Conic (SHG)		
** X-Y does not allow selection of Spheroid ** State Plane Coordinates allows choice of only Clarke 1866 and GRS 1980 from the Spheroid list*		

B.2 Coordinate Systems Options

The following sections describe each of the Coordinate Systems that are available from the **Map Coordinate Information** dialog box.

B.2.1 X-Y System

When you choose **X-Y** for the coordinate system (Figure B.2), you need only make a selection for **Units** (U.S. Feet, Meters, or International Feet).



Figure B.2 Map Coordinate Information, X-Y System

B.2.2 Geographic System

The **Geographic** coordinate system (Figure B.3) requires that you specify both **Units** (Radians, Seconds of Arc, or Degrees of Arc) and **Spheroid** (see list in Figure B.3).



Figure B.3 Map Coordinate Information, Geographic System

B.2.3 Universal Transverse Mercator System

The **Universal Transverse Mercator** coordinate system (Figure B.4) requires you to specify both **Units** (U.S. Feet, Meters, or International Feet) and **Spheroid** (same list as shown in Figure B.3).

Additionally, you need to type in the **UTM Zone**.



Figure B.4 Map Coordinate Information, Universal Transverse Mercator System

B.2.4 State Plane Coordinates System

When you choose the **State Plane Coordinates** system (Figure B.5), you must select **Units** (U.S. Feet Meters, or International Feet) and **Spheroid**. The options for Spheroid are limited to Clarke 1866(NAD27) and GRS 1980(NAD83).

You also must type in a **Zone**.



Figure B.5 Map Coordinate Information, State Plane Coordinates System

B.2.5 Albers Equal-Area Conic System

The **Albers Equal-Area Conic** coordinate system (Figure B.6) requires a selection for both **Units** (U.S. Feet, Meters, or International Feet) and **Spheroid** (same list as shown in Figure B.3).

Additional required information includes: **Latitude of the first standard parallel**; **Latitude of the second standard parallel**; **Longitude of the central meridian**; **Latitude of the projection origin**; **False easting**, and **False northing**.



Figure B.6 Map Coordinate Information, Albers Equal-Area Conic System

When specifying latitudes, use **N** or **S**. For longitudes, use **E** or **W**. You may either type these into the fields, or use the SPACEBAR on your keyboard to toggle between the acceptable entries (after placing your cursor in the first box of either the latitude or longitude field).

B.2.6 Lambert Conformal Conic System

The **Lambert Conformal Conic** coordinate system (Figure B.7) requires a selection for both **Units** (U.S. Feet, Meters, or International Feet) and **Spheroid** (same list as shown in Figure B.3).



Figure B.7 Map Coordinate Information, Lambert Conformal Conic System

Additional required information includes: **Latitude of the first standard parallel**; **Latitude of the second standard parallel**; **Longitude of the central meridian**; **Latitude of the projection origin**; **False easting**; and **False northing**.

When specifying latitudes, use **N** or **S**. For longitudes, use **E** or **W**. You may either type these into the fields, or use the SPACEBAR on your keyboard to toggle between the acceptable entries (after placing your cursor in the first box of either the latitude or longitude field).

B.2.7 Transverse Mercator System

For the **Transverse Mercator** coordinate system (Figure B.8), you must choose both the **Units** (U.S. Feet, Meters, or International Feet) and **Spheroid** (same list as shown in Figure B.3).



Figure B.8 Map Coordinate Information, Transverse Mercator System

Additional required information includes: **Scale factor at central meridian**; **Longitude of the central meridian**; **Latitude of the projection origin**; **False easting**; and **False northing**.

When specifying latitudes, use **N** or **S**. For longitudes, use **E** or **W**. You may either type these into the fields, or use the SPACEBAR on your keyboard to toggle between the acceptable entries (after placing your cursor in the first box of either the latitude or longitude field).

B.2.8 Albers Equal-Area Conic (SHG) System

The **SHG** version of the **Albers Equal-Area Conic (SHG)** coordinate system (Figure B.9) provides a set of default parameters. You only need to make a selection for **Spheroid** (the same list as shown in Figure B.3).

You need not change the default parameters for **Units**, the **Latitude of the first standard parallel**, the **Latitude of the second standard parallel**, the **Longitude of the central meridian**, the **Latitude of the projection origin**, the **False easting**, or the **False northing**.



Figure B.9 Map Coordinate Information, Albers Equal-Area Conic (SHG) System

B.2.9 Polar Sterographic (HRAP) System

The **Polar Sterographic (HRAP)** coordinate system (Figure B.10) requires that you specify both the **Units** (U.S. Feet, Meters, or International Feet) and **Spheroid** (same list as shown in Figure B.3).

Additional information required includes the **Axis (Semi-major and Semi-minor)**, the **Central Meridian**, the **Latitude of true scale**, **False easting**, and **False northing**.



Figure B.10 Map Coordinate Information, Polar Sterographic (HRAP) System

When specifying **Central Meridian**, use **E** or **W**. For the **Latitude of true scale**, use **N** or **S**. You may either type these into the fields, or use the SPACEBAR on your keyboard to toggle between the acceptable entries (after placing your cursor in the first box of either the Central Meridian or Latitude field).

Appendix C
Using Map Editors

Table of Contents

Section **Page**

C Using Map Editors
C.1 USGS Digital Line Graph Maps (*.dlg) C-2
C.2 ArcView® Shapefiles (*.shp) C-3
C.2.1 Line and Polygon Shapefiles C-3
C.2.2 Point Shapefiles C-4
C.3 ArcInfo® DEM, ASCII DEM, and ASCII NetTIN Maps C-4

List of Figures

Figure Number

C.1 Layer Selector Dialog Box C-1
C.2 USGS Digital Line Graph Editor C-2
C.3 Shapefile Display Options Dialog Box C-3
C.4 Point Color Chooser Dialog Box C-4
C.5 Elevation Options Dialog Box C-5

Appendix C
Using Map Editors

Map layers can be any of the seven formats supported by ResSim and described in Chapter 3, Section 3.4.1. These formats include ArcView® Shapefiles, AutoCAD® DXF files, Raster images, United States Geological Survey (USGS) Digital Line Graphs, USGS Digital Elevation Model files, ASCII NET TIN files, and ArcInfo® DEM files. ResSim Version 1.1 allows you to configure several options for each type of map (except for AutoCAD® DXF files). Additional customization is in development for future versions of ResSim.

To access the map layer editors for a map layer, open the **Layer Selector** (Figure C.1) by selecting **Layers...** from the **View** menu of any module (note that some layers are visible only in specific modules; see Chapter 4). Double-click on the map layer name in the Layer Tree or right-click on the map layer name and select **Properties** from the shortcut menu. An editor specific to the type of map will open.

The following sections describe the map layer editors currently available in ResSim.



Figure C.1 Layer Selector Dialog Box

C.1 USGS Digital Line Graph Maps (*.dlg)

If the map layer you wish to configure is a USGS Digital Line Graph map (*.*dlg*), the **Properties** command opens the **USGS Digital Line Graph Editor** (Figure C.2). The location of the map in your ResSim directory is shown at the top of the dialog box. When ResSim interacts with a *dlg* file, it automatically creates a *dlgbin* file for use within the watershed.



Figure C.2 USGS Digital Line Graph Editor

With this properties editor, you can specify the **Default Color** of the map and choose whether or not **Nodes**, **Lines**, and **Areas** are displayed in the watershed. You can also set the **Saturation** and **Brightness** of the display. You control the **Saturation** (the amount of black) and the **Brightness** (the amount of white) by typing in a number between 0 and 1.

When you click on the **Default Color** button in the USGS Digital Line Graph Options Editor, the **Color Chooser** appears (see Appendix D).

C.2 ArcView® Shapefiles (*.shp)

This layer type is the native data structure for the ArcView® GIS program. Shapefiles store non-topological geometry and attribute information for the spatial features of a data set. There are three kinds of shapefiles (*.shp): Line shapefiles, Polygon shapefiles, and Point shapefiles.

C.2.1 Line and Polygon Shapefiles

If the map layer you wish to configure is a Line shapefile (e.g., rivers and streams) or a Polygon shapefile (e.g., lakes), the **Properties** command opens the **Shapefile Display Options** dialog box (Figure C.3). The location of the map in your ResSim directory is shown at the top of the dialog box.

With this properties editor, you can choose whether or not **Labels**, **Lines**, and **Areas** are displayed in the watershed.

To specify colors, you can choose **Draw Using Default Color** or you can select the component you wish to customize (*e.g.,* AREA). The colors and values associated with this component will appear in the **Color/Value** table. Double-click on the color table to access the **Color Chooser** (see Appendix D).



Figure C.3 Shapefile Display Options Dialog Box

Click **OK** to close the **Shapefile Display Options** dialog box. From the **Layer Selector** dialog box, click **Apply** and the color for the selected field will appear in the display area. If you wish to save your changes, from the **File** menu, choose **Save Watershed**. Changes are saved to a file with the extension of *.gdr*. For example, in Figure C.3, the shapefile name is *np_lakes.shp* and if you made changes and saved the watershed, a file named *np_lakes.gdr* is created in the *maps* directory for your watershed.

C.2.2 Point Shapefiles

If the map layer you wish to configure is a point shapefile, the **Properties** command opens the **Point Color Chooser** dialog box (Figure C.4), which works exactly like the **Color Chooser** (see Appendix D for instructions). From the color palette, select a color and click **OK**. The **Color Chooser** will close. From the **Layer Selector** dialog box, click **Apply** and the color for the points will appear in the display area.



Figure C.4 Point Color Chooser Dialog Box

C.3 ArcInfo® DEM, ASCII DEM, and ASCII NetTIN Maps

If the map layer you wish to configure is an ArcInfo® DEM (**.asc*), ASCII DEM (**.dem*), or ASCII NetTIN (**.net*) file, the **Properties** command opens the **Elevation Options** Editor (Figure C.5). The filename of the map appears at the top of the dialog box.

This properties editor allows you to choose the following color contour from the list: Aspect Shading, Grayscale, Linear, Precipitation, Red-Green-Blue, or Terrain. You can also define the **Tic Interval** and set the Maximum/Minimum values for **Contour Limits**. By default, Contour Limits are set to **System Specified Min/Max Values**. If you deselect the checkbox, you can enter custom values. The **Draw Edges** checkbox is specifically for ASCII NetTIN files. If selected, the edges of the triangles that make up an ASCII NetTIN file will be drawn.

You can control the **Brightness** (the amount of white, measured from 0.0 to 1.0), **Saturation** (the amount of black, measured from 0.0 to 1.0), and **Transparency** (the level of opacity or alpha, measured from 0.0 to 1.0) of your gridded data layer either by moving the sliders or by typing values into the white text fields. The color scale on the right side of the editor will update according to your selections.

If you are using elevation maps, you may wish to choose Aspect Shading as the color contour and activate the **Aspect Shading** option. Aspect Shading uses a single color and makes the map appear in relief by placing an imaginary light source above the map and shading the elevation contours.

When the Aspect Shading option is selected, you can use the **Angle** slider to adjust the angle of the light source.

By default, the **Maximum Clipping** and **Minimum Clipping** options are deselected. If you activate these options, the **Value** sliders and **Color** buttons become available. The **Value** sliders allow you to specify the amount of Clipping within the Contour Limits you have specified; you can also type values into the text boxes. When you click on the **Color** buttons, the **Color Chooser** appears (see Appendix D).



Figure C.5 Elevation Options Dialog Box

Appendix D
Using the Color Chooser

Table of Contents

Section **Page**

D Using the Color Chooser
D.1 Swatches D-1
D.2 HSB Colors D-2
D.3 RGB Colors D-2

List of Figures

Figure Number

D.1 Color Chooser: Swatches Tab D-1
D.2 Color Chooser: HSB Tab D-2
D.3 Color Chooser: RGB Tab D-2

Appendix D

Using the Color Chooser

The **Color Chooser** affords great flexibility when you need to select default colors for map layers, labels, and background colors in your watershed display. The **Color Chooser** has three tabs: **Swatches**, **HSB**, and **RGB**, offering three methods for choosing a color. For each method, the preview area allows you to see your choice before applying changes.

D.1 Swatches

To select a color from the **Swatches** tab (shown in Figure D.1), click on the swatch of the color you want. The **Recent** panel keeps track of your choices so you can return to them easily.



Figure D.1 Color Chooser: Swatches Tab

D.2 HSB Colors

To select a color from the **HSB** tab (shown in Figure D.2), click on the color gradient.

To select hue, move the slider up and down the vertical color scale; the **R**ed, **G**reen, and **B**lue hex values display in the **RGB** boxes to the right.

You can also change the **H**ue, **S**aturation, and **B**rightness by selecting the radio buttons beside the **H**, **S**, and **B** text boxes and typing in values or using the increase/decrease values buttons.



Figure D.2 Color Chooser: HSB Tab

Hue (H) is measured in a circle from 0 to 359 degrees (0=red, 60=yellow, 120=green, 180=cyan, 240=blue, 300=magenta).

Saturation (S) is the amount of black, measured from 0 to 100%.

Brightness (B) is the amount of white, measured from 0 to 100%.

D.3 RGB Colors

To select a color from the **RGB** tab (shown in Figure D.3), use the sliders or type in hue values to select the **Red**, **Green**, and **Blue** values to produce the color you want.



Figure D.3 Color Chooser: RGB Tab

Appendix E
Using HEC-DssVue

Table of Contents

Section **Page**

E Using HEC-DssVue
E.1 The HEC-DssVue Data Selection List Window E-1
E.1.1 Menu Options E-3
E.1.2 Menu Buttons E-4
E.1.3 Data Selection Fields and Buttons E-4
E.2 Opening a DSS Database File for Browsing E-5
E.3 Sorting DSS Pathnames by Parts E-6
E.4 Selecting DSS Pathnames E-6
E.5 Using Plots and Tables to Visualize DSS Data E-6
E.6 Editing Tabular Data in HEC-DssVue E-8
E.7 Performing Math Functions in HEC-DssVue E-8
E.8 Entering Time-Series Data Manually in HEC-DssVue E-11
E.9 Entering Paired Data Manually in HEC-DssVue E-12
E.10 Renaming DSS Records in HEC-DssVue E-13
E.11 Copying Records into a DSS File in HEC-DssVue E-14
E.12 Duplicating Records in HEC-DssVue E-14
E.13 Merging Records into a DSS File in HEC-DssVue E-15
E.14 Squeezing DSS Files in HEC-DssVue E-15
E.15 Viewing DSS Status in HEC-DssVue E-16
E.16 Deleting Records from a DSS File E-16
E.17 Undoing Most Recent Revisions E-17
E.18 Printing Plots and Tables in HEC-DssVue E-17

List of Figures

Figure Number

E.1 HEC-DssVue - Data Selection List Window, Condensed Catalog Displayed E-2
E.2 HEC-DssVue - Data Selection List Window, Pathname Parts Displayed E-2
E.3 HEC-DssVue - Data Selection List Window, Pathname List Displayed E-3
E.4 Search Pathnames Option E-4

List of Figures (continued)

Figure Number **Page**

E.5 Search by Parts Option E-4
E.6 Data Selection List Buttons E-4
E.7 Open HEC-DSS File Browser E-5
E.8 Example Plot from HEC-DssVue....E-7
E.9 Example Tabulation from HEC-DssVue E-7
E.10 Edit Menu -- Allow Editing Option....E-8
E.11 HEC-DssVue Math Functions Dialog Box E-9
E.12 HEC-DssVue Math Functions, Statistics Tab....E-9
E.13 HEC-DssVue Save As Dialog Box E-10
E.14 HEC-DssVue Manual Time Series Data Entry Dialog Box....E-11
E.15 HEC-DssVue Manual Paired Data Entry Dialog Box E-12
E.16 HEC-DssVue Rename Records Dialog Box....E-13
E.17 HEC-DssVue Copy Records into HEC-DSS File Dialog Box E-14
E.18 HEC-DssVue New Pathname Parts for Duplicate Records Dialog Box E-14
E.19 HEC-DssVue Merge (copy all records) into HEC-DSS File Dialog Box E-15
E.20 HEC-DssVue Squeeze Progress Window (Example) E-16
E.21 HEC-DssVue Squeeze Confirmation Message (Example) E-16
E.22 HEC-DSS File Manager Status Window E-16
E.23 Confirm List of Records to be Deleted E-17
E.24 Confirmation Message that Records have been Deleted....E-17

Appendix E

Using HEC-DssVue

Included within the framework of ResSim is **HEC-DssVue**, a tool that allows you to access data stored in HEC-DSS database files. With HEC-DssVue, data may be plotted, tabulated, edited, and manipulated with over fifty mathematical functions. In addition to these functions, HEC-DssVue provides several utility functions, such as entering data sets into a database, renaming data sets, copying data sets to other DSS database files, and deleting data sets. You can launch HEC-DssVue from any ResSim module by choosing **HEC-DssVue** from the **Tools** menu.

DSS files refer to time-series data by *pathnames* representing records. Pathnames are separated into six parts (delimited by slashes "/") labeled "A" through "F." For "regular" time-series records, the naming conventions for describing the contents of the six pathname parts are:

A Project name

B Location or gage identifier

C Data variable, such as FLOW or PRECIP

D Starting date in the format 01JAN1980.

E Time interval

F Additional user-defined descriptive information

With HEC-DssVue, you can select data sets from a list of pathnames (or *catalog*) in the database and visualize the data in tabular or graphical form. The list of pathnames can be displayed as a straight list of pathnames, or as a list of pathnames separated into parts. You can refine the list by searching for either a string in the pathnames or for pathname parts.

In ResSim, you will use HEC-DssVue mainly as a viewing tool for DSS data. This Appendix will review some of the general functions in HEC-DssVue. For further detail, see the *HEC-DssVue User's Manual* (HEC, 2003b).

E.1 The HEC-DssVue Data Selection List Window

HEC-DssVue is available from any of the ResSim modules. From the **Tools** menu, select **HEC-DssVue**. Figure E.1 shows the main window (the **Data Selection List**) of HEC-DssVue, using the **Condensed Catalog** option from the **View** menu to list the pathnames of the data records in the opened DSS file. Using the Condensed Catalog option, time-series data sets are abridged so that the date range for the entire data set is displayed in the "D-part" column.



Figure E.1 HEC-DssVue - Data Selection List Window, Condensed Catalog Displayed

From the **View** menu, you can also choose to view the pathnames using all of the **Pathname Parts** (Figure E.2), in a **Pathname List** (Figure E.3), or with **No Pathnames** displayed.



Figure E.2 HEC-DssVue - Data Selection List Window, Pathname Parts Displayed



Figure E.3 HEC-DssVue - Data Selection List Window, Pathname List Displayed

E.1.1 Menu Options

Menu options in the HEC-DssVue Data Selection List window allow you to search for, select, and edit DSS data sets; control the display of pathnames; and access plots and tables, among other tasks. The HEC-DssVue menus are as follows:

File — **File** menu commands are **New**, **Open**, and **Close**. The **File** menu also lists your most recently used files.

Edit — **Edit** menu commands are **Undo**, **Cut**, **Copy**, **Paste**, **Delete**, **Edit Data**, and **Select All**.

View — The **View** menu allows you to customize the display of DSS pathnames and search pathnames. Available commands are **Pathname List**, **Pathname Parts**, **Condensed Catalog**, **No Pathnames**, **Refresh Catalog**, **Search pathnames by string**, and **Search pathnames by parts**.

Display — Use the **Display** menu to open plots and tables with the **Plot** and **Tabulate** commands.

Utilities — The **Utilities** menu provides access to **Math Functions**, **Manual Data Entry** (**Time-Series** and **Paired Data**), and it allows you to **Rename Records**, **Copy Records**, **Duplicate Records**, **Merge Files**, **Squeeze**, and view **DSS Status**.

E.1.2 Menu Buttons

Menu buttons provide shortcuts to frequently used Menu commands:

Opens an HEC-DSS **File** (same as **Open** in the **File** menu).

Displays data as a **Plot** (same as **Plot** in the **Display** menu).

Displays data in **Tabular** form (same as **Tabulate** in the **Display** menu).

E.1.3 Data Selection Fields and Buttons

The HEC-DssVue Data Selection List displays the **Filename** of the opened DSS file. Displayed beneath the filename are the number of pathnames shown in the list, the number of pathnames selected, the total number of pathnames in the database file, and the size of the database file (in kilobytes).

The HEC-DssVue Data Selection List also provides a search area where you can **Search Pathnames** (Figure E.4) or **Search Parts** (Figure E.5). You choose your search option from the **View** menu.

Figure E.4 Search Pathnames Option

Figure E.5 Search by Parts Option

Once you have opened a DSS file, its records appear in a list beneath the search area.

The complete pathnames of "selected" records appear in the Selection area beneath the list of all records.

Also, there are five buttons (Figure E.6) at the bottom of the Data Selection List window.

Figure E.6 Data Selection List Buttons

1. You select a record by highlighting it and clicking the **Select** button. Until you highlight a pathname, the Select button remains inactive.
2. To de-select the record, you highlight the record in the selected list, then click the **De-Select** button.

3. You can also de-select all selected records by clicking the **Clear Selections** button.
4. The **Restore Selections** button restores all selections you have most recently cleared or de-selected.
5. You can set the time window with the **Set Time Window** button, and subsequent plots, tables, statistics, etc., will reflect the time-series data within that specified time window.

E.2 Opening a DSS Database File for Browsing

If you know the name of the DSS database **File** you wish to browse, you can type the **File** name (including the path) directly into the **File Name** box in the HEC-DssVue Data Selection List to open the DSS file.

Otherwise, choose **Open** from the **File** menu or click the button to select the DSS database **File** you want.

An **Open HEC-DSS File** browser window will open, as shown in Figure E.7.



Figure E.7 Open HEC-DSS File Browser

In the **Open HEC-DSS File** browser window, use the standard Windows controls to browse to the DSS **File** that you wish to open, then click **Open**.

Once you have opened a DSS file, the HEC-DssVue Data Selection List window displays the filename, the number of pathnames shown in the list, the number of pathnames selected, the total number of pathnames in the database file, and the size of the database file (in kilobytes). The individual pathnames display in a table beneath the search area.

E.3 Sorting DSS Pathnames by Parts

You can use the filters provided to sort DSS pathnames by parts.

Choose **Search pathnames by parts** from the **View** menu. Then, use the lists in the **Search By Parts** section of the HEC-DssVue Data Selection List to show the pathnames you want to select from. Click on the **blank cell** at the top of each list to show the unfiltered list.

E.4 Selecting DSS Pathnames

Once you have filtered the listing of pathnames, you can select them by double clicking on the desired names in the list (which adds them to the box on the bottom of the Data Selection List window). You can also highlight the pathname(s) from the list then click the **Select** button. Until you select a pathname(s), the **Select** button remains inactive.

If you wish to select all of the pathnames, choose **Select All** from the **Edit** menu.

E.5 Using Plots and Tables to Visualize DSS Data

Once the lower box contains all the pathnames you wish to display, you can access plots and tables.

To do this, you can select **Plot** or **Tabulate** from the **Display** menu, or you can click on the **Plot** button or the **Tabulate** button.

Figure E.8 shows an example plot and Figure E.9 shows the corresponding tabulated values produced using HEC-DssVue. The parameters for the plots are labeled and color-coded, date ranges are specified along one axis, and the units of measure are specified along the other axis. You can resize the plot window by grabbing the corner of the window and dragging it to the desired size. You can also select the **Zoom** tool and then zoom in on the data by moving the mouse to a position on the graph, holding down the left mouse button, moving the mouse so that the new mouse position defines a rectangle of the area to enlarge, then releasing the mouse button. To zoom out, just right-click anywhere in the graph area. To view the tabular form of the plot, you can select the **Tabulate** command from the **File** menu of the Plot window.

HEC-DssVue tabulates data in a vertical scrolling window that shows the ordinate number (starting from the start date/time), the date and time stamp, and the values for the selected data sets. You can view the tabular data in plot format by selecting the **Plot** command from the **File** menu of the Table window.

In tables produced by the HEC-DssVue Data List Selector, you have several options for displaying the tabular data. From the table's **View** menu, you can choose to display commas in the number by selecting the

Show Commas command. You can also opt to display **Date and Time Separately**, which will split the date-time stamp into two columns. Another option is to display the **Date with 4 Digits**, instead of the default two. Also, you can set the precision of decimal places for your data by selecting **Show Decimal Places** and selecting the number of decimal places you wish to display.



Figure E.8 Example Plot from HEC-DssVue



Ordinate	Date / Time	SAYERS-CON... ELEV-ZONE OLDOPS----0	SAYERS-FLO... ELEV-ZONE OLDOPS----0	SAYERS-INAC... ELEV-ZONE OLDOPS----0	SAYERS-POOL ELEV OLDOPS----0	SAYERS-POOL FLOW-IN OLDOPS----0	SAYERS-POOL FLOW-OUT OLDOPS----0
Units		ft	ft	ft	ft	cfs	cfs
Type		INST-VAL	INST-VAL	INST-VAL	INST-VAL	INST-VAL	INST-VAL
1	26 Nov 93 07:00	626.47	657.00	590.00	610.13	291	255.0
2	26 Nov 93 08:00	626.46	657.00	590.00	610.13	290	255.0
3	26 Nov 93 09:00	626.45	657.00	590.00	610.13	289	255.0
4	26 Nov 93 10:00	626.43	657.00	590.00	610.12	289	246.6
5	26 Nov 93 11:00	626.42	657.00	590.00	610.12	288	242.4
6	26 Nov 93 12:00	626.41	657.00	590.00	610.12	288	242.4
7	26 Nov 93 13:00	626.39	657.00	590.00	610.12	287	242.4
8	26 Nov 93 14:00	626.38	657.00	590.00	610.12	286	246.6
9	26 Nov 93 15:00	626.37	657.00	590.00	610.12	286	246.6
10	26 Nov 93 16:00	626.35	657.00	590.00	610.12	285	246.6
11	26 Nov 93 17:00	626.34	657.00	590.00	610.12	284	246.6
12	26 Nov 93 18:00	626.33	657.00	590.00	610.10	284	246.6
13	26 Nov 93 19:00	626.32	657.00	590.00	610.10	283	246.6
14	26 Nov 93 20:00	626.30	657.00	590.00	610.10	282	246.6
15	26 Nov 93 21:00	626.29	657.00	590.00	610.10	282	246.6
16	26 Nov 93 22:00	626.28	657.00	590.00	610.09	281	246.6
17	26 Nov 93 23:00	626.26	657.00	590.00	610.09	281	246.6
18	26 Nov 93 24:00	626.25	657.00	590.00	610.09	281	246.6
19	27 Nov 93 01:00	626.24	657.00	590.00	610.09	282	246.6
20	27 Nov 93 02:00	626.22	657.00	590.00	610.09	283	246.6
21	27 Nov 93 03:00	626.21	657.00	590.00	610.07	285	246.6
22	27 Nov 93 04:00	626.20	657.00	590.00	610.07	286	246.6
23	27 Nov 93 05:00	626.18	657.00	590.00	610.07	288	246.6
24	27 Nov 93 06:00	626.17	657.00	590.00	610.07	290	246.6

Figure E.9 Example Tabulation from HEC-DssVue

E.6 Editing Tabular Data in HEC-DssVue

In HEC-DssVue, you can edit the tabular data directly from a tabular data window. Selecting **Allow Editing** from the **Edit** menu of the table (Figure E.10) allows you to manually edit the data in the table.

You can also use shortcut menu commands to edit data in tables.

If you make any edits, HEC-DssVue prompts you to save changes to the data set when you close the window.



Figure E.10 Edit Menu -- Allow Editing Option

E.7 Performing Math Functions in HEC-DssVue

To perform math functions in HEC-DssVue:

1. Select the data set on which you want to perform a math function.
2. Choose **Math Functions** from the **Utilities** menu. A dialog box will appear, as shown in Figure E.11.
3. As appropriate, select one of the six tabs (**Arithmetic**, **General**, **Time Conversion**, **Hydrologic**, **Smoothing**, and **Statistics**). You will most likely find that the information available from the **Statistics** tab is very useful when analyzing data and results. An example of the Statistics screen is shown in Figure E.12.



Figure E.11 HEC-DssVue Math Functions Dialog Box



Figure E.12 HEC-DssVue Math Functions, Statistics Tab

4. After you have selected the appropriate math function and required parameters for the function, click the **Compute** button.
5. To view the results, click the **Plot** or **Tabulate** button and the results will be displayed as a comparison against the original data.

6. To *save the new values in place of the original values*, click the **Save** button (or select **Save** from the **File** menu). HEC-DssVue will ask you to confirm that you wish to replace the original data.

7. To *save the new values as a new record*, click the **Save As** button (or select **Save As** from the **File** menu). A **Save As** dialog box will open, as shown in Figure E.13. Enter the new pathname information and click **OK** to save the record.



Figure E.13 HEC-DssVue Save As Dialog Box

There are many very useful math functions available in HEC-DssVue. This Appendix only covers the basic functionality for accessing the functions. The *HEC-DssVue User's Manual* (HEC, 2003b) is the primary reference for further information and details for using the Math Function Utilities.

E.8 Entering Time-Series Data Manually in HEC-DssVue

To enter Time-Series data manually:

1. From the **Utilities** menu, choose **Manual Data Entry**, then select **Time Series...**. The **Manual Time Series Data Entry** dialog box (Figure E.14) will open.



Figure E.14 HEC-DssVue Manual Time Series Data Entry Dialog Box

2. Type the **Pathname Parts** into the A, B, C, and F fields. DssVue will define the D-part of the pathname based on the dates/times you enter for the data. You must select an appropriate time interval (E-part) from the list. The complete pathname will automatically appear in the **Pathname** field. Alternately, you can enter the pathname into the **Pathname** field and the parts will appear in the **Pathname Parts** fields.
3. Enter the **Start Date** (*e.g.,* 30 Mar 2002).
4. Enter the **Start Time** (*e.g.,* 1400).
5. Enter the **Units** (*e.g.,* cfs, feet, ...).

6. Select a record type from the **Type** list. Your options are PER-AVER, PER-CUM, INST-VAL, and INST-CUM.
7. Using the **Manual Entry** tab, the **Date/Time** fields will fill in automatically according to the start date and time you have entered; or, using the **Automatic Generation** tab, enter the **End Date** and **End Time**.
8. Using the **Manual Entry** tab, type the **data values** into the third column; or, using the **Automatic Generation** tab, enter the **Fill Value**.
9. To view the data in plot form, click the **Plot** button.
10. To save the new time-series record, click **Save**.

E.9 Entering Paired Data Manually in HEC-DssVue

To enter Paired Data manually:

1. From the **Utilities** menu, choose **Manual Data Entry**, then select **Paired Data**. The **Manual Paired Data Entry** dialog box (Figure E.15) will open.



Figure E.15 HEC-DssVue Manual Paired Data Entry Dialog Box

2. Type the **Pathname Parts** into the A, B, C, D, E, and F fields. The C-part name should reflect the X curve name - Y curve name. The complete pathname will automatically appear in the

Pathname field. You can also enter the pathname into the **Pathname** field; the parts will appear in the **Pathname Parts** fields.

3. Select the **Number of Curves** (Y curves) from the list.
4. Enter the **X Units** and the **Y Units**.
5. Choose the **X Type** and **Y Type** scale from the lists. Available options are: Linear, Log, and Probability.
6. In the table, the **Y ordinates** column will split into individual columns according to the **Number of Curves** you have specified.
7. Type the data values into the **X ordinates** and **Y ordinates** columns.
8. To view the data in plot form, click the **Plot** button.
9. To save the new time-series record, click **Save**.

E.10 Renaming DSS Records in HEC-DssVue

To Rename a DSS Record:

1. Select the record(s) either by double-clicking on it or by highlighting it then clicking the **Select** button. From the **Utilities** menu, select **Rename Records**. The **Rename Records to** dialog box (Figure E.16) will open.



Figure E.16 HEC-DssVue Rename Records Dialog Box

2. Type the new **Pathname Parts** into the A, B, C, or F fields.
3. Click **OK**. A confirmation message will appear, stating that the record(s) has been renamed.

E.11 Copying Records into a DSS File in HEC-DssVue

To Copy records into a DSS file:

1. Select the record(s) either by double-clicking on it or by highlighting it then clicking the **Select** button. From the **Utilities** menu, select **Copy Records**. The **Copy Records into HEC-DSS File** dialog box (Figure E.17) will open.



Figure E.17 HEC-DssVue Copy Records into HEC-DSS File Dialog Box

2. Type in a new DSS filename or select an existing DSS file into which you want to copy the record and click **Open**. A confirmation message will appear, stating that the record has been copied to the DSS file you specified.

E.12 Duplicating Records in HEC-DssVue

To Duplicate a record:

1. Select the record(s) either by double-clicking on it or by highlighting it then clicking the **Select** button. From the **Utilities** menu, select **Duplicate Records**. The **New pathname parts for duplicate records** dialog box (Figure E.18) will open.



Figure E.18 HEC-DssVue New Pathname Parts for Duplicate Records Dialog Box

2. Type the new **Pathname Parts** into the A, B, C, or F fields.
3. Click **OK**. A confirmation message will appear, stating that the record(s) has been duplicated.

E.13 Merging Records into a DSS File in HEC-DssVue

To Merge a record into a DSS file:

1. Select the record(s) either by double-clicking on it or by highlighting it then clicking the **Select** button.
2. Choose **Merge** from the **Utilities** menu. The **Merge (copy all records) into HEC-DSS File** dialog box (Figure E.19) will open.



Figure E.19 HEC-DssVue Merge (copy all records) into HEC-DSS File Dialog Box

3. Type in a new DSS filename or select an existing DSS file into which you want to merge the record(s) and click **Open**. A confirmation message will appear, stating that the record(s) has been merged into the DSS file you specified.

E.14 Squeezing DSS Files in HEC-DssVue

When you delete or rename records, a HEC-DSS file can accumulate inactive space. The **Squeeze** command removes inactive space by copying all valid data to a new file then renaming the new file to the old filename. The **Squeeze** command also automatically re-adjusts the internal HEC-DSS table sizes to optimize access to data.

To squeeze a DSS file, open the file and select **Squeeze** from the **Utilities** menu. A window will appear indicating the status of the squeeze process, as shown by the example in Figure E.20. When the process is complete, a confirmation will appear (Figure E.21)



Figure E.20 HEC-DssVue Squeeze Progress Window (Example)



Figure E.21 HEC-DssVue Squeeze Confirmation Message (Example)

E.15 Viewing DSS Status in HEC-DssVue

The **HEC-DSS File Manager Status** window displays the number of HEC-DSS files you have accessed during the current session and, for each file, the name and location, whether the file is currently open, the first and last times you accessed the file, and the total number of accesses. To view DSS Status, select **DSS Status** from the **Utilities** window. The **HEC-DSS File Manager Status** window will open (Figure E.22).



Figure E.22 HEC-DSS File Manager Status Window

E.16 Deleting Records from a DSS File

To Delete records from a DSS file:

1. Select the record(s) either by double-clicking on it or by highlighting it then clicking the **Select** button.
2. Choose **Delete** from the **Edit** menu.
3. A confirmation message will appear asking you to verify the records to be deleted (Figure E.23)

4. If the list correctly identifies the record(s) to be deleted, select **Yes**, and a confirmation message will appear (Figure E.24) telling you the record(s) has been deleted. Otherwise, select **No**, and the records will not be deleted.



Figure E.23 Confirm List of Records to be Deleted

Figure E.24 Confirmation Message that Records have been Deleted

E.17 Undoing Most Recent Revisions

There may be an occasion where you make a revision to your DSS file and then want to "undo" that revision. An **Undo** option is available from the **Edit** menu to undo the *LAST revision that you made* to your DSS file. For example, if you inadvertently delete a record, you can choose to "undo" that deletion, and the record will be restored.

E.18 Printing Plots and Tables in HEC-DssVue

You can print plots and tables by selecting **Print** from the **File** menu of the plot and table windows. For more details on the printing capabilities, see Appendix F.

If you wish to change the appearance or the layout of the plots or tables, there are a number of options available to you.

In the plots, you can change the appearance of the lines by changing the line color and background color, and the font and style of the text labels. See Chapter 14, Section 14.5.2.2 for additional details for customizing plots.

Appendix F
Copying and Printing ResSim Data

Table of Contents

Section **Page**

F Copying and Printing ResSim Data
F.1 Saving Plots and Templates....F-2
F.1.1 Save Plot to a File....F-2
F.1.2 Saving and Applying Plot Templates....F-2
F.2 Copying Plots to the Clipboard....F-3
F.3 Printing Plots....F-3
F.4 Copying, Exporting, and Printing Tabulated Data....F-5
F.4.1 Copying Tabulated Data to the Clipboard....F-5
F.4.2 Exporting Tabulated Data....F-6
F.4.3 Printing Tabulated Data....F-7
F.5 Printing Simulation Reports....F-9

List of Figures

Figure Number

F.1 Plot Window - File Menu....F-1
F.2 Plot Window - File Menu: Save Plot....F-2
F.3 Plot Window - File Menu: Save Plot Template....F-2
F.4 Plot Window - File Menu: Print Dialog Box....F-3
F.5 Page Setup Dialog Box....F-3
F.6 Printer Margins Dialog Box....F-3
F.7 Print Preview of a Plot (Example)....F-4
F.8 Print Multiple Plots Dialog Box....F-4
F.9 Print Multiple Preview Dialog Box (Example)....F-5
F.10 Copy Command from Edit Menu of Tabulated Data Window....F-6
F.11 Copy Command from Shortcut Menu of Tabulated Data....F-6
F.12 Table Export Options Dialog Box....F-6
F.13 Print Command from File Menu of Tabulated Data Window....F-7
F.14 Print Command from Shortcut Menu of Tabulated Data....F-7
F.15 Print Properties Dialog Box....F-7
F.16 Print Preview of a Table (Example)....F-8
F.17 Print Dialog Box....F-8
F.18 Print Preview of Flow Summary Report....F-9

Appendix F

Copying and Printing ResSim Data

Plots and tables in HEC-ResSim offer detailed views of data and model results that you can print or copy and paste into other applications. You can also print reports generated by the program.

The **File** menu in ResSim plots, illustrated in Figure F.1, contains several commands that allow you to save the plot, save the plot's template, apply a template to the plot, copy the plot to the clipboard to be pasted into other applications (such as Microsoft® Word, Excel, etc.), and print the plot. These commands are also available when the data is tabulated.



Figure F.1 Plot Window - File Menu

F.1 Saving Plots and Templates

When a plot is displayed, you can choose to save the plot as a file on your computer. You can also choose to save or apply a template.

F.1.1 Save Plot to a File

From the **File** menu of a plot, when you select **Save As...** (to save the plot to a file on your computer), a dialog box appears (Figure F.2). Provide a **File name** and select from the following **Files of type**: Windows Metafile (*.wmf), JPEG (*.jpg, *.jpeg), and Portable Network Graphics (*.png).



Figure F.2 Plot Window - File Menu: Save Plot

F.1.2 Saving and Applying Plot Templates

Once you have customized an individual plot, you can save its settings as a **Template** that you can apply to other plots. To create a template based upon a plot, you will use the **Save Template...** option from the **File** menu of the plot window. Figure F.3 shows the dialog box that appears for saving a template. Provide a **File name** and choose whether the template will be available for **All Applications** or for **This Watershed only**.



Figure F.3 Plot Window - File Menu: Save Plot Template

Similarly, you can apply **Templates** to use previously defined properties to an individual plot. To apply a template to a new plot, you will use the **Apply Template** option in the **File** menu of a plot window.

F.2 Copying Plots to the Clipboard

Use the **Copy to Clipboard** command in the plot window's **File** menu to copy a plot to the clipboard. You can then paste the plot as an image into another application such as Microsoft® Word, Excel, etc.

F.3 Printing Plots

The **Print** command in the plot window's **File** menu opens the **Print** dialog box (Figure F.4), where you can choose your printer (by **Name**), set printer **Properties**, and specify the **Number of copies** to print. You can also select **Print to File** to print your plot to a **File** instead of to a printer.



Figure F.4 Plot Window - File Menu: Print Dialog Box

The **Page Setup** command in the plot window's **File** menu opens the **Page Setup** dialog box (Figure F.5), where you can set the page **Orientation**, choose to print **Page Numbers**, select the **Printer Scale**, and set the **Margins**. The **Set Margins** button opens the **Printer Margins** dialog box (Figure F.6).



Figure F.5 Page Setup Dialog Box



Figure F.6 Printer Margins Dialog Box

The **Print Preview** command in the plot window's **File** menu allows you to view the plot as it will be printed. Figure E.7 shows an example.



Figure E.7 Print Preview of a Plot (Example)

Finally, with the **Print Multiple** command in the plot window's **File** menu, you can print several plots on one page.

The **Print Multiple** dialog box (Figure F.8) shows all of the currently opened plots in the **Available Plots** pane. To select plots for printing, double-click on them and they will move to the **Selected Plots** pane.

Next, use the slider bars to specify the number of plots you wish to appear horizontally and vertically on the page. The grid to the right of the sliders reflects your choices.



Figure F.8 Print Multiple Plots Dialog Box

You can also access the **Page Setup** and **Print Preview** commands from the **File** menu of the **Print Multiple** dialog box. Figure F.9 shows an example print preview of multiple plots.



Figure F.9 Print Multiple Preview Dialog Box (Example)

F.4 Copying, Exporting, and Printing Tabulated Data

When tabulating plotted data, the **File**, **Edit**, and shortcut menus are available and offer several commands that allow you to print as well as copy and paste data into other applications, such as Microsoft® Excel and Word.

F.4.1 Copying Tabulated Data to the Clipboard

To copy tabulated data to the clipboard, use the **Copy** command in the tabulated data window's **Edit** menu (Figure F.10) or right-click inside the tabulated data and select **Copy** from the shortcut menu (Figure F.11). You can then paste the tabulated data as tab-separated values into another application such as Microsoft® Excel or Word.



Figure F.10 Copy Command from Edit Menu of Tabulated Data Window



Figure F.11 Copy Command from Shortcut Menu of Tabulated Data

F.4.2 Exporting Tabulated Data

You can also use the **Export** command in the shortcut menu (see Figure F.11) to export a table to a file, which you can then open in another application.

The **Export** command opens the **Table Export Options** dialog box (Figure F.12).



Figure F.12 Table Export Options Dialog Box

In the **Table Export Options** dialog box, you can choose the **Field Delimiter** (Tab, Space, Comma, or Colon), specify **Fixed-Width Columns**, choose to display **Quoted Strings**, **Include Column Headers** and **Row Headers**, and choose to **Print Gridlines** and **Title**.

F.4.3 Printing Tabulated Data

You can access the **Print** command from either the **File** menu (Figure F.13) of the tabulated data window or from the shortcut menu (Figure F.14) of the tabulated data. The **Print Preview** command is also available in the shortcut menu.



Figure F.13 Print Command from File Menu of Tabulated Data Window



Figure F.14 Print Command from Shortcut Menu of Tabulated Data

The **Print** and **Print Preview** commands open the **Print Properties** dialog box (Figure F.15), which offers options on three tabs.

The **Page** tab allows you to specify the page **Orientation**, **Scaling**, and **Selection**. You can also choose to print the table as **ASCII**, to **Repeat Headers** on every page, and print the **Gridlines**.

On the **Header/Footer** tab, you can type in the header and footer you want to appear on your printed pages.



Figure F.15 Print Properties Dialog Box

The **Table Title** tab offers a default title for the table based on the data source. You may edit this title.

On the **Print Properties** dialog box, the **Print** button performs two functions, depending on whether you arrived at the dialog box via the **Print** command or the **Print Preview** command.

From the **Print Preview** command, the **Print** button on the **Print Properties** dialog box opens a Print Preview window, which allows you to view the data as it will be printed. Figure F.16 shows an example. The **Print** button at the top of the Print Preview window will bring up the **Print Dialog Box** (see Figure F.17).



Figure F.16 Print Preview of a Table (Example)

From the **Print** command, the **Print** button on the **Print Properties** dialog box opens the **Print** dialog box (Figure F.17). Here you can choose your printer (by **Name**), set printer **Properties**, and specify the **Number of copies** to print. You can also select **Print to File** to print your plot to a **File** instead of to a printer.



Figure F.17 Print Dialog Box

F.5 Printing Simulation Reports

You can print reports from the **Reports** menu in any of the ResSim modules. For example, several simulation reports are available from the **Report** menu in the **Simulation** module (see "Viewing Summary Reports" in Chapter 14, Section 14.5.3).

From the **File** menu of a report, select **Print**. The **Print Properties** dialog box will open (as previously shown in Figure F.15). The **Print Preview** capability is available from the shortcut menu of the summary reports. As an example, Figure F.18 shows the **Print Preview** for the **Flow Summary** report.



Location/Parameter	Average	Maximum	Minimum
Bald Eagle Total			
Regulated Flow (cfs)	1025	4552	393
Unregulated Flow (cfs)	1319	9640	439
Cumulative Local Flow (cfs)	771	4422	251
Beech Ck Station			
Regulated Flow (cfs)	410	2622	118
Unregulated Flow (cfs)	958	7810	303
Cumulative Local Flow (cfs)	410	2622	118
Blanchard			
Regulated Flow (cfs)	250	434	130
Unregulated Flow (cfs)	547	5454	174
Cumulative Local Flow (cfs)	0	0	0
Fishing Ck Jct			
Regulated Flow (cfs)	968	4237	370
Unregulated Flow (cfs)	1254	9240	416
Cumulative Local Flow (cfs)	706	4107	221
Marsh Ck Jct			
Regulated Flow (cfs)	336	875	150
Unregulated Flow (cfs)	533	5196	194
Cumulative Local Flow (cfs)	86	745	20
Milesburg Jct			
Regulated Flow (cfs)	501	5320	155
Unregulated Flow (cfs)	501	5320	155
Cumulative Local Flow (cfs)	501	5320	155
Mill Hall			
Regulated Flow (cfs)	709	2904	275
Unregulated Flow (cfs)	998	7837	320
Cumulative Local Flow (cfs)	450	2774	135
RR_Beech-Mill			
Regulated Flow (cfs)	664	2708	264
Unregulated Flow (cfs)	959	7615	309
Cumulative Local Flow (cfs)	411	2578	118
RR_Blanc-Marsh			
Regulated Flow (cfs)	250	434	130

Figure F.18 Print Preview of Flow Summary Report

Appendix G
References

Hydrologic Engineering Center, 1995. *"HEC-DSS (Data Storage System), User's Guide and Utility Manuals, March 1995, CPD-45"*, U. S. Army Corps of Engineers, Davis, CA.

Hydrologic Engineering Center, 2003a. *"Corps Water Management System (CWMS) Documentation, CWMS User's Manual (DRAFT), February 2003",* U. S. Army Corps of Engineers, Davis, CA.

Hydrologic Engineering Center, 2003b. *"HEC-DSSVue, HEC Data Storage System Visual Utility Engine, User's Manual, Version 1.0, January 2003, CPD-79"*, U. S. Army Corps of Engineers, Davis, CA.

Hydrologic Engineering Center, 2003c. *"HEC-FIA, Flood Impact Analysis, User's Manual, April 2003, CPD-81"*, U. S. Army Corps of Engineers, Davis, CA.

U.S. Army Corps of Engineers, 1987. *"EM 1110-2-3600, Management of Water Control Systems, Engineer Manual, 30 November 1987"*, Washington, D. C.

U.S. Army Corps of Engineers, 1991. *"SSARR Model, Streamflow Synthesis and Reservoir Regulation, User Manual, January 1991"*, Northwestern Division, Portland, OR.