

Public Information Session

Veterans of Foreign Wars (VFW) Hall Post 2179

Port Monmouth, NJ

October 29, 2015

David Gentile USACE Project Manager











History & Overview

- The project is authorized for construction under Section 101 of the Water Resources Development Act of 2000.
- Public Law 113-2, the Disaster Relief Appropriation Act of 2013, Chapter 4
- Authorized but Unconstructed (ABU) ongoing construction project 100% Federal Funding for initial construction(Saves State and Municipality regular Cost Share)
- Hurricane Sandy Limited Reevaluation Report (HSLRR) approved 4 Dec 2013
- Project First Cost: \$105M
- Executed Project Partnership Agreement (PPA) with NJDEP on 31 January 2014
- Operation & Maintenance is Non-Fed responsibility

Environmental Requirements

Phase I

- ▶ National Environmental Policy Act (NEPA) complete (Record of Decision(ROD) 2008; Finding of No Significant Impact (FONSI) 2009)
- ▶ Water Quality/Federal Consistency received (May 2013)
- Benthic, Threatened & Endangered species, and dune planting monitoring

Phase II

- Supplemental NEPA to incorporate design changes
- Wetland Mitigation Required; assessment of impacts and mitigation requirements ongoing
- Geotechnical Boring Permit was Completed
- Pre-application meeting with NJDEP was held and 5 construction permits will be required
- ▶ Wetland mitigation, vegetation and tidal exchange monitoring







Phases and Features

Phase I (Construction complete)

- \$18M was spent on the construction of phase 1
 - ▶ Dune
 - ▶ Groin
 - ▶ Pier Extension

Phase II (Under design)

- Phase 2 will be broken down into 5 contracts starting in Spring of 2016 such that construction for the project should be completed by 2020
 - ▶ Tide Gate
 - Pump Stations
 - Levees
 - Floodwalls
 - Road Closure Structures
 - Road Regrading
 - ► Interior Drainage Structures
 - Wetland Mitigation





Line of Defense




- Overall Project Elevation 13' NAVD
- Dune Elevation 15' NAVD





Beachfill, Groin, & Pier Extension



Port Monmouth Beachfill:

-Dune Elevation 15' NAVD (16' NGVD) -389,602cy of fill was completed on 12 July 2014

Port Monmouth Groin:

Length= 305 LF Crest Width= 13 ft

Port Monmouth Pier Extension:

Length= 195 LF

Construction Completed:

2 July 2015

Renourishment:

68k-95k cyds/10 years





Beachfill, Groin, & Pier Extension



Beachfill, Groin, & Pier extension



Phase 2 Project Features and Examples





Pump Station

Locations:

Contract 2 Pump Station at Pews Creek- 120 cfs Contract 5 Pump Station at Compton Creek-60cfs













Lift Gate







Lift Gate







Lift Gate








Levee



Levee Typical Section

- Various locations
- Elevation +13' NAVD
- Required vegetation free zone 15' from edge of swale













Floodwall










Floodwall Typical Section

- Various locations
- •Elevation +13' NAVD 88
- •Required vegetation free 15' from edge of swale







Floodwall-Typical Finish















Road Closure Gate



Henry Hudson Trail

-Wrap around the floodwall to Campbell Ave Road Closure Gate







Road Regrading and Raising



Route 36 310 LF



Wilson Ave 190 LF









Interior Drainage





- Contract 2 Pump Station at Pews Creek
- Contract 5 Pump Station at Compton Creek

Interior Drainage structures through the levee/floodwall

- Drainage structures with flap valves, duck bills and sluice gate
- Swales along levee/floodwall and to pump station





Utility Relocations

- Sanitary
- Water
- Gas
- Electric





Mitigation











Questions concerning the public information session should be directed to:

Mr. David Gentile Project Manager, USACE

e-mail: david.t.gentile@usace.army.mil



