

Appendix A

APPENDIX 'A'

Guidelines for percentage payments for partially complete work

<u>Description</u>	<u>Allowance (Cumulative)</u>
Clearing and Grubbing	
• Felled and slashed	35
• Bucked and piled (slashings, brush and logs)	60
• Grubbed	75
• Burned or chipped and removed	98
• Substantially complete including cleanup	100
Excavation and Embankment	
• Pioneered	5
• Drilled	20
• Blasted	35
• Roughed out to grade	85
• Roadbed finished to grade	90
• Slopes seeded	98
• Substantially complete including cleanup	100
Structural Excavation	
• Excavation complete	85
• Backfill complete	98
• Substantially complete including cleanup	100
Aggregate Courses	
• Crushed and stockpiled onsite	50
• Placed on roadway	80
• Spread, compacted and tested	98
• Substantially complete including cleanup	100
Asphalt Pavements	
• Aggregates crushed and stockpiled onsite	50
• Placed, compacted and tested	98
• Substantially complete including cleanup	100

PCC Pavement

- Forms set 35
- Concrete in place 90
- Forms removed and testing complete 98
- Substantially complete including cleanup 100

Concrete Structures

- Falsework erected 10
- Forming complete 20
- Concrete in place 80
- Forms removed 90
- Concrete tested and finished 98
- Substantially complete including cleanup 100

Steel Structures

- Falsework erected 10
- Steel in place 80
- Bolting and welding complete 90
- Painting complete 98
- Substantially complete including cleanup 100

Notes:

- (1) These percentages are typical. They may be adjusted based on a detailed analysis of circumstances on given project.
- (2) Whenever partially complete work entails continuing maintenance, an appropriate percentage should be retained to cover those costs.