



### REINFORCED CONCRETE HEADWALL

PIPE ARCH SIZE Span x rise	CONCRETE (cu yd)			
	Skew Angle			
	0°	15°	30°	45°
6'-1" x 4'-7"	3.2	3.4	3.7	4.6
7'-0" x 5'-1"	3.5	3.7	4.1	5.0
8'-2" x 5'-9"	4.0	4.2	4.7	5.7
9'-6" x 6'-5"	4.4	4.6	5.1	6.2
11'-5" x 7'-3"	5.0	5.2	5.8	7.1
12'-10" x 8'-4"	5.8	6.0	6.7	8.2
13'-11" x 8'-7"	6.2	6.4	7.1	8.7
15'-4" x 10'-4"	6.6	6.8	7.6	9.3
16'-3" x 10'-10"	7.3	7.5	8.3	9.5


- NOTE:**
1. CONCRETE: Chamfer all exposed edges  $\frac{3}{4}$  inch.
  2. REINFORCING STEEL: Grade 60 (ASTM A615 or A996) deformed billet steel bars conforming to AASHTO M 31. The minimum concrete cover to the face of any bar is 2 inches unless otherwise shown.
  3. HEADWALL TYPE: Use type A Step Bevel headwalls for round pipe unless otherwise specified in the Special Contract Requirements.
  4. STEP BEVEL: The variable dimension indicated for the height or step conform to manufacturer's recommendations unless otherwise specified in the Special Contract Requirements.
  5. CUTOFF WALLS: The minimum depth shown may be reduced in solid rock, provided wall is keyed into the rock at least 12".
  6. ANCHOR BOLTS: Conform to ASTM A307-04. Galvanize in accordance with ASTM A153.
  7. BEDDING: Construct a firm and uniform foundation before placing the bedding. Use clean  $\frac{3}{8}$  inch sandy material for bedding unless otherwise specified in the Special Contract Requirements.
  8. ESTIMATED QUANTITIES: The concrete quantities are based on a 3 foot cut-off wall and 1:1.5 fill slopes for each of the skew angles. Interpolate concrete quantities for headwalls not shown. Reinforcing steel is estimated at 68 lb/cu yd of concrete excluding the weight of the anchor bolts.



**TYPE A STEP BEVEL FOR ROUND PIPE**





**TYPE B FULL BEVEL FOR ROUND PIPE**



**STEP BEVEL FOR PIPE ARCH CULVERT**

### REINFORCED CONCRETE HEADWALL

PIPE SIZE Diameter	CONCRETE (cu yd)							
	TYPE A STEP BEVEL				TYPE B FULL BEVEL			
	Skew Angle				Skew Angle			
48"	3.2	3.2	3.3	3.5	2.7	3.0	3.4	3.4
60"	3.6	3.7	3.8	4.0	3.7	3.7	3.8	4.0
72"	4.1	4.1	4.2	4.5	4.2	4.3	4.4	4.6
84"	4.5	4.6	4.7	5.0	4.8	4.8	5.0	5.3
96"	5.1	5.2	5.3	5.7	5.3	5.4	5.6	5.9
108"	5.6	5.7	5.9	6.3	5.9	6.0	6.2	6.7
120"	6.0	6.1	6.3	6.8	6.5	6.6	6.8	7.3
132"	6.9	7.0	7.3	7.9	7.1	7.2	7.5	8.0
144"	7.4	7.5	7.8	8.5	7.7	7.9	8.1	8.8
156"	7.9	8.0	8.3	9.1	8.4	8.5	8.8	9.5
168"	8.6	8.8	9.2	10.0	9.0	9.2	9.5	10.4
180"	8.9	9.1	9.4	10.3	9.7	9.8	10.2	11.1



**PIPE-ARCHES**  
**ROUND PIPES**  
**MULTIPLE PIPE INSTALLATION**

NO SCALE


U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
WESTERN FEDERAL LANDS HIGHWAY DIVISION

U.S. CUSTOMARY DETAIL


**REINFORCED CONCRETE HEADWALL**

DETAIL APPROVED FOR USE 11/2006  
REVISIONS:


DETAIL  
W601-10



**TYPE A STEP BEVEL FOR ROUND PIPE**



**TYPE B FULL BEVEL FOR ROUND PIPE**



**STEP BEVEL FOR PIPE ARCH CULVERT**



**REINFORCED CONCRETE HEADWALL**

PIPE ARCH SIZE Span x rise	CONCRETE (m3)			
	Skew Angle			
	0°	15°	30°	45°
1855 x 1400	2.4	2.6	2.8	3.5
2060 x 1500	2.7	2.8	3.1	3.8
2415 x 1700	3.1	3.2	3.3	4.4
2845 x 1905	3.4	3.5	3.9	4.7
3480 x 2210	3.8	4.0	4.4	5.4
3910 x 2540	4.5	4.6	5.1	6.3
4240 x 2615	4.7	4.9	5.4	6.7
4675 x 3150	5.0	5.2	5.8	7.1
4955 x 3300	5.6	5.7	6.3	7.3

**REINFORCED CONCRETE HEADWALL**

PIPE SIZE Diameter	CONCRETE (m3)							
	TYPE A STEP BEVEL				TYPE B FULL BEVEL			
	Skew Angle				Skew Angle			
	0°	15°	30°	45°	0°	15°	30°	45°
1200	2.5	2.5	2.6	2.8	2.2	2.4	2.7	2.7
1500	2.8	2.8	2.9	3.1	2.8	2.8	2.9	3.1
1800	3.1	3.1	3.2	3.4	3.2	3.3	3.4	3.5
2100	3.4	3.5	3.6	3.8	3.7	3.7	3.8	4.1
2400	3.9	4.0	4.1	4.4	4.1	4.1	4.3	4.5
2700	4.3	4.4	4.5	4.8	4.5	4.6	4.7	5.1
3000	4.6	4.7	4.8	5.2	5.0	5.0	5.2	5.6
3300	5.3	5.4	5.6	6.0	5.4	5.5	5.7	6.1
3600	5.7	5.7	6.0	6.5	5.9	6.0	6.2	6.7
3900	6.0	6.1	6.3	7.0	6.4	6.5	6.7	7.3
4200	6.6	6.7	7.0	7.6	6.9	7.0	7.3	8.0
4500	6.8	7.0	7.2	7.8	7.4	7.5	7.8	8.5

- NOTE:**
1. CONCRETE: Chamfer all exposed edges 20 mm.
  2. REINFORCING STEEL: Grade 420 (ASTM A615M or A996M) deformed billet steel bars conforming to AASHTO M 31. The minimum concrete cover to the face of any bar is 50 mm unless otherwise shown.
  3. HEADWALL TYPE: Use type A Step Bevel headwalls for round pipe unless otherwise specified in the Special Contract Requirements.
  4. STEP BEVEL: The variable dimension indicated for the height or step conform to manufacturer's recommendations unless otherwise specified in the Special Contract Requirements.
  5. CUTOFF WALLS: The minimum depth shown may be reduced in solid rock, provided wall is keyed into the rock at least 300 mm.
  6. ANCHOR BOLTS: Conform to ASTM A307-04. Galvanize in accordance with ASTM A153M.
  7. BEDDING: Construct a firm and uniform foundation before placing the bedding. Use clean 10 mm sandy material for bedding unless otherwise specified in the Special Contract Requirements.
  8. ESTIMATED QUANTITIES: The concrete quantities are based on a 900 mm cut-off wall and 1:1.5 fill slopes for each of the skew angles. Interpolate concrete quantities for headwalls not shown. Reinforcing steel is estimated at 32 kg/m3 of concrete excluding the weight of the anchor bolts.
  9. Furnish hardware in the metric sizes shown. Equivalent US Customary sizes may be used when metric sizes are unavailable.
  10. Dimensions without units are millimeters.



NO SCALE

U.S. DEPARTMENT OF TRANSPORTATION  
FEDERAL HIGHWAY ADMINISTRATION  
WESTERN FEDERAL LANDS HIGHWAY DIVISION

METRIC DETAIL

**REINFORCED CONCRETE HEADWALL**

DETAIL APPROVED FOR USE 11/2006

REVISID: \_\_\_\_\_

DETAIL WM601-10