


RIDOT

Transportation

Management Plans:

An Overview



LEVEL 1 TRANSPORTATION MANAGEMENT PLAN
SIGNIFICANT PROJECT

Project Name: 146 (LIS) & Willow Pond Bridge No. 412
RI Design Contract No.:
RI Construction Contract No.: 2009-CH-042
Municipalities: Town of Lincoln
Submission: ADV Date: 30-Dec-2009

NO SCALE
TABLE OF CONTENTS

Section Title	Page Number
TMP Roles and Responsibilities	2
Project Information	4
Traffic Conditions Prior to Start of Work	5
Expected Traffic Conditions During the Work	9
Transportation Management Strategies	
Traffic-Related Work Restrictions	10
Temporary Traffic Control Plans	12
Public Information Plan	13
Transportation Operations Plan	14
Performance Monitoring Plan	15
Changes to TMP & Contingency Plans	16
TMP Approvals	16
List of Attachments	17

2009-CH-042 Route 146 TMP REV 0
Town of Lincoln 03/10/10
Page 1 of 17

May 3, 2011



Russell B. Holt, P.E.

Senior Civil Engineer

Traffic Engineering Unit

Rhode Island Department of Transportation

Rhode Island Facts



- Population: **1,018** per Sq. Mi.
- Served by Three Interstate Routes
 - **I-95** (190,000 ADT)
 - **I-195** (170,000 ADT)
 - **I-295** (90,000 ADT)
- RIDOT Owns/Maintains:
 - **1,102** Highway-Miles
 - ~2,900 Lane-Miles
 - **644** Bridges
 - ~20% Structurally Deficient
 - **790** Traffic Signals
- **80 Roadway Fatalities/Year**


Work Zones in Rhode Island do cause impacts!



RIDOT Policy on TMPs

- Work Zone Safety & Mobility Policy/DPM
 - Adopted December 2008
 - Require:

- Identification
- Assessment
- Selection
- Management
- TMP Design



RIDOT Work Zone Impact Levels

Work Zone Impact Level	Work Anticipated to Include Lane Closures?	Anticipated Duration of Work	ADT on Most Heavily Traveled Roadway within Project Limits	Anticipated Level of Public Interest	Anticipated Degree of Adverse Impact to Road Users Without Mitigation	Possible Examples
1	Yes	Very Long	> 50,000	Very High	Very High	Reconstruction Projects on major freeways
2	Yes	Moderate to Very Long	> 15,000	Moderate to High	High	Major bridge Projects on principal arterials
3	Yes	Short to Very Long	Any	Low to Moderate	Moderate	Resurfacing Projects on minor arterials
4	No	Short to Long	Any	Low	Low	Short-term maintenance activities

RIDOT Work Zone Impact Levels

Work Zone Impact Level	Work Anticipated to Include Lane Closures?	Anticipated Duration of Work	ADT on Most Heavily Traveled Roadway within Project Limits	Anticipated Level of Public Interest	Anticipated Degree of Adverse Impact to Road Users Without Mitigation	Possible Examples
1	Yes	Very Long	> 50,000	Very High	Very High	Reconstruction Projects on major freeways
2	Yes	Moderate to Very Long	> 15,000	Moderate to High	High	Major bridge Projects on principal arterials
3	Yes	Short to Very Long	Any	Low to Moderate	Moderate	Resurfacing Projects on minor arterials
4	No	Short to Long	Any	Low	Low	Short-term maintenance activities

RIDOT Transportation Management Strategies

1. Traffic Control, Coordination, Contracting (TCC&C) Strategies

- A. Traffic Control Strategies
- B. Traffic Control Devices
- C. Project Coordination and Contracting Strategies



2. Public Information (PI) Strategies

- A. Public Awareness Strategies
- B. Road User Information Strategies



3. Transportation Operations (TO) Strategies

- A. Demand Management Strategies
- B. Corridor/Network Management Strategies
- C. Work Zone Safety Management Strategies
- D. Traffic/Incident Management and Enforcement Strategies



4. Performance Monitoring (PM) Strategies

RIDOT Transportation Management Strategies

PERFORMANCE MONITORING STRATEGIES

Team meetings

Windshield surveys

Public surveys

Surveillance: Traffic counts

Surveillance: Traffic queues/delays

Surveillance: Travel times

Surveillance: Crash data

Assessment: Mobility

Assessment: Safety

Road safety audits (construction)

TMP Development on RIDOT Projects

TABLE 1. Primary Work Zone-Related Tasks/Responsibilities during Project Development

		Task Description	Responsible Party (Assisting Party)			
PLANNING ¹		Assign Project Work Zone Impact Level	CPS or PM			
		<i>Work Zone Impact Level</i>	1	2	3	4
			SIGNIFICANT	SIGNIFICANT		
		<i>Anticipated Level of Adverse Impact to Road Users without Mitigation</i>	VERY HIGH	HIGH	MODERATE	LOW
PRELIMINARY DESIGN		Identify relevant TMP stakeholders	D (PM)	D (PM)		
		Meet with CM, PA, CS, & other TMP stakeholders to Identify work zone safety and mobility concerns	PM (D)	PM (D)		
		Identify potential PI and TO Strategies & Estimate their implementation costs ²	D	D		
		Identify preliminary construction sequence approach(es)	D	D		
		Perform preliminary work zone impacts assessment & Reevaluate Work Zone Impact Level	D	D	D	
		Initiate appropriate level TMP	D	D		
FINAL DESIGN		Update relevant TMP stakeholders list & Identify new work zone safety and mobility concerns ³	PM (D)	PM (D)		
		Select appropriate PI and TO Strategies	D	D	D	
		Develop (and/or Select RIDOT Typical) TTC Plans	D	D	D	D
		Perform final work zone impacts assessment(s) & Reevaluate Work Zone Impact Level	D	D	D	D
		Quantitatively analyze traffic impacts	D	D	D ⁴	
		Select recommended construction sequence approach	D	D		
		Estimate TMP implementation costs ² & Include provisions for TMP implementation in PS&E	D	D	D ⁵	D ⁵
		Develop/Complete appropriate level TMP	D	D	D	D
	Approve TMP ⁴	TMC, STE, & CE	TMC, STE, & CE	TMC, STE, & CE	TMC & STE	
PRE-CON		Assign TMP Implementation Managers	CM & C	CM & C	CM & C or M	CM & C or M

Preliminary Design

Final Design

TMP Development on RIDOT Projects


- Designer obtains appropriate TMP Template from RIDOT
 - One Template (Microsoft Excel format) for each Work Zone Impact Level
 - Guidance notes provided in comment form on TMP Templates
- TMP updated iteratively throughout Design as strategies are selected, TTC plans are developed, and Project changes occur
 - PI, TO, and PM strategies **are** explicitly identified in TMP
 - TCC&C strategies **are not** explicitly identified in TMP

TMP Development on RIDOT Projects

- Final Design Documentation
 - TMP submitted as part of each major Final Design submission (e.g., 30%, 90%, PS&E, ADV, & Award)
 - One copy of TMP typically submitted to the following:
 - Project Manager
 - Traffic Engineer
 - FHWA Rhode Island Division Office (if Project oversight)
 - Construction Management Section
 - Transportation Management Center
 - Work zone safety and/or mobility-related analyses/reports should be provided as TMP attachments unless already included in other Final Design reports

TMP Development on RIDOT Projects

- RIDOT arranges for identification of *TMP Implementation Managers* and TMP Approvals



- For **Significant Projects**, the RIDOT and Designer indicate appropriate *TMP Development Managers* for the Project



RIDOT TMP Templates

Level 1 & 2
(16 pages)

Level 3
(3 pages)

Level 4
(2 pages)

Developing and Implementing Transportation Management Plans for Work Zones

U.S. Department of Transportation
Federal Highway Administration

May 3, 2011

(Browse Thru TMP Templates)

**LEVEL 1
TRANSPORTATION
MANAGEMENT
PLAN**

**SIGNIFICANT
PROJECT**

Project Name: _____
RI Design Contract No(s): _____
RI Construction Contract No(s): _____
Municipality: _____
Submission: _____ Date: _____

Insert Project Photo/Warning Here

TABLE OF CONTENTS


Section Title	Page Number
TMP Roles and Responsibilities	2
Project Information	6
Traffic Conditions Prior to Start of Work.....	8
Expected Traffic Conditions During the Work.....	9
Transportation Management Strategies	
Traffic-Related Work Restrictions.....	10
Temporary Traffic Control Plans.....	11
Public Information Plan.....	12
Transportation Operations Plan.....	13
Performance Monitoring Plan.....	14
Changes to TMP & Contingency Plans	15
TMP Approvals	15
List of Attachments	16

(Browse Thru Example TMP)

**LEVEL 1
TRANSPORTATION
MANAGEMENT
PLAN**

**SIGNIFICANT
PROJECT**

Project Name: **146(1R) & Wilbur Road Bridge No. 415**
RI Design Contract No(s):
RI Construction Contract No(s): **2009-CH-042**
Municipalities: **Town of Lincoln**
Submission: **ADV** Date: **30-Dec-2009**



NO SCALE
TABLE OF CONTENTS

Section Title	Page Number
TMP Roles and Responsibilities	2
Project Information	6
Traffic Conditions Prior to Start of Work.....	8
Expected Traffic Conditions During the Work.....	9
Transportation Management Strategies	
Traffic-Related Work Restrictions.....	10
Temporary Traffic Control Plans.....	12
Public Information Plan.....	13
Transportation Operations Plan.....	14
Performance Monitoring Plan.....	15
Changes to TMP & Contingency Plans	16
TMP Approvals	16
List of Attachments	17

2009-CH-042 Route 146 TMP REV/2 Template Rev: 03-11-09 Page 1 of 17

RIDOT TMP Training/Resources

- Late 2008: Introductory session at local ITE Meeting




- Early 2009: RIDOT Training Sessions
 - Internal (Designers, Managers, Field Staff)
 - External (Consultants)

- Established E-Mail Account:
RIDOTWorkZones@dot.ri.gov



Challenges / Next Steps

- Designers don't always consider full realm of potential strategies
- Inefficiencies with revising TMPs in construction
- Ideally TMPs will be incorporated into RIDOT's web-based **Project Management Portal (PMP)**



The screenshot displays the RIDOT Project Management Portal (PMP) interface. The main content area shows a table of projects with columns for BSC, Contract Name, Contractor, BE, EN, Notice to Proceed Date, and Substantial Completion Date. The table lists various projects, including those related to Route 4, Safety Systems, and Pavement Systems.

BSC	Contract Name	Contractor	BE	EN	Notice to Proceed Date	Substantial Completion Date
2005-CN-079	Routelink Rt. 403 - Route 4	CADI CORPORATION	Primeau	Lorberis	11/23/2005	11/06/2007
2005-CN-084	Interchange, Phase II	CADI CORPORATION	Hayes	Lorberis	01/17/2006	07/04/2008
2005-CT-084	Reynolds Drivng for RPY 2005-2006	MS-JAY SAFETY SYSTEMS	Dales	Gedlinis	02/28/2005	11/30/2006
2007-CT-018	2007 Streetside Pavement Strngng - Limited Access	MS-JAY SAFETY SYSTEMS	Dales	Harzans		
2007-CT-017	2007 Streetside Pavement Strngng - North	TRAPPC HARZANS INC.	Dales	Harzans		
2007-CT-014	2007-2008 Streetside Pavement Strngng - East Bay	SAFETY HAWKING INC.	Dales	Harzans		
2007-CT-047	2007-2008 Streetside Signng and Strngng Improvements	SAFETY HAWKING INC.	Dales	Harzans		
2008-CT-028	2008-2009 Streetside Pavement Strngng - Limited Access	SAFETY HAWKING INC.	Dales	Harzans		
2008-CT-026	2008-2009 Streetside Pavement Strngng - Central	MS-JAY SAFETY SYSTEMS	Dales	Harzans		
2008-CT-027	2008-2009 Streetside Pavement Strngng - South	MS-JAY SAFETY SYSTEMS	Dales	Harzans		
2008-CT-026	2008-2010 Streetside Pavement Strngng - North	TRAPPC HARZANS INC.	Dales	Lay	04/22/2009	
2008-CT-027	2008-2010 Streetside Pavement Strngng - East Bay	TRAPPC HARZANS INC.	Dales	Lay	04/22/2009	

Questions Welcome...



RIDOTWorkZones@dot.ri.gov