

COMPREHENSIVE MONITORING STUDY OF A BENEFICIAL REUSE PROJECT AT EGMONT KEY, FL

Katherine E. Brutsché, Ph.D. (presenter)

Coraggio Maglio, P.E., Jase D. Ousley, P.G.,

Deborah S. Shafer, Ph.D., Matthew B.

Taylor, Cheryl E. Pollock, P.E.

US Army Corps of Engineers (USACE)

Engineer Research and Development Center

Aubree Hershoin, Ph.D. & Millan Mora, P.E.

USACE Jacksonville District

Ping Wang, Ph.D., Zachary J. Tyler

University of South Florida



Engineer Research and
Development Center



BUILDING STRONG®

US ARMY CORPS OF ENGINEERS



Outline

- Introduction
- Research Objectives
- Project Monitoring
- 2014 Dredging and Placement
- Results
- Summary and Conclusions



BUILDING STRONG®




Innovative solutions for a safer, better world

Egmont Key


- Virtually uninhabited island located at the mouth of Tampa Bay, Florida
- Cultural and environmental resources
 - Historical structures
 - Bird nesting
 - Turtle nesting
- Highly dynamic island due to its location
- Continually maintained through beach nourishments on north tip of the island





Time-series aerial photos

1942



2014 1993 1982




Slides Courtesy of USF

Source: Esri, DigitalGlobe, GeoEye, IGN, USDA, USGS, AEX, Geomatics, Aergrid, IGN, ICF, swisstopo, and the GIS User Community

Previous Placements

1999



2002



2005




2007



Slides Courtesy of USF

Previous BU – Egmont Key 2001, 2006 & 2011

- Ebb dominated system



Egmont Key

- Dredging commenced November 2014
- Material dredged from Tampa Entrance Channel
- Placement in a traditional beach nourishment and a cross-shore swash zone placement
- In situ fine content approximately 20% passing the #230 sieve
 - Exception to Florida Sand Rule was made for Egmont due to its environmental and cultural resources
- Ideal opportunity to study R&D to address environmental concerns and regulations



Definitions

- **Traditional Placement** – placement of material to “build a beach” using longitudinal dikes to increase settlement. This projects purpose is to create a wide flat dry beach berm.



Definitions

- **Cross Shore Swash Zone Placement (CSSZ)** – placement of dredged material by discharging material directly into the swash zone until a delta builds and then extending outfall shore perpendicular thus building a “point” (salient) feature.



21 Feb 15

29 Apr 15



BUILDING STRONG[®]



, better world

Images Courtesy of GLDD

Research Objectives

- To track the fine sediment loss through the dredging process and quantify their effects on the placement area.
 - If fine sediments can be more broadly utilized, regulatory standards could be changed which would ultimately save the USACE's limited dredging funds.
- To test several types of relatively inexpensive light and photosynthetically active radiation (PAR) sensors.
 - If lower-cost PARs can be correlated with turbidity measurements, they could be more broadly utilized as an alternative measurement method.
- To compare dredging conditions with ambient conditions.
 - Natural turbidity may be similar to that associated with dredging of fine sediments, lending additional justification to modification of regulatory standards.
- To compare CSSZ and traditional placements




Why worry about fines?

- Compaction and density issues
 - Thought to be an issue for sea turtle nesting
- Light attenuation
 - Dredge plume associated with fine sediments and impacts to biological resources
- Sediment color
 - Impacts to sea turtle male to female ratio, incubation period and reduces hatching success
 - Aesthetic issues
- Overall grain size
 - May not match existing beach



Project Monitoring

- Pre-dredging
 - Vibracores taken in channel
 - Sediment analysis
- During/Post-dredging
 - Cameras
 - Surveying
 - Sediment sampling and analysis
 - Dredge and Placement
 - Compaction testing
 - Light/PAR sensors
 - Munsell color



Sea turtle nesting surveys

BUILDING STRONG®

ERDC

Innovative solutions for a safer, better world

2014 Dredging and Placement



UAV flight aerial 16 March 2015



Image Courtesy of USACE Jacksonville District

ERDC

BUILDING STRONG®

Innovative solutions for a safer, better world

Results

- Fines Content and Density
- Morphological Evolution
- Compaction- Cone Penetrometer
- Munsell Color
- Light Attenuation
- Sea Turtle Nesting



BUILDING STRONG®

ERDC

Innovative solutions for a safer, better world

Fines Content and Density

Tampa Harbor MD - Egmont Key 2014		
	# of Samples	Avg. % by wt. passing 230 sieve
In-situ	80	20.7
pre-Beach	6	0.03
post-Dredged	21	0.51
Traditional	14	0.52*
CSSZ	7	0.49*




* Sampling occurred within 72 hours of placement completion

Tampa Harbor MD - Egmont Key 2014			
	# of Samples	Value avg. (kg/m3)	% Greater
Density			
pre-Beach	7	1405.1	0.0%
post-Dredged	17	1471.6	4.7%
Traditional	11	1476.0	5.0%
CSSZ	6	1463.5	4.2%



Images Courtesy of GLDD

Traditional Beach Nourishment




BUILDING STRONG®

ERDC

Innovative solutions for a safer, better world

R23 Profiles with % Fines




USF UNIVERSITY OF SOUTH FLORIDA



BUILDING STRONG®

Innovative solutions for a safer, better world

R21 Profiles with % Fines




USF UNIVERSITY OF SOUTH FLORIDA

ERDC

BUILDING STRONG®

Innovative solutions for a safer, better world

R25 Profiles with % Fines




USF UNIVERSITY OF SOUTH FLORIDA



BUILDING STRONG®

Innovative solutions for a safer, better world

R19 with % Fines




USF UNIVERSITY OF SOUTH FLORIDA



BUILDING STRONG®

Innovative solutions for a safer, better world

Cross-shore Swash Zone Nourishment




BUILDING STRONG®


ERDC

Innovative solutions for a safer, better world

R12 Profiles with % Fines



R11 Profiles with % Fines




BUILDING STRONG®



Innovative solutions for a safer, better world

R10 Profiles with % Fines



BUILDING STRONG®



Innovative solutions for a safer, better world



UAV aerial Courtesy of USACE Jacksonville District
HHT Surveys and GIS performed by USF

Munsell Color

Tampa Harbor MD - Egmont Key 2014

	# of Samples	Value avg.
In-situ	80	4.36*
pre-Beach	13	5.9
post-Dredged	24	5.3
Traditional	16	5.0
CSSZ	8	5.9



*Munsell color value < 5 unacceptable for beach placement in Florida

NOTES: Triplicate measurements of hue, value, and chroma were collected from three areas on each moist sand sample using a digital colorimeter (CR-400, Konica Minolta, Osaka, Japan).




BUILDING STRONG®


ERDC

Innovative solutions for a safer, better world


Light Attenuation Background Monitoring – Pipe



Light Attenuation Base Station



Daisy Chain



Light Attenuation Monitoring – Tire




BU

Instrument Biofouling




Preventing Data Quality Degradation Due to Biofouling through the Use of Copper Tape

Without Copper Tape



With Copper Tape



Light Attenuation Long-term Monitoring

Egmont Key, FL
Long-term
Deployment Map
14 Nov – 15 Dec




BUILDING STRONG®

Image Courtesy of GLDD




Light Attenuation Long-term Monitoring

Turbidity versus PAR values



Dredging 19 Nov. – 28 Dec.

Dredging 21 Jan. – 6 Mar.



Sea Turtle Nesting 2015



Nesting as of 16 August 2015



Image Courtesy of USACE Jacksonville District



BUILDING STRONG®

Innovative solutions for a safer, better world

CSSZ vs. Traditional Placement

- **Less linear feet of beach impacted for equivalent volume**
 - CSSZ
- **Reduced environmental Impacts**
 - Cementation
 - Munsell Color
 - Shorebird impacts
- **Material is not visible to public**
- **Lower cost**
 - Construction – less beach equipment
 - Reduced pipeline extensions
 - Maintenance – less escarpment, tilling
- **Purely performance based regulations**
 - More beneficial reuse
 - Lower costs - better bids due to more equipment able to perform work



Image Courtesy of GLDD



Summary and Conclusions

- Grain Size sampling indicates significant “fines” losses through dredging process
- Longshore spreading of both nourishment types occurred
- Most of the sediment gained from longshore spreading appeared in the intertidal to subtidal zones
- Fine material initially located at the toe of the fill no longer appears along profile
- Munsell Color and Compaction similar to pre-conditions
- Turbidity decreases when not pumping
 - Copper tape reduced impacts of biofouling
- Turtle nesting appears lower in traditional nourishment than CSSZ, however overall number of nests may not have been impacted



Acknowledgements

Great Lakes Dredge and Dock – Mr. Manny Vianzon, Ms. Lynn Nietfeld, Ms. Kate Mason, Mr. Michael Tolivar, Mr. Robert Ramsdell III, Mr. Bill Hanson

University of South Florida – Dr. Ping Wang, Mr. Zachary Tyler Mr. Mark Horwitz

U.S. Fish and Wildlife Service – Mr. Peter Plage and Mr. Stan Garner

Florida Department of Environmental Protection – Mr. Tom Watson

Tampa Bay Pilots Association – Ms. Leslie Head

Florida Fish and Wildlife Conservation Commission – Dr. Robbin Trindell

USACE Tampa Field Office – Mr. Andy Cummings, Ms. Tina Underwood, Ms. Erin Duffy

USACE Jacksonville District – Mr. Bryan Merrill, Mr. Mike Hensch, Mr. Vic Wilhelm, Mr. Tom Spencer.

USACE Engineer Research and Development Center – Mr. Coraggio Maglio, Mr. Jase Ousley, Mr. Matthew Taylor, Mr. John Bull, Ms. Cheryl Pollock, Dr. Deborah Shafer, Mr. Tommy Kirkland, Dr. Jacob Berkowitz, Mr. Jason Pietroski

U.S. Coast Guard – Mr. Darren Pauly, Mr. Ivan Meneses



BUILDING STRONG®



Innovative solutions for a safer, better world

Questions?

Contacts:

Katherine Brutsché

Katherine.E.Brutsche@usace.army.mil

Coraggio Maglio

Coraggio.K.Maglio@usace.army.mil



BUILDING STRONG®

ERDC

Innovative solutions for a safer, better world