



Local Officials Guide for Coastal Construction

Design Considerations, Regulatory Guidance, and
Best Practices for Coastal Communities

FEMA P-762 / February 2009



FEMA

Local Officials Guide for Coastal Construction

Design Considerations, Regulatory Guidance, and
Best Practices for Coastal Communities

FEMA P-762 / February 2009

Cover Photo: Courtesy of Jennifer Smits/FEMA



FEMA

Any opinions, findings, conclusions, or recommendations expressed in this publication do not necessarily reflect the views of FEMA. Additionally, neither FEMA nor any of its employees makes any warrantee, expressed or implied, or assumes any legal liability or responsibility for the accuracy, completeness, or usefulness of any information, product, or process included in this publication. Users of information from this publication assume all liability arising from such use.

Acknowledgements

The preparation of this document was sponsored by the FEMA Mitigation Directorate. It has been developed based on the work of several recent publications, new insights from recent hurricanes, the post-disaster assessment findings of FEMA Mitigation Assessment Teams, and other sources of information on residential coastal construction. The principal contributing authors of the supporting reference documents are gratefully acknowledged.

For this manual, the following individuals are acknowledged:

Primary Authors:

Scott Tezak, URS Corporation – Project Manager

David K. Low, DK Low & Associates, LLC

Adam Reeder, PBS&J

Contributors:

Chris Hudson – FEMA Headquarters – Project Monitor

John Ingargiola – FEMA Headquarters

Jacob Anderson – FEMA Headquarters

Marcus Barnes – FEMA Headquarters

Ken Wallace – FEMA Region III

Mark Vieira – FEMA Region IV

John Plisich – FEMA Region IV

Chuck Gregg – FEMA Region VI

Jeffrey Lusky – FEMA Region IX

Byron Hilado – PBS&J

Mike J. Robinson – PBS&J

Rebecca Quinn – RCQuinn Consulting

Wanda Edwards – Institute for Business and Home Safety (IBHS)

William Coulbourne – Applied Technology Council

Chris Jones – Christopher P. Jones

Project Review Committee

The authors and editors gratefully acknowledge the invaluable assistance and advice provided by the following reviewers:

Jhun De La Cruz – FEMA Headquarters

Lois Forster – FEMA Headquarters

Tim Tolbert – City of Santa Rosa, Florida

Joe Lamb – City of Port Aransas, Texas

William York – W.H. York Consulting

Timothy Reinhold – Institute for Business and Home Safety (IBHS)

Randy Noelle – Builder

Stuart McDonald –Mercedes Homes

Mike Rimoldi – FLASH

David Conover – International Code Council (ICC)

Steve Van Note – International Code Council (ICC)

Phil Line – American Forest & Paper Association (AF&PA)

Kenneth Ford – National Association of Home Builders (NAHB)

Dana Bres – U.S. Department of Housing and Urban Development (HUD/PATH)

Steve Mitchell – City of Pascagoula, Mississippi

Don Burrell – City of Beaumont, Texas

Lalo Flores – Missouri City, Texas

Edward Beasley – City of Portland, Texas

Robert Daehn – City of Kingsville, Texas

San Nelson – Texas Department of Insurance

Robert Smalley – City of Chesapeake, Virginia



FEMA

FEMA P-762
Catalog No. 09064-1

Contents

1 Introduction

- 1.1 Objectives 1-1
- 1.2 Target Audience 1-1
- 1.3 Scope..... 1-1
- 1.4 Using the Guide..... 1-2
- 1.5 Coastal Construction versus Inland Construction 1-4
- 1.6 Building Codes..... 1-5

2 Coastal Hazards and Considerations

- 2.1 Flood Hazards: General Design Considerations..... 2-1
- 2.2 Wind Hazards: General Design Considerations 2-19
- 2.3 Other Hazards..... 2-32

3 Investigating Regulatory Requirements

- 3.1 Floodplain Management Requirements and Building Codes..... 3-1
- 3.2 Building Codes and Standards 3-11
- 3.3 Coastal Barrier Resources Act of 1982 3-18
- 3.4 Coastal Zone Management Regulations 3-19
- 3.5 Use of the National Flood Insurance Program and Code Crosswalk 3-20

4 Permits and Inspections

- 4.1 Introduction..... 4-1
- 4.2 Coastal Building Official/Floodplain Administrator’s Responsibilities 4-2
- 4.3 Freeboard..... 4-5
- 4.4 The Pre-development Conference/Pre-application Meeting 4-6
- 4.5 Coastal Construction Permit Application Steps..... 4-8
- 4.6 Permit Plan Submittal Requirements 4-8
- 4.7 Elevation Certificates 4-10
- 4.8 Inspections 4-11
- 4.9 Enforcement and Violations 4-14
- 4.10 Variance Process 4-15
- 4.11 Supplemental Information 4-16

5 Coastal Construction and Continuous Load Paths

- 5.1 Continuous Load Path..... 5-1
- 5.2 Types of Load Paths 5-4
- 5.3 Identifying Load Paths in Buildings 5-5
- 5.4 Building Codes and Standards 5-7
- 5.5 Continuous Load Paths and Building Success 5-8

6 Coastal Foundations and Best Practices

| | | |
|-----|--|------|
| 6.1 | Introduction | 6-1 |
| 6.2 | Building Codes and Coastal Foundations | 6-2 |
| 6.3 | Foundations in Coastal Areas | 6-2 |
| 6.4 | Elevating Buildings in Coastal Areas..... | 6-5 |
| 6.5 | Soils Investigation | 6-24 |

7 Building Framing Systems and Best Practices

| | | |
|-----|---------------------------------|------|
| 7.1 | Introduction | 7-1 |
| 7.2 | Diaphragms and Shear Walls..... | 7-2 |
| 7.3 | Roof Construction..... | 7-4 |
| 7.4 | Wall Construction..... | 7-8 |
| 7.5 | Floor Construction | 7-18 |

8 Roof Coverings and Best Practices

| | | |
|-----|---|------|
| 8.1 | Introduction | 8-1 |
| 8.2 | Roof Coverings: General Code Requirements | 8-3 |
| 8.3 | Re-roofing Code Requirements and Best Practices | 8-12 |

9 Exterior Cladding Components and Best Practices

| | | |
|-----|---|------|
| 9.1 | Introduction | 9-1 |
| 9.2 | Exterior Wall Coverings and Claddings | 9-1 |
| 9.3 | Exterior Covering and Best Practices..... | 9-6 |
| 9.4 | Exterior Floor Coverings | 9-11 |
| 9.5 | Soffits | 9-12 |
| 9.6 | Concrete and Masonry Walls..... | 9-12 |

10 Windows and Doors

| | | |
|------|--|-------|
| 10.1 | Introduction | 10-1 |
| 10.2 | Window and Door Failure..... | 10-1 |
| 10.3 | Windborne Debris Protection Systems..... | 10-4 |
| 10.4 | Protection Requirements for Windborne Debris | 10-6 |
| 10.5 | Window and Door Leakage | 10-11 |
| 10.6 | Window and Door Assembly Capacities | 10-12 |
| 10.7 | Garage Doors | 10-14 |
| 10.8 | Additional Resources | 10-16 |

Figures

| | | |
|-----|--|-----|
| 2-1 | Floodplain along an open coast..... | 2-2 |
| 2-2 | Long Beach, Mississippi: Aerial photo of apartment complex | 2-3 |
| 2-3 | Gulf Shores, West Beach, Alabama: Aerial overview | 2-4 |

2-4 Gulf Shores, West Beach, Alabama: Insufficient pile embedment2-4

2-5 Orange Beach, Alabama: Collapse of five-story, multi-family building2-5

2-6 Orange Beach, Alabama: Collapse of five-story, multi-family building2-5

2-7 Hydrostatic loads on buildings2-6

2-8 Hydrodynamic loads on a building or building element2-7

2-9 Gulfport, Mississippi: Floodborne debris.....2-8

2-10 Example of surge, wave, and debris damage.....2-9

2-11 Example of surge, wave, and debris damage.....2-9

2-12 Big Lagoon, Alabama: Buildings constructed on piles2-9

2-13 Orange Beach, Alabama: Significant erosion caused a parking slab to fail2-11

2-14 Gulf Shores, Alabama: House on pile foundation.....2-11

2-15 Gulf Shores, Alabama: House on pile foundation.....2-11

2-16 Coastal wave height and stillwater depth.....2-12

2-17 Flood probability chart.....2-14

2-18 Example of a Digital Flood Insurance Rate Map (DFIRM).....2-17

2-19 Coastal flood hazard areas2-17

2-20 Hurricane-prone regions and special wind regions2-21

2-21 Wind-induced pressures on a building.....2-23

2-22 Wind pressure as a function of wind speed.....2-25

2-23 Internal pressure condition when the dominant opening is in the windward wall2-28

2-24 Internal pressure condition when the dominant opening is in the leeward wall.....2-29

2-25 Ocean Springs, Mississippi: Apartment complex severely damaged by wind.....2-31

2-26 Gulf Shores, Alabama: Partition walls destroyed by interior pressurization2-31

2-27 New Orleans, Louisiana: Neighborhood with homes and vehicles flooded.....2-33

3-1 Minimum NFIP V Zone Requirements.....3-6

3-2 Minimum NFIP A Zone Requirements.....3-8

3-3 Recommended Elevation for Buildings in Coastal A Zones and V Zones.....3-10

3-4 The hurricane-prone regions along the coastline of the United States.....3-17

4-1 Permitting and Construction Process Overview4-9

5-1 Dade County, Florida, Hurricane Andrew (1992): Load path failure at end gable5-2

5-2 North Carolina, Hurricane Fran (1996): Load path failure in a foundation5-2

5-3 Punta Gorda, Florida: Roof framing damage and loss due to load path failure 5-3

5-4 Punta Gorda, Florida: Load path failure in connections for a roof system 5-3

5-5 Pass Christian, Mississippi: Newer home damaged from internal pressurization 5-4

5-6 Loads applied to the exterior walls of a building 5-5

5-7 Technical Fact Sheet No. 10, Page 1 5-6

5-8 Technical Fact Sheet No. 10, Page 2 5-7

5-9 Big Lagoon, Florida: Elevated building, constructed to newer code..... 5-9

5-10 Big Lagoon, Florida: This house was elevated on piles..... 5-9

5-11 Big Lagoon, Florida: This house was elevated on piles..... 5-9

6-1 Recommended open-foundation practice for buildings in the Coastal A Zone and V Zone 6-4

6-2 Navarre Beach, Florida: Slab-on-grade foundation failure due to erosion 6-4

6-3 Navarre Beach, Florida: Close-up of foundation failure shown in Figure 6-2..... 6-5

6-4 Plaquemines Parish, Louisiana: Home that had been elevated on fill 6-6

6-5 Building failure caused by undermining of crawlspace foundation during Hurricane Fran 6-8

6-6 Failure of crawlspace foundation, which was undermined by scour..... 6-8

6-7 Typical stem wall foundation 6-10

6-8 Fort Myers Beach, Florida: Oceanfront house constructed on an open foundation..... 6-11

6-9 Fort Myers Beach, Florida: Newly constructed house elevated on an open foundation 6-12

6-10 Dauphin Island, Alabama: Successful pile foundation following Hurricane Katrina..... 6-13

6-11 Dauphin Island, Alabama: Structure near collapse due to insufficient pile embedment..... 6-13

6-12 Long Beach, Mississippi: Structure removed from its foundation by wave action 6-14

6-13 Pile installation methods 6-15

6-14 Diagonal bracing schematic..... 6-17

6-15 Knee brace connection example 6-18

6-16 Elevation view (right) of a concrete pile foundation using grade beams..... 6-19

6-17 Successful use of a breakaway wall..... 6-21

6-18 Building damages due to the incorrect construction of a breakaway wall..... 6-21

6-19 Possible failure modes for masonry piers 6-22

6-20 Pass Christian, Mississippi: Performance comparison of shallow, open foundations..... 6-23

6-21 Belle Fontaine Point, Jackson County, Mississippi: Column connection failure..... 6-23

7-1 Load transfer between diaphragms and shear wall 7-2

7-2 Horizontal diaphragm and diaphragm components..... 7-3

7-3 Vertical shear walls and shear wall components..... 7-3

7-4 Loss of roof sheathing due to inadequate fastening..... 7-4

7-5 Exterior views of connection between roof sheathing and roof trusses 7-6

7-6 Interior views of connection between roof sheathing and roof trusses 7-6

7-7 Detail of masonry wall-to-roof trusses 7-7

7-8 Horizontal loadings exerted on exterior walls 7-9

7-9 Segmented shear walls 7-10

7-10 Perforated shear walls 7-10

7-11 Shear wall anchor 7-12

7-12 Example of balloon framing..... 7-13

7-13 Additional bracing at a gable end wall 7-13

7-14 Improperly braced gable walls..... 7-14

7-15 Residential use of a moment frame 7-15

7-16 Uplift connections around framed opening..... 7-16

7-17 Designed of a reinforced masonry wall system 7-18

7-18 Wooden I-joists used for floor framing 7-20

8-1 Instance where wind pressures exceeded the strength of the asphalt roofing..... 8-2

8-2 Gulfport, Mississippi: Winds dislodged roof-mounted equipment 8-2

8-3 Example of an augmented underlayment installation 8-5

8-4 Example of proper shingle installation..... 8-6

8-5 Roof failures that resulted from improper starter-strip installation..... 8-7

8-6 Roof failures that resulted from asphalt shingles being installed in a raking fashion..... 8-7

8-7 Loss of asphalt shingle roofing along hip 8-7

8-8 Clay tile roof failure. The tiles were dislodged due to inadequate anchorage 8-8

8-9 Storm damage to a tile roof system..... 8-9

9-1 Examples of moisture barrier systems..... 9-4

9-2 Examples of moisture barrier systems..... 9-4

9-3 Proper siding lapping to prevent moisture penetration 9-5

9-4 Roof flashing..... 9-7

9-5 Window flashing details 9-7

9-6 Comparison of typical high-wind siding verses standard siding 9-8

9-7 The center of the nailing slot is the proper fastener location 9-8

9-8 Proper fastener clearance..... 9-8

9-9 Example of wood siding on a wood-framed house 9-9

9-10 Figure illustrating the layout of brick ties at house under construction 9-10

9-11 Waveland, Mississippi: House with collapsed brick veneer due to insufficient wall ties..... 9-10

9-12 Example of an exterior floor covering system damaged by Hurricane Ivan 9-11

10-1 Punta Gorda, Florida: Failure of a roof structure from pressurization 10-2

10-2 Puerto Rico: Failure due to inadequate pressure rating of window..... 10-3

10-3 Punta Gorda, Florida: Glazing failure due to windborne debris from displaced roofing 10-3

10-4 Glazing failure due to windborne debris 10-3

10-5 Pensacola, Florida: Example of an insufficient shuttering system 10-7

10-6 Pensacola, Florida: Failure of glazing from windborne debris..... 10-10

10-7 Punta Gorda Isles, Florida: Anchorage failure in sliding glass door failure 10-12

10-8 Negative pressure failure of garage door..... 10-15

10-9 Positive pressure failure of garage door 10-15

Tables

2-1 Enhanced Fujita Scale 2-20

2-2 Saffir-Simpson Hurricane Scale 2-22

2-3 Wind Pressure Example for Exposure B..... 2-26

2-4 Wind Pressure Example for Exposure C 2-27

3-1 Code Crosswalk 3-22

10-1 Tables 2 and 3 from ASTM E1996 10-9

Appendix:..... A-1