

EASTERN TIE-IN

Updated August 2015

BUILDING STRONG®

U.S. ARMY CORPS OF ENGINEERS

Public safety is the Corps of Engineers' top priority. Congress has fully authorized and funded the Hurricane and Storm Damage Risk Reduction System (HSDRRS) for southeast Louisiana. The \$14.45 billion HSDRRS includes five parishes and consists of 350 miles of levees and floodwalls; 73 non-Federal pumping stations; 3 canal closure structures with pumps; and 4 gated outlets.

Project Summary

The Eastern Tie-In project, located on the west bank of the Mississippi River in the vicinity of the town of Oakville in Plaquemines Parish, ties into the existing Hero Canal levee, crosses Highway 23, and links to the Mississippi River Levee system.

The structural features being built by the Corps reduce the risk associated with a storm surge event that has a one percent chance of occurring in any given year, or a 100-year storm surge. The total construction value for the Eastern Tie-In projects is an estimated \$81 million.

Project Features

The Eastern Tie-In project connects the Mississippi River Levees with the existing Hero Canal Levee. This system includes the following



features: a navigable stoplog gate across the Hero Canal, levees, a pump station, emergency shelter, a floodwall, a floodgate across Highway 23, a railroad gate and a tie-in levee at the Mississippi River Levee.

U.S. ARMY CORPS OF ENGINEERS – TEAM NEW ORLEANS 7400 Leake Avenue, New Orleans, LA 70118 | www.mvn.usace.army.mil Visit the following links to follow us on Facebook, Twitter and Flickr: www.facebook.com/neworleansdistrict www.twitter.com/teamneworleans www.flickr.com/teamneworleans



EASTERN TIE-IN

Updated August 2015

BUILDING STRONG®

The Corps determined that a double swing gate system was the most reliable way to close the system across Highway 23 because it is a proven reliable risk reduction feature. It requires minimal training and advanced preparation; it can be closed in four hours or less, allowing travel lanes to be quickly closed and opened in the event of a storm. An emergency by-pass road was constructed for authorized vehicles when the gate is closed.

Project Status

The Eastern Tie-In is split into 3 contracts. All three contracts are complete:

U.S. ARMY CORPS OF ENGINEERS

- WBV-09a Includes earthen levees, Oakville Pump Station, emergency shelter and the emergency bypass road.
- WBV-09b Includes the stoplog closure structure on the Hero Canal.
- WBV-09c Includes the floodwalls, highway swing gates and the railroad swing gate at Hwy 23.



WBV-09a Pump station along Oakville Levee



WBV-09c Closed Highway Swing Gate



WBV-09b Stoplog Structure on Hero Canal

U.S. ARMY CORPS OF ENGINEERS – TEAM NEW ORLEANS 7400 Leake Avenue, New Orleans, LA 70118 | <u>www.mvn.usace.army.mil</u> Visit the following links to follow us on Facebook, Twitter and Flickr. <u>www.facebook.com/neworleansdistrict</u> <u>www.twitter.com/teamneworleans</u> <u>www.flickr.com/teamneworleans</u>