Southeast Louisiana Drainage Project Orleans Parish



Dwyer Road Subbasin Landscape Development

March 24, 2015



US Army Corps of Engineers BUILDING STRONG_®

Meeting Purpose

- Overview of Southeast Louisiana Project
- Drainage Improvements for the Dwyer Subbasin
- Post-construction landscape planning
- Obtain community input on landscape design



Flood Damages

- May 1995: 6-hour rainfall averaged 12 in
- Some locations up to 28 inches in the 24-hour period
- Since 1978, well over \$1 billion in damages from rainfall flooding



- Fiscal Year 1996 Energy and Water Development Appropriations Act (Nov '95)
- 1996 Water Resources Development Act (Oct '96)
- Department of Defense Appropriations Act, 2006; Supplemental Appropriations Act, 2008; Consolidated Security, Disaster Assistance, and Continuing Appropriations Act, 2009

Orleans Parish Projects





Coastal Protection and Restoration Authority of Louisiana

Project Partnership Agreement between USACE and CPRA executed January 16, 2009

Project Cooperation Agreement between USACE and the Sewerage & Water Board of New Orleans executed January 23, 1997

Summary of Orleans Parish Improvements

- \$1.4 billion in work authorized
 - ► \$997M Federal
 - ► \$407M non-Federal
- Adding approximately 3,500 cfs to East Bank stations and 1,800 cfs to West Bank
- East Bank: 65,000 linear feet of canal improvements
- West Bank: 44,000 linear feet of canal improvements





U.S. Army Corps of Engineers, New Orleans District Southeast Louisiana Urban Flood Control Program (SELA) ORLEANS PARISH MAP 1 OF 1: OCTOBER 2014 ORLEANS PROJECTS AND STATUS



Dwyer Subbasin Drainage Improvements

- Dwyer Pumping Station completed January 2011
 - New 1050 cfs Pumping Station
- Dwyer Outfall Canal completed August 2004
 - New 22-ft x 10-ft below ground canal from the Pump Station to the Industrial Canal
- Dwyer Intake Canal completed October 2013
 - New below ground box culvert ranging in size from 10 ft x 10ft to 14 ft x 11 ft
 - Camelia Street to Dwyer Pump Station (approx 6,800 linear feet)

TOTAL CONSTRUCTION COST: \$91.7 Million



Dwyer Subbasin Drainage Improvements



Benefits:

- Provide flood risk reduction for a 10year storm event
 - 3 inches 1st hour, 9 inches over a 24 hour period)
- Works in conjunction with existing drainage system



Dwyer Road Community Communication

January 2009 kick-off:

- Neighborhoods Partnership Network, Melia and Rosedale Neighborhood representatives
 - Requested walking path for safe place to walk & exercise
- Continued communication throughout drainage project:
 - Pathway
 - Trees along pathway for community cohesion/beautification
 - Preserve and enhance scenic and aesthetic qualities



Dwyer Road Post Construction Landscape Planning



Design Considerations – site conditions:

- Below ground obstructions:
 - Two large drainage culverts (12 ft wide and 10 ft wide)
 - Limited cover prohibits large or medium trees
- Above ground obstructions:
 - Overhead power lines & residential distribution lines prohibits planting of large trees



Dwyer Road Post Construction Landscape Planning

Design Considerations – site conditions:

- Compliance with City Planning, Parks and Parkways, and Department of Public Works
 - city ordinances and guides for planting
 - city's master plan for land use
 - Americans with disabilities act
 - Protection of existing infrastructure and public property
 - Coordination with city of New Orleans Parks and Parkways regarding picking a proper and suitable tree selection
 - pest issues, trimming requirements, hearty tree varieties, well suited for climate
 - Incorporate some native trees with ornamental trees



Dwyer Road Post Construction Community Input

Preliminary Community Feedback:

- Pathway– curved walkway
- Trees similar to those on Claiborne
 - Taller trees are not possible with site conditions similar medium sized trees included in concept
- Trees at corners should not block views and signage
- Desire for benches similar to Joe Brown
 - Will be incorporated







Dwyer Road Landscape Planning







Dwyer Road Landscape Planning







Grancy Greybeard

Chinese Pistache



Spruce Pine



Bay Magnolia



Vitex





Dwyer Road Landscape Planning



What is the next step?

Develop detailed Plans and Specifications:

- Specific trees will be determined based on design criteria in conjunction with the existing survey layout
- Consider size both height and canopy
- Sustainability

Schedule for planting:

Current schedule – planting early calendar year 2016



Open Discussion - Feedback

CONTACT INFORMATION:

U.S. Army Corps of Engineers, New Orleans District: Caitlin Campbell, Public Affairs: (504) 862-2545 Lori Wingate, Project Manager: (504) 862-1285

WEBSITES:

http://www.mvn.usace.army.mil/ www.swbno.org/work_drainageSELA.asp

